

AL-V-B-231

1900-1901

Carney - Ewald House
Mount Savage
Private

Carney - Ewald House is located on Carney Road near Mount Savage. The irregularly shaped building is two and one-half stories tall and four bays wide on the facade. Projecting two and one-half story bays are located on the facade and southwestern elevation. The vernacular styled building exhibits Queen Anne influences.

This dwelling was constructed for William Ewald, the superintendent of motive power for the Cumberland and Pennsylvania Railroad. In the late 1930's clay tennis courts were installed near the house. The house has been the home of the Carney family since 1950.

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

AND/OR COMMON

Carney-Ewald House

2 LOCATION

STREET & NUMBER

Carney Road

CITY, TOWN

Mount Savage

VICINITY OF

CONGRESSIONAL DISTRICT

6th

STATE

Maryland

COUNTY

Allegany County

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL <input checked="" type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES, RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES, UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input checked="" type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER

4 OWNER OF PROPERTY

NAME

Charles Carney et al

Telephone #: 264-4175

STREET & NUMBER

General Delivery

CITY, TOWN

Mount Savage

VICINITY OF

STATE, zip code
Maryland

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC

Allegany County Courthouse

Liber #: 232

Folio #: 336

STREET & NUMBER

30 Washington Street

CITY, TOWN

Cumberland

STATE
Maryland 21502

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

None

DATE

FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

16-11-231

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input checked="" type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input checked="" type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Carney-Ewald House is located on Carney Road near Mount Savage. The irregularly shaped building is two and one-half stories tall and four bays wide on the southeastern-facing facade. Projecting two story bays are on the facade and the southwestern elevation. Wall construction is frame with horizontal tongue and groove flushboard covered with insul brick siding. Imbricated and square wooden shingles cover the upper gable ends. The gable roof is covered with asphalt shingles and has snowbirds. Eaves consist of a boxed cornice, soffit, bed mould, frieze with dentils, returns and decorative bargeboard. Bracketed pendants are located on the projecting bays. The house rests on a high foundation of random ashlar stone.

A wraparound veranda on the facade has rounded corners and a hipped roof supported by bracketed turned posts. The porch has turned balusters and a lattice-like base. A hip roofed porch on the northeastern elevation has turned posts. Windows are 1/1 sashes, some in pairs on the second story. Round headed attic windows are 1/1 sashes with drip moulding. The main entrance in the center of the facade includes a one light transom and a one light of beveled glass, three decorated panels and original hardware. An entrance on the northeastern elevation has a pedimented one light transom and a door of one light and three panels. Three chimneys of white glazed bricks have corbeled caps and are located on the interior and inside ends.

Rooms of the house are irregularly arranged with an offset hallway with one room to the right and three to the left. An open stairway facing the entrance is of one and one-half flights and two landings. Trim of the stairway includes a paneled string with pendants, a decorative square newel and turned balusters, all of oak. Walls of the house are plastered with a tall baseboard. Chimney outlets are located in every room and a new brick fireplace has been installed in the dining room. Interior doors are of four panels with engraved plates and pedimented oversized transoms. Interior window surrounds are pedimented. Walls of the kitchen have a quarter-round baseboard and tall vertical wainscoting of beaded flush board.

In addition to the house the property has been improved by the construction of a small barn and clay tennis courts.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES	1900-1901	BUILDER/ARCHITECT
----------------	-----------	-------------------

STATEMENT OF SIGNIFICANCE

The Carney-Ewald House was built in 1900-1901 for William Ewald. Ewald began his career as an apprentice at the Cumberland and Pennsylvania Railroad shops in Mount Savage. After working for five years in the Pittsburgh shops of the Pennsylvania Railroad, Ewald returned to Mount Savage to become the foreman of the C & P Railroad shops. (Scharf, p. 1064) The C & P RR shops in Mount Savage were established in the 1850s and continued well into the 20th century manufacturing and rebuilding locomotives. (Steg et al, p. 210) In 1913 William Ewald was made the superintendent of motive power for the railroad. (Scharf, p. 1064)

Oral tradition indicates that the house was designed by Ewald and constructed by C & P RR employees. (Interview) The large frame building is of a vernacular style with Queen Anne influences. In the late 1930s clay tennis courts were installed near the house. The property was sold to the Carney family in 1950. (Liber 232, Folio 336)

AL-16-231

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Carney, Charles, "The History of Mount Savage." Unpublished paper prepared for the Maryland Cooperative Extension Service, 1967.

Scharf, John T., History of Western Maryland, Philadelphia: L. H. Everts Company, 1882.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE _____ COUNTY _____

STATE _____ COUNTY _____

11 FORM PREPARED BY

NAME / TITLE

David A. Dorsey, Historian

ORGANIZATION

Maryland Historical Trust/Bureau of Mines

DATE

April 1981

STREET & NUMBER

Shaw House, 21 State Circle

TELEPHONE

301-269-2438

CITY OR TOWN

Annapolis

STATE

Maryland 21401

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 4i, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.


RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

AL-V-B-231


#9 (cont.)

Stegmaier, Harry et al, Allegheny County-A History. Parsons, West Virginia:
McClain Printing Company, 1976.

Interview with Mrs. Alice Ayers Carney, Mount Savage 11/13/80.



FLOOR PLAN - FIRST FLOOR
NOT TO SCALE



ROOF PLAN
NOT TO SCALE

AL-V-B-231

CARNEY - EWALD HOUSE
MOUNT SAVAGE, ALLEGANY COUNTY MARYLAND

DAVID A. DORSEY NOV. 1980



Cumberland, MD-PA
 USGS 7.5 Minute Series
 Scale 1:24,000
 1949; photorevised 1974

AL-V-B-231
 Carney-Ewald House
 Carney Road
 Mount Savage



AL-V-B-231
Carney/Ewald House
Allegheny Co., MD
David A. Dorsey 11/80
Western elev.



AL-V-B-231

Carney / Ewald House

Allegany Co., MD

David A. Dorsey 11/80

Eastern elev.