

Hocking House
AL-V11 -A-005
144 East Main Street, Frostburg
1855

The Hocking House was built in 1855 on a tract of land known as "The Hotel". The land was part of the estate of Robert Clarke, Sr., one of the original settlers of the area that is now Frostburg. The house located on the northern side of the National Road, was a fashionable residence until ¹⁹⁴² ~~1855~~ when it was converted into a clubhouse. Local tradition suggests that it was one of three stations of the underground railroad in Frostburg.

The house is a good example of transitional Green Revival-Italianate architecture, a style that is somewhat rare in Allegany County. Italianate elements of the building, the shape, roof, eaves, and window design, are more pronounced than the subtler Greek Revival influence in the design of the entrance and the central gable. Although in fair condition the building is structurally sound.

28

United States Department of the Interior
Heritage Conservation and Recreation Service

For HCERS use only

received

date entered

National Register of Historic Places Inventory—Nomination Form

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic Hocking House

and/or common

2. Location

street & number 144 East Main Street N/A not for publication

city, town Frostburg vicinity of _____ congressional district Sixth

state Maryland code 24 county Allegheny code 001

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input checked="" type="checkbox"/> commercial
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input type="checkbox"/> private residence
			<input type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property

name Clarence E. Miller

street & number 140 East Main Street

city, town Frostburg vicinity of _____ state Maryland 21532

5. Location of Legal Description

courthouse, registry of deeds, etc. Allegheny County Courthouse

street & number 30 Washington Street

city, town Cumberland state Maryland 21502

6. Representation in Existing Surveys

title Maryland Historical Trust
Historic Sites Inventory has this property been determined eligible? yes no

year 1974 federal state county local

depository for survey records Maryland Historical Trust

city, town Annapolis state Maryland 21401

United States Department of the Interior
National Park Service

For NPS use only

received

date entered

National Register of Historic Places
Inventory—Nomination Form

Hocking House

Continuation sheet Allegany County, Maryland

Item number

7

Page 3

DESCRIPTION SUMMARY

The Hocking House is a circa 1855 2½ story, three-bay, hip-roofed dwelling which exhibits features characteristic of the transitional Greek Revival-Italianate style, located in Frostburg, Allegany County, Maryland. The house is constructed of brick laid in four-course American bond, separated from its coursed ashlar foundation by a plain water table. The principal (south) facade is symmetrical, with extremely tall paired 4/6 windows flanking the recessed central entrance. The entrance retains its original bracketed entablature supported on flat pilasters. Similar brackets decorate the boxed roof cornice. A shallow cross gable defines the central bay. On the interior, the building exhibits a center hall plan, and retains considerable original trim, including interior shutters, double doors, and mantelpieces. The trim employs decorative motifs characteristic of the period, including elliptical arches and engaged pilasters. A cartouche embellishes a carved slate fireplace surround. A 1½ story gabled brick addition, apparently contemporaneous with the main block, extends to the rear, with a modern shed-roofed addition abutting it.

7. Description

AL-VII-A-005

Condition		Check one	Check one
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance FOR SUMMARY SEE CONTINUATION SHEET #3
GENERAL DESCRIPTION:

The Hocking House is located at 144 East Main Street, on the north side of the street near the present center of Frostburg.

This finely proportioned transitional Greek Revival-Italianate building is square, 2½-stories tall with a low hip roof and a wide, three bay symmetrical facade (south elevation). Resting on a foundation of coursed ashlar stone, a plain water table separates this from the walls, which are of brick, laid in American common bond in a variation of four stretchers to one row of headers. The hip roof is covered with asphalt shingles. A shallow cross gable marks the central bay of the front facade. The projecting box cornice is supported by decorative brackets. Large chimneys, located within each gable end and at the peaks of the hip roof, have been removed.

Although altered with the addition of modern windows and aluminum baffle, the recessed entranceway to the main facade still retains original fabric, including flat pilasters supporting a bracketed, slightly projecting entablature, also supported with brackets like the cornice above it. Walking through a modern door, one enters the original recessed foyer, also pedimented, complete with beaded stained glass transom, sidelights, and a six-paneled door with original hardware.

Flanking the entranceway are extremely tall paired windows, separated by a thin wooden decorative strip, with 4/6 double hung sash. These have simple sills, with flat simply adorned lintels. Extremely fine wrought iron guards are attached to the base of each window. On the second floor, windows are similar, but smaller than those found below. These are also paired, utilizing 4/4 double hung sash, simple wooden sills, and slightly splayed brick lintels. In the peak of the cross gable is a small paired roundheaded arch window, each portion containing six panes. Sills and lintels are identical to those found on the second floor level. All other windows in each gable end are 6/6 double hung sash, also with splayed brick lintels.

A gabled addition, attached to the northwestern corner of the building appears to be contemporaneous to the main block. This 1½-story tall structure also on a stone foundation is also laid in common bond brick. A small interior end chimney is found within the northern gable end. A modern shed roofed addition of white glazed bricks abuts the east facade of the gabled addition and at its intersection with the south (rear) facade of the main block.

Entering the first floor from the foyer, one walks down a long hall which originally led through double doors to a music room to the east, and through single doors into a living and dining room, respectively, on the west. One of the double doors leading to the music room has been recently covered, thus allowing access only through one door. Double doors which opened between the living and dining rooms have been closed. Even though these changes have been made, the elliptical arches over each set of doors remain. Windows are all pegged and retain original interior shutters.

SEE CONTINUATION SHEET 1.

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY

RECEIVED

DATE ENTERED.

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

Hocking House
Allegany County
Maryland

CONTINUATION SHEET

ITEM NUMBER

7

PAGE

1

(DESCRIPTION, continued)

An open-string stairway perpendicular to the hallway is located in the southeast corner of the main block. It runs up two flights and serves the bedrooms above. An elliptical arched opening supported by engaged pilasters notes the stairway's intersection with the front hall.

Three mantels in the living and dining rooms are wooden, with simple molding. A fourth fireplace, on the eastern wall of the music room is more ornate. Constructed of slate, it has a decorative cartouche which supports a plain shelf. A fifth fireplace in the 1½-story addition has been covered with paneling.

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates c. 1855-1858 Builder/Architect unknown

Statement of Significance (in one paragraph)

Applicable Criteria: C

The Hocking House is significant for its architecture. Constructed between 1855-1858, the house is an outstanding example of the transitional Greek Revival-Italianate architecture in mid-nineteenth century Frostburg, a medium-sized town in western Allegany County. In its refined proportions and detailing, the house reflects the architectural sophistication of this town during the mid-nineteenth century. During this period, the expansion of local industries including lumber, coal, iron, and locomotive concerns, and improvements in transportation and communication made possible by the development of the National Road (Main Street), supported Frostburg's growth and affected the tastes of the town's citizens. The Hocking House reflects the increasing urbanity of this period; brick construction sets it apart from the majority of Frostburg's mid-nineteenth century dwellings, which are wooden; the Italianate influence apparent in its detailing and in its tall windows distinguishes it from most other houses of its period, whose design emphasizes the more conservative Greek Revival influence.

HISTORY AND SUPPORT

The Hocking House was built between 1855-1858 on a tract of land known as "The Hotel."¹ The land was part of the estate of Robert Clarke, Sr. one of the original settlers of the area. Clarke owned most of which is now the town of Frostburg and its surroundings.² His children, Mary and Robert, Jr. inherited the estate in 1794.³ Mary married George McCulloh who lost, through financial difficulties, his entire estate in 1821.⁴ After having the inheritance in trust for twenty-eight years, Mary regained the use of the land and began to sell lots.⁵

In 1855, the second of three quarter-acre lots which George McCulloh laid out on the northern side of the National Road "near the town of Frostburg" was sold to John Taylor and his wife, who erected this brick house sometime between 1855-1858.⁶ It is interesting to note that the house, now almost in the center of Frostburg, was outside the town's boundaries in 1865.⁷

The house was occupied by the Taylor family for a short time after its construction until 1858, when it was sold to the McCarty family, who lived there during the Civil War.⁸ Local tradition suggests that the house was a "stop" of the "underground railway", but no written records exist to substantiate this claim. The Kane family occupied the building from 1865 to 1901.⁹

Although research has not produced any information on the Taylor and Kane families, much is known about the Hocking family, who owned the property from 1901 to 1942. Mr. G. Dud Hocking lived in the house and worked in a series of local hardware stores and banks in Frostburg. Mr. G. Dud Hocking inherited his father's musical gatherings in town. He also published a number of church anthems, most notable "Come Holy Spirit" in 1896.¹⁰

UNITED STATES DEPARTMENT OF THE INTERIOR
HERITAGE CONSERVATION AND RECREATION SERVICE

FOR HCRS USE ONLY

RECEIVED

DATE ENTERED.

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

Hocking House
Allegany County
Maryland

CONTINUATION SHEET

ITEM NUMBER

8

PAGE

2

(SIGNIFICANCE, continued)

From 1942 to 1947, the building served as the lodge of the Royal Order of Moose. For twenty eight years until 1975, it was maintained as the clubhouse of the Young Men's Republican Club of Frostburg.¹¹ The building is now used as a private boarding house for students at Frostburg State College.

¹Allegany County Land Records, Liber 13, Folio 170.

²John T. Scharf, History of Western Maryland (Philadelphia: L.H. Everts Co.) p. 517.

³Ibid.

⁴Ibid., and Allegany County Equity #261.

⁵Allegany County Equity #807.

⁷Ibid., Liber 23, Folio 314.

⁸Ibid., Liber 17, Folio 537, and Liber 23, Folio 314.

⁹Ibid., Liber 23, Folio 314, Liber 90, Folio 2, Liber 194, Folio 200.

¹⁰Frostburg: A Centennial History, 1912, pg. 47. Frostburg Mining Journal, August 27, 1896.

9. Major Bibliographical References

AL-VII-A-005

SEE CONTINUATION SHEET #3

10. Geographical Data

Acreage of nominated property Less than one acre

Quadrangle name Frostburg

Quadrangle scale 1:24,000

UMT References

A

1	8	6	7	8	1	0	0	4	3	9	1	3	6	0
Zone			Easting				Northing							

B

Zone			Easting				Northing							

C

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification The property measures 92' along Main Street and is 165' deep; it is further described in the deed recorded in Deed Book 483, page 89. The nominated property consists of a single town lot.

List all states and counties for properties overlapping state or county boundaries

state	N/A	code	county	code
state		code	county	code

11. Form Prepared By

name/title Mark R. Edwards and David A. Dorsey

organization Maryland Historical Trust date August 1980

street & number 21 State Circle telephone (301) 269-2438

city or town Annapolis state Maryland 21401

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the Heritage Conservation and Recreation Service.

State Historic Preservation Officer signature [Signature] 10-28-82

title STATE HISTORIC PRESERVATION OFFICER date

For HCRS use only
I hereby certify that this property is included in the National Register
date

Keeper of the National Register

Attest: date

Chief of Registration

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

Hocking House

AND/OR COMMON

2 LOCATION

STREET & NUMBER

144 East Main Street

Sixth

CITY, TOWN

Frostburg

___ VICINITY OF

CONGRESSIONAL DISTRICT

STATE

Maryland

COUNTY

Allegany

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> MUSEUM
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> COMMERCIAL
<input type="checkbox"/> SITE	<input checked="" type="checkbox"/> PUBLIC ACQUISITION	<input checked="" type="checkbox"/> ACCESSIBLE	<input type="checkbox"/> EDUCATIONAL
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> ENTERTAINMENT
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> GOVERNMENT
		<input type="checkbox"/> NO	<input type="checkbox"/> INDUSTRIAL
			<input type="checkbox"/> MILITARY
			<input checked="" type="checkbox"/> TRANSPORTATION
			<input type="checkbox"/> OTHER: student housing

4 OWNER OF PROPERTY

NAME

Clarence E. Miller

Telephone #: 689-9271

STREET & NUMBER

140 East Main Street

CITY, TOWN

Frostburg

___ VICINITY OF

Maryland STATE Zip code

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE
REGISTRY OF DEEDS, ETC.

Allegany County Courthouse

Liber #: 483

Folio #: 89

STREET & NUMBER

30 Washington Street

CITY, TOWN

Cumberland

Maryland STATE Zip code

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

___ FEDERAL ___ STATE ___ COUNTY ___ LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

AL-111-A-005

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input checked="" type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input checked="" type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Hocking House is located at 144 East Main Street in Frostburg. This transitional Greek-Revival-Italianate building is square, two and one-half stories tall and three bays wide. Wall construction is of brick laid in American common bond in a variation of four stretchers to one row of headers. It rests on a high foundation of coursed ashlar stone with a plain water table. The medium hipped gable roof is covered with asphalt shingles with a central gable on the southwest. Eaves consist of a boxed cornice, soffit, and bed mould with many decorative brackets. Large inside end and interior chimneys apparent in old photographs have been removed.

The main entrance in the center of the southwestern facade includes a large pediment with scrolled brackets and flat pilasters on the exterior. The recessed entrance is also pedimented and includes a three part leaded stained glass transom, sidelights and a six paneled door with original hardware. Windows all have paneled interior shutters and are pegged. Pedimented first floor windows on the southwest are tall and narrow double four over six light sashes with mullion and false wrought iron balconies. Second floor windows on the southwest are double two over two light sashes with mullion and flat brick arches. In the central gable are double semicircular arched windows with six lights fixed, mullion, and semicircular brick arches. Other windows are wide six over six lights with radiating flat brick arches.

A gabled addition on the northwestern corner is one and one half stories. It is of brick with the same variation and rests on a stone foundation. Visible windows are three over three light eyebrows, an inside end chimney is of brick. A shed addition of white glazed brick abuts the gabled addition on the southeast.

CONTINUE ON SEPARATE SHEET IF NECESSARY

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION		
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE		
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN		
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER		
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION		
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)		
		<input type="checkbox"/> INVENTION				

SPECIFIC DATES ca. 1855

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

The Hocking House was built in 1855 on a tract of land known as "The Hotel" (1) The land was part of the estate of Robert Clarke, Sr. one of the original settlers of the area. Clarke owned most of what is now the town of Frostburg and its surroundings. (2) His children Mary and Robert, Jr. inherited the estate in 1794. (3) Mary married George McCulloh who through his financial problems almost lost the entire estate in 1821. (4) After having her inheritance in trust for twenty-eight years Mary regained the use of the land in 1849 and began to sell lots. (5)

In 1855 the second of three quarter acre lots which George McCulloh laid out on the northern side of the National Road" near the town of Frostburg" was sold to John Taylor and his wife who built the brick house.(6) It is interesting that the house, almost in the center of Frostburg was outside the town's boundaries in 1865.(7)

The house was occupied by the Taylors for a short time after its construction until 1858 when it was sold to the McCarty family who lived there during the Civil War. (8) Local tradition suggests that the house was a "stop" on the "underground railway" through tunnels in the basement but no written records support this idea. The Kane family occupied the building from 1865 until 1901, and between 1901 and 1942 it was the home of the Hocking family. (9) For five years it was the lodge of the Loyal Order of Moose and for twenty eight years until 1975 it was maintained as the club house of the Young Men's Republican Club of Frostburg. (10)

The Hocking House is a good example of transitional Greek Revival-Italianate architecture, a style that is somewhat rare in Allegany County. Italianate elements are more pronounced than the Greek Revival characteristics of the building. The square shape, heavily bracketed eaves, tall and narrow first floor principal facade windows, the low pitched hip roof, and semicircular arched second and one half floor windows of Hocking House are features common to the Italianate style. The subtler Greek

(cont.)

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Allegany County Land Records
 Scharf, John T., History of Western Maryland, Philadelphia: L.H. Everts Co.)1882
 Allegany County Equity

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 92'x72'x165'

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	COUNTY
STATE	COUNTY

11 FORM PREPARED BY

NAME / TITLE David A. Dorsey, Historic Sites Coordinator

ORGANIZATION Allegany County Historic Sites November 9, 1979

STREET & NUMBER 3 Pershing Street TELEPHONE 777-5944

CITY OR TOWN Cumberland STATE Maryland 21502

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
 The Shaw House, 21 State Circle
 Annapolis, Maryland 21401
 (301) 267-1438

Interior Description

The interior of the house is arranged with a central hallway with one room on each side. Wide entrance arches leading to these rooms have been closed. The larger room, on the northwest, has been converted into two rooms. Plaster walls have a high baseboard and wainscoting on the second floor. Windows have slight pediments and interior shutters. Second floor entrances have three light transoms.

An open stairway perpendicular to the hallway is of two flights and one landing with a decorated string and decorative balusters. An elliptical arched opening with flat columns leads to the stairway on the first floor.

Three fireplaces are wooden with simple moulding and located on chimney breasts parallel to walls. A fourth fireplace is marble with a decorative cartouche and spandrel. It has been converted to gas and has metal mouldings around the hearth. A fifth fireplace in the addition has been covered with paneling.

Revival influence is seen in the recessed main entrance which includes a horizontal transom and an exterior pediment supported by flat pilasters. The central gable positioned above the main entrance is reminiscent of pedimented Greek-Revival entrances. Simple interior mouldings and transomed interior doorways are also common to the style.

Although in fair condition the building is structurally sound. Fluted columns from the entrance and chimneys which were removed remain in storage. Hocking House stands as a physical reminder of the cultural awareness of the earlier residents of Allegany County.

- (1) Allegany County Land Records, Liber 13, Folio 170
- (2) John T. Scharf, History of Western Maryland (Philadelphia: L.H. Everts Co.)p.517
- (3) Ibid
- (4) Ibid, and Allegany County Equity #261
- (5) Allegany County Equity #807
- (6) Allegany County Land Records, Liber 13 , Folio 170 and Liber 23, Folio 314
- (7) Ibid, Liber 23, Folio 314
- (8) Ibid, Liber 17, Folio 537, and Liber 23, Folio 314
- (9) Ibid, Liber 23, Folio 314, Liber 90, Folio 2, Liber 194, Folio 200
- (10) Ibid, Liber 194, Folio 100 and Liber 483, Folio 89

6101045410

MARYLAND HISTORICAL TRUST WORKSHEET

A1-VII-005

NOMINATION FORM

for the NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

SEE INSTRUCTIONS

1. NAME					
COMMON: transitional Greek Revival - Italinat house					
AND/OR HISTORIC:					
2. LOCATION					
STREET AND NUMBER: 144 East Main Street					
CITY OR TOWN: Frostburg					
STATE: Maryland		COUNTY: Allegany			
3. CLASSIFICATION					
CATEGORY (Check One)		OWNERSHIP		STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District	<input checked="" type="checkbox"/> Building	<input type="checkbox"/> Public	Public Acquisition:	<input type="checkbox"/> Occupied	Yes:
<input type="checkbox"/> Site	<input type="checkbox"/> Structure	<input checked="" type="checkbox"/> Private	<input type="checkbox"/> In Process	<input checked="" type="checkbox"/> Unoccupied	<input type="checkbox"/> Restricted
<input type="checkbox"/> Object	<input type="checkbox"/> Both	<input type="checkbox"/> Being Considered	<input type="checkbox"/> Preservation work in progress	<input type="checkbox"/> No	<input type="checkbox"/> Unrestricted
PRESENT USE (Check One or More as Appropriate)					
<input type="checkbox"/> Agricultural	<input type="checkbox"/> Government	<input type="checkbox"/> Park	<input type="checkbox"/> Transportation	<input type="checkbox"/> Comments	
<input type="checkbox"/> Commercial	<input type="checkbox"/> Industrial	<input type="checkbox"/> Private Residence	<input type="checkbox"/> Other (Specify)	_____	
<input type="checkbox"/> Educational	<input type="checkbox"/> Military	<input type="checkbox"/> Religious	_____	_____	
<input type="checkbox"/> Entertainment	<input type="checkbox"/> Museum	<input type="checkbox"/> Scientific	_____	_____	
4. OWNER OF PROPERTY					
OWNER'S NAME: Frostburg Lodge No. 348, Order of Moose, Inc.					
STREET AND NUMBER: 210 West Main Street					
CITY OR TOWN: Frostburg			STATE: Maryland		
5. LOCATION OF LEGAL DESCRIPTION					
COURTHOUSE, REGISTRY OF DEEDS, ETC: Allegany County Courthouse					
STREET AND NUMBER: 30 Washington Street					
CITY OR TOWN: Cumberland			STATE: Maryland		
Title Reference of Current Deed (Book & Pg. #): 216-127					
6. REPRESENTATION IN EXISTING SURVEYS					
TITLE OF SURVEY:					
DATE OF SURVEY: <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> County <input type="checkbox"/> Local					
DEPOSITORY FOR SURVEY RECORDS:					
STREET AND NUMBER:					
CITY OR TOWN:			STATE:		

7. DESCRIPTION	
CONDITION	(Check One)
	<input type="checkbox"/> Excellent <input type="checkbox"/> Good <input checked="" type="checkbox"/> Fair <input type="checkbox"/> Deteriorated <input type="checkbox"/> Ruins <input type="checkbox"/> Unexposed
	(Check One)
	<input checked="" type="checkbox"/> Altered <input type="checkbox"/> Unaltered <input type="checkbox"/> Moved <input checked="" type="checkbox"/> Original Site
DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE	
<p>114 East Main Street in Frostburg, Allegany County, is located on the north side of the street near the intersection of Bowery Street.</p> <p>The house is a mid nineteenth century transitional Greek Revival-Italinate structure of brick construction with a dressed stone foundation, two and a half stories high, with a cross gable on the symmetrical facade (south side), and several brackets supporting the roof. The bricks of the principal facade (south side) are laid in American Common bond (4 stretchers and one headed). The center entranceway is recessed and flanked by flat plain pilasters with a bracketed entablature. The facade windows are double-hung wooden sashes and are grouped in pairs. The first floor windows have four-over-six sashes, heavy entablatures, and iron balconies. The double windows in the cross gable have round tops and single sashes of six lights.</p> <p>The building is structurally sound although rapidly deteriorating. The interior may have been altered in recent years when converted for use by a club.</p>	

SEE INSTRUCTIONS

8. SIGNIFICANCE			
PERIOD (Check One or More as Appropriate) <input type="checkbox"/> Pre-Columbian <input type="checkbox"/> 16th Century <input type="checkbox"/> 18th Century <input type="checkbox"/> 20th Century <input type="checkbox"/> 15th Century <input type="checkbox"/> 17th Century <input checked="" type="checkbox"/> 19th Century			
SPECIFIC DATE(S) (If Applicable and Known) <u>mid 19th</u>			
AREAS OF SIGNIFICANCE (Check One or More as Appropriate)			
<input type="checkbox"/> Aboriginal <input type="checkbox"/> Prehistoric <input type="checkbox"/> Historic <input type="checkbox"/> Agriculture <input checked="" type="checkbox"/> Architecture <input type="checkbox"/> Art <input type="checkbox"/> Commerce <input type="checkbox"/> Communications <input type="checkbox"/> Conservation	<input type="checkbox"/> Education <input type="checkbox"/> Engineering <input type="checkbox"/> Industry <input type="checkbox"/> Invention <input type="checkbox"/> Landscape <input type="checkbox"/> Architecture <input type="checkbox"/> Literature <input type="checkbox"/> Military <input type="checkbox"/> Music	<input type="checkbox"/> Political <input type="checkbox"/> Religion/Phi- losophy <input type="checkbox"/> Science <input type="checkbox"/> Sculpture <input type="checkbox"/> Social/Human- itarian <input type="checkbox"/> Theater <input type="checkbox"/> Transportation	<input type="checkbox"/> Urban Planning <input type="checkbox"/> Other (Specify) <hr/> <hr/> <hr/> <hr/> <hr/>
STATEMENT OF SIGNIFICANCE			
<p>144 East Main Street is a mid nineteenth century transitional Greek Revival-Italininate house. Of the two houses of this type that line East Main Street, 144 is one of a very few to retain much of its original external decoration. Obviously a fine house in its day, the building was converted for use by a club in the mid twentieth century. The present owner, who is contemplating demolition, purchased the property in July, 1974. It would be a great loss to Frostburg's architectural heritage since the facade is in such a near original state and the opportunity for restoration so good.</p>			

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Allegany County Land Records, Courthouse, Cumberland, Maryland.

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreege Justification:

The property measures approximately 92' x 165'.

SEE INSTRUCTIONS

11. FORM PREPARED BY

NAME AND TITLE:
 Ronald L. Andrews, Historic Site Survey

ORGANIZATION: Tri-County Council for Western MD, Inc. DATE: 4/29/75

STREET AND NUMBER:
 Algonquin Motor Inn, Suite 510

CITY OR TOWN: Cumberland STATE: Maryland

12. State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National State Local

 Signature

INVENTORY NO: _____

DATE: 11/7

REMODELING: Drastic, moderate, minor

AL-VII-A-005 *000*

NAME OF PROPERTY: _____

LOCATION OF PROPERTY: 144 E Main St

DIRECTION DWELLING FACES: SW

NAME OF OWNER: _____

ADDRESS: _____

STORIES: 1() 2() 3() 4() 5() 6() BAYS: 1() 2() 3() 4() 5() 6() 7() ()

WINGS, ADDITIONS: NE gable brick Shed brick on SE of ① Brick 3/3 lights on 1/4 limits 1 1/2 stories

DWELLING SHAPE: (square, cross, rectangular)

4x1 bricks

WALL CONSTRUCTION:

- () FRAME: Bevel, clapboard, weatherboard, wood shingles, board & batten (type?)
- () BRICK: Bond type - common, English, Flemish. Sketch variants. 4x1
- () STONE: Bond type - rubble, ashlar (random or regular), quoins-plain, rusticated
- () LOG
- () OTHER: Coverings

1st sw 4/6 narrow double windows
pegged ped. cement sills false

WALL FEATURES: Belt Course, Pilasters, Others wrought iron balcony

FOUNDATIONS: (High, Low, Brick, Stone) course ashlar

WATER TABLE: None, (Plain, Beveled, Moulded Brick)

wood sills eyma recta mould.

WINDOWS, TRIM, SHUTTERS: 1/1() 2/2() 6/6() 9/6() 9/9() other() stained glass
paneled interior shutters pegged () nailed () wide () narrow () mitred () pediment ()

ENTRANCE, DOORS: LOCATION: center sw wood - ped w/ deco brackets pilasters
HARDWARE: original() replaced() leaded stained glass transom
FAN LIGHT, TRANSOM, SIDE LIGHTS, PLAIN 3 light & sidelights boarded
Paneled, Vertical, Horizontal Boards up w/ panel. 6 panel door ped.

CORNICE, BARGE, EAVES: (crown, fascia, soffit, bed)
original() replaced() rafter ends, modillions, dentils, frieze, architrave

ROOF: Gable front, Gable flank, (Hip), Shed, Mansard, Gambrel, Flat, Dormers # _____
MATERIAL: wood shingles, slate, tin, asphalt; original() replaced()

PORCHES: SHAPE OF ROOF - shed() hip() gable()

CHIMNEYS: Number: 1 Brick() Stone() Corbeled() original() replaced()
Location: Flush end() Inside end() Outside end() Central() Interior()

ARCHES: Door & Windows: Keystone, Flat, Segmental, Semicircular

COMMENTS: Brick Vossair double 2 1/2 on 2nd sw
central gable 2 1/2 floor sw w/ double 6
light semi o arches -

USE: _____
SIGNIFICANCE: _____
DATE CONSTRUCTED: _____
CONDITION: _____

FLOOR PLAN:

- CENTRAL HALL: Two rooms, each side; double parlor, one side
- SIDE HALL: One room deep, two rooms deep
- IRREGULAR

STAIRWAYS:

- ENCLOSED: Single flight, two flights with landing
- OPEN: Single flight, two flights - one landing, three flights - two landings
- DOG-LEG
- DOG-LEG with WINDERS
- SPIRAL *deco string*
- ROUNDED
- SYMMETRICAL DIVIDED FLIGHTS *elliptical opening w/ pilasters columns*

WALL FINISH:

- PLASTER
- PANELED: original; replaced
- BOARD PARTITION: baseboard, cornice, chair rail, wainscot

FIREPLACES:

1 marble spandrel & cartouche - gas fixtures
metal mould
 NUMBER 4
 LOCATION: parallel to walls, diagonal *dinning breast.*
 MANTELS: wood mouldings, pilasters, columns, masonry, marble *mouldings*

DOORS: paneled, board and batten, flush
 HARDWARE: original; replaced

DOOR & WINDOW TRIM:

- PLAIN
- ARCHITRAVE
- SYMMETRIC with CORNER BLOCKS
- FLUTED
- FLUTED with CORNER BLOCKS
- ARCHED OPENINGS: eliptical, tudor

2nd Floor Simple ped
& 3 high transoms
high baseboard chair rail
interior windows ped.
shutters.

NOTES:

TITLE SEARCH

Hocking House

AL-~~VII~~-A-005VII

Allegany County Deed: Liber 483, Folio 89
 Grantee: Clarence E. Miller and Catherine D. Miller Date: December 4, 1975
 Grantor: William R. Carscaden and William R. Davis Consideration: \$8,500.00
 Notes: Grantors are co-receivers for Frostburg Republican Club-sold at public sale as a result of Equity Case #32028

Allegany County Deed: Liber 216, Folio 127 Date: July 10, 1947
 Grantee: Young Mens Republican Club of Frostburg
 Grantor: Frostburg Lodge #348 Loyal Order of of Moose, Inc.

Allegany County Deed: Liber 194, Folio 100 Date: June 16, 1942
 Grantee: The Loyal Order of Moose of Frostburg, Md. Inc.
 Grantor: G. Dud Hocking et al

Allegany County Wills:Liber S, Folio 456 Date: January 10, 1942
 Grantee: G. Dud Hocking and Willian Hocking
 Grantor: Mary E. Hocking
 Notes: Grantor conveyed $\frac{1}{2}$ interest -other half from from Catherine Hocking

Allegany County Deed: Liber 90, Folio 2 Date: October 24, 1901
 Grantee: Mary E. Hocking and Catherine Hocking Consideration: \$4,000.00
 Grantor: Harriet A. Kane

Allegany County Deed: Liber 23, Folio 314 Date: March 28, 1865
 Grantee: Harriet A. Kane Consideration: \$5,000.00
 Grantor: James McCarty and Margaret McCarty
 Notes: Described as being near the town of Frostburg on the National Road one of three lots laid out by George McColloh

Allegany County Deed: Liber 17, Folio 537 Date: November 25, 1858
 Grantee: James McCarty and Margaret McCarty Consideration: \$3,500.00
 Grantor: John W. Taylor and Ellen B. Taylor

Allegany County Deed: Liber 17, Folio 182 Date: July 23, 1858
 Grantee: Ellen B. Taylor Consideration: \$3,500.00
 Grantor: Mary McColloh

Allegany County Deed: Liber 17, Folio 181
Grantee: Mary McColloh
Grantor: John W. Taylor and Ellen B. Taylor

Date: July 23, 1858
Consideration: \$3,500.00

Allegany County Deed: Liber 13, Folio 170
Grantee: John W. Taylor and Ellen B. Taylor
Grantor: Mary McColloh
Notes: Includes map showing vacant lots laid out by George McColloh

Date: May 15, 1855
Consideration: \$5.00

Allegany County Deed: Liber 5, Folio 503

Grantee: Mary McColloh
Grantor: George McColloh and Samuel M. Semmes, trustee

Date: May 3, 1849

Notes: Trust transferred to Semmes as a result of Equity #807. McColloh's lands were put into trust in 1821 to pay debts- they had neglected to return lands so Mary McColloh went to court for her land after debts had been paid.

Allegany County Deed: Liber L. Folio 231

Grantee: Brice W. Howard, trustee
Grantor: George McColloh and Mary McColloh

Date: September 17, 1821

Notes: Lands put into trust in Equity #261 to pay debts of George McColloh

Allegany County Wills

Grantee: Mary Clarke and Robert Clarke, Jr.
Grantor: Robert Clarke, Sr.


Date: March 3, 1794

Notes: All his lands in Maryland, Virginia, and elsewhere deeded to children. Mary Clarke married George McColloh 1806.


1" = 1/8"

HOCKING HOUSE
144 E. MAIN ST
FROSTBURG, MD.

AL-VII-A-005




DRAWN BY: RICH MILLER
DATE: 11-10-79



Frostburg, MD - PA Quad
 U.S.G.S. 7.5 minute series
 1949
 scale 1:24000

Site No. Al-VII-005
 144 East Main Street



AL-VII-A-005

HOCKING HOUSE
ALLEGANY COUNTY, MD.

18-678100-4391360

4392
4391
ALLEGANY GROVE 2.4 MI.
CUMBERLAND 7 MI.



REBEL
STINGS

COUNTRY Jamboes
FEATURING THE COUNTRYMEN
REBEL STINGS & THE JAMBOES
MAY 4 DANCING 5
FREE BERRY BREAD
FREE COFFEE

FIGURE 40.

005
AL-VII-A-~~0000~~

144 EAST MAIN STREET, FROSTBURG
1



PROTESTANT
COLLEGE

FIGURE 40.

Hocking House

144 E. Main St.
Frostburg
Allegany Co., Md.
SE view
January, 1975

RONALD L. ANDREWS

AI - VII - 005



144 E. Main St.
Frostburg
Allegany Co., Md.
south side
January, 1975

RONALD L. ANDREWS

A1-1V-005



AL-VII-A-003

HACKING HOUSE

144 S MAIN FRASHER



AL-VII-A 003
Hocking House
149 E. Main Frostburg



AZ-VII-A-335
Hacking House
144 E. Main Frostburg



Hocking House

M- VII- A-005



Hooping House
A1-VII-A-005



1 Hochberg House

Al - VII - A - 005



Hocking House

A1-VII-A-005



Hocking House

A1- VII- A-005



Hocking House

At- VII - A 005



Hocking House
A1-411-A-005



Hocking House
A1-VII-A-005



Hocking House

A1-VII-A-005



Hocking House

AS-511-A-005



Hocking House

AS-VII-005-