

AA-1024
Catherine Bell Warfield House
Odenton
Private

1903-1905

The Catherine Bell Warfield House is important architecturally as a fine and highly intact example of an early-twentieth century vernacular farm dwelling. The two-and-a-half story, frame, gable-front-and-hipped-roof-wing, single-pile, l-shaped dwelling has a three-bay front facade spanned by a full-width, hipped-roofed screen porch. The house also has four outbuildings--a corn crib, garage, a shed (former smokehouse) and alleged pickers shanty.

The Catherine Bell Warfield House was built between 1903 and 1905 by Paul Allen Warfield, the husband of the woman for whom the house is named. The \$17,000 construction cost, as well as the fine quality of detail and woodwork, are indicators of the Warfield's affluence. Paul Allen Warfield was prominent in local and regional politics and a friend of Theodore Roosevelt.

AA-1024
Catherine Bell Warfield House
Odenton

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Western Shore

Chronological /Developmental Period: Industrial/Urban Dominance

Prehistoric/Historic Period Theme: Architecture

Resource Type:

Category: Building

Historic Environment: Rural

Historic Function and Use: Dwelling

Known Design Source: None

Maryland Historical Trust State Historic Sites Inventory Form

Survey No. AA-1024

Magi No.

DOE yes no

1. Name (indicate preferred name)

historic Catherine Bell Warfield House

and/or common

2. Location

street & number 999 Francis Station Road not for publicationcity, town Odenton vicinity of congressional district

state Maryland county Anne Arundel

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input checked="" type="checkbox"/> agriculture
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
	<input type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input checked="" type="checkbox"/> private residence
			<input type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Peppercorn Land Limited Partnership

street & number C/O Constellation Real Estate, 8815 Center Park Drive telephone no.:

city, town Columbia state and zip code: Maryland 21045

5. Location of Legal Description

courthouse, registry of deeds, etc. Anne Arundel County Courthouse liber 4306

street & number 7 Church Circle folio 632

city, town Annapolis state Maryland

6. Representation in Existing Historical Surveys

title

date federal state county local

depository for survey records

city, town state

7. Description

Survey No. AA-1024

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input checked="" type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input type="checkbox"/> altered	<input type="checkbox"/> moved date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Catherien Bell Warfield House is situated on a large lot at the terminus of Francis Station Road. The dwelling faces northeast and is surrounded by numerous mature oak and cedar trees. Heavy stands of trees and vegetation are located north and southwest of the house with uncultivated fields present on the other sides.

This two-and-a-half story, frame, gable-front-and-hipped-roof-wing dwelling has a three-bay front facade spanned by a full-width, hipped-roofed screen porch. The building's single-pile, L-shaped plan is augmented by a gable-roofed rear kitchen block. This is aligned parallel to the main axis of the building, rather than the typical perpendicularly placed ell arrangement, and only partially extends across the rear facade. A now enclosed, small one-story porch is located at the intersection of this block and the front wing. All sections rest on a thick, rubble ironstone foundation, and are original to the house.

The building's irregular roofline is the result of a complex relationship between different roof types. Only one dormer is present and is located on the front of the hipped-roof wing section. The cornice is boxed and features partial returns in the gables. Two narrow stove chimneys are present. One is internal, while the second is external the western wall. Interior stove placement suggests the former presence of another stack.

Fenestration consists of two-over-two double hung sash windows, and are arranged singly throughout the house. A two-story bay window is present on the eastern side of the house and the attic is illuminated by a small, two-over-two opening placed in the front gable, as well as the dormer window.

Although the house has irregular massing and a complex roofline construction, the plan is a traditional center-passage plan with the principal entrance located in the center of the northeast elevation. The building's floor plan features two rooms on either side of a center hall. Each room was heated by a stove located adjacent the interior wall. Communication between the front section and the kitchen wing is provided through an opening at the end of the hall, as well as through a doorway that connects the dining room (located on the left side of the hall) and the kitchen.

Except for the kitchen, interior trim is largely intact throughout the house. Door and window surrounds are deeply reeded with bull's eye corner blocks. The closed-string staircase has a square, reeded newel post, further embellished with carved rosettes and urn-shaped headpiece and a molded stringboard.

Four outbuildings are associated with the Catherine Bell Warfield House. These are a corn crib, garage, and a shed reported to be a former smokehouse. Oral tradition identifies the fourth building as a pickers shanty (used to house seasonal farm workers). All are in good to fair condition and display 20th century building techniques.

8. Significance

Survey No. AA-1024

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)


Specific dates	1903-05	Builder/Architect	Paul Allen Warfield					
Check:	Applicable Criteria:	<input type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/> C	<input type="checkbox"/> D			
	and/or							
	Applicable Exception:	<input type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/> C	<input type="checkbox"/> D	<input type="checkbox"/> E	<input type="checkbox"/> F	<input type="checkbox"/> G
	Level of Significance:	<input type="checkbox"/> national	<input type="checkbox"/> state	<input checked="" type="checkbox"/> local				

Prepare both a summary paragraph of significance and a general statement of history and support.

The Catherine Bell Warfield House was built between 1903 and 1905 and is named for the wife of the dwelling's builder and first occupant. The twelve-and-half acres of land where the house and associated buildings stand previously belonged to Francis and Hester Bell, the parents of Catherine Bell Warfield (1). The house was constructed by Catherine's husband, Paul Allen Warfield, a builder by trade, and cost \$17,000.

The house is architecturally significant as a fine and highly intact example of an early-twentieth century vernacular dwelling. Its historic integrity is enhanced by the retention of most of the original outbuildings. The house's size and high level of interior embellishment reflects the relative affluence of the Warfield family. Numerous members of Paul Allen Warfield's family held public office, serving as Justices of the Peace and local constables. Paul Allen Warfield is reported to have been very prominent and politically connected. Oral tradition claims Warfield was a friend of President Theodore Roosevelt, and that he made Roosevelt a walking stick from Chestnut grown on the property (2).

The Catherine Bell Warfield House and most outbuildings are in very good condition and retain a high level of historic integrity.



ODENTON
 USGS 7.5 minute series
 Scale: 1:24,000
 1957, photo revised 1979

Site Number: AA-1024
Site Name: Catherine Bell Warfield House
Location: 999 Francis Station Road, Odenton



AA-1024

Catherine Bell Warfield House

Anne Arundel Co, Maryland

Sherr. M. Marsh, Photographer

October 1996

Negative at Maryland SHPO

NE Perspective (camera facing SW)

Photo 1 of 6



AA-1024

Catherine Bell Warfield House

Anne Arundel CO, Maryland

Sherr. M. Marsh, photographer

October 1996

Negative at Maryland SHPO

Stair Hall

Photo 2 of 6



AA-1024

Catherine Bell Warfield House

Anne Arundel CO, Maryland

Sherril M. Marsh, photographer

October 1996

Negative at Maryland SHPO

Garage, Camera facing east

Photo 3 of 6



AA-1024

Catherine Bell Warfield House

Anne Arundel Co., Maryland


Sherril M. Marsh, photographer

October 1996

Negative at Maryland SHPU

Reported Pickers Shanti, camera facing South

Photo 4 of 6



AA-1024

Catherine Bell Warfield House

Anne Arundel Co, Maryland

Sherril M. Marsh, Photographer

October 1996

Negative at Maryland SHPO

outbuilding, camera facing south

photo 5 of 6



AA-1024

Catherine Bell Warfield House

Anne Arundel Co., Maryland

Sherr. M. Marsh, Photographer

October 1976

Negative at Maryland SHPO

SHED, camera facing west

Photo 6 of 6



14-1037

Admission to the ...

... ..

... ..

... ..

... ..

... ..



1. $\frac{1}{2} \times \frac{3}{4} = \frac{3}{8}$

2. $\frac{2}{3} \times \frac{5}{6} = \frac{10}{18} = \frac{5}{9}$

3. $\frac{1}{4} \times \frac{3}{5} = \frac{3}{20}$

4. $\frac{3}{7} \times \frac{2}{8} = \frac{6}{56} = \frac{3}{28}$



164-2

164-2-1

164-2-2

164-2-3

164-2-4

164-2-5

164-2-6

164-2-7

164-2-8

164-2-9

164-2-10

164-2-11



1-1-1-1

1-1-1-1

1-1-1-1

1-1-1-1



1. The first part of the document is a list of names and addresses.

2. The second part is a list of names and addresses.

3. The third part is a list of names and addresses.

4. The fourth part is a list of names and addresses.

5. The fifth part is a list of names and addresses.

6. The sixth part is a list of names and addresses.

7. The seventh part is a list of names and addresses.

8. The eighth part is a list of names and addresses.

9. The ninth part is a list of names and addresses.







PA 1004

Princess Hill

Anne Arundel County Md

Shelby Spivey, photographer

April 1992

MD 1000

views to property



15
20
25

30
35
40
45

50
55
60
65

65
70
75
80

80
85
90
95

95
100
105
110



AA 1024

International Maritime House

1000 ...

Shelby ... Photographer

April 1992

1000 ...

Wichita



17. 12. 19

Catherine Bell Victoria House

Arno Road, Sydney NSW

John G. G. G. G. G.

John G. G.

John G. G.

John G. G.



AA 1000

William Hill 17th Ave

James Amundson Court 100

photography

Apr 1000

MD CHPS

living room 1



FA 1021

Continued with Venn's $\frac{1}{2}$ "1021"

As a result of study MD

Study plan

April 2002

MD 111

Research



A

Woods Mill, Woodfield, Va.

1000 Hundred, 1000 ft. 1000

1000 ft. 1000 ft. 1000 ft.

April 10, 1900

1000 SHP

1000 ft.



15-1024

Calligraphy Bell Museum House

Handwritten notes

Handwritten notes

April 2002

SHIPO

bedroom 2



Annex

Catherine Bell Washington

Anne Arundel County MD

Friday 9:00 - 10:00 AM

April 2002

MD: HPO

Living room



AF 1024

Catherine Bell

Anne Arundel County MD

Shelby Springs, Chesapeake

April 2002

MS SHPC

dingy.com