

AA-110
Childs Residence
Millersville
Private

Circa 1840 with a
circa 1852 addition

The Childs Residence (George Miller Residence and Millersville store and Post Office) is located within the town of Millersville in central Anne Arundel County. The complex consists of three buildings: (1) a circa 1840 frame dwelling with a large, circa 1852, frame addition; (2) a circa 1840 frame smokehouse/dairy; and (3) a circa 1920 frame store. The dwelling consists of two sections: a circa 1840 one-room plan, 1-1/2 story structure with a rear ell from which extends a larger, circa 1852, two-story central passage, double-pile plan dwelling. The house rests on a low stone foundation, is covered with weatherboard siding, and has a standing seam metal gable roof. Exterior decorative trim is confined to the one-story facade porch. The interior plan and finishings have been maintained with minor alterations. The circa 1840 heavy timber-frame constructed smokehouse has a rosehead nail studded door. A dairy was added in the late 19th century. The store was constructed in 1920 after a fire destroyed an earlier one on the site.

The Childs Residence (George Miller Residence and Millersville Store and Post Office) is locally significant as the dwelling of the first Postmaster in Millersville, Anne Arundel County, and for having continuously served as the Post Office and community store for 130 years. Millersville, named for the first Postmaster, George Miller, was the first Post Office to be designated, in 1841, along the Annapolis & Elkridge Railroad (the A&E). Completed in 1840, the A&E was one of the earliest rail lines in this country, connecting Annapolis with the Washington branch of the B&O Railroad.

**United States Department of the Interior
National Park Service**

For NPS use only

**National Register of Historic Places
Inventory—Nomination Form**

received

date entered

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic George Miller Residence and Millersville Store and Post Office

and or common Childs Residence (preferred)

2. Location

street & number 1003 Cecil Avenue N/A not for publication

city, town Millersville N/A vicinity of Fourth Congressional District

state Maryland code 24 county Anne Arundel code 003

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input checked="" type="checkbox"/> commercial
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input checked="" type="checkbox"/> private residence
			<input type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property

name Isabella W. Childs

street & number 1003 Cecil Avenue

city, town Millersville N/A vicinity of state Maryland 21108

5. Location of Legal Description

courthouse, registry of deeds, etc. Anne Arundel County Courthouse

street & number Church Circle

city, town Annapolis state Maryland 21401

6. Representation in Existing Surveys

title Maryland Historical Trust
Historic Sites Inventory has this property been determined eligible? yes no

date 1978 federal state county local

depository for survey records Maryland Historical Trust, 21 State Circle

city, town Annapolis state Maryland 21401

7. Description

AA-110

Condition		Check one	Check one
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date <u>N/A</u>
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

Number of Resources		Number of previously listed National
Contributing	Noncontributing	Register properties included in this
<u> 3 </u>	<u> 0 </u> buildings	nomination: <u> 0 </u>
<u> 0 </u>	<u> 0 </u> sites	
<u> 0 </u>	<u> 0 </u> structures	Original and historic functions and
<u> 0 </u>	<u> 0 </u> objects	uses: residential, commercial
<u> 3 </u>	<u> 0 </u> Total	

DESCRIPTION SUMMARY:

The Childs Residence (George Miller Residence and Millersville store and Post Office) is located within the town of Millersville in central Anne Arundel County. It is situated in the southeast corner of the intersection of Cecil Avenue and Millersville Road (Rt. 175) and faces south, toward the abandoned Annapolis & Elkridge Railroad bed. The Childs Residence complex consists of three buildings: (1) a circa 1840 frame dwelling with a large, circa 1852, frame addition; (2) a circa 1840 frame smokehouse/dairy; and (3) a circa 1920 frame store. The dwelling consists of two sections: a circa 1840 one-room plan, 1½ story structure with a rear ell from which extends a larger, circa 1852, two-story central passage, double-pile plan dwelling. The house rests on a low stone foundation, is covered with weatherboard siding, and has a standing seam metal gable roof. Exterior decorative trim is confined to the one-story facade porch. The interior plan and finishings have been maintained with minor alterations. The circa 1840 heavy timber-frame constructed smokehouse has a rosehead nail studded door. A dairy was added in the late 19th century. The store was constructed in 1920 after a fire destroyed an earlier one on the site.

For General Description, see Continuation Sheet No. 1

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only

received

date entered

Childs Residence

Continuation sheet Anne Arundel County, MD

Item number

7

Page

1

GENERAL DESCRIPTION:

The dwelling is composed of two parts. The main block, constructed in circa 1852, is a two-story frame, slightly asymmetrical, central passage, double-pile plan house with a gable roof. At the east gable end, the main block abuts an earlier (circa 1840) one room plan, 1-1/2 story frame house with a slightly lower, 1-1/2 story rear ell. The main block is wider than the earlier wing, creating a broken facade line with the wing set back from the main block. The wing and ell are covered with more steeply pitched gable roofs than the main block.

The house rests on a low stone foundation. The exterior walls are covered with weatherboard siding which is painted white. The gable roofs are covered with standing-seam metal which is painted red. There are four interior gable end brick chimneys in the main block, and two in the east wing--one at the east gable end and another at the north gable end of the ell.

A one-story hip roof porch supported by eight turned posts with jig-sawn brackets runs across the facade of the house, following the broken facade line. The porch rests on a low brick foundation. In addition to the ornate brackets, the porch is embellished further with a dentilled cornice. A louvered screen closes the west end of the porch.

The principal entrance is located on the facade, south elevation, of the main block. It is composed of a six-panel door, flanked by four-pane sidelights. The rear entrance (north elevation) is covered by a door hood supported by diagonal bracing. There is an entrance in the wing on the facade which consists of a late 19th century arched-panel door. There are two entrances into the ell, both on the west elevation. The southernmost has a batten door. Just to the north of this entrance there is evidence of a seam in the wall, suggesting that the north end of the ell which measures two bays, one of which is an entrance, was either originally a separate structure which was later moved and joined to the house, or that it occupies its original site and the ell was extended to connect it with the house.

The windows in the house are predominately 6/6 sash windows with louvered shutters. The first story facade of the main block has large 2/2 sash windows which extend to the floor. The half-story level of the wing has 3/6 sash windows on the facade, and 6 pane casement windows on the remaining elevations.

Interior: The original floor plan of the house and finishings have been maintained, with minor alterations. The central passage of the main block contains the stair which rises along the west partition wall to the second floor.

AA-110

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only

received

date entered

Childs Residence

Continuation sheet Anne Arundel County, MD

Item number

7

Page

2

GENERAL DESCRIPTION (continued)

The stair is composed of a mid-19th century slender, tapered newel post and plain, square balusters, two per tread. The east rooms of the main block are joined by a wide opening which was originally closed off by double, six-panel doors. The mantel in the southeast room is a plain mid-19th century wooden mantel, similar to the other mantels in the house, with one exception. The northeast room of the main block has an ornate marbelized slate mantel centered on the east wall. Unfortunately, the center medallion piece is missing. The names of some members of the Cecil family are inscribed into the upper right corner of this mantel and into the windows in this room.

The floors in the main block on the first floor are the original wide pine boards.

There are two interesting pieces of hardware in the main block of the house. They are two Carpenter-type iron rim locks: one on the front door and the other on an interior batten door to the northwest room (now a kitchen). The front door lock is encased in a metal box and has a round brass patent seal which bears the arms of England surrounded by "Carpenter & Tildesley, Manufactures." The other lock is on a wide, beaded batten door which leads from the central passage at the north end into the northwest room. It is a wooden box lock with a similar brass seal which bears the same arms of England motif, but with "John Young, Patent" surrounding it. Two holes on either side of the keyhole indicate where a handle may once have been secured.

The east wing is accessed through a door in the northeast room of the main block. Centered on the east wall of this one-room section of the house is a plain mid-19th century mantel. To the left are built-in cupboards with raised panel doors. The ell is now used for storage. There is an interesting iron latch-lock that survives on the batten door in the ell.

Other buildings associated with this property include the circa 1840 smokehouse/dairy and a circa 1920 store. The smokehouse is a heavy timber frame constructed building which is covered with wide weatherboard siding, some of which appears to be the original riven boards. The building measures 12 feet 5 inches square and rests on a low stone foundation. The gable roof is covered with corrugated metal; a vestigial ventilator survives at the ridge line. The opening to the smokehouse is on the south elevation. It has a batten door covered with rosehead nails, which once added extra security for the meat stored inside. The door is hinged on the inside with metal strap hinges.

See Continuation Sheet No. 3

AA-110

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only

received

date entered

Childs Residence

Continuation sheet Anne Arundel County, MD

Item number

7

Page

3

GENERAL DESCRIPTION (continued)

The east elevation of the smokehouse has an entrance to the dairy. This appears to have been cut in at a later date. Steps lead down to the dairy just inside the door.


The circa 1920 store replaces an earlier one on this site. According to the present owner, the present store was built to look like the earlier one which burned. The present store, now used as an antique store, is a rectangular, 1-1/2 story building with the facade oriented toward the east gable end (toward Cecil Avenue). The facade entrance and one on the north elevation are covered with door hoods supported by diagonal bracing. Windows are 6/6 sash with louvered shutters.

Other outbuildings known to have stood on this property include a tobacco barn, chicken house, summer kitchen and a privy.

1. The Carpenter locks were invented in England by James Carpenter in 1800. An improvement was made with the assistance of John Young and patented in 1830. James Tildesley, the son-in-law of Carpenter, joined the firm in 1844. These locks were manufactured in large numbers by a number of firms in the second half of the 19th century and enjoyed widespread use in this country.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form



Childs Residence

Continuation sheet Anne Arundel County, MD Item number 8 Page 4

HISTORY AND SUPPORT:

Based on the architectural evidence, construction of the Childs Residence dwelling was begun in circa 1840. In 1839, John Miller of Anne Arundel County purchased 470 acres, parts of "Hammonds Inclosure" and "Abingdon" from Charles and Rebecca Waters, also of Anne Arundel County, for \$7005.00.¹ In 1852, John Miller sold a parcel known as "Millersville," comprising 13 5/8 acres, and including "the buildings erected thereon" to his son, George Miller, for \$3,000.00.²

U.S. population census data for 1840 reveals that John Miller was the head of a household of nine persons and was employed in agriculture. George Miller is listed separately, and was employed in commerce.³

U.S. Postmaster Appointment Records record that George Miller was appointed the first Postmaster of Millersville at the age of 20 on July 24, 1841.⁴ It seems apparent that George Miller constructed a dwelling (the earlier portion of the present Childs Residence) for himself on a portion of his father's land by 1840, and was operating a store, either from this structure or another that no longer survives. The purchase of land by John Miller, the construction of a dwelling, and the opening of George Miller's store coincide with the completion of the Annapolis and Elkridge Railroad in 1840. The dwelling stands just a few feet north of the A&E Railroad bed and proved to be an ideal location.

The frame smokehouse dates from this first construction period.

George Miller is listed in the 1850 census as a storekeeper with real estate valued at \$1,000.⁵ By this time he was married to Harriet R. Miller. Two years later, John Miller sold the "Millersville" parcel to his son, George Miller. Construction of the main block of the dwelling probably dates from this time.

During this period Millersville grew as a commercial center, rivaling the preeminence of Indian Landing on the Severn River as central Anne Arundel County's transportation center. Equity records for many of the surrounding farms cite the close proximity to both Millersville Station on the A&E Railroad and the wharf at Indian Landing. Martenet's map of 1860 shows a blacksmith shop, store and Post Office and George Miller's dwelling all located on Miller's property.

In 1860, after the death of John Miller, 75 acres of his property were conveyed by his children to his son, George Miller.⁶ Nine years later George Miller and his wife sold all of their property to Owen Cecil, a large landholder in the community.⁷ The Millers apparently left the area. Six days after Owen Cecil acquired the Miller property, his son Leonidas Cecil was appointed the Postmaster of Millersville.⁸ Leonidas Cecil received title to this property after his father's death in 1882. Owen Cecil died owning over 1,000 acres of land valued at \$30,000.00.

AA-110

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only

received

date entered

Childs Residence
Continuation sheet Anne Arundel County, MD

Item number

8

Page

5

HISTORY AND SUPPORT (continued)

According to the present owner, Leonidas Cecil moved the store from the house and constructed a new building in the late 19th century for the store and Post Office, directly west of the dwelling, across what is now Cecil Avenue.

After Leonidas Cecil's death in 1894, Nathan Childs, the father-in-law of the present owner, became the Postmaster in 1899.¹⁰ Thirteen years later, Helen S. Cecil, widow of Leonidas Cecil, sold the Millersville property to Nathan Childs.¹¹ In circa 1920, the store burned, but was rebuilt on the same site by Child's to resemble the original store built by Cecil.¹²

At Child's death in 1930, his son Nathan W. Childs inherited the property and continued the family tradition as Postmaster of Millersville.¹³ In the 1930s, the store was moved back into the dwelling and occupied the west side of the main block. In the 1940s it was again moved back into the store building across Cecil Avenue. The Childs offered a complete line of merchandise. The store and Post Office continued to operate until the retirement of Nathan W. Childs in 1972. His retirement brought to an end 130 years of continuous mercantile and postal service from this site.

Footnotes:

1. Anne Arundel County Land Records, Liber WSG No. 23, Folio 592.
2. Land Records, Liber NHG No. 1, Folio 101.
3. U.S. Population Census, 1840.
4. Record of Appointment of Postmasters, Vol. 9, 1832-1843, (Washington, D.C.: National Archives & Records Service, 1973).
5. U.S. Population Census, 1850.
6. Land Records, Liber NHG No. 9, Folio 28.
7. Land Records, Liber SH No. 3, Folio 225.
8. Record of Appointment of Postmasters, Vol. 24, 1857-1874.
9. Land Records, Liber Sh No. 22, Folio 558; Equity Records #908, Nov. 22, 1883.
10. Record of Appointment of Postmasters, Vol. 62, 1888-1930.
11. Land Records, Liber GW No. 92, Folio 4.
12. Interview with Isabella W. Childs, January 23, 1985.
13. Record of Appointment of Postmasters, Vol. 62, 1888-1930.

9. Major Bibliographical References

AA-110

See Footnotes, Continuation Sheet No. 5

10. Geographical Data

Acreeage of nominated property approx. 3 acres

Quadrangle name Odenton, MD

Quadrangle scale 1:24000

UTM References

A

1	8	3	5	7	3	3	0	4	3	2	4	1	3	0
Zone				Easting				Northing						

B

Zone				Easting				Northing						

C

Zone				Easting				Northing						

D

Zone				Easting				Northing						

E

Zone				Easting				Northing						

F

Zone				Easting				Northing						

G

Zone				Easting				Northing						

H

Zone				Easting				Northing						

Verbal boundary description and justification

Boundaries are depicted on the attached map; the nominated property, approximately 3 acres, encompasses all elements of the resource within their immediate setting.

List all states and counties for properties overlapping state or county boundaries

state N/A code county code

state code county code

11. Form Prepared By

name/title Ms. Donna Ware

Anne Arundel County Historic Sites Survey

organization Anne Arundel County Planning & Zon. date 1985

street & number Arundel Center telephone (301) 224-1270


city or town Annapolis state Maryland 21401

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature  date 1-30-86

title STATE HISTORIC PRESERVATION OFFICER date

For NPS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

Attest:

date


Chief of Registration


AA-110

Childs Residence

Anne Arundel Co., MD

Scale: 1" = 10'





AA-110
 Childs Residence
 Anne Arundel County, MD
 Scale 1" = 200'

----- National Register boundary, 1/86

Maryland Historical Trust State Historic Sites Inventory Form

on Nat. Reg.

1. Name (indicate preferred name)

historic George Miller Residence and Millersville Store and Post Office

and/or common Childs Residence (preferred)

2. Location

street & number 1003 Cecil Avenue not for publication

city, town Millersville vicinity of congressional district

state MD county Anne Arundel

3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input checked="" type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Isabella W. Childs

street & number 1003 Cecil Avenue telephone no.: (301) 923-3167

city, town Millersville state and zip code MD 21108

5. Location of Legal Description

courthouse, registry of deeds, etc. Anne Arundel County Courthouse liber

street & number Church Circle folio

city, town Annapolis state MD

6. Representation in Existing Historical Surveys

title Maryland Historical Trust Inventory

date 1978 federal state county local

depository for survey records Maryland Historical Trust

city, town Annapolis state MD

7. Description

Survey No. AA-110

<u>X</u> excellent	___ deteriorated	<u>X</u> unaltered	<u>X</u> original site	
___ good	___ ruins	___ altered	___ moved	date of move _____
___ fair	___ unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Description Summary:

The Childs Residence (George Miller Residence and Millersville store and Post Office) is located within the town of Millersville in central Anne Arundel County. It is situated in the southeast corner of the intersection of Cecil Avenue and Millersville Road (Rt. 175) and faces south, toward the abandoned Annapolis & Elkridge Railroad bed. The Childs Residence complex consists of three buildings: (1) a circa 1840 frame dwelling with a large, circa 1852, frame addition; (2) a circa 1840 frame smokehouse/dairy; and (3) a circa 1920 frame store.

The dwelling consists of two sections: a circa 1840 one-room plan, 1-1/2 story structure with a rear ell from which extends a larger, circa 1852, two-story central passage, double-pile plan dwelling. The house rests on a low stone foundation, is covered with weatherboard siding, and has a standing seam metal gable roof. Exterior decorative trim is confined to the one-story facade porch. The interior plan and finishings have been maintained with minor alterations. The circa 1840 heavy timber-frame constructed smokehouse has a rosehead nail studded door. A dairy was added in the late 19th century. The store was constructed in 1920 after a fire destroyed an earlier one on the site.

General Description:

The dwelling is composed of two parts. The main block, constructed in circa 1852, is a two-story frame, slightly asymmetrical, central passage, double-pile plan house with a gable roof. At the east gable end, the main block abuts an earlier (circa 1840) one room plan, 1-1/2 story frame house with a slightly lower, 1-1/2 story rear ell. The main block is wider than the earlier wing, creating a broken facade line with the wing set back from the main block. The wing and ell are covered with more steeply pitched gable roofs than the main block.

The house rests on a low stone foundation. The exterior walls are covered with weatherboard siding which is painted white. The gable roofs are covered with standing-seam metal which is painted red. There are four interior gable end brick chimneys in the main block, and two in the east wing--one at the east gable end and another at the north gable end of the ell.

A one-story hip roof porch supported by eight turned posts with jig-sawn brackets runs across the facade of the house, following the broken facade line. The porch rests on a low brick foundation. In addition to the ornate brackets, the porch is embellished further with a dentilled cornice. A louvered screen closes the west end of the porch.

The principal entrance is located on the facade, south elevation, of the main block. It is composed of a six-panel door, flanked by four-pane sidelights. The rear entrance (north elevation) is covered by a door hood supported by

8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates **Builder/Architect**

check: Applicable Criteria: A B C D
and/or
Applicable Exception: A B C D E F G

Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

Summary Paragraph

The Childs Residence (George Miller Residence and Millersville Store and Post Office) is locally significant as the dwelling of the first Postmaster in Millersville, Anne Arundel County, and for having continuously served as the Post Office and community store for 130 years. Millersville, named for the first Postmaster, George Miller, was the first Post Office to be designated, in 1841, along the Annapolis & Elkridge Railroad (the A&E). Completed in 1840, the A&E was one of the earliest rail lines in this country, connecting Annapolis with the Washington branch of the B&O Railroad.

Today Millersville is still a small crossroads village, surrounded by existing and proposed modern residential and industrial park development. The Childs Residence is the focal point of the town; it is the visual link to the past significance of this rural commercial center.

Architecturally, the Childs Residence is typical of the popular form of mid-19th century domestic architecture in America. It has been relatively unaltered and has retained its architectural integrity, giving a sense of time and place to the village of Millersville. Also noteworthy are the surviving smokehouse and rural store.

History and Support

Based on the architectural evidence, construction of the Childs Residence dwelling was begun in circa 1840. In 1839, John Miller of Anne Arundel County purchased 470 acres, parts of "Hammonds Inclosure" and "Abingdon" from Charles and Rebecca Waters, also of Anne Arundel County, for \$7005.00.¹ In 1852, John Miller sold a parcel known as "Millersville," comprising 13 5/8 acres, and including "the buildings erected thereon" to his son, George Miller, for \$3,000.00.²

U.S. population census data for 1840 reveals that John Miller was the head of a household of nine persons and was employed in agriculture. George Miller is listed separately, and was employed in commerce.³

#7. Continuation sheet, page 2.

diagonal bracing. There is an entrance in the wing on the facade which consists of a late 19th century arched-panel door. There are two entrances into the ell, both on the west elevation. The southernmost has a batten door. Just to the north of this entrance there is evidence of a seam in the wall, suggesting that the north end of the ell which measures two bays, one of which is an entrance, was either originally a separate structure which was later moved and joined to the house, or that it occupies its original site and the ell was extended to connect it with the house.

The windows in the house are predominately 6/6 sash windows with louvered shutters. The first story facade of the main block has large 2/2 sash windows which extend to the floor. The half-story level of the wing has 3/6 sash windows on the facade, and 6 pane casement windows on the remaining elevations.

Interior: The original floor plan of the house and finishings have been maintained, with minor alterations. The central passage of the main block contains the stair which rises along the west partition wall to the second floor. The stair is composed of a mid-19th century slender, tapered newel post and plain, square balusters, two per tread. The east rooms of the main block are joined by a wide opening which was originally closed off by double, six-panel doors. The mantel in the southeast room is a plain mid-19th century wooden mantel, similar to the other mantels in the house, with one exception. The northeast room of the main block has an ornate marbelized slate mantel centered on the east wall. Unfortunately, the center medallion piece is missing. The names of some members of the Cecil family are inscribed into the upper right corner of this mantel and into the windows in this room.

The floors in the main block on the first floor are the original wide pine boards.

There are two interesting pieces of hardware in the main block of the house. They are two Carpenter-type iron rim locks: one on the front door and the other on an interior batten door to the northwest room (now a kitchen). The front door lock is encased in a metal box and has a round brass patent seal which bears the arms of England surrounded by "Carpenter & Tildesley, Manufactures." The other lock is on a wide, beaded batten door which leads from the central passage at the north end into the northwest room. It is a wooden box lock with a similar brass seal which bears the same arms of England motif, but with "John Young, Patent" surrounding it. Two holes on either side of the keyhole indicate where a handle may once have been secured.

The east wing is accessed through a door in the northeast room of the main block. Centered on the east wall of this one-room section of the house is a plain mid-19th century mantel. To the left are built-in cupboards with raised panel doors. The ell is now used for storage. There is an interesting iron latch-lock that survives on the batten door in the ell.

Other buildings associated with this property include the circa 1840 smokehouse/dairy and a circa 1920 store. The smokehouse is a heavy timber frame constructed building which is covered with wide weatherboard siding, some of which appears to be the original riven boards. The building measures 12 feet 5 inches square and rests on a low stone foundation. The gable roof is covered

#7. Continuation sheet, page 3.

with corrugated metal; a vestigial ventilator survives at the ridge line. The opening to the smokehouse is on the south elevation. It has a batten door covered with rosehead nails, which once added extra security for the meat stored inside. The door is hinged on the inside with metal strap hinges.

The east elevation of the smokehouse has an entrance to the dairy. This appears to have been cut in at a later date. Steps lead down to the dairy just inside the door.

The circa 1920 store replaces an earlier one on this site. According to the present owner, the present store was built to look like the earlier one which burned. The present store, now used as an antique store, is a rectangular, 1-1/2 story building with the facade oriented toward the east gable end (toward Cecil Avenue). The facade entrance and one on the north elevation are covered with door hoods supported by diagonal bracing. Windows are 6/6 sash with louvered shutters.

Other outbuildings known to have stood on this property include a tobacco barn, chicken house, summer kitchen and a privy.

1. The Carpenter locks were invented in England by James Carpenter in 1800. An improvement was made with the assistance of John Young and patented in 1830. James Tildesley, the son-in-law of Carpenter, joined the firm in 1844. These locks were manufactured in large numbers by a number of firms in the second half of the 19th century and enjoyed widespread use in this country.

#8. Continuation sheet, page 2.

U.S. Postmaster Appointment Records record that George Miller was appointed the first Postmaster of Millersville at the age of 20 on July 24, 1841.⁴ It seems apparent that George Miller constructed a dwelling (the earlier portion of the present Childs Residence) for himself on a portion of his father's land by 1840, and was operating a store, either from this structure or another that no longer survives. The purchase of land by John Miller, the construction of a dwelling, and the opening of George Miller's store coincide with the completion of the Annapolis and Elkridge Railroad in 1840. The dwelling stands just a few feet north of the A&E Railroad bed and proved to be an ideal location.

The frame smokehouse dates from this first construction period.

George Miller is listed in the 1850 census as a storekeeper with real estate valued at \$1,000.⁵ By this time he was married to Harriet R. Miller. Two years later, John Miller sold the "Millersville" parcel to his son, George Miller. Construction of the main block of the dwelling probably dates from this time.

During this period Millersville grew as a commercial center, rivaling the preeminence of Indian Landing on the Severn River as central Anne Arundel County's transportation center. Equity records for many of the surrounding farms cite the close proximity to both Millersville Station on the A&E Railroad and the wharf at Indian Landing. Martenet's map of 1860 shows a blacksmith shop, store and Post Office and George Miller's dwelling all located on Miller's property.

In 1860, after the death of John Miller, 75 acres of his property were conveyed by his children to his son, George Miller.⁶ Nine years later George Miller and his wife sold all of their property to Owen Cecil, a large landholder in the community.⁷ The Millers apparently left the area. Six days after Owen Cecil acquired the Miller property, his son Leonidas Cecil was appointed the Postmaster of Millersville.⁸ Leonidas Cecil received title to this property after his father's death in 1882. Owen Cecil died owning over 1,000 acres of land valued at \$30,000.00.

According to the present owner, Leonidas Cecil moved the store from the house and constructed a new building in the late 19th century for the store and Post Office, directly west of the dwelling, across what is now Cecil Avenue.

After Leonidas Cecil's death in 1894, Nathan Childs, the father-in-law of the present owner, became the Postmaster in 1899.¹⁰ Thirteen years later, Helen S. Cecil, widow of Leonidas Cecil, sold the Millersville property to Nathan Childs.¹¹ In circa 1920, the store burned, but was rebuilt on the same site by Childs to resemble the original store built by Cecil.¹²

At Childs' death in 1930, his son Nathan W. Childs inherited the property and continued the family tradition as Postmaster of Millersville.¹³ In the 1930's, the store was moved into the dwelling and occupied the west side of the main block. In the 1940's, it was again moved back into the store building across Cecil Avenue. The Childs offered a complete line of merchandise. The store and Post Office continued to operate until the retirement of Nathan W. Childs in 1972. His retirement brought to an end 130 years of continuous mercantile and postal service from this site.

#8. Continuation sheet, page 3

1. Anne Arundel County Land Records, Liber WSG No. 23, Folio 592.
2. Land Records, Liber NHG No. 1, Folio 101.
3. U.S. Population Census, 1840.
4. Record of Appointment of Postmasters, Vol. 9, 1832-1843, (Washington, D.C.: National Archives & Records Service, 1973).
5. U.S. Population Census, 1850.
6. Land Records, Liber NHG No. 9, Folio 28.
7. Land Records, Liber SH No. 3, Folio 225.
8. Record of Appointment of Postmasters, Vol. 24, 1857-1874.
9. Land Records, Liber SH No. 22, Folio 558; Equity Records #908, Nov. 22, 1883.
10. Record of Appointment of Postmasters, Vol. 62, 1888-1930.
11. Land Records, Liber GW No. 92, Folio 4.
12. Interview with Isabella W. Childs, January 23, 1985.
13. Record of Appointment of Postmasters, Vol. 62, 1888-1930.

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

AND/OR COMMON Child's Residence

2 LOCATION

STREET & NUMBER

1003 Cecil Avenue
east side of Cecil Ave., south of Millersville Rd. intersect

CITY, TOWN

Millersville

— VICINITY OF

CONGRESSIONAL DISTRICT

STATE

COUNTY Anne Arundel

3 CLASSIFICATION

CATEGORY

- DISTRICT
- BUILDING(S)
- STRUCTURE
- SITE
- OBJECT

OWNERSHIP

- PUBLIC
- PRIVATE
- BOTH
- PUBLIC ACQUISITION**
- IN PROCESS
- BEING CONSIDERED

STATUS

- OCCUPIED
- UNOCCUPIED
- WORK IN PROGRESS
- ACCESSIBLE**
- YES: RESTRICTED
- YES: UNRESTRICTED
- NO

PRESENT USE

- AGRICULTURE
- COMMERCIAL
- EDUCATIONAL
- ENTERTAINMENT
- GOVERNMENT
- INDUSTRIAL
- MILITARY
- MUSEUM
- PARK
- PRIVATE RESIDENCE
- RELIGIOUS
- SCIENTIFIC
- TRANSPORTATION
- OTHER:

4 OWNER OF PROPERTY

NAME Esabella W. Childs

Telephone #:

STREET & NUMBER

CITY, TOWN Millersville

— VICINITY OF

STATE, zip code

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC

Anne Arundel

Liber #: 2335 map 30 p.160
Folio #: 705

STREET & NUMBER

CITY, TOWN

STATE

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

—FEDERAL —STATE —COUNTY —LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input checked="" type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Childs Residence is located on the east side of Cecil Ave., south of the intersection of Millersville Rd., facing south. The Annapolis and Elkridge Railroad, which began service in 1840, ran a few feet from the house.

The structure is a two part, two story, frame dwelling consisting of a five bay main section joined by a an L shaped wing on the east elevation. Both sections are covered with weatherboards.

A five bay screened porch with a slightly inclined shed roof extends across the south front, the west side of which is fitted with louvered blinds. A porch with a bracketed cornice extends across the south front of the wing and joins the main porch.

The main entrance is in the center bay front elevation. Another entrance, in the center bay north elevation, is sheltered by a small shed roof on brackets.

Most of the windows in the building contain 6/6 light double-hung sash flanked by louvered shutters. The exceptions occur on the west side of the house which was used as a store in the late 19th century. Windows in the west bays, south elevation contain 2/2 light sash, and there is one large window in the west bay, north elevation containing a large 6 light window. The window above it on the second floor is the same. The fenestration on the wing is irregular. The west elevation has an off center entrance with the north window close to it and the south window close to the end of the wall.

The house has a standing seam tin, gable roof with the ridge running east-west. An inside end chimney is on the north slope of the east end and the south slope of the west end of the roof. There are also small inside end chimneys on the east and south gable ends of the wing.

A large frame meathouse covered with clapboards and a steep gable roof is found near the northwest corner of the house.

Interior: The house has a center hall plan with two rooms on either side. The stairs are on the east wall of the hall. A fireplace with a marble finish slate mantel is on the east wall of the south room. The front (south) room of the wing has a fireplace with a simple mantel. Built into the wall on the north side of the mantel is a paneled cupboard (full length), and a small cupboard is found in the south side of the chimney breast.

Several very large trees, including an elm-that is thought to be 200 years old-and a maple are close to the house.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input checked="" type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES *mid 19th c.*

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

approximate;
 For ^{approximate;} 120 years the four Millersville post masters have lived with their familys in this house near the tracks (now gone) of the Annapolis and Elkridge Railroad. In very good condition , the house is atypical, rambling , mid 19th century farm house. An examination of the interior shows that the wing was probably built before the main section of the house. A large frame meat house stands slightly north of the house.

The town of Millersville grew up around the Annapolis and Elkridge Railroad. George Miller, who ^{is thought to have} built or had built this house, was the first postmaster(c. 1842-1869). The postoffice, which today stands across the street from the house, burned c. 1913, but it was rebuilt to look as it did before the fire. The second postmaster(c. 1896-1899), a Mr. L. De Cecil ran a store in the house, the large windows on the west side of the house showing its location. Nathan Childs became postmaster in 1900 and his son, Nathan, tokk over for his father in 1930. He held the job until 1972 when the postoffice closed and moved to a new location. Today the crossroads at MILLersville appears much as it probably did when the Annapolis and Elkridge Railroad came through and the post office was a freight office and general store.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

interview with Mrs. Nathan Childs, Sept. 19, 1978

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	COUNTY
STATE	COUNTY

11 FORM PREPARED BY

NAME / TITLE	Marion Morton Carroll-Historic Sites Surveyor	
ORGANIZATION	A.A. Ct. Dept. of Planning and Zoning	DATE Oct. 1978
STREET & NUMBER	Arundel Center	TELEPHONE
CITY OR TOWN	Annapolis	STATE

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

0201105504
 AA-17-N-a
 (map 15)
 (110)

MARYLAND HISTORICAL TRUST WORKSHEET

NOMINATION FORM
 for the
 NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

AA-110

SEE INSTRUCTIONS

1. NAME

COMMON:
 Childs residence

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER:
 South side of Millersville Road at Cecil Avenue

CITY OR TOWN:
 Millersville

STATE: Maryland COUNTY: Anne Arundel

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object	<input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure <input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both	<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No

PRESENT USE (Check One or More as Appropriate)

<input type="checkbox"/> Agricultural	<input type="checkbox"/> Government	<input type="checkbox"/> Park	<input type="checkbox"/> Transportation	<input type="checkbox"/> Comments
<input type="checkbox"/> Commercial	<input type="checkbox"/> Industrial	<input checked="" type="checkbox"/> Private Residence	<input type="checkbox"/> Other (Specify)	_____
<input type="checkbox"/> Educational	<input type="checkbox"/> Military	<input type="checkbox"/> Religious	_____	_____
<input type="checkbox"/> Entertainment	<input type="checkbox"/> Museum	<input type="checkbox"/> Scientific	_____	_____

4. OWNER OF PROPERTY

OWNER'S NAME:
 Esabella W. Childs

STREET AND NUMBER:
 Millersville

CITY OR TOWN: STATE: 21108
 Maryland

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC:
 Anne Arundel County Courthouse

STREET AND NUMBER:
 Annapolis Maryland

CITY OR TOWN: STATE:
 Map #30, AD #4, Parcel #160 Liber/folio #2335/705

Title Reference of Current Deed (Book & Pg. #):

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:

DATE OF SURVEY: Federal State County Local

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN: STATE:

7. DESCRIPTION	
CONDITION	(Check One)
	<input type="checkbox"/> Excellent <input checked="" type="checkbox"/> Good <input type="checkbox"/> Fair <input type="checkbox"/> Deteriorated <input type="checkbox"/> Ruins <input type="checkbox"/> Unexposed
	(Check One)
	<input type="checkbox"/> Altered <input checked="" type="checkbox"/> Unaltered <input type="checkbox"/> Moved <input checked="" type="checkbox"/> Original Site
DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE	
<p>This 2 story frame house is located at the center of the Millersville community which grew up around the Annapolis and Elkridge Railroad in the mid - 19th century. There are stores, the station, a post office and a school marked on the 1878 map at this cross-roads.</p> <p>The house has a center hall plan, with end chimneys and an A-roof. There is a smaller wing at its east end and there is a large frame meat house just north of the house.</p>	

SEE INSTRUCTIONS

8. SIGNIFICANCE			
PERIOD (Check One or More as Appropriate)			
<input type="checkbox"/> Pre-Columbian	<input type="checkbox"/> 16th Century	<input type="checkbox"/> 18th Century	<input type="checkbox"/> 20th Century
<input type="checkbox"/> 15th Century	<input type="checkbox"/> 17th Century	<input checked="" type="checkbox"/> 19th Century	
SPECIFIC DATE(S) (If Applicable and Known)			
AREAS OF SIGNIFICANCE (Check One or More as Appropriate)			
<input type="checkbox"/> Aboriginal	<input type="checkbox"/> Education	<input type="checkbox"/> Political	<input type="checkbox"/> Urban Planning
<input type="checkbox"/> Prehistoric	<input type="checkbox"/> Engineering	<input type="checkbox"/> Religion/Phi-	<input type="checkbox"/> Other (Specify)
<input type="checkbox"/> Historic	<input type="checkbox"/> Industry	losophy	_____
<input type="checkbox"/> Agriculture	<input type="checkbox"/> Invention	<input type="checkbox"/> Science	_____
<input type="checkbox"/> Architecture	<input type="checkbox"/> Landscape	<input type="checkbox"/> Sculpture	_____
<input type="checkbox"/> Art	<input type="checkbox"/> Architecture	<input type="checkbox"/> Social/Human-	_____
<input type="checkbox"/> Commerce	<input type="checkbox"/> Literature	itarian	_____
<input type="checkbox"/> Communications	<input type="checkbox"/> Military	<input type="checkbox"/> Theater	_____
<input type="checkbox"/> Conservation	<input type="checkbox"/> Music	<input type="checkbox"/> Transportation	_____
STATEMENT OF SIGNIFICANCE			

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Empty box for Major Bibliographical References.

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

APPROXIMATE ACREAGE OF ~~NOMINATED~~ PROPERTY: *86 acres*

Acreage Justification:

Large empty box for Acreage Justification.

SEE INSTRUCTIONS

11. FORM PREPARED BY

NAME AND TITLE:
Amy Hiatt

ORGANIZATION: **Anne Arundel County Office of Planning and Zoning** DATE: **August 1975**

STREET AND NUMBER:
Arundel Center

CITY OR TOWN: **Annapolis** STATE: _____

12. State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National State Local


Signature


AA-110

Childs Residence

Anne Arundel Co., MD


Scale: 1" = 10'






AA-110
Childs Residence
Anne Arundel County, MD
Scale 1" = 200'

----- National Register boundary



Odenton, MD
USGS 7.5 Minute Series
Scale 1:24,000
1957; photorevised 1979

AA-110
Childs Residence
1003 Cecil Avenue
Millersville



4326
4323
4322
4321

(ROUND BAY)
5662 II SE

7.3 MI TO U.S. 140

18-357330-
4324130

CHILDS
RESIDENCE

ANNE ARUNDEL
COUNTY,
MARYLAND

AA-110



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Facade - S. Elev and E. Elev.



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Facade - S. elev.



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

East elev.



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

West elev. of ell



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Dwelling, smokehouse/dairy,
looking S.W.



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Dwelling & smokehouse/dairy,

looking east



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

View of facade porch, looking
west



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Entrance into East wing, facade,
S. elev.



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Entrance into main block,

S. elev.



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Int.: Central passage, main
block; view toward S. elev.



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Int.: Central passage, main
block; view to stair & N.
partition



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Int.: Marbleized mantel, E.
wall, 1st floor, N.E. room,
main block



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Int.: Mid-19th century mantel,

E. wall, 1st fl., S.E. room,

main block



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Int.: Mantel & cupboards,
east wall, east wing



AA-110


Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Int.: Carpenter & Tildesley
lock, front door, S. wall,
main block

THE UNIVERSITY OF CHICAGO PRESS



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Int.: Wood lock on batten door,
main block, N.W. room



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Int: Latch lock on batten door,
west wall of ell wing



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Circa 1920 Store - facade -
east elev.



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Smokehouse/dairy, S. elev. and
east gable end



AA-110

Childs Residence

Anne Arundel County, MD

D. Ware, 4/85

Smokehouse door with rosehead
nails, S. elev.



AA-110
Child's Residence
Millersville
South front
Marion Carroll
Sept. 1978



ANTIQUES

AA-110
Childs Residence
Millersville
Post office build.
Marion Carroll
Sept. 1978



10

(map 15)

CA-17-N-a

Childs residence

North Elevation

amb. 5/75