

**CAPSULE SUMMARY**  
**Moreau M. Casler House (AA-1125)**  
**219 King George Street**

The building at 219 King George Street was originally constructed in the period between 1923 and 1927 for photographer, Moreau M. Casler. The modest stucco building, a relatively early example of an integrated garage within the main block of the dwelling, was the last of six dwellings to be erected on the western side of King George Street between Maryland Avenue and Martin Street. Historically associated with both the William Paca House and the Hammond-Harwood House, the property was subdivided into individual lots by Martin Smith in 1902. Since its construction, the single-family dwelling has been owned and primarily occupied by just three families.

The Colonial Revival style dwelling, L-shaped in plan, consists of a principal two-story block and rear garage wing, both of which are covered with character-defining and intersecting gambrel roofs. The roofs are clad with asphalt shingles and feature two brick chimneys. This stucco-clad wood frame dwelling is sited with its end wall facing King George Street and its main facade facing the driveway, creating an inner court.

MARYLAND HISTORICAL TRUST  
MD INVENTORY OF HISTORIC PROPERTIES

Inventory No. AA-1125

=====

1. Name of Property

=====

historic name Moreau M. Casler House

common/other name \_\_\_\_\_

=====

2. Location

=====

street & number 219 King George Street not for publication \_\_\_\_\_

city or town Annapolis vicinity \_\_\_\_\_ state Maryland code MD

county Anne Arundel code 003 zip code 21401

=====

3. State/Federal Agency Certification N/A

=====

4. National Park Service Certification N/A

=====

5. Classification

=====

Ownership of Property (Check all that apply)

private  
 public-local  
 public-State  
 public-Federal

Category of Property (Check only one box)

building(s)  
 district  
 site  
 structure  
 object

Number of Resources within Property

Contributing		Noncontributing	
<u>1</u>	_____	_____	buildings
_____	_____	_____	sites
_____	_____	_____	structures
_____	_____	_____	objects
<u>1</u>	_____	_____	Total

Is this property listed in the National Register?

Yes  Name of Listing Annapolis Historic District

No \_\_\_\_\_

Maryland Inventory of Historic Properties  
Moreau M. Casler House  
219 King George Street  
Annapolis, Maryland

Inventory No. AA-1125  
Page 2

=====  
6. Function or Use  
=====

Historic Functions (Enter categories from instructions)

Cat: DOMESTIC Sub: Single Dwelling

Current Functions (Enter categories from instructions)

Cat: DOMESTIC Sub: Single Dwelling

=====  
7. Description  
=====

Architectural Classification (Enter categories from instructions)

Colonial Revival

Materials (Enter categories from instructions)

foundation Brick

roof Cross Gambrel: Asphalt Shingles

walls Stucco

other \_\_\_\_\_

Narrative Description (Describe the historic and current condition of the property.)

See Continuation Sheet No. 7-1

=====  
8. Statement of Significance  
=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties  
Moreau M. Casler House  
219 King George Street  
Annapolis, Maryland

Inventory No. AA-1125  
Page 4

=====  
Areas of Significance (Enter categories from instructions)

Architecture  
\_\_\_\_\_  
\_\_\_\_\_

Period of Significance 1923-1948  
\_\_\_\_\_  
\_\_\_\_\_

Significant Dates 1923-1927  
\_\_\_\_\_  
\_\_\_\_\_

Significant Person (Complete if Criterion B is marked above)  
\_\_\_\_\_

Cultural Affiliation Undefined  
\_\_\_\_\_  
\_\_\_\_\_

Architect/Builder Unknown  
\_\_\_\_\_  
\_\_\_\_\_

Narrative Statement of Significance (Explain the significance of the property.)

See Continuation Sheet No. 8-1

Maryland Inventory of Historic Properties  
Moreau M. Casler House  
219 King George Street  
Annapolis, Maryland

Inventory No. AA-1125  
Page 5

=====  
9. Major Bibliographical References  
=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Anne Arundel County Land and Will Records. Anne Arundel County Courthouse and Maryland State Archives, Annapolis, Maryland.

Archives of Maryland, XXXVIII, "Act for Keeping Good Rules and Orders," 1696.

Papenfuse, Edward and Jane McWilliams. "Southern Urban Society After the Revolution: Annapolis, Maryland, 1782-1786." Final Report for NEH Grant #H69-0-178, Historic Annapolis Foundation, 1969.

Record Group 29, "Records of the Bureau of the Census." 1880, 1900, 1910, and 1920 Census; Anne Arundel County, Maryland.

Warren, Marion E. and Mame Warren, The Train's Done Been and Gone, Annapolis, MD: M.E. Warren, 1976.

Maps and Drawings

Magnus, Charles. Bird's Eye View of the City of Annapolis, 1864, Reproduced 1967.

Sachse, Edward. Bird's Eye View of the City of Annapolis, circa 1858. Maryland Hall of Records, MdHR G 1213-349.

Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1903, 1908, 1913, 1921, 1930, and 1954 updated.

Maryland Inventory of Historic Properties  
Moreau M. Casler House  
219 King George Street  
Annapolis, Maryland

Inventory No. AA-1125  
Page 6

=====  
10. Geographical Data  
=====

Acreage of Property 4350 Square Feet

**Verbal Boundary Description (Describe the boundaries of the property.)**

The property designated as 219 King George Street is located on Parcel 1364 as shown on Grid 11, Map 4Z in the City of Annapolis.

**Boundary Justification (Explain why the boundaries were selected.)**

The building has been historically associated with this property since its construction between 1923 and 1927.

=====  
11. Form Prepared By  
=====

name/title L. Trieschmann & K. Williams, Architectural Historians  
organization Traceries date February 2, 1998  
street & number 5420 Western Avenue telephone 301/656-5283  
city or town Chevy Chase state MD zip code 20815  
=====

12. Property Owner  
=====

name Wade and C.H. DeWeese  
street & number 219 King George Street telephone \_\_\_\_\_  
city or town Annapolis state MD zip code 21401  
=====

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. AA-1125

Section 7 Page 1

Moreau M. Casler House

name of property

Annapolis, Maryland

county and state

=====  
The two-story stuccoed dwelling at 219 King George Street was constructed between 1923 and 1927 in a Colonial Revival style. The dwelling, L-shaped in plan, consists of a principal block and rear garage wing, both of which are covered with character-defining and intersecting gambrel roofs. The roofs are clad with asphalt shingles and feature two brick chimneys. This house provides a relatively early example of an integrated garage and illustrates the architectural transition from freestanding garages at the rear of lots to those included within the main house. Prior to the 1920s, garages were invariably separate back buildings; after 1930, they are almost always connected or built under the house. The dwelling is sited with its end wall facing King George Street and its main facade facing the driveway, creating an inner court.

The facade (northeast elevation) facing King George Street consists of the two-bay-wide stuccoed end wall of the main block of the gambrel-roofed house. A one-story hipped roof sunroom with banks of eight-light sash abuts the first story of this end wall, while two 6/6 windows articulate the second story. An exterior end brick chimney is located between the two windows on this wall. The sunroom, occupying the site of an original wing, appears relatively contemporary in design. It is set upon a low concrete foundation and its hipped roof is clad with standing seam metal.

The northwest elevation of the main block, facing the driveway of the house, is three bays wide with a pedimented entry porch occupying the center bay on the first story and 6/6 windows defining the other bays. The central entry porch consists of narrow columns supporting the side walls of an entablature and, in turn, an open vaulted pediment. The second story of the house, located in the front slope of the steep gambrel, has three shed dormers with 6/6 windows. All of the windows have square-edged trim.

The southeast elevation of the main block has two windows on the first story, including a pair of 6/6 windows on center of the wall and one 6/6 casement window in the rear bay. The basement has two three-light windows.

The garage wing intersects the southwest end wall of the main house and projects beyond it, forming the L-shaped footprint of the building. This rear wing consists of a garage on the first story and living space above. The northeast elevation of the garage wing, facing the driveway, has double garage door openings in the first story and a single 6/6 shed dormer in the front slope of the gambrel roof above. The garage doors have cross bracing in their

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. AA-1125

Section 7 Page 2

Moreau M. Casler House  
name of property  
Annapolis, Maryland  
county and state

=====

lower half and eight-light windows. The northwest end wall of the garage wing is two bays deep and has an overhanging second story. The bays on both the first and second stories have two 6/6 windows.

The southwest elevation of the house features a contemporary two-story addition spanning the central section of the rear wall and leaving one bay of the gambrel end wall of the main block of the house exposed. This end wall has two 10-light replacement doors on the first story and a single 6/6 window in the gambrel end at the second story. The addition consists of banks of eight-light casement windows which take advantage of the southern exposure of the house.

The interior of the building was not accessible for survey.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. AA-1125

Section 8 Page 1

Moreau M. Casler House  
name of property  
Annapolis, Maryland  
county and state

=====  
The building at 219 King George Street was originally constructed in the period between 1923 and 1927 for photographer Moreau M. Casler. The modest Colonial Revival style building, a relatively early example of an integrated garage within the main block of the dwelling, was the last of six dwellings to be erected on the western side of King George Street between Maryland Avenue and Martin Street. Historically associated with both the William Paca House and the Hammond-Harwood House, the property was subdivided into individual lots by Martin Smith in 1902. Since its construction, the single-family dwelling has been owned and primarily occupied by just three families.

**PROPERTY HISTORY**

The property on which 219 King George Street stands was one of four lots that historically was associated with both the William Paca House at 186 Prince George Street and the Hammond-Harwood House at 19 Maryland Avenue. Together with Lots 92, 93, and 104, Lot 105 was devised in 1726 by Thomas Bordley to his sons, John and Thomas, Jr. By 1761, the property was under the ownership of William Stevenson, the second husband of Isabella Bordley. Stevenson conveyed all four lots with their improvements to Thomas Johnson, Jr. for L290 in 1762. Johnson, a prominent Maryland planter, subdivided the property and conveyed Lots 94 and 105 separately to Edward Lloyd for L180 in 1763. Within ten years, Lloyd had traded Lots 92 and 105 with Matthias Hammond in exchange for Lots 90 and 107. Hammond, also a prominent planter, increased his neighborhood holdings to the north when he purchased Lots 91 and 106 from Denton Hammond in 1774. That same year, Hammond improved the spacious corner property by having a traditional five-part plan dwelling erected at 19 Maryland Avenue to the designs of William Buckland. Lot 105 provided the impressive dwelling with an expansive rear yard that was fashionably landscaped.

Never having lived in the imposing house, Hammond bequeathed the property to his nephew John Hammond upon his death in 1786. Philip Hammond sold the dwelling, utilized only as rental property, to Ninan Pinkney for \$3,000. Within a year, Pinkney conveyed it to Annapolis Mayor Jeremiah T. Chase, one-time resident of the dwelling. Upon the death of Chase in 1828, the property was bequeathed to Matilda Chase McBlair, who devised it to lawyer William and Hester Anne Harwood (the granddaughter of Jeremiah Chase). The property was maintained by the Harwoods until their deaths in 1900 and 1890, respectively. Hester Anne and Lucy, the unmarried daughter of the Harwoods, inherited the Hammond-Harwood

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. AA-1125

Section 8 Page 2

Moreau M. Casler House

name of property

Annapolis, Maryland

county and state

=====  
House in 1900.

In 1901, Hester Anne and Lucy Harwood subdivided the property, conveying the rear portion along King George Street to Martin M. and Catherina Smith for \$6,000. Smith, a baker and confectioner with commercial space at 108-110 Main Street (AA-538 and AA-540), immigrated to Annapolis via Washington, DC from Liebenspin, Germany in the 1860s. The undeveloped property along King George Street was subsequently subdivided by Smith for a profit, with four narrow lots being sold individually by 1906. In 1902, Smith was assessed \$1,680 for the unimproved property along King George Street that he still owned.

**BUILDING HISTORY**

A fifth lot, located between 217 and 221 King George Street (AA-1124 and AA-1126) was retained by Smith until January of 1919. Designated as 219 King George Street, the unimproved lot was purchased by Moreau M. and Berth Casler. Moreau Casler, born in New York about 1859, was the son of Marcus Casler and Mary Heath Casler, who owned and occupied the properties at 199, 201, and 203-205 Hanover Street (AA-1103 and AA-524). Moreau Casler, who worked as a photographer, eventually committed suicide by shooting himself.

The Caslers improved the small tract on King George Street by having the L-shaped, Colonial Revival style dwelling erected in the period between 1923 and 1927. Unlike many of the single-family dwellings in this urban area of the city, the stucco-clad structure encompassed a one-car garage with glazed and paneled wood doors. The Caslers retained ownership of the wood frame dwelling until June of 1927, when it was conveyed to Henry C. and Gertrude Mack Dinger. The city directory notes that the Dingers occupied the single-family dwelling at 219 King George Street, being assessed \$6,997 in 1929 for the property. Educated as an attorney, Dinger transferred ownership of the property in 1945 to his daughter, Helen J. Dinger. As Helen Dinger continued to reside in New York City, the King George Street property was leased as rental property. The city directory documents that R.B. Pirie occupied the building in 1949.

In November of 1950, Helen Josephine Dinger was declared incompetent, and William W. Townshend, Jr. was appointed as trustee for her estate. Townshend, empowered to convey the Annapolis

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. AA-1125

Section 8 Page 3

Moreau M. Casler House  
name of property  
Annapolis, Maryland  
county and state

=====

property, sold the dwelling at 219 King George Street to Wade and Catherine H. DeWeese of Long Island, New York. Nine months later, the DeWeeses enlarged their holdings to include the rear portion of property fronting on Cumberland Court (laid in May 1950).

A retired Captain in the United States Navy, Wade DeWeese and his wife, Catherine, have occupied the building at 219 King George Street for almost fifty years. Catherine DeWeese also owned rental property at 210 King George Street (AA-1136) between 1967 and 1970.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. AA-1125

Moreau M. Casler House

name of property

Annapolis, Maryland

county and state

=====  
HISTORIC CONTEXT:

**Geographic Organization:** Western Shore

**Chronological/Development Period (s):**

Industrial/Urban Dominance (1870-1930)  
Modern Period (1930-present)

**Prehistoric/Historic Period Theme (s):**

Architecture, Landscape Architecture, and  
Community Planning

**RESOURCE TYPE(S)**

**Category:** Building

**Historic Environment:** Urban

**Historic Function (s):** DOMESTIC/Single Dwelling

**Known Design Source:** Unknown

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. AA-1125

Moreau M. Casler House  
name of property  
Annapolis, Maryland  
county and state

=====  
**Chain of Title for 219 King George Street:**

- 1718: James Parrock, executor of Benjamin Fordham, to Thomas Bordley  
Land Records of Anne Arundel County  
Liber IB 2 Folio 498
- 1726: Thomas Bordley devised to sons John and Thomas Bordley, Jr.  
Lots 92, 93, 104, and 105  
Will Records of Anne Arundel County  
Liber L 19 Folio 99
- 1747: Thomas Bordley, Jr. devised his portion of the four lots to brother John Bordley  
Will Records of Anne Arundel County  
Liber L 25 Folio 310
- 1757: John Bordley devised to wife Isabella Bordley  
Will Records of Anne Arundel County  
Liber L 31 Folio 212
- 1761: Isabella Bordley Stevenson to Robert Sterling  
Land Records of Anne Arundel County  
Liber BB 2 Folio 563
- 1762: Robert Sterling to William Stevenson, husband of Isabella Bordley Stevenson  
Land Records of Anne Arundel County  
Liber BB 2 Folio 601
- 1762: William Stevenson to Thomas Johnson, Jr.  
Lots 92, 93, 104, and 105  
Land Record of Anne Arundel County  
Liber LB Folio 276
- 1763: Thomas Johnson, Jr. to Edward Lloyd  
Lots 92 and 105 with houses  
Land Records of Anne Arundel County  
Liber BB 3 Folio 77

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. AA-1125

Moreau M. Casler House  
name of property  
Annapolis, Maryland  
county and state

- =====
- 1772: Edward Lloyd to Matthias Hammond  
Lots 92 and 105 with houses  
Land Records of Anne Arundel County  
Liber IB 3 Folio 405
- 1774: Denton Hammond to Matthias Hammond  
Lots 91 and 106  
Land Records of Anne Arundel County  
Liber IB 4 Folio 361
- 1786: Matthias Hammond bequeathed to nephew  
John Hammond  
Will Records of Anne Arundel County  
Liber NH 5 Folio 122
- 1789: John Hammond to brother Philip Hammond  
Land Records of Anne Arundel County  
Liber NH 5 Folio 122
- 1810: Philip Hammond to Ninan Pinkney  
Land Records of Anne Arundel County  
Liber NH 15 Folio 619
- 1811: Ninan Pinkney to Jeremiah T. Chase  
Land Records of Anne Arundel County  
Liber WSG 1 Folio 141
- February 6, 1865: Matilda Chase McBlair devised to William  
and Hester Anne Harwood  
Will Records of Anne Arundel County  
Liber RID 1 Folio 43
- February 11, 1871: William and Hester Anne Harwood  
bequeathed to daughters Hester Anne, II  
and Lucy Harwood  
Land Records of Anne Arundel County  
Liber SH 5 Folio 277
- July 2, 1873: Alexander Randall, Trustee, to Hester  
Anne, II and Lucy Harwood  
Land Records of Anne Arundel County  
Liber SH 7 Folio 514


MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. AA-1125

Moreau M. Casler House  
name of property  
Annapolis, Maryland  
county and state

=====

August 1, 1901:	Hester Anne, II and Lucy Harwood to Martin M. and Katherine Smith Land Records of Anne Arundel County Liber GW 22 Folio 33
January 13, 1919:	Martin M. Smith, widower, to Moreau M. and Bertha Casler Land Records of Anne Arundel County, Liber WNW 9 Folio 426
June 28, 1927:	Moreau M. and Bertha Casler to Henry C. and Gertrude Mack Dinger Land Records of Anne Arundel County, Liber FSR 14 Folio 173
April 30, 1945:	Henry C. Dinger, attorney, to Helen J. Dinger Land Records of Anne Arundel County, Liber JHH 331 Folio 224
January 22, 1951:	William W. Townshend, Jr., Trustee for the estate of Helen Josephine Dinger, Incompetent (appointed November 11, 1950), to Wade and Catherine H. DeWeese Land Records of Anne Arundel County, Liber JHH 611 Folio 291
October 22, 1951:	Frederick McNair, III, to Wade and Catherine H. DeWeese Frontage along Cumberland Court Land Records of Anne Arundel County, Liber JHH 650 Folio 317



INSET  
1" = 100'

AA-1125

219 KING GEORGE ST

UNITED STATES NAVAL ACADEMY  
P. 1400



MAP OF ANNAPOLIS, No.4-6  
Maryland Department of Assessments and Taxation  
1967; Revised 1991  
Scale 1' = 200'



AA-1125

219 KING GEORGE ST

ANNAPOLIS, MD

TRACERIES

FEB 1998

MD SHPO

LOOKING SOUTH

1/OF 4



AA-1125

219 KING GEORGE ST

ANNAPOLIS, MD

TRACERIES

FEB 1998

MD SHPO

LOOKING SW

2 OF 4



AA-1125

219 KING GEORGE ST  
ANNAPOLIS, MD

TRACERIES

APRIL 1998

MD SHPO

LOOKING SW

3 OF 4



AA-1125

219 KING GEORGE ST

ANNAPOLIS, MD

TRACERIES

FEB 1998

MD SHPO

LOOKING NORTH

4 OF 4

MARYLAND HISTORICAL TRUST  
 21 STATE CIRCLE  
 SHAW HOUSE  
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET  
 Individual Structure Survey Form

SURVEY NUMBER: <u>AA 1125</u>	
NEGATIVE FILE NUMBER:	
UTM REFERENCES: Zone/Easting/Northing	
U.S.G.S. QUAD. MAP:	
PRESENT FORMAL NAME:	
ORIGINAL FORMAL NAME:	
PRESENT USE: SF Res	
ORIGINAL USE: SF Res	
ARCHITECT/ENGINEER:	
BUILDER/CONTRACTOR:	
PHYSICAL CONDITION OF STRUCTURE: Excellent ( ) Good (x) Fair ( ) Poor: ( )	
THEME:	
STYLE: Colonial Revival	
DATE BUILT: 1897-1903	

COUNTY: Anne Arundel
TOWN: Annapolis
LOCATION: 219 King George
COMMON NAME:
FUNCTIONAL TYPE: RES Map 34 Par 101
OWNER: DeWeese Wade & C M
ADDRESS: 219 King George Annapolis, MD 21401
ACCESSIBILITY TO PUBLIC: Yes (x) No ( ) Restricted ( )
LEVEL OF SIGNIFICANCE: Local (✓) State ( ) National ( )

GENERAL DESCRIPTION:

Structural System

- Foundation: Stone ( ) Brick (x) Concrete ( ) Concrete Block ( )
- Wall Structure
  - Wood Frame: Post and Beam ( ) Balloon (x)
  - Wood Bearing Masonry: Brick ( ) Stone ( ) Concrete ( ) Concrete Block ( )
  - Iron ( ) D. Steel ( ) E. Other:
- Wall Covering: Clapboard ( ) Board and Batten ( ) Wood Shingle ( ) Shiplap ( )  
 Novelty ( ) Stucco (x) Sheet Metal ( ) Aluminum ( ) Asphalt Shingle ( )  
 Brick Veneer ( ) Stone Veneer ( ) Asbestos Shingle ( )  
 Bonding Pattern: Other:
- Roof Structure
  - Truss: Wood (x) Iron ( ) Steel ( ) Concrete ( )
  - Other:
- Roof Covering: Slate ( ) Wood Shingle ( ) Asphalt Shingle (x) Sheet Metal ( )  
 Built Up ( ) Rolled ( ) Tile ( ) Other:
- Engineering Structure:
- Other:

Appendages: Porches ( ) Towers ( ) Cupolas ( ) Dormers ( ) Chimneys (x) Sheds ( ) Ells (x)  
 Wings (x) Other:

Roof Style: Gable ( ) Hip ( ) Shed ( ) Flat ( ) Mansard (x) Gambrel ( ) Jerkinhead ( )  
 Saw Tooth ( ) With Monitor ( ) With Bellcast ( ) With Parapet ( ) With False Front ( )  
 Other:

Number of Stories: 2

Number of Bays: 2 x 2

Approximate Dimensions: 20 x 52

Entrance Location: Mosth side elevation

THREAT TO STRUCTURE: No Threat (x) Zoning ( ) Roads ( ) Development ( ) Deterioration ( ) Alteration ( ) Other:
--

LOCAL ATTITUDES: Positive ( ) Negative ( ) Mixed ( ) Other:
---

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

Gambrel roof "L" plan cottage with shed roof wall dormers; flat shallow cornices with returns; entrance at right elevation with good pedimented porch; simple molded trim at windows and door; rear section of "L" is garage at first floor; one story porch at street end infilled with full height casements.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

Moderate example of 20thC Dutch Colonial of importance to streetscape.

REFERENCES:

MAP: (Indicate North In Circle)




SURROUNDING ENVIRONMENT:  
Open Lane( )Woodland( )Scattered Buildings( )  
Moderately Built Up( X)Densely-Built Up( )  
Residential(X)Commercial( )  
Agricultural( )Industrial( )  
Roadside Strip Development( )  
Other:

RECORDED BY: Russell Wright

ORGANIZATION: Historic Annapolis, Inc

DATE RECORDED: Aug. 1983



MARYLAND

AVENUE

GEORGE STREET

GEORGE STREET

STREET

FRANCIS ST

RCLE

CORNHILL STREET

FLEET STREET

PINKNEY STREET

EAST STREET

MARKET ST.

MARTIN

RANDALL STREET

CONPROMISE

AA 1125  
ANNAPOLIS HIST. DIST.

SCALE IN FEET  
0 50 100 200 300 400 500





219 King George

AA 1125

Annapolis, Anne Arundel County

Russell Wright July, 1982

Maryland Historical Trust,

Annapolis, Maryland

NW Elevation/camera facing SE