

CAPSULE SUMMARY
46 Cornhill Street
(AA-1312)

The dwelling at 46 Cornhill Street along with 48 Cornhill Street, is one of a pair of buildings constructed in 1878 on Cornhill Street by prominent African American physician William Bishop. The dwelling served as rental property throughout much of its history and survives as a good example of mid-to late 19th-century worker class rental property in Annapolis.

The modest-sized dwelling is a two-story, two-bay, side-entry building of frame construction with the facade sheathed in German siding. It is set upon a slightly raised brick pier foundation, and is covered with a low gable roof clad with standing seam metal. A brick chimney (wood burning stove flue) projects from off-center of the gable roof. A two-story frame ell, clad with asbestos shingles, is set upon a brick pier foundation and extends off the rear wall of the main block of the house. A one-story shed roof extension abuts this two-story ell.

MARYLAND HISTORICAL TRUST
MD INVENTORY OF HISTORIC PROPERTIES

Inventory No. AA-1312

=====

1. Name of Property

=====

historic name _____
common/other name _____

=====

2. Location

=====

street & number 46 Cornhill Street not for publication _____
city or town Annapolis vicinity _____ state Maryland code MD
county Anne Arundel code 003 zip code 21401

=====

3. State/Federal Agency Certification N/A

=====

4. National Park Service Certification N/A

=====

5. Classification

=====

Ownership of Property (Check all that apply)

- private
- public-local
- public-State
- public-Federal

Category of Property (Check only one box)

- building(s)
- district
- site
- structure
- object

Number of Resources within Property

Contributing		Noncontributing	
<u>1</u>	_____	_____	buildings
_____	_____	_____	sites
_____	_____	_____	structures
_____	_____	_____	objects
<u>1</u>	_____	<u>0</u>	Total

Is this property listed in the National Register?

Yes Name of Listing Annapolis Historic District
No

Maryland Inventory of Historic Properties
46 Cornhill Street
Annapolis, Maryland

Inventory No. AA-1312
Page 2

=====
6. Function or Use
=====

Historic Functions (Enter categories from instructions)

Cat: Domestic Sub: Single Dwelling

Current Functions (Enter categories from instructions)

Cat: Domestic Sub: Single Dwelling

=====
7. Description
=====

Architectural Classification (Enter categories from instructions)

Vernacular

Materials (Enter categories from instructions)

foundation Brick

roof Gable: Standing Seam Metal

walls Wood: German Siding (facade)

other Asbestos Shingles

Narrative Description (Describe the historic and current condition of the property.)

See Continuation Sheet No. 7-1

=====
8. Statement of Significance
=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties
46 Cornhill Street
Annapolis, Maryland

Inventory No. AA-1312
Page 4

=====
Areas of Significance (Enter categories from instructions)

Architecture

Social/Cultural

Period of Significance 1878

pre 1885

1930-1954

Significant Dates 1878

pre 1885

1930-1954

Significant Person (Complete if Criterion B is marked above)

Cultural Affiliation Undefined

Architect/Builder Unknown

Narrative Statement of Significance (Explain the significance of the property.)

See Continuation Sheet No. 8-1

=====
9. Major Bibliographical References
=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Anne Arundel County Land Records. Anne Arundel County Courthouse and Maryland State Archives, Annapolis, Maryland.

"Historic View of Annapolis from State House", circa 1876-1877, in possession of William McWilliams, Jr, owner of 41 State Circle.

Johnson, Bakari, Research Historian, "Inventory of African American Historical and Cultural Resources, Anne Arundel County, Maryland," Annapolis, MD: Maryland commission on African American History and Culture, December 1994, Updated April 1995

Papenfuse, Edward. *In Pursuit of Profit, The Annapolis Merchants in the Era of the American Revolution, 1763-1805.* Baltimore, MD: The Johns Hopkins University Press, 1975.

Papenfuse, Edward and Jane McWilliams. "Southern Urban Society after the Revolution: Annapolis, Maryland, 1782-1786." Final Report for NEH Grant #H69-0-178, Historic Annapolis Foundation, 1969.

Record Group 29 "Records of the Bureau of the Census." 1880, 1900, 1910 and 1920 Census; Anne Arundel County, Maryland.

Radoff, Morris L., *The State House at Annapolis*, Annapolis, MD: 1972.

Smith, Richard W., Research Prepared on Cornhill Street. Not published: December 20, 1995.

Warren, Marion E. and Mame Warren, *The Train's Done Been and Gone*, Annapolis, MD: M.E. Warren, 1976.

Maps and Drawings

Bird's Eye View of the City of Annapolis, Charles Magnus, 1864, Reproduced, 1967. *Bird's Eye View of the City of Annapolis*, Edward Sachse, ca. 1858. (Maryland Hall of Records, MdHR G 1213-349)

Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1897, 1903, 1908, 1913, 1921, 1930, 1954.

=====
10. Geographical Data
=====

Acreege of Property Less than one acre

Verbal Boundary Description (Describe the boundaries of the property.)

The building at 46 Cornhill Street is located on Parcel 866 on Tax Map 4-6, dated 1991.

Boundary Justification (Explain why the boundaries were selected.)

The building at 46 Cornhill Street has been historically associated with Parcel 866 since its construction in 1878.

=====
11. Form Prepared By
=====

name/title L. Trieschmann & K. Williams, Architectural Historian
organization Traceries date March 12, 1996
street & number 5420 Western Avenue telephone 301/656-5283
city or town Chevy Chase state MD zip code 20815
=====

12. Property Owner
=====

name Bettilee Covert
street & number 46 Cornhill Street telephone 280-5545
city or town Annapolis state MD zip code 21401
=====

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-1312

Section 7 Page 1

46 Cornhill Street

name of property

Annapolis, Maryland

county and state

=====
The modest two-story, two-bay frame house at 46 Cornhill Street is one of a pair of dwellings built in 1878. Located on the north side of Cornhill Street, mid-block between State Circle and the Market House, the pair of houses are separated from each other on the first story by a covered passageway leading to the rear yards. The building fronts directly on Cornhill Street with a sizable side yard along the east elevation.

EXTERIOR DESCRIPTION

The dwelling at 46 Cornhill Street is a two-story, two-bay, side-entry building of frame construction with the facade sheathed in German siding. Set upon a slightly raised brick pier foundation, the house is covered with a low gable roof, clad with standing seam metal. A brick chimney (wood burning stove flue) projects off-center from the gable roof. A two-story frame ell, clad with asbestos shingles, is set upon a brick pier foundation and extends from the rear wall of the main block of the house. A one-story ell stood on the site as early as 1885 according to the Sanborn Map and is most likely still part of the existing structure. The second floor was added to the between 1930 and 1954. A one-story shed roof extension abuts this two-story ell.

The facade (south elevation) is divided into two bays with a side entry located in the west end bay. This entry has a fifteen-light replacement door set beneath a single-light transom, and is finished by square-edged trim and projecting cornice. A single 2/2 window is located next to the door on the first story and two 2/2 windows are found in the second story. All of the windows have square-edged surrounds with a projecting cornice. The passageway between the 46 Cornhill and its twin at 48 Cornhill is closed to the street by a wooden gate.

The east elevation is sheathed with asbestos shingles and includes the east elevation of the main block of the house and the rear ell. The main block has one 6/6 window on the first story and two 2/2 windows on the second story. The surrounds on the second story windows are identical to those found on the facade, while the first story window has molded surrounds. The ell has one 6/6 window in the first story and one 2/2 window in the second story.

Neither the rear or the interior of the house were accessible for survey.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-1312

Section 8 Page 1

46 Cornhill Street
name of property
Annapolis, Maryland
county and state

=====
The pair of dwellings at 46-48 Cornhill Street, constructed in 1878, are typical examples of the domestic rowhouse building form constructed principally as worker-class rental property in Annapolis during the mid- to late 19th century. The two-story dwelling at 46 Cornhill Street, along with its twin at 48 Cornhill Street, was constructed by prominent African American physician William Bishop. The building, which traditionally served as rental property, was sold separately by the Bishop heirs from 48 Cornhill Street in 1909. Currently, the buildings at 46-48 Cornhill Street contribute to the historical and cultural understanding of the city's working class environment in the late 19th and early 20th centuries.

SITE HISTORY

The land presently designated as 46 Cornhill Street was originally a portion of the land surveyed and set aside for Governor Francis Nicholson in 1696. Nicholson, influential in the town planning of Annapolis, directed that the land located to the south of the State House, encompassed by State Circle, Main, Francis, and East streets be specifically set aside for use as a garden, vineyard, and site of a summer house.¹ In 1699, Francis Nicholson left Maryland to serve as the Governor of Virginia, but retained part of his Annapolis properties until his death in 1728.

In 1704 following the destruction of all Annapolis land records, the portion of Nicholson's land that extended from the State House to the Market Space was claimed by Thomas Bordley. The Bordley family retained ownership of the entire tract of land until 1770, when it was sold to Charles Wallace (1717-1812).

Charles Wallace, by then a prominent member of the merchant community, began his career in the 1740s as a staymaker² and, in 1771, joined forces with Joshua Johnson and John Davidson, creating the mercantile firm of Wallace, Davidson, and Johnson. In addition to his mercantile business, Wallace involved himself in real estate and building ventures. In 1771, Wallace began the construction of the third State House and provided the supplies necessary in the

¹ "Act for Keeping Good Rules and Order." *Archives of Maryland*, XXXVIII, 1696. It is not certain how the land was actually used.

² From St. Anne's Parish Register, 1: 79, as quoted in Edward C. Papenfuse, *In Pursuit of Profit*, (Baltimore, MD: The Johns Hopkins University Press, 1975), p. 234-5, footnote 35.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-1312

Section 8 Page 2

46 Cornhill Street

name of property

Annapolis, Maryland

county and state

=====
building's construction. Unwilling to continue to work on the building for lack of what he considered to be adequate financial compensation, Wallace resigned as principal contractor in December 1779.³ Wallace died in 1812, leaving personal property appraised at \$23,774.20 and extensive real estate in Annapolis and Anne Arundel County.⁴

PROPERTY HISTORY

Upon the completion of his subdivision of Fleet and Cornhill streets, Wallace began to sell and lease lots on his property. Many of the lots were improved by the construction of single dwellings, taverns, and stables. On May 5, 1772, Charles Wallace leased the property corresponding today with the frame houses at 46-48 Cornhill Street to Robert Lambert.

The lease for the unimproved property, designated as Lot 5, was conveyed numerous times between 1772 and 1847, when the lease and property title were eventually sold to Richard S. Hardesty. Although Hardesty was beginning to subdivide Lot 5, the property at 46-48 Cornhill Street remained unimproved. In 1854, Hardesty conveyed the two parcels to George Taylor.

Little is known about George Taylor, except that he died in 1866 and that he built the brick dwelling at 89 East Street (AA-489). Following his death, Taylor's estate was devised between his two sons. To his son, Lemuel M. Taylor, he bequeathed "...the dwelling house and lot of ground fronting on East and Fleet streets...."⁵ Acting as executor for his father's estate, George M. Taylor conveyed the property fronting on Cornhill Street to the Trustees of the Methodist Episcopal Church. The deed of sale indicates that prior to his death George Taylor had agreed to convey the property for \$5000 in February 1866; however, the sale was not realized until after his death.

³ A letter written by Charles Wallace explaining his reasons for not finishing the state house is reprinted in Morris L. Radoff, *The State House at Annapolis* (Hall of Records Commission, Department of General Services: Annapolis, MD., 1972), p 87.

⁴ Papenfuse, pp 234-235.

⁵ Will Liber SH 5 Folio 593

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-1312

Section 8 Page 3

46 Cornhill Street
name of property
Annapolis, Maryland
county and state

=====

BUILDING HISTORY

The day after receiving ownership of the unimproved property, the M.E. Church sold it to African American William Bishop. Bishop died about 1872, naming his wife as executor. By 1878, ownership of the property was referred to the courts in Equity Case 659: Bishop versus Bishop. The court ruled on November 8, 1878 that Dr. William Bishop receive ownership of the two dwelling houses at 46-48 Cornhill Street. The buildings do not appear on G.M. Hopkins' 1878 *Atlas of Anne Arundel County, Maryland*, thus indicating that they were constructed in 1878, prior to the court ruling in November 1878.

A leading African American physician in Anne Arundel County, Dr. Bishop was a graduate of Howard University School of Medicine and served as medical missionary in Liberia in the 1880s. He was instrumental in the founding of the Provident Hospital for Blacks in Baltimore, as well as the Annapolis Emergency Hospital (now known as the Anne Arundel Medical Center).⁶

The 1880 census records show that the building at 46 Cornhill Street was occupied by tenant Gilbert Murdock, a green grocer. In 1900, the census records indicate that Daniel Wiggins, a landsman for the United States Naval Academy, occupied the building. The Bishop heirs continued to own the rental building at 48 Cornhill Street until 1973, occupying it themselves in the 1930s; while the building at 46 Cornhill Street had been conveyed separately by Annie Bishop in 1909.

For the early part of the 20th century, the building was owned and used as rental property by Pasquale and Luisa Del Balzo. The census records for 1920 show that carpenter Joseph Holland and his family resided in the dwelling. By 1925, the building was sold to Joseph Wright, who conveyed it in 1938 to the Capital City Building and Loan Association. During the middle part of the 20th century, the building was conveyed numerous times and continued to be used as rental property. In 1946, 46 Cornhill Street was purchased by Freddie and Rachel Smith, who owned it over forty years. Freddie Smith devised the property to Victoria C. Sims, who immediately conveyed it to present owner-occupant Bettilee J. Covert.

⁶ Johnson, Bakari, Research Historian, "Inventory of African American Historical and Cultural Resources, Anne Arundel County, Maryland," (Annapolis, MD: Maryland Commission on African American History and Culture, December 1994, Updated April 1995), p. 22.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-1312

46 Cornhill Street
name of property
Annapolis, Maryland
county and state

=====
HISTORIC CONTEXT:

Geographic Organization: Western Shore

Chronological/Development Period (s):

Industrial/Urban Dominance, 1870-1930
Modern Period, 1930-present

Prehistoric/Historic Period Theme (s):

Architecture, Landscaped Architecture, and
Community Planning
Social/Education/Cultural

RESOURCE TYPE(S)

Category: Building
Historic Environment: Urban
Historic Function (s): Domestic: Single Dwelling
Known Design Source: Unknown

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-1312

46 Cornhill Street
name of property
Annapolis, Maryland
county and state

=====
Chain of Title for 48 Cornhill Street:

1704: Thomas Bordley claimed property of Francis Nicholson

March 1770: Charles Wallace purchased property from State House to Market Space from J.B. Bordley
Provincial Court Judgement,
Liber DD 5 Folio 35

May 5, 1772: Charles Wallace leased Lot 5 to Robert Lambert
Land Records of Anne Arundel County,
Liber B Folio 361

October 12, 1772: Robert Lambert sold lease to Hugh Henley
Land Records of Anne Arundel County,
Liber B Folio 363

October 12, 1772: Hugh Henley sold lease to Philip Meroney
Land Records of Anne Arundel County,
Liber B Folio 364

March 21, 1775: Philip Meroney sold lease to Thomas Gassaway, Jr.
Land Records of Anne Arundel County,
Liber B Folio 404

February 1, 1779: Thomas Gassaway, Jr. sold lease to George Gaston
Land Records of Anne Arundel County,
Liber NH 1 Folio 15

September 24, 1779: George Gaston sold lease to Richard Beard, Jr.
Land Records of Anne Arundel County,
Liber IB 5 Folio 653

March 18, 1784: Richard Beard, Jr. leased all of Lot 5 to James West
Provincial Court Deed,
Liber TFH 1 Folio 218

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-1312

46 Cornhill Street

name of property

Annapolis, Maryland

county and state

=====
May 5, 1809: James West gives sold lease to Henry
Thompson, son-in-law
Land Records of Anne Arundel County,
Liber NH 12 Folio 74

September 23, 1811: Henry Thompson sold lease to Seth Sweeter
Land Records of Anne Arundel County,
Liber WSG 1 Folio 129

January 17, 1812: Seth Sweeter sold lease to Priscilla
Wyvill
Land Records of Anne Arundel County,
Liber WSG 1 Folio 315

October 2, 1817: Susanna and Walter Wyvill sold lease to
James Medford
Land Records of Anne Arundel County,
Liber EH 5 Folio 152

September 9, 1820: Nicholas Brewer, Sr., Trustee for Charles
Wallace estate, sold to George McCubbin
and Nicholas Brewer, Jr.
Land Records of Anne Arundel County,
Liber WSG 12 Folio 629

June 23, 1832: James Medford sold lease to Jeremiah
Hughes
Land Records of Anne Arundel County,
Liber WSG 17 Folio 112

June 23, 1832: Jeremiah Hughes sold lease to Basil
Shepherd
Land Records of Anne Arundel County,
Liber WSG 17 Folio 231

November 16, 1847: Jeremiah Hughes, George and Eleanor
McCubbin, Nicholas and Catharine Brewer
and Basil Shepard sold lease and title to
Richard S. Hardesty
Land Records of Anne Arundel County,
Liber JHN 2 Folio 617

November 14, 1854: Richard Hardesty to George Taylor
Land Records of Anne Arundel County,
Liber NHG 4 Folio 172

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-1312

46 Cornhill Street
name of property
Annapolis, Maryland
county and state

- =====
- 1866: George Taylor devised property to sons
Lemuel K. Taylor and George M. Taylor
- December 30, 1869: George M. Taylor, executor of the
deceased George Taylor, to Trustees of
the M.E. Church
Land Records of Anne Arundel County,
Liber SH 4 Folio 164
- December 31, 1869: Trustees of the M.E. Church to William
Bishop
Land Records of Anne Arundel County,
Liber SH 4 Folio 166
- ca. 1872: William Bishop died and Charity Bishop is
named executor of the will
Will Records of Anne Arundel County,
Liber RID 2 Folio 237
- November 8, 1878: Equity Case 659: Bishop versus Bishop.
Dr. William Bishop, grandson of William
Bishop, awarded ownership of buildings at
46 and 48 Cornhill Street
Land Records of Anne Arundel County,
Liber GW 70 Folio 165
- October 6, 1904: Dr. William Bishop devised to wife Annie
Elizabeth Bishop
Will Records of Anne Arundel County,
Liber RB 1 Folio 262
- March 11, 1909: Annie E. Bishop to Pasquale and Luisa Del
Balzo
Land Records of Anne Arundel County,
Liber GW 70 Folio 165
- November 20, 1925: Pasquale and Luisa Del Balzo to Joseph
Wright
Land Records of Anne Arundel County,
Liber WMB 17 Folio 494
- October 8, 1938: Joseph and Sarah Wright to Capital City
Building and Loan Association
Land Records of Anne Arundel County,
Liber FAM 191 Folio 188

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-1312

46 Cornhill Street
name of property
Annapolis, Maryland
county and state


=====

March 6, 1945: Capital City Building and Loan
Association to Carroll H. Hynson
Land Records of Anne Arundel County,
Liber JHH 324 Folio 465

April 15, 1946: Carroll H. Hynson to Freddie and Rachel
Smith
Land Records of Anne Arundel County,
Liber JHH 359 Folio 19

pre-1982: Freddie Smith, widower, devised to
Victoria C. Sims, subject to the right of
occupancy by Bertha Carter

April 8, 1982: Victoria C. Sims to Bettilee J. Covert
Land Records of Anne Arundel County,
Liber 3483 Folio 372



MAP OF ANNAPOLIS, No. 4-6
 Maryland Department of Assessments and Taxation
 1967; Revised 1991
 Scale 1" = 200'

AA 1312



AA-1312

46 CORNHILL ST
ANNAPOLIS, MD

TRACERIES

MARCH 1996

MD SHPO

SOUTH ELEVATION

1 OF 2



AA-1312

46 CORNHILL STREET

ANNAPOLIS, MD

TRACERIES

MARCH 1996

MD SHPO

EAST ELEVATION

2 OF 2

MARYLAND HISTORICAL TRUST
 21 STATE CIRCLE
 SHAW HOUSE
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET
 Individual Structure Survey Form

SURVEY NUMBER: <u>AA 1312</u>
NEGATIVE FILE NUMBER:
UTM REFERENCES: Zone/Easting/Northing
U.S.G.S. QUAD. MAP:
PRESENT FORMAL NAME:
ORIGINAL FORMAL NAME:
PRESENT USE: SF Res
ORIGINAL USE: SF Res
ARCHITECT/ENGINEER:
BUILDER/CONTRACTOR:
PHYSICAL CONDITION OF STRUCTURE: Excellent () Good () Fair (X) Poor: ()
THEME:
STYLE: Vernacular (Annapolis Federal)
DATE BUILT: c.1810

COUNTY: Anne Arundel
TOWN: Annapolis
LOCATION: 46 Cornhill Street
COMMON NAME:
FUNCTIONAL TYPE: Res Map 32 Par 375
OWNER: Victoria C. Sims ADDRESS: 185 Clay Street Annapolis, MD 21401
ACCESSIBILITY TO PUBLIC: Yes (X) No () Restricted ()
LEVEL OF SIGNIFICANCE: Local (J) State () National () <input checked="" type="radio"/>

GENERAL DESCRIPTION:

Structural System

- Foundation: Stone () Brick (X) Concrete () Concrete Block ()
- Wall Structure
 - Wood Frame: Post and Beam (X) Balloon ()
 - Wood Bearing Masonry: Brick () Stone () Concrete () Concrete Block ()
 - Iron () D. Steel () E. Other:
- Wall Covering: Clapboard () Board and Batten () Wood Shingle () Shiplap ()
 Novelty () Stucco () Sheet Metal () Aluminum () Asphalt Shingle ()
 Brick Veneer () Stone Veneer () Asbestos Shingle (X)
 Bonding Pattern: Other:
- Roof Structure
 - Truss: Wood (X) Iron () Steel () Concrete ()
 - Other:
- Roof Covering: Slate () Wood Shingle () Asphalt Shingle () Sheet Metal (X)
 Built Up () Rolled () Tile () Other:
- Engineering Structure:
- Other:

Appendages: Porches () Towers () Cupolas () Dormers () Chimneys (X) Sheds () Ells (X)
 Wings () Other: Stoop

Roof Style: Gable (X) Hip () Shed () Flat () Mansard () Gambrel () Jerkinhead ()
 Saw Tooth () With Monitor () With Bellcast () With Parapet () With False Front ()
 Other:

Number of Stories: 2

Number of Bays: 2 x 3

Approximate Dimensions: 10 x 45

Entrance Location: Left

THREAT TO STRUCTURE: No Threat (X) Zoning () Roads () Development () Deterioration () Alteration () Other:	LOCAL ATTITUDES: Positive () Negative () Mixed () Other:
--	---

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

Simple boxed cornice; molded window and transom lit door caps; asbestos shingles.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

One of a pair of Vernacular Annapolis Federal, unrestored but important to the streetscape.

REFERENCES:

MAP: (Indicate North In Circle)



SURROUNDING ENVIRONMENT:

Open Lane()Woodland()Scattered Buildings()
Moderately Built Up()Densely-Built Up(✓)
Residential()Commercial()
Agricultural()Industrial()
Roadside Strip Development()
Other:

RECORDED BY:


Russell Wright

ORGANIZATION:

Historic Annapolis, Inc

DATE RECORDED:

Aug. 1983



MARYLAND

AVENUE

GEORGE STREET

STREET

GEORGE STREET

STREET

BOAT

FRANCIS ST

CORNHILL STREET

FLEET STREET

PINKNEY STREET

EAST STREET

MARKET SP.

MARTIN

RANDALL STREET

CONPROMISE

AA 1312
ANNAPOLIS HIST DIST.

0 50 100 200 300 400 500 SCALE IN FEET





46 Cornhill

AA 1312

Annapolis, Anne Arundel County

Russell Wright July, 1982

Maryland Historical Trust,

Annapolis, Maryland

SW Elevation/camera facing NE