

Capsule Summary for 5 Randall Court (AA-1318)

The duplex, located at 5 and 6 Randall Court, was constructed between the years 1908 and 1913. Built as two single family dwellings with an interior connecting parlor door, the houses appear as one individual building. The two-and-half-story houses, documented to be constructed by Joseph Wilmer, are similar in size and scale to other structures on the block, especially 4 Randall Court, which was the home of Wilmer. Constructed with the main entries facing Randall Court, historically called Randall Place, the houses are located on property that was originally part of the large tract of land associated with the Bordley-Randall house. The construction of the building provides a good example of the subdivision and development of a once-large 18th century Annapolis estate into a more densely-built area.

The single family dwellings were owned and leased by the same owners from the time of their construction until the late 1930s. Since that time the houses have been owner occupied. The house located at 5 Randall Court has had little or no visible alterations to the interior or exterior.

MARYLAND HISTORICAL TRUST
MD INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY

Inventory No. AA-1318

=====

1. Name of Property

=====

historic name _____

other names 5 Randall Court; 5 Randall Place; 5 North Street

=====

2. Location

=====

street & number 5 Randall Court not for publication _____

city or town Annapolis vicinity _____

state Maryland code _____ county _____ code _____

zip code _____

=====

3. State/Federal Agency Certification

N/A

=====

4. National Park Service Certification

N/A

=====

5. Classification

=====

Ownership of Property (Check all that apply)

- private
- public-local
- public-State
- public-Federal

Category of Property (Check only one box)

- building(s)
- district
- site
- structure
- object

Number of Resources within Property

Contributing		Noncontributing	
<u>1</u>	_____	_____	buildings
_____	_____	_____	sites
_____	_____	_____	structures
_____	_____	_____	objects
<u>1</u>	_____	_____	Total

Is this property listed in the National Register?

Yes Name of Listing Annapolis Historic District

No _____

Maryland Inventory of Historic Properties
Annapolis Survey
5 Randall Court
Anne Arundel County, Maryland

Inventory No. AA-1318
(Page 2)

=====
6. Function or Use
=====

Historic Functions (Enter categories from instructions)

Cat: Domestic Sub: Single Dwelling

Current Functions (Enter categories from instructions)

Cat: Domestic Sub: Single Dwelling

=====
7. Description
=====

Architectural Classification (Enter categories from instructions)

Shingle Style

Materials (Enter categories from instructions)

foundation Stone

roof Standing Seam Metal

walls Wood Shingles over Frame

other _____

Narrative Description (Describe the historic and current condition of the property.) See Continuation Sheet No. 7-1

=====
8. Statement of Significance
=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties
Annapolis Survey
5 Randall Court
Anne Arundel County, Maryland

Inventory No. AA-1318
(Page 4)

=====
Areas of Significance (Enter categories from instructions)
Architecture

Period of Significance 1908-1913

Significant Dates 1908-1913

Significant Person (Complete if Criterion B is marked above)

Cultural Affiliation

Architect/Builder unknown

Narrative Statement of Significance (Explain the significance of the property.) See Continuation Sheet No. 8-1

Maryland Inventory of Historic Properties
Annapolis Survey
5 Randall Court
Anne Arundel County, Maryland

Inventory No. AA-1318
(Page 5)

=====

9. Major Bibliographical References

=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Articles, Books, Published and Unpublished Resources

Anderson, Elizabeth B. Annapolis: A Walk Through History. Centreville, MD: Tidewater Publishers, 1984.

Anne Arundel County Assessment Records. 1876-1896; 1896-1905; 1904-1910. Maryland State Archives. Record Group C35.

Anne Arundel County Land Records. Anne Arundel County Courthouse and Maryland State Archives, Annapolis, Maryland.

McIntire, Robert Harry. Annapolis Maryland Families. Baltimore: Gateway Press, Inc., 1979.

The Maryland Comprehensive Historic Preservation Plan. Maryland Historical Trust. Department of Economic and Community Development, June 1986.

Papenfuse, Edward. "Southern Urban Society after the Revolution: Annapolis, Maryland, 1782-1786." Final Report for NEH Grant #H69-0-178, Historic Annapolis Foundation, 1969.

Record Group 29 "Records of the Bureau of the Census." 1900, 1910 and 1920 Census; Anne Arundel County, Maryland.

Maps and Drawings

Bird's Eye View of the City of Annapolis, Chas. Magnus, 1864, Reproduced, 1967.

Gray's New Map of Annapolis, Anne Arundel County, MD., 1877.

Hopkins, G.M. Map of Annapolis, 1878.

Map of Annapolis, Southern Map Company, Baltimore, MD., 1905.

Plan of Annapolis, Geo. H. Shafer, 25 July 1718.

Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1897, 1903, 1908, 1913, 1921, 1930, 1954.

Photographs

Hayman Collection, 1920ca-1930ca. Record Group SC1406. Annapolis, Maryland: Maryland State Archives.

Mame Warren Collection, 1859-1910. Record Group SC985. Annapolis, Maryland: Maryland State Archives.

Maryland Inventory of Historic Properties
Annapolis Survey
5 Randall Court
Anne Arundel County, Maryland

Inventory No. AA-1318
(Page 6)

=====
10. Geographical Data
=====

Acreage of Property less than 1 acre

Verbal Boundary Description (Describe the boundaries of the property.)

The property designated 5 Randall Court occupies Parcel 1076 on Tax Map 32 of Annapolis.

Boundary Justification (Explain why the boundaries were selected.)

This parcel has been associated with the property since the construction of the attached dwellings on the site between 1908 and 1913.

=====
11. Form Prepared By
=====

name/title Kim Williams & L. Trieschmann/Architectural Historians
organization Traceries date June 18, 1993
street & number 3712 Thronapple Street telephone (301) 656-2142
city or town Chevy Chase state MD zip code 20815

=====
12. Property Owner
=====

name Mrs. Wye J. Allanbrook
street & number 5 Randall Court telephone 280-5263
city or town Annapolis state MD zip code 21401
=====

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1318

Section 7 Page 1

5 Randall Court

name of property

Anne Arundel County, MD

county and state

=====
The duplex, located at 5 and 6 Randall Court, was constructed between the years 1908 and 1913. The houses front on North Street to the south and a walkway in Randall Court to the north. Constructed as two single family dwellings with an interior connecting parlor door, the houses appear as an individual building. The two-and-one-half-story houses, documented to be constructed by Joseph Wilmer, are similar in size and scale to other structures on the block, especially 4 Randall Court, which was the home of Wilmer. The front elevation faces onto Randall Court, while the south elevation extends along North Street. The west and east elevations are separated from the neighboring dwellings by approximately 15 feet. The front entry of 6 Randall Court has been moved to the west elevation and the inset porch enclosed. The eastern portion of the duplex, located at 5 Randall Court, has no known exterior alteration.

Built in the Shingle Style, the duplex at 5 and 6 Randall Court is an expansive, two-and-half-story, wood shingle building with a cross gambrel roof covered in standing seam metal. The front elevation, approximately 80 feet wide, is six bays wide and originally featured two separate porch entries that mirrored one another. The wide overhanging cornice emphasizes the gambrel roofline. A wooden beltcourse protrudes from above the first story windows. The roof is covered with standing seam metal. Two exterior corbel capped brick chimneys, of 7 course American bond brick, project from the west and east elevations. A large shared interior brick chimney protrudes from the center of the building. The full basement, with one interior division wall, can be accessed from the interior of each house. The composition stone foundation is visible from the interior of the basement. The basement has vertical 3-light hopper windows.

The front elevation of 5 Randall Court features, on the first floor, a front gambrel entry bay and a modest front gable bay. The recessed porch, located in the gambrel bay, features a main entry flanked by leaded glass sidelights. The entry door is wood and glass with recessed panels. The second story gambrel roof is supported by three tuscan columns with a wide entablature, set on a stone pier foundation. The second story of the gambrel bay has two 2/1 windows and one 2/1 window in the attic story. The window surrounds are plain with a slightly projecting lintel. The front gable bay has 2/1 ribbon windows on the first and second story with the same projecting lintel.

The east elevation, approximately 40 feet deep, has an exterior end

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1318

Section 7 Page 2

5 Randall Court

name of property

Anne Arundel County, MD

county and state

=====
brick chimney flanked by two 6-light casement windows on the first story, and two 2/1 windows on the second story. A shed roof dormer has been added to the gambrel roof at the second story on the northeast corner.

The south elevation, located on North Street, has the identical window placement as 6 Randall Court. Two side entries are located in a recess situated in the center of the building where the houses divide. The windows are single and double 2/1 or 6-light casements. The casement windows exist between the actual floor levels and are located on the landings of the interior main stairs. A shed roof dormer is located on the second story on the southeast corner. The windows surrounds are plain with projecting lintels. A ribbon 10-light casement window has been installed in the recessed entry.

The interior of the house at 5 Randall Court is a two room plan with a large side hall. The main entry on Randall Court leads into the large hall that contains a substantial dog-legged stairway and a monumental rough cut stone mantle and chimney breast. The thin pine wood floors run the width of the room. The baseboards are eight inches in height and are topped with a bowtell molding. A molded plate rail has been added approximately five feet from the floor. Crown molding, with a ovolo pattern, encompasses the room. The door and window molding is plain with a wide entablature and projecting cornice. The dog-leg stairway, approximately four feet wide, has an open flight with two recessed panel newel posts. The starting step of the stair has circle ends. The open stringer has panels with square nosing on the treads. The square balusters support the carved rail, which is typical of the 1904-1927 period. The half-landing has landing square newel posts, without the panels. The second floor landing has double square newels that extend to the first floor ceiling, creating square drops. The rough cut stone chimney breast, located on the east wall, has a projecting stone mantle shelf and a stone hearth.

The main parlor, located to the west of the hall, is accessed through an arched opening with a keystone. The molding, with the exemption of the plate rail and addition of a chair rail, is the same as the main hall. A built-in bookcase was added in the late 1980s by the present owner and the original bookcase was removed from the narrow west interior wall. An arched cabinet, with exposed wood and glass doors, was created, possibly in the 1940s, when the interior passageway between 5 and 6 Randall Court was

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1318

Section 7 Page 3

5 Randall Court

name of property

Anne Arundel County, MD

county and state

=====
enclosed. Double panelled doors lead into the kitchen, which was renovated in 1988. At that time, the butler's stairs and the pantry were removed from the first floor. A balustrade and rail remain in the original opening to the landing.

The second floor of the house has the same molding and flooring as the first floor. The central leads into one bathroom and four bedrooms. A small speaking tube is located in the hall between two of the bedrooms. The bathroom was renovated in the 1940s. The large bedrooms have closets that have been added at a later date evidenced by the existence of baseboard in the closet. A picture rail, in all four bedrooms, is located at the base of the window entablature. The southeast bedroom has an open/closed dog-legged stair with the same paneled newel and square balusters as exist in the main stair hall on the first floor. The stairs lead to a half-landing, closed from view by a five paneled door, that extends to the full attic. The walls of the half-landing are stucco with the same molding seen throughout the house. The closed stairs of the butler that lead to the attic have been hidden from view by a door in the second floor hall. At an unknown point in time, the stair hall was used as bathroom and a toilet was installed at the landing. The ceiling was removed and a higher ceiling was installed, creating a counter-like effect in the attic above, to allow for adequate headroom. The bathroom was removed in 1988 by the present owner.

The attic, originally one room extending the length of 5 and 6 Randall Court, was divided possibly at the same time as the basement. The floor is finished in random width wood boards, while the walls and ceiling remain unfinished. The stair walls have beaded board.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1318

Section 8 Page 1

5 Randall Court

name of property
Anne Arundel County, MD
county and state

=====
Built in the period 1908-1913, the two attached houses at 5 and 6 Randall Court, historically Randall Place, are located on property that was originally part of the large tract of land associated with the Bordley-Randall house. The construction of the building provides a good example of the subdivision and development of a once-large 18th century Annapolis estate into a more densely-built area.

Designated as Lots 76, 77, 78, 79 and 80 on the Stoddert Map of 1718, the Bordley-Randall house property was originally bounded by College Avenue (originally called Tabernacle Avenue), Prince George Street, Maryland Avenue, State Circle and North Street. The Thomas Bordley family, who owned the property from 1726 to 1810 built the large Bordley-Randall house. In 1811, following John Beale Bordley's death, John Johnson, Chancellor of Maryland, bought the property and sold it that same year to William S. Green. In 1847, Alexander Randall purchased the property and, during the latter half of the 19th century, began to subdivide and improve portions of the large tract of land with commercial and residential buildings.

Following Alexander Randall's death in 1880, the parcel of land on which 5 and 6 Randall Court stand today was acquired, in 1897, by Randall family member Wyatt Wirt Randall, grandson of Alexander Randall, from Alexander Randall trustees. At that time, the cobblestone path known as Randall Place was laid.¹ In 1903, Wyatt Wirt Randall sold the property to Joseph R. Wilmer. Six years earlier, in 1896, Joseph R. Wilmer, a professor, had purchased the adjacent property at 4 Randall Place. Having built his own house at 4 Randall Place in 1896-1897, Wilmer then constructed the two attached houses at 5 and 6 Randall Place. Although local history holds that Wilmer built the two attached houses for his two daughters, U.S. Census Records indicate that in 1900 Wilmer had three daughters of age 11, 3 and 2 and one son, age 9. It is highly unlikely that he would have constructed the two houses for such young children. Furthermore, in 1911 Wilmer deeded the undivided half-interest of both houses to his wife, Isabella, and in 1915, Wilmer and his wife sold both properties to Allan C. Hill.

The 1920 U.S. Census records indicate that the new owners of 5 and

¹ Liber GW3, Folio 375.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1318

Section 8 Page 2

5 Randall Court
name of property
Anne Arundel County, MD
county and state

=====

6 Randall Place rented the properties out.² During the mid-20th century, the two houses changed hands several times, but were generally sold as a unit. In 1959, then-owner Edith Reid Lazenby sold 5 Randall Place to Phyllis F. Nield and Van K. Nield and in 1962 sold 6 Randall Place to Merrill B. Walker, Jr. and Mary McBride Walker, thereby dividing the ownership of the pair of houses.³

The house at 5 Randall Place is currently owned and occupied by Wye J. Allanbrook.

² The 1920 Census Records do not give the addresses on Randall Place, so the name of the occupants for the specific properties cannot be ascertained. Based upon the census data, however, it appears that four of the five houses on Randall Place are occupied by U.S. Navy officers, while the fifth is occupied by a general store manager.

³Local oral history maintains that Joseph Lazenby and his wife, Edith, divided the house into two units at the time of the marriages of their daughter's in the 1940s. The oral history further contends that the original kitchen was located in 5 Randall Court and after the division of the house, a modern 1940s kitchen was installed in 6 Randall Court. Based on the Sanborn Map of 1913, deed research, and physical evidence in the house, it can be surmised that Joseph Wilmer did in fact construct the building as two separate dwellings with one interior connecting door that has since been enclosed.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1318

5 Randall Court

name of property

Anne Arundel Co., MD

county and state

=====

Historic Period Theme: Architecture, Landscape Architecture &
Community Planning

Geographic Organization: Western Shore

Chronological/Developmental Period: Industrial/Urban Dominance,
1870-1930

Resource Type(s): Standing Structures

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1318

5 Randall Court
name of property

Annapolis, Maryland
county and state

=====



Chain of Title for 5 Randall Court:

- Pre 1726: Thomas Bordley's will devises all real estate in Annapolis (except Lots 92, 93, 104, 106 and lot on Francis Street) to son Stephen. Wife Ariana is executor
Wills L 19 Folio 99
- 1730: Lease to John Wolfe from the Bordleys
TI #1 Folio 268
- 1730: Mortgage on property between John Wolfe and Daniel Dulaney and John Tunstall
TI #1 Folio 22
- 1764: Stephen Bordley to his brother John Beale Bordley (real estate) and sister Elizabeth Bordley (house and furnishings)
Wills L 33 Folio 39
- 1789: Elizabeth Bordley to John Beale Bordley
Wills JG 1 Folio 107
- 1798: Philip B. Key is a tenant
Federal Direct Tax f.2
- pre 1801: John Beale Bordley to John Johnson
Liber NH 16 Folio 607
- 1811: John Johnson gets the title to the land as per Bordley's will
Liber NH 16 Folio 607
- 1811: John Johnson to William S. Green
Liber WSG 1 Folio 1
- 1847: Trustee for William S. Green to Alexander Randall
Liber JHN 2 Folio 440
- 1880: John Wirt, Blanchard, and B. Alexander Randall appointed Executors and Trustees under the Will of Alexander Randall, deceased. Equity 1987
Will BRD 42 Folio 452


- 1897: Randall Trustees to Wyatt W. Randall
Liber GW 6 Folio 462
- 1903: Wyatt W. Randall to Joseph R. Wilmer
Liber GW 33 Folio 88
- 1911: Joseph R. Wilmer deeded un-divided half interest to wife,
Isabella Wilmer
Liber GW 83 Folio 333
- 1915: Joseph R. and Isabella H. Wilmer to Allan C. Hill
Liber GW 117 Folio 93
- 1920: Allan C. Hill to Prentis P. and Henrietta A. Bassett
Liber WNW 37 Folio 244
- 1922: Prentis P. Bassett deeded un-divided half interest to wife,
Henrietta
as part of divorce agreement
Liber WNW 56 Folio 162
- 1930: Henrietta A. Bassett defaults on mortgage and Nicholas H.
Green is appointed Trustee. Equity 6388
Liber FSR 78 Folio 227
- 1933: Trustee to Howard M. and Lorene B. Bradbury
Liber FSR 107 Folio 494
- 1936: Bradbury to Beatrice E. Hart
Liber FAM 157 Folio 62
- 1941: Beatrice Hart to George E. Rullman, Trustee for Lazenby
Estate
Liber JHH 251 Folio 34
- 1959: Edith Reid Lazenby to Phyllis F. Nield and son Van K. Nield
Liber 1294 Folio 385
- 1965: Phyllis F. and Van K. Nield to Henry J. Tarantino, Trustee
Liber 1908 Folio 156
- 1965: Trustee to Phyllis F. Nield, Van K. and Sally Huntington
Nield
Liber 1908 Folio 159
- 1988: Nields to John Vincent Jamison, III and Wye J. Allanbrook
Liber 4679 Folio 471
- 1990: John Vincent Jamison, III deeded un-divided half interest
to Wye J. Allanbrook
Liber 5042 Folio 855

44-1318

1st Floor




2ND FLOOR



5 Randall Court 44-1318

COLLEGE



Map of Annapolis, No. 32
 Maryland Department of Assessments and Taxation
 1967; Revised 1991
 Scale 1' = 200'

AA-1318



AA-1318
5 RANDALL COURT
ANNAPOLIS, MARYLAND
TRACERIES
JUNE, 1993
MARYLAND SHPO
SOUTH ELEVATION
1/11



AA-1318
5 RANDALL COURT
ANNAPOLIS, MARYLAND
TRACERIES
JUNE, 1993
MARYLAND SHPO
2ND AND 3RD FLOOR DETAIL, S ELEVATION
2/11



AN-51-2

AA-1318
5 RANDALL COURT
ANNAPOLIS, MARYLAND
TRACERIES
JUNE, 1993
MARYLAND SHPO
NORTHEAST ELEVATION
3/11



AA-1318
5 RANDALL COURT
ANNAPOLIS, MARYLAND
TRALERIES
JUNE, 1993
MARYLAND SHPO
FRONT ENTRY, NORTH ELEVATION
A/11



AA-1318

5 RANDALL COURT
ANNAPOLIS, MARYLAND

TRACERIES

JUNE, 1993

MARYLAND SHPO

1ST FLOOR MAIN STAIR, EAST ROOM

5/11



AA-635

5 RANDALL COURT
ANNAPOLIS, MARYLAND

TRALERIES

JUNE, 1993

MARYLAND SHPO

1ST FLOOR, MANTLE IN EAST ROOM

6/11



AA-1318
5 RANDALL COURT
ANNAPOLIS, MARYLAND
TRALERIES
JUNE, 1993
MARYLAND SHPO
1ST FLOOR, LOOKING WEST
7/11



AA-1318

STRANDALL COURT
ANNAPOLIS, MARYLAND

TRALERIES

JUNE, 1993

MARYLAND SHPO

1ST FLOOR, WEST WALL

3/11



AA-1318
5 RANDALL COURT
ANNAPOLIS, MARYLAND
TRACERIES

JUNE, 1993

MARYLAND SHPO

2ND FLOOR HALL VIEW FROM STAIR

9/11



AA-1318

5 RANDALL COURT
ANNAPOLIS, MARYLAND

TRALERIES

JUNE, 1993

MARYLAND SHPO

2ND FLOOR INTERIOR, NE ROOM

10/11

IMAGES for TWO PIANOS
and ORCHESTRA



The NATIONAL MUSEUM
of WOMEN in the ARTS



AA-1318

5 RANDALL COURT
ANNAPOLIS, MARYLAND

TRACERIES

JUNE, 1993

MARYLAND SHPO

2ND FLOOR STAIR, S ROOM

11/11

MARYLAND HISTORICAL TRUST
 21 STATE CIRCLE
 SHAW HOUSE
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET
 Individual Structure Survey Form

SURVEY NUMBER: AA 1318
NEGATIVE FILE NUMBER:
UTM REFERENCES: Zone/Easting/Northing
U.S.G.S. QUAD. MAP:
PRESENT FORMAL NAME:
ORIGINAL FORMAL NAME:
PRESENT USE: SF Res
ORIGINAL USE: SF Res
ARCHITECT/ENGINEER:
BUILDER/CONTRACTOR:
PHYSICAL CONDITION OF STRUCTURE: Excellent () Good (<input checked="" type="checkbox"/>) Fair () Poor: ()
THEME:
STYLE: Shingle
DATE BUILT: 1908-1913

COUNTY: Anne Arundel
TOWN: Annapolis
LOCATION: 6 North St. 5 North St.
COMMON NAME:
FUNCTIONAL TYPE: RES Map 32 Par 601
OWNER: Nield Phyllis F ADDRESS: 5 00 Randall Pl Annapolis, MD 21401
ACCESSIBILITY TO PUBLIC: Yes (<input checked="" type="checkbox"/>) No () Restricted ()
LEVEL OF SIGNIFICANCE: Local (<input checked="" type="checkbox"/>) State () National (<input type="checkbox"/>)

GENERAL DESCRIPTION:

Structural System

- Foundation: Stone () Brick () Concrete () Concrete Block ()
- Wall Structure
 - Wood Frame: Post and Beam () Balloon ()
 - Wood Bearing Masonry: Brick () Stone () Concrete () Concrete Block ()
 - Iron () D. Steel () E. Other:
- Wall Covering: Clapboard () Board and Batten () Wood Shingle () Shiplap ()
 Novelty () Stucco () Sheet Metal () Aluminum () Asphalt Shingle ()
 Brick Veneer () Stone Veneer () Asbestos Shingle ()
 Bonding Pattern: Other:
- Roof Structure
 - Truss: Wood () Iron () Steel () Concrete ()
 - Other:
- Roof Covering: Slate () Wood Shingle () Asphalt Shingle () Sheet Metal ()
 Built Up () Rolled () Tile () Other:
- Engineering Structure:
- Other:

Appendages: Porches () Towers () Cupolas () Dormers () Chimneys () Sheds () Ells ()
 Wings () Other: Cross Gambrel

Roof Style: Gable () Hip () Shed () Flat () Mansard () Gambrel () Jerkinhead ()
 Saw Tooth () With Monitor () With Bellcast () With Parapet () With False Front ()
 Other:

Number of Stories: 2½

Number of Bays: 4 x 3

Approximate Dimensions: 40 x 35

Entrance Location: Inset @ Right

THREAT TO STRUCTURE: No Threat (<input checked="" type="checkbox"/>) Zoning () Roads () Development () Deterioration () Alteration () Other:	LOCAL ATTITUDES: Positive () Negative () Mixed () Other:
--	---

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

Cross gambrel roof with assymetrical fenestration in end wall; shed wall dormers at side elev ation in almost vertical lower plane of roof; projection front gambrel end breaks at juncture of the two units that make up the pair with entrances at but sides of perpendicular walls. All windows with molded caps; all cornices and rakes molded; end wall chimney.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

Important part of pair of American Queen Ann/Shingle style residences, critical to streetscape and important as types.

REFERENCES:

MAP: (Indicate North In Circle)



SURROUNDING ENVIRONMENT:

Open Lane()Woodland()Scattered Buildings()
Moderately Built Up(✓)Densely-Built Up()
Residential()Commercial()
Agricultural()Industrial()
Roadside Strip Development()
Other:

RECORDED BY:

Russell Wright

ORGANIZATION:


Historic Annapolis, Inc

DATE RECORDED:

Aug. 1983



AA 1318
ANNAPOLIS HIST. DIST.





6 North

AA 1318

Annapolis, Anne Arundel County

Russell Wright July, 1982

Maryland Historical Trust,

Annapolis, Maryland

NE Elevation/camera facing sw