

Capsule Summary for 6 Randall Court (AA-1319)

The duplex, located at 5 and 6 Randall Court, was constructed between the years 1908 and 1913. Built as two single family dwellings with an interior connecting parlor door, the houses appear as one individual building. The two-and-half-story houses, documented to be constructed by Joseph Wilmer, are similar in size and scale to other structures on the block, especially 4 Randall Court, which was the home of Wilmer. Constructed with the main entries facing Randall Court, historically called Randall Place, the houses are located on property that was originally part of the large tract of land associated with the Bordley-Randall house. The construction of the building provides a good example of the subdivision and development of a once-large 18th century Annapolis estate into a more densely-built area.

The single family dwellings were owned and leased by the same owners from the time of their construction until the late 1930s. Since that time the houses have been owner occupied. The house located at 6 Randall Court has had an alteration to the Randall Court facade and the interior has been altered slightly.

MARYLAND HISTORICAL TRUST
MD INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY

Inventory No. AA-1319

1. Name of Property

historic name _____

other names 6 Randall Court; 6 Randall Place; 6 North Street

2. Location

street & number 6 North Street not for publication _____

city or town Annapolis vicinity _____

state Maryland code _____ county _____ code _____

zip code _____

3. State/Federal Agency Certification

N/A

4. National Park Service Certification

N/A

5. Classification

Ownership of Property (Check all that apply)

- private
 public-local
 public-State
 public-Federal

Category of Property (Check only one box)

- building(s)
 district
 site
 structure
 object

Number of Resources within Property

Contributing Noncontributing

<u>1</u>	_____	buildings
_____	_____	sites
_____	_____	structures
_____	_____	objects
<u>1</u>	_____	Total

Is this property listed in the National Register?

Yes Name of Listing Annapolis Historic District

No _____

Maryland Inventory of Historic Properties
Annapolis Survey
6 Randall Court
Anne Arundel County, Maryland

Inventory No. AA-1319
(Page 2)

=====
6. Function or Use
=====

Historic Functions (Enter categories from instructions)

Cat: Domestic Sub: Single Dwelling

Current Functions (Enter categories from instructions)

Cat: Domestic Sub: Single Dwelling

=====
7. Description
=====

Architectural Classification (Enter categories from instructions)

Shingle Style

Materials (Enter categories from instructions)

foundation Stone
roof Standing Seam Metal
walls Wood Shingles over Frame
other _____

Narrative Description (Describe the historic and current condition of the property.) See Continuation Sheet No. 7-1

=====
8. Statement of Significance
=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties
Annapolis Survey
6 Randall Court
Anne Arundel County, Maryland

Inventory No. AA-1319
(Page 4)

=====
Areas of Significance (Enter categories from instructions)

Architecture

Period of Significance 1908-1913

Significant Dates 1908-1913

Significant Person (Complete if Criterion B is marked above)

Cultural Affiliation _____

Architect/Builder unknown

Narrative Statement of Significance (Explain the significance of the property.) See Continuation Sheet No. 8-1

Maryland Inventory of Historic Properties
Annapolis Survey
6 Randall Court
Anne Arundel County, Maryland

Inventory No. AA-1319
(Page 5)

=====
9. Major Bibliographical References
=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Articles, Books, Published and Unpublished Resources

Anderson, Elizabeth B. Annapolis: A Walk Through History.
Centreville, MD: Tidewater Publishers, 1984.

Anne Arundel County Assessment Records. 1876-1896; 1896-1905;
1904-1910. Maryland State Archives. Record Group C35.

Anne Arundel County Land Records. Anne Arundel County Courthouse
and Maryland State Archives, Annapolis, Maryland.

McIntire, Robert Harry. Annapolis Maryland Families. Baltimore:
Gateway Press, Inc., 1979.

The Maryland Comprehensive Historic Preservation Plan. Maryland
Historical Trust. Department of Economic and Community
Development, June 1986.

Papenfuse, Edward. "Southern Urban Society after the Revolution:
Annapolis, Maryland, 1782-1786." Final Report for NEH Grant
#H69-0-178, Historic Annapolis Foundation, 1969.

Record Group 29 "Records of the Bureau of the Census." 1900, 1910
and 1920 Census; Anne Arundel County, Maryland.

Maps and Drawings

Bird's Eye View of the City of Annapolis, Chas. Magnus, 1864,
Reproduced, 1967.

Gray's New Map of Annapolis, Anne Arundel County, MD., 1877.

Hopkins, G.M. Map of Annapolis, 1878.

Map of Annapolis, Southern Map Company, Baltimore, MD., 1905.

Plan of Annapolis, Geo. H. Shafer, 25 July 1718.

Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1897, 1903, 1908,
1913, 1921, 1930, 1954.

Photographs

Hayman Collection, 1920ca-1930ca. Record Group SC1406. Annapolis,
Maryland: Maryland State Archives.

Mame Warren Collection, 1859-1910. Record Group SC985. Annapolis,
Maryland: Maryland State Archives.

Maryland Inventory of Historic Properties
Annapolis Survey
6 Randall Court
Anne Arundel County, Maryland

Inventory No. AA-1319
(Page 6)

=====
10. Geographical Data
=====

Acreege of Property less than 1 acre

Verbal Boundary Description (Describe the boundaries of the property.)

The property designated 6 Randall Court occupies Parcel 1042 on Tax Map 32 of Annapolis.

Boundary Justification (Explain why the boundaries were selected.)

This parcel has been associated with the property since the construction of the attached dwellings on the site between 1908 and 1913.

=====
11. Form Prepared By
=====

name/title Kim Williams & L. Trieschmann/Architectural Historians
organization Traceries date June 18, 1993
street & number 3712 Thronapple Street telephone (301) 656-2142
city or town Chevy Chase state MD zip code 20815

=====
12. Property Owner
=====

name Mr. and Mrs. Roy Kinard
street & number 6 Randall Court telephone 263-5323
city or town Annapolis state MD zip code 21401

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1319

Section 7 Page 1

6 Randall Court

name of property

Anne Arundel County, MD

county and state

=====

The duplex, located at 5 and 6 Randall Court, was constructed between the years 1908 and 1913. The houses front on North Street to the south and a walkway in Randall Court to the north. Constructed as two single family dwellings with an interior connecting parlor door, the houses appear as an individual building. The two-and-half-story houses, documented to be constructed by Joseph Wilmer, are similar in size and scale to other structures on the block, especially 4 Randall Court, which was the home of Wilmer. The front elevation faces onto Randall Court, while the south elevation extends along North Street. The west and east elevations are separated from the neighboring dwellings by approximately 15 feet. The front entry of 6 Randall Court has been moved to the west elevation and the inset porch enclosed. The eastern portion of the duplex, located at 5 Randall Court, has no known exterior alteration.

Built in the Shingle Style, the duplex at 5 and 6 Randall Court is an expansive, two-and-half-story, wood shingle building with a cross gambrel roof covered in standing seam metal. The front elevation, approximately 80 feet wide, is six bays wide and originally featured two separate porch entries that mirrored one another. The wide overhanging cornice emphasizes the gambrel roofline. A wooden beltcourse protrudes from above the first story windows. The roof is covered with standing seam metal. Two exterior corbel capped brick chimneys, of 7 course American bond brick, project from the west and east elevations. A large shared interior brick chimney protrudes from the center of the building. The full basement, with one interior division wall, can be accessed from the interior of each house. The composition stone foundation is visible from the interior of the basement. The basement has vertical 3-light hopper windows.

The front elevation of 6 Randall Court features, on the first floor, a front gambrel entry bay and a modest front gable bay that originally mirrored the elevation on 5 Randall Court. The recessed porch has been enclosed, and have ribbon 10-light casement windows, to create an additional room on the first floor. The second story has two 2/1 windows and one 2/1 window in the attic story. The window surrounds are plain with a slightly projecting lintel. The front gable bay has 2/1 ribbon windows on the first and second story and is identical to 5 Randall Court.

The west elevation, approximately 40 feet deep, has an exterior end brick chimney flanked by two 2/1 windows on the first story, and two 2/2 windows on the second story. The replacement entry door,

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1319

Section 7 Page 2

6 Randall Court
name of property
Anne Arundel County, MD
county and state

=====

originally located on the north elevation, is wood and glass with recessed panels. The entry is ornamented by pilaster and dentil molding. A shed roof dormer has been added to the gambrel roof at the second story on the northeast corner.

The south elevation, located on North Street, has the identical window placement as 6 Randall Court. A side entry is located in a recess situated in the center of the building where the houses divide. The original side entry within the recess has been enclosed. The windows are single and double 2/2 or 6-light casements. The casement windows exist between the actually floor levels and are located on the landings of the interior main stairs. A shed roof dormer is located on the second story on the southwest corner. The windows surrounds are plain with projecting lintels.

The interior of the house at 6 Randall Court is a two room plan with a large side hall. The main entry on Randall Court leads into a small foyer that was created in the 1950s when the recessed porch was enclosed. This foyer extends into the large hall that contains a substantial dog-legged stairway and a monumental rough cut stone mantle and chimney breast. The thin wood floors run the width of the room. The baseboard, approximately eight-inches in height, has a beaded top. Crown molding, with a ovulo pattern, encompasses the room. The door and window molding is plain with a wide entablature and projecting cornice. The dog-leg stairway, approximately four feet wide, has an open flight with two recessed panel newel posts. The starting step of the stair has circle ends. The open stringer has panels with square nosing on the treads. The square balusters support the carved rail, which is typical of the 1904-1927 period. The half-landing has landing square newel posts, without the panels. The second floor landing has double square newels that extend to the first floor ceiling, creating square drops. The trim of the window located on the half-landing of the stairs has been added at a later date, this is evidenced by the existence of bead molding and shelves at the side of the opening. The rough cut stone chimney breast, located on the west wall, has a projecting stone mantle shelf and a stone hearth.

The main parlor, that measures 20 feet by 30 feet, is located to the east of the hall, is accessed through an arched opening with a keystone. The molding is the same as the main hall. An original built-in bookcase is located to the left of the door. An arched opening that is now enclosed, possibly done in the 1940s, was the interior passageway between 5 and 6 Randall Court. A smaller

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1319

Section 7 Page 3

6 Randall Court
name of property
Anne Arundel County, MD
county and state

=====

mantle, with a carved ovulo and bowed entablature, has a brick opening and stone hearth. Built-in shelves stand to the south of the chimney breast. A 1940s kitchen and bathroom are to the south of the parlor.¹ Closed butler's stairs are located in the southwest corner of the kitchen.

A study, measuring 8 feet by 10 feet, was constructed when the original main entry was moved to the north elevation. The room, overlooking Randall Court with ribbon windows, has 15-light double french door. Built-in, floor to ceiling, bookcases are on the south interior wall.

The second floor was inaccessible and therefore not included in the survey. A floor plan was, however, provided by the present owner, and states the second floor has two bathrooms, located at the north end of the house, and four bedrooms.

¹Oral history provided by the present owners state that the house did not have a kitchen when constructed and the original kitchen was located in 5 Randall Court. Historic documentation and physical evidence located with 5 and 6 Randall Court may prove that a kitchen did exist in the present location in 6 Randall Court and was renovated in the 1940s.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1319

Section 8 Page 1

6 Randall Court

name of property
Anne Arundel County, MD
county and state

=====
Built in the period 1908-1913, the two attached houses at 5 and 6 Randall Place are located on property that was originally part of the large tract of land associated with the Bordley-Randall house. The construction of the two houses provides a good example of the subdivision and development of a once-large 18th century Annapolis estate into a more densely-built area.

Designated as Lots 76, 77, 78, 79 and 80 on the Stoddert Map of 1718, the Bordley-Randall house property was originally bounded by College Avenue (originally called Tabernacle Avenue), Prince George Street, Maryland Avenue, State Circle and North Street. The Thomas Bordley family, who owned the property from 1726 to 1810 built the large Bordley-Randall house. In 1811, following John Beale Bordley's death, John Johnson bought the property and sold it that same year to William S. Green. In 1847, Alexander Randall purchased the property and, during the latter half of the 19th century, began to subdivide and improve portions of the large tract of land with commercial and residential buildings.

Following Alexander Randall's death in 1880, the parcel of land on which 5 and 6 Randall Court stand today was acquired, in 1897, by Randall family member Wyatt Wirt Randall, grandson of Alexander Randall, from Alexander Randall trustees. At that time, the cobblestone path known as Randall Place was laid.² In 1903, Wyatt W. Randall sold the property now occupied by 5 and 6 Randall Court to Joseph R. Wilmer. Six years earlier, in 1896, Joseph R. Wilmer, a professor, had purchased the adjacent property at 4 Randall Place. Having built his own house at 4 Randall Place in 1896-1897, Wilmer then constructed the two attached houses at 5 and 6 Randall Place. Although local history holds that Wilmer built the two attached houses for his two daughters, U.S. Census Records indicate that in 1900 Wilmer had three daughters of age 11, 3 and 2 and one son, age 9. It is highly unlikely that he would have constructed the two houses for such young children. Furthermore, in 1911 Wilmer deeded the undivided half-interest of both houses to his wife, Isabella and in 1915, Wilmer and his wife sold both properties to Allan C. Hill.

The 1920 U.S. Census records indicate that the new owners of 5 and

² Liber GW3, Folio 375.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1319

Section 8 Page 2

6 Randall Court
name of property
Anne Arundel County, MD
county and state

=====

6 Randall Place rented the properties out.³ During the mid-20th century, the two houses changed hands several times, but were generally sold as a unit. In 1959, then-owner Edith Reid Lazenby sold 5 Randall Place to Phyllis F. Nield and Van K. Nield and in 1962 sold 6 Randall Place to Merrill B. Walker, Jr. and Mary McBride Walker, thereby dividing the ownership of the pair of houses.⁴

The property at 6 Randall Place is currently owned and occupied by Mr. and Mrs. Roy Kinard.

³ The 1920 Census Records do not give the addresses on Randall Place, so the name of the occupants for the specific properties cannot be ascertained. Based upon the census data, however, it appears that four of the five houses on Randall Place are occupied by Naval Academy officers, while the fifth is occupied by a general store manager.

⁴Local oral history maintains that Joseph Lazenby and his wife, Edith, divided the house into two units at the time of the marriages of their daughter's in the 1940s. The oral history further contends that the original kitchen was located in 5 Randall Court and after the division of the house, a modern 1940s kitchen was installed in 6 Randall Court. Based on the Sanborn Map of 1913, deed research, and physical evidence in the house, it can be surmised that Joseph Wilmer did in fact construct the building as two separate dwellings with one interior connecting door that has since been enclosed.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1319

6 Randall Court
name of property
Anne Arundel Co., MD
county and state

=====

Historic Period Theme: Architecture, Landscape Architecture &
Community Planning

Geographic Organization: Western Shore

Chronological/Developmental Period: Industrial/Urban Dominance,
1870-1930

Resource Type(s): Standing Structures

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1319

6 Randall Court
name of property

Annapolis, Maryland
county and state

=====

Chain of Title for 6 Randall Court:



- Pre 1726: Thomas Bordley's will devises all real estate in Annapolis (except Lots 92, 93, 104, 106 and lot on Francis Street) to son Stephen. Wife Ariana is executor
Wills L 19 Folio 99
- 1730: Lease to John Wolfe from the Bordleys
TI #1 Folio 268
- 1730: Mortgage on property between John Wolfe and Daniel Dulaney and John Tunstall
TI #1 Folio 22
- 1764: Stephen Bordley to his brother John Beale Bordley (real estate) and sister Elizabeth Bordley (house and furnishings)
Wills L 33 Folio 39
- 1789: Elizabeth Bordley to John Beale Bordley
Wills JG 1 Folio 107
- 1798: Philip B. Key is a tenant
Federal Direct Tax f.2
- pre 1801: John Beale Bordley to John Johnson
Liber NH 16 Folio 607
- 1811: John Johnson gets the title to the land as per Bordley's will
Liber NH 16 Folio 607
- 1811: John Johnson to William S. Green
Liber WSG 1 Folio 1
- 1847: Trustee for William S. Green to Alexander Randall
Liber JHN 2 Folio 440
- 1880: John Wirt, Blanchard, and B. Alexander Randall appointed Executors and Trustees under the Will of Alexander Randall, deceased. Equity 1987
Will BRD 42 Folio 452

- 1897: Randall Trustees to Wyatt W. Randall
Liber GW 6 Folio 462
- 1903: Wyatt W. Randall to Joseph R. Wilmer
Liber GW 33 Folio 88
- 1911: Joseph R. Wilmer deeded un-divided half interest to wife,
Isabella Wilmer
Liber GW 83 Folio 333
- 1915: Joseph R. and Isabella H. Wilmer to Allan C. Hill
Liber GW 117 Folio 93
- 1925: Allan C. Hill to Prentis P. and Henrietta A. Bassett
Liber WMB 12 Folio 434
- 1930: Prentis P. Bassett deeded un-divided half interest to wife,
Henrietta
as part of divorce agreement
Liber FSR 78 Folio 226
- 1930: Henrietta A. Bassett defaults on mortgage and Nicholas H.
Green is appointed Trustee. Equity 6388
Liber FSR 78 Folio 227
- 1933: Trustee to Howard M. and Lorene B. Bradbury
Liber FSR 107 Folio 494
- 1936: Bradbury to Beatrice E. Hart
Liber FAM 157 Folio 62
- 1936: Beatrice Hart to George E. Rullman, Trustee for Lazenby
Estate
Liber FAM 181 Folio 26
- 1962: Edith Reid Lazenby to Merrill B. Walker, Jr. and Mary
McBride Walker
Liber LNP 1611 Folio 364
- 1965: Walkers to Roy F. Kinard
Liber 1881 Folio 105

44 1319

2ND FLOOR PLAN

BASED ON VERBAL DESCRIPTION




door to terrace
FIRST FLOOR

6 RANDALL COURT
17 JUNE 1993

AA-1319

COLLEGE



Map of Annapolis, No. 32 *AA-1319*
 Maryland Department of Assessments and Taxation
 1967; Revised 1991
 Scale 1' = 200'



AA-1319

6 RANDALL COURT
ANNAPOLIS, MARYLAND

TRACERIES

JUNE, 1993

MARYLAND SHPO

SW ELEVATION

1/16



AA-1319
6 RANDALL COURT
ANNAPOLIS, MARYLAND
TRALERIES
JUNE, 1993
MARYLAND SHPO
NORTH ELEVATION
2/16



AA-1319

6 RANDALL COURT
ANNAPOLIS, MARYLAND

TRACERIES

JUNE, 1993

MARYLAND SHPO

FRONT ENTRY, WEST ELEVATION

3/16



AA-1319

6 RANDALL COURT
ANNAPOLIS, MARYLAND
TRALERIES

JUNE, 1993

MARYLAND SHPO

1ST FLOOR LOOKING EAST

4/16



AA 2019

6 MANORIAL COURT

ANNAPOLIS, MARYLAND


TRACE THE S.

1/21/2019

MARYLAND SHPO

1ST FLOOR MANTS - SOUTH EAST ROOM

5/16



WARTLAND
HISTORIC
PRESERVATION
MONTH

WARTLAND HISTORIC PRESERVATION MONTH

AA-1319

6 RANDALL COURT
ANNAPOLIS, MARYLAND
TRACERIES

JUNE, 1993

1ST FLOOR, EAST ROOM

6/16



AA 1219

FRANZALL COURT

ANNE ARDOR, MARYLAND

TRACT 1155

JUNE, 1993

MARYLAND SHPC

1ST BLOCK, DORNING, WEST

7116



AD 1319

638 DALL COURT
ANNAPOLIS, MARYLAND
TRAILER 5

JUNE 1993

MARYLAND SAPO

1ST FLOOR MANTLE PEST ROOM

8/16



LA 1219

6 KANSAS ST. COURT
ANNAPOLIS, MARYLAND
TRACER'S

JUNE, 1993

MARYLAND SHRO

1ST FLOOR, MAIN STAIR, EAST ROOM

9/16



AA-1319

6 RANDALL COURT
ANNAPOLIS MARYLAND

TRAILER

JUNE, 1993

MARYLAND SHPO

1ST FLOOR MAIN STAIR

10/10



AA-1319

1/2 RANDALL COURT
ANNAPOLIS, MARYLAND

TRACER 15"

JUNE, 1992

MARILENE SHED

1ST FLOOR MAIN STAIR, NORTH FOOT

11/16



AA-1319

6 RANDALL COURT
ANNAPOLIS, MARYLAND

TRACERIES

JUNE, 1992

MARYLAND STATE

1ST FLOOR, TRENCH EXCAVATION FROM

12/10



AA-1319

2nd FLOOR COURT

ANNAPOLIS, MARYLAND

TRACERILLS

JUNE, 1993

MARYLAND SAPO

1ST FLOOR, SUNROOM BOOK CASE DETAIL, E WALL

13/1/93



AA-1319

6 RANDALL COURT
ANNAPOLIS, MARYLAND

TRACERIES

JUNE, 1993

MARYLAND SHFO

BASEBOARD AND FLOOR DETAIL, 1ST FLOOR

14/110



AA-1319

6 RANDALL COURT

ANNAPOLIS, MARYLAND

TRACERIES

JUNE, 1993

MARYLAND SHPO

1ST FLOOR, CORNER MOLDING

15/110



AA-1319

6 RANDALL COURT
ANNAPOLIS, MARYLAND
TRAILERIES

JUNE, 1993

MARYLAND SHPO

1ST FLOOR, KITCHEN (PARTIAL) AND REAR
STAIR

16/16

MARYLAND HISTORICAL TRUST
 21 STATE CIRCLE
 SHAW HOUSE
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET
 Individual Structure Survey Form

SURVEY NUMBER: AA 1319
NEGATIVE FILE NUMBER:
UTM REFERENCES: Zone/Easting/Northing
U.S.G.S. QUAD. MAP:
PRESENT FORMAL NAME:
ORIGINAL FORMAL NAME:
PRESENT USE: SF Res
ORIGINAL USE: SF Res
ARCHITECT/ENGINEER:
BUILDER/CONTRACTOR:
PHYSICAL CONDITION OF STRUCTURE: Excellent () Good () Fair (x) Poor: ()
THEME:
STYLE: Shingle
DATE BUILT: 1908-1913

COUNTY: Anne Arundel
TOWN: Annapolis
LOCATION: 8-North-St. 6 North St.
COMMON NAME:
FUNCTIONAL TYPE: RES Map 32 Par 557
OWNER: Hillman Richard & Lisa ADDRESS: x Randall Ct. SEE 1993 FORM FOR CORRECT OWNER Annapolis, MD 21401
ACCESSIBILITY TO PUBLIC: Yes (x) No () Restricted ()
LEVEL OF SIGNIFICANCE: Local (✓) State () National ()

GENERAL DESCRIPTION:

Structural System

- Foundation: Stone () Brick (x) Concrete () Concrete Block ()
- Wall Structure
 - Wood Frame: Post and Beam () Balloon (x)
 - Wood Bearing Masonry: Brick () Stone () Concrete () Concrete Block ()
 - Iron () D. Steel () E. Other:
- Wall Covering: Clapboard () Board and Batten () Wood Shingle (x) Shiplap ()
 Novelty () Stucco () Sheet Metal () Aluminum () Asphalt Shingle ()
 Brick Veneer () Stone Veneer () Asbestos Shingle ()
 Bonding Pattern: Other:
- Roof Structure
 - Truss: Wood (x) Iron () Steel () Concrete ()
 - Other:
- Roof Covering: Slate () Wood Shingle () Asphalt Shingle () Sheet Metal (x)
 Built Up () Rolled () Tile () Other:
- Engineering Structure:
- Other:

Appendages: Porches () Towers () Cupolas () Dormers () Chimneys () Sheds () Ells ()
 Wings () Other:

Roof Style: Gable () Hip () Shed () Flat () Mansard () Gambrel () Jerkinhead ()
 Saw Tooth () With Monitor () With Bellcast () With Parapet () With False Front ()
 Other: Cross Gambrel

Number of Stories: 2½

Number of Bays: 4 x 3

Approximate Dimensions: 40 x 35

Entrance Location: Inset @ Left

THREAT TO STRUCTURE: No Threat (x) Zoning () Roads () Development () Deterioration () Alteration () Other:	LOCAL ATTITUDES: Positive () Negative () Mixed () Other:
--	---

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

Cross gambrel roof with assymetrical fenestration in end wall; shed wall dormers at side elevation in almost vertical lower plane of roof; projectin front gambrel end breaks at juncture of the two units that make up the pair, with entrances at but sides of perpendicular walls. All windows with molded caps; all cornices and rakes molded; end wall chimney.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

Important part of pair of American Queen Ann/Shingle style residences, critical to streetscape and important as types.

REFERENCES:

MAP: (Indicate North In Circle)



SURROUNDING ENVIRONMENT:

Open Lane()Woodland()Scattered Buildings()
Moderately Built Up()Densely-Built Up()
Residential()Commercial()
Agricultural()Industrial()
Roadside Strip Development()
Other:

RECORDED BY:


Russell Wright

ORGANIZATION:


Historic Annapolis, Inc

DATE RECORDED:

Aug. 1983



AA 1319
ANNAPOLIS HIST. DIST.





8 North St.

AA 1319

Annapolis, Anne Arundel County

Russell Wright July, 1982

Maryland Historical Trust,

Annapolis, Maryland

NE Elevation/camera facing SW