

Capsule Summary of 199-201 Main Street (AA-1323)

The property designated 199-201 Main Street is one of three sections making up the building designated 199-207 Main Street. The long building, divided into three shop units, was constructed between 1891 and 1893 as a single frame structure. This building replaced an earlier 18th-century building on a portion of the site which formed the northwestern end of a row of three attached Georgian buildings from 195-199 Main Street, historically known as the Coffee House.¹ Located on the southwest side of Main Street, the building from 199-207 Main Street is designed as a vernacular expression of the American Renaissance style which was widely promoted by the national architecture firm of McKim, Meade and White. The building stands as an example of the influence that national stylistic design trends had on local architecture.

As a whole, the 2-1/2-story building is of frame construction and is set upon a brick foundation. The walls, originally covered with weatherboard,² are clad with asbestos shingles. The mansard roof is covered with asphalt shingles on the front walls and standing seam metal on the top. The building is divided into three commercial units each of which feature individualized storefronts in the first story, a group of three windows recessed behind arched openings on the second story and pedimented dormers projecting from the mansard roof at the attic level. A continuous cornice as well as well as a continuous storefront cornice³ extends across the front of the building. The three units face Main Street, and extend back to an alley via a series of rear ells, all of which have been added onto in a haphazard manner over the years.

¹ Two of the buildings originally forming the property known as the Coffee House, 195 and 197 Main Street, although altered, are still intact. For more information on the Coffee House, see the MHT form for 197 Main Street (AA-576).

² Historic photos show the original weatherboard siding. The weatherboard is also visible underneath the present cladding in certain places where asbestos shingles are deteriorating.

³ Based upon historic photographs, it does not appear as if this storefront cornice is original. A continuous balustrade set upon a projecting cornice originally extended across the front.

MARYLAND HISTORICAL TRUST
MD INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY

Inventory No. AA-1323

=====

1. Name of Property

=====

historic name _____

other names 99-101 Main or Church Street

=====

2. Location

=====

street & number 199-201 Main Street not for publication _____

city or town Annapolis vicinity _____

state Maryland code _____ county Anne Arundel code _____

zip code 21401

=====

3. State/Federal Agency Certification

N/A

=====

4. National Park Service Certification

N/A

=====

5. Classification

=====

Ownership of Property (Check all that apply)

- private
 public-local
 public-State
 public-Federal

Category of Property (Check only one box)

- building(s)
 district
 site
 structure
 object

Number of Resources within Property

Contributing Noncontributing

<u>1</u>	_____	buildings
_____	_____	sites
_____	_____	structures
_____	_____	objects
<u>1</u>	_____	Total

Is this property listed in the National Register?

Yes Name of Listing Annapolis Historic District

No _____

=====
6. Function or Use
=====

Historic Functions (Enter categories from instructions)

Cat: Commerce/Trade Sub: Store

Current Functions (Enter categories from instructions)

Cat: Commerce/Trade Sub: Store

=====
7. Description
=====

Architectural Classification (Enter categories from instructions)

Colonial Revival

Materials (Enter categories from instructions)

foundation Brick

roof Asphalt shingles

Standing seam metal

walls Asbestos shingles over weatherboard

other _____

Narrative Description (Describe the historic and current condition of the property.) See Continuation Sheet No. 7-1

=====
8. Statement of Significance
=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties
Annapolis Survey
199-201 Main Street
Anne Arundel County, Maryland

Inventory No. AA-1323
Page 4

=====
Areas of Significance (Enter categories from instructions)

Architecture

Period of Significance 1891-1893

Significant Dates 1891-1893

Significant Person (Complete if Criterion B is marked above)

Cultural Affiliation _____

Architect/Builder unknown

Narrative Statement of Significance (Explain the significance of the property.) See Continuation Sheet No. 8-1

=====
9. Major Bibliographical References
=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Articles, Books, Published and Unpublished Resources

Anderson, Elizabeth B. Annapolis: A Walk Through History.
Centreville, MD: Tidewater Publishers, 1984.

Anne Arundel County Assessment Records. 1876-1896; 1896-1905.
Maryland State Archives. Record Group C35.

Anne Arundel County Land Records. Anne Arundel County Courthouse
and Maryland State Archives, Annapolis, Maryland.

Baltz, Shirley. The Quays of the City, An Account of the Bustling
Eighteenth Century Port of Annapolis. Annapolis, MD: The Liberty
Tree, Ltd., 1975.

Cromley, Elizabeth and Stephen Calloway. The Elements of Style, A
Practical Encyclopedia of Interior Architectural Details. New
York: Simon and Schuster, 1991.

Jennings, Jan and Herbert Gottfried. American Vernacular Design,
1870-1940. New York: Van Nostrand Reinhold Company, 1985.

----- American Vernacular Interior Architecture,
1870-1940. Ames, IW: Iowa State University
Press, 1988.

Longstreth, Richard. The Buildings of Main Street. Washington,
D.C.: The Preservation Press, 1987.

Lounsbury, Carl R. An Illustrated Glossary of Early Southern
Architecture and Landscape. New York: Oxford University Press,
1994.

The Maryland Comprehensive Historic Preservation Plan. Maryland
Historical Trust. Department of Economic and Community
Development, June 1986.

McAlester, Virginia and Lee McAlester. A Field Guide to American
Houses. New York: Alfred A. Knopf, 1985.

McIntire, Robert Harry. Annapolis Maryland Families. Baltimore:
Gateway Press, Inc., 1979.

Maryland Inventory of Historic Properties
Annapolis Survey
199-201 Main Street
Anne Arundel County, Maryland

Inventory No. AA-1323
Page 6

=====
National Register Bulletin: How to Complete the National Register
Registration Form 16A. Washington, D.C.: National Park Service,
1991.

Papenfuse, Edward. In Pursuit of Profit, The Annapolis Merchants
in the Era of the American Revolution, 1763-1805. Baltimore, MD:
The Johns Hopkins University Press, 1975.

----- . "Southern Urban Society after the Revolution:
Annapolis, Maryland, 1782-1786." Final Report for NEH Grant
#H69-0-178, Historic Annapolis Foundation, 1969.

Radoff, Morris L. Buildings of the State of Maryland at Annapolis
Publication No. 9. Annapolis, MD: The Hall of Records Commission,
1954.

Record Group 29 "Records of the Bureau of the Census." 1900, 1910
and 1920 Census; Anne Arundel County, Maryland.

Warfield, J.D. The Founders of Anne Arundel and Howard Counties,
Maryland. Westminster, MD: Family Line Publications, 1990.

Warren, Mame. Then Again...Annapolis, 1900-1965. Annapolis, MD:
Time Exposure Limited, 1990.

Maps and Drawings

Bird's Eye View of the City of Annapolis, Charles Magnus, 1864,
Reproduced, 1967. Bird's Eye View of the City of Annapolis, Edward
Sachse, ca. 1858. (Maryland Hall of Records, MdHR G 1213-349)
Church Circle, Annapolis, MD, ca. 1790. Watercolor by C. Milburn.
Gray's New Map of Annapolis, Anne Arundel County, MD., 1877.
Hopkins, G.M. Map of Annapolis, 1878.
Map of Annapolis, Southern Map Company, Baltimore, MD., 1905.
Plan of Annapolis, Geo. H. Shafer, 25 July 1718.
Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1897, 1903, 1908,
1913, 1921, 1930, 1954.

Photographs

Hayman Collection, 1920ca-1930ca. Record Group SC1406. Annapolis,
Maryland: Maryland State Archives.

Mame Warren Collection, 1859-1910. Record Group SC985. Annapolis,
Maryland: Maryland State Archives.

Photographic Collection at the Historic Annapolis Foundation.

=====
City Directories

Mullin-Kille and Capital-Gazette City Directory of Annapolis, MD.
Ohio: Mullin-Kille; Evening Capital; and the Maryland
Gazette, 1949.

Polk's City Directory of Annapolis, MD. New York: R.L. Polk and
Co., 1928, 1954.

=====
10. Geographical Data
=====

Acreage of Property less than 1 acre

Verbal Boundary Description (Describe the boundaries of the
property.)

The property designated as 199-201 Main Street occupies Parcel 753
on Tax Map 4-6.

Boundary Justification (Explain why the boundaries were selected.)

The property designated 199-201 Main Street has been associated
with Parcel 753 since 1925 when the lot on which the building at
199-207, built 1891-1893 and divided into three units, was divided
into two lots.

=====
11. Form Prepared By
=====

name/title K. Williams & L. Trieschmann - Architectural Historians
organization Traceries date May 25, 1994
street & number 5420 Western Avenue telephone (301) 656-5283
city or town Chevy Chase state MD zip code 20815
=====

12. Property Owner
=====

name Shirley D. Williams
street & number 1995 Fairfax Road telephone _____
city or town Annapolis state MD zip code 21401
=====

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1323

Section 7 Page 1 199-201 Main Street
name of property
Anne Arundel County, MD
county and state

=====

The property designated 199-201 Main Street is one of three sections making up the building designated 199-207 Main Street. The long building, divided into three shop units, was constructed between 1891 and 1893 as a single frame structure. This building replaced an earlier 18th-century building on a portion of the site which formed the northwestern end of a row of three attached Georgian buildings from 195-199 Main Street, historically known as the Coffee House.¹ Located on the southwest side of Main Street, the building from 199-207 Main Street is designed as a vernacular expression of the American Renaissance style which was widely promoted by the national architecture firm of McKim, Meade and White.

As a whole, the 2-1/2-story building is of frame construction and is set upon a brick foundation. The walls, originally covered with weatherboard,² are clad with asbestos shingles. The mansard roof is covered with asphalt shingles on the front walls and standing seam metal on the top. The building is divided into three commercial units each of which feature individualized storefronts in the first story, a group of three windows recessed behind arched openings on the second story and pedimented dormers projecting from the mansard roof at the attic level. A continuous cornice as well as well as a continuous storefront cornice³ extends across the front of the building. The three units face Main Street, and extend back to an alley via a series of rear ells, all of which have been added onto in a haphazard manner over the years.

The unit designated as 199-201 Main Street is the far southeastern unit of the building. The front elevation of 199-201 consists of a side-passage entry and storefront on the first story, a group of three windows on the second story, and a pedimented dormer above at the attic level. The side-passage entry of the first story is located in the southeast end of the facade and leads to the upper

¹ Two of the buildings originally forming the property known as the Coffee House, 195 and 197 Main Street, although altered, are still intact. For more information on the Coffee House, see the MHT form for 197 Main Street (AA-576).

² Historic photos show the original weatherboard siding. The weatherboard is also visible underneath the present cladding in certain places where asbestos shingles are deteriorating.

³ Based upon historic photographs, it does not appear as if this storefront cornice is original. A continuous balustrade set upon a projecting cornice originally extended across the front.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY Inventory No. AA-1323
CONTINUATION SHEET

Section 7 Page 2 199-201 Main Street
name of property
Anne Arundel County, MD
county and state

=====
levels of the building; the store entry is located at the northwest end and leads directly into the first story store. The side-passage entry has a single 9-light, cross-panel wood replacement door, while the store entry holds an all-glass replacement door with a wood frame. The doors are reached by two brick steps; because of the incline of the street, this unit is the only one of the three which has brick steps. Between the two doors is a 15-light replacement show window, set upon a masonry foundation and clad with vertical board siding. In front of the show window is a brick planter, surrounded by a wrought iron railing. Immediately above the show windows and doors is a horizontal band or frieze board of wood, clad with vertical board siding, and bearing the name of the store. A continuous bracketed wood cornice extends above this frieze board; four pairs of wood brackets interspersed by dentils divide the unadorned frieze and support the narrow projecting cornice shelf.

The second story features a group of three 6/1 windows, separated from each other by side casing and all recessed behind an arched opening in the wall surface. This arched opening was originally flanked at its upper sides by open roundels in the weatherboard walls; these have been covered by the asbestos shingles. A continuous wood cornice with four small wood brackets dividing the narrow frieze board and supporting the projecting cornice shelf extends across the entire facade of the group of three buildings. The attic level, formed by the mansard roof, has a large pedimented dormer with three 6/1 windows. The tympanum of the pediment is louvred for ventilation.

The southwest elevation is the only other exposed elevation of the attached building. It consists of the rear wall of the 2-1/2-story building and a two-story rear ell projecting from its southeast end. The rear wall of the 2-1/2-story section is located in the northwest end bay; it has a window filled with an air conditioning unit on the first story, a 6/1 window also with an air conditioning unit in the lower sash on the second story. A shed roof dormer with a pair of 6/1 windows projects from the center of the mansard roof. The two-story projecting ell is constructed of frame and is covered with asbestos shingles on the side. Abutting the rear of this two-story ell is a single-story shed roof addition, with a make-shift second story enclosed porch with plywood walls added atop it. The southwest wall of the single-story ell is similarly clad with asbestos shingles and has two 6/1 windows. A parged brick chimney is located against this back wall and extends above

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY Inventory No. AA-1323
CONTINUATION SHEET

Section 7 Page 3 199-201 Main Street
name of property
Anne Arundel County, MD
county and state

=====

the ell; a metal flue with a metal flue pot projects from the brick chimney.

The northwest elevation of the rear ell has a single 6/1 window on the first story and a three-light window with a granite sill at the basement level.

The interior of the building, on the first floor, contains no historic elements other than the 8" double-beaded baseboard. The acoustical tile ceiling is covered with track lighting and the floor is carpeted. The upper floors were not accessible and therefore not included in the survey.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY Inventory No. AA-1323
CONTINUATION SHEET

Section 8 Page 1 199-201 Main Street
name of property
Anne Arundel County, MD
county and state

=====
The building at 199-207 Main Street was constructed as a single building divided into three commercial units designated as 199-201; 203-205; and 207 Main Street in the period between 1891 and 1893.⁴ The building is designed in a vernacular expression of the American Renaissance style of architecture that was being promoted by the national firm of McKim, Meade and White. The building stands as an example of the influence that national stylistic design trends had on local architecture. The southeastern end section of the building was erected on the site of an earlier 18th-century building which had formed the attached row from 195-199, and known historically as the Coffee House.⁵

The property was originally part of a large tract of land owned by Colonel Philemon Lloyd. At his request, the property was surveyed and documented as Lot 48 on the Stoddert Map of 1718. Colonel Philemon Lloyd, born in 1646, was the son of Colonel Edward and Alice (Crouch) Lloyd.⁶ Following the death of Lloyd in circa 1732-1738, Daniel Dulany inherited lots 48, 49, and 50. Daniel Dulany was the second husband of Henrietta Maria Lloyd Chew, the daughter of Philemon Lloyd. In 1748, Dulany sold the three lots with houses to his daughter Henrietta Maria Dulany and her husband, Edward Dorsey.⁷ Dorsey subdivided lot 48 in 1757, leasing one part to Thomas Hyde and another part to Charles Wallace for 99 years.

In 1772, a Provincial Court case divided the property of Henrietta Maria Dulany between her daughters, Mary Chew Paca and Margaret Chew Bordley. William and Mary Paca received all of lot 48.⁸ William Paca was a signer of the Declaration of Independence and third governor of Maryland. His wife was Mary Chew, daughter of Samuel and Henrietta Maria (Lloyd) Chew. Following the death of

⁴ The buildings do not appear on the 1891 Sanborn Map. Land record Liber SH 43 Folio 206 and dated 1/25/1893, mentions the "frame stores lately erected."

⁵ For information on the Coffee House, see the MHT form for 197 Main Street (AA-576).

⁶Robert Harry McIntire. Annapolis Maryland Families. (Baltimore: Gateway Press, Inc., 1979), p. 433.

⁷Liber RB 3 Folio 6

⁸ Provincial Court Judgement, Liber DD 18 Folio 527

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY Inventory No. AA-1323
CONTINUATION SHEET

Section 8 Page 2 199-201 Main Street
name of property
Anne Arundel County, MD
county and state

=====

Paca, Mary Chew married Daniel Dulany.⁹

In 1773, the Pacas conveyed the property to leasee Charles Wallace. Wallace, a prominent member of the merchant community, began his career in Annapolis in the 1740s as a staymaker.¹⁰ In 1769, he purchased a large tract of undeveloped land that stretched from the foot of Church Street up to State House Circle. Laying out the property into lots, Wallace established two streets, Fleet and Cornhill Streets. In 1771, Wallace began the construction of the third State House, additionally providing supplies for the buildings erection. Unable to complete the building, he resigned in December 1779. Wallace joined forces with Joshua Johnson and John Davidson, creating the merchantile firm of Wallace, Davidson, and Johnson for the first time in 1771. Virtually unaffected by the commercial decline of Annapolis, Wallace died in 1812, leaving personal property appraised at \$23,774.20 and extensive real estate in Anne Arundel County and Annapolis.¹¹ The estate was bequeathed to his sister, Mary Howard.

In 1797, Mary Howard died, leaving the property to her children, Catherine Howard Latimer and Rebecca Howard Hanson.¹² Rebecca Howard was married to Alexander Contee Hanson, editor of the "Federalist" and United States Senator.¹³ Hanson, son of the Chancellor of Maryland, was a staunch Federalist and frank opponent of Madison's administration and the War of 1812.¹⁴ The Federal Direct Tax of 1798 charged Alexander C. Hanson and Randolph B. Latimer with three two-story brick houses on Church Street (Main Street), presumably 195 and 197 Main Street and a third similarly attached building which was on the site now occupied by 199-201 Main Street.

⁹Warfield, p. 235-237.

¹⁰Maryland Gazette (August 30, 1749).

¹¹ Edward C. Papenfuse. In Pursuit of Profit (Baltimore, MD: The Johns Hopkins University Press, 1975), pp 234-235.

¹² Lot Histories.

¹³Warfield, p. 316.

¹⁴Warfield, p. 340.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1323

Section 8 Page 3

199-201 Main Street
name of property
Anne Arundel County, MD
county and state

=====
In 1813, Mary Howard's heirs entered a suit for rents for Wallace's property, and in 1817, James, George and John Shaw, Trustees, sold part of Lot 48, including the current site of 199-207 Main Street, to Dennis Claude.

The property remained in Claude family hands until 1890, when it was purchased by Albert Gottschalk. In the period between 1891 and 1893, Albert Gottschalk bought adjacent lots to the one formerly owned by the Claude family, thereby amassing a parcel of land which today corresponds with 199-207 Main Street. A deed dated January 25, 1893 describes the placement of a fence as "dividing the same from certain frame stores lately erected by Albert Gottschalk."¹⁵ This deed reference, along with the Sanborn Maps, indicate that the building with its three store units from 199-207 Main Street was constructed between 1891 and 1893. Albert Gottschalk owned the three stores until his death in 1921.

In 1897, the store at 191-201 Main Street is shown on the Sanborn Map as a confectionery store. According to the census records for 1900, the building was leased by printer Samuel Brewer and his family. By 1903, the store had been transformed into a fruit store; it survived as such at least until 1913. In 1921, the store is listed as a barber shop. This change in use may correspond with the change in ownership: following Albert Gottschalk's death, the building was purchased by Leon L. Parker. Four years later, Parker defaulted on his mortgage and the property was sold at public sale on April 17, 1924 to Alexander Grott. An equity case ensued which named William E. Miller co-purchaser of the property. Following the equity case, the property from 199-207 was broken up into individual lots; 199-201 was retained by Alexander A. Grott, and 203-207 held onto by William E. Miller. Following this transaction, 199-201 Main Street changed hand several times and continued to operate as a store.

It is currently owned by Shirley D. Williams and houses retail space on the first story, leased to New World Sports Shop, with apartment space on the upper stories.

¹⁵ Liber SH 43 Folio 206

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1323

199-201 Main Street
name of property
Anne Arundel County, MD
county and state

=====

Historic Period Theme: Architecture, Landscape Architecture
and Community Planning

Geographic Organization: Western Shore

Chronological/Developmental Period: Industrial/Urban Dominance
1870-1930

Resource Type(s): Standing Structure

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1323

199-201 Main Street
name of property
Anne Arundel County, MD
county and state

=====
Chain of Title for 199-201 Main Street:

- 1718: All of Lot 48 on Stoddert's Map of Annapolis, owned by Philemon Lloyd
Stoddert Notebook, #51
- 1732-1738: Philemon Lloyd died and bequeathed it to daughter, Henrietta Maria Chew Dulany and her husband, Daniel Dulany.
- 1748: Daniel Dulany conveyed to Edward Dorsey and wife Henrietta Maria Dulany
Liber RB 3 Folio 6
- 1752: Edward and Henrietta Maria Dorsey to James Chalmers, 7 year lease of 25 feet on Church Street
Liber BB 2 Folio 589
- 1757: Edward Dorsey leased to Charles Wallace for 99 years
Part of lot 48, 50 feet on Church Street
Liber BB 2 Folio 54
- 1772: All of lot 48 divided in Provincial Court case between Mary Paca and Margaret Bordely, daughters of Henrietta Maria Dulany. Mary Paca received ground rent for leases.

Provincial Court Judgements Liber DD 18 Folio 527
- 1773: William and Mary Paca to Charles Wallace
Liber IB 4 Folio 285
- 1797: Property owned by Mary Howard, sister of Charles Wallace. Bequeathed to her daughters Catherine Latimer and Rebecca Hanson
- 1798: Federal Direct Tax: Alexander C. Hanson and Randolph B. Latimer for three, two-story brick dwellings on Church Street.
- 1813: Chancery case vs. Mary Howard's heirs and Charles Wallace's executors.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1323

199-201 Main Street
name of property
Anne Arundel County, MD
county and state

- =====
- 1816: Chancery Court Case between Mary Howard's heirs with James Shaw appointed as Trustee to sell property. Sold part of Parcel 48 to Dennis Claude.
- 1856: William Tell Claude, Trustee to Dennis Claude to Dr. Dennis Claude
Liber NHG 5 Folio 497
- 1871: Abram, Rachel, William Tell Claude, Dennis Claude Handy and Nannie D. Handy to Elizabeth Harwood
Liber SH 6 Folio 130
Dr. Dennis Claude died leaving property to wife Anna Claude and her heirs, Anne C. Handy, Abram, William Tell and Elizabeth. Anne C. Handy died; her portion went to sole heir Dennis Claude Handy. The family agreed to sell one parcel of ground on Main Street with a brick house and frame building to Elizabeth for \$6,000.00
- 1872: Elizabeth Harwood to William Tell
Liber SH 6 Folio 466
Being part of lot conveyed in previous deed (SH6/130)
- 1876: Heirs of Dr. Dennis Claude and William Tell Claude to Elizabeth Harwood
Liber SH 26 Folio 626
Elizabeth Harwood died intestate leaving property to Abram and D. Claude Handy; the latter of whom has since died devising his interest to Mannie D. Handy
- 1885: Elizabeth Harwood to Abram and Rachel and Dennis Claude Handy and Nannie Handy
Liber SH 26 Folio 626
William Tell Claude deceased, seized property on Main and conveyed to William Tell by Elizabeth Harwood and nephew D. Claude Handy
- 1890: Abram Claude and Rachel A. Claude and Anna D. Handy to Albert Gottschalk
Liber SH 36 Folio 381
- 1890: Albert Gottschalk and Grafton Ridout
Liber Sh 37 Folio 124
The two parties agree to exchange triangular parcels of land on Church Street which abut each other.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1323

199-201 Main Street
name of property
Anne Arundel County, MD
county and state

- =====
1893: Hannah Ann Gray to Albert Gottschalk of Baltimore
Liber SH 43 Folio 208
Deed describes fence to be erected on the lot as "...at the northwest corner of brick house now owned by Hannah Ann Gray on Church Street...and running with the gable or partition wall of said property dividing the same from certain frame stores lately erected by Albert..." (199-207 Main Street).
- 1921: Joseph Gottschalk and Mercantile Trust and Deposit Company of Baltimore, Trustee of estate of Albert Gottschalk to Leon L. Parker
Liber WNW 42 Folio 366


Albert Gottschalk's will, SRM 81/36 (1890) appointed Joseph Gottschalk and Bank as Trustees with full power to sell. Being the same property conveyed to Albert Gottschalk by three previous deeds.
- 1925: Richard B. Tippet, Assignee to Alexander Grott and William Miller.
Liber WMB22 Folio 37
A public sale on 4/17/1924. Tippet was empowered to sell in a mortgage from Leon L. and Frances Parker who defaulted on their mortgage. Includes 199-207 Main Street.
- 1925: Richard B. Tippet, Assignee to Alexander A. Grott
Liber WMB 17 Folio 119
Public sale on 4/17/1924, where Richard B. Tippet is named as assignee to sell property.
- 1925: Alexander and Ida Grott to Richard B. and Hazel Tippet
Liber WMB 17 Folio 120
One lot on Main (199-201 Main) and one lot on Duke of Gloucester
- 1931: Richard B. and Hazel Tippet to Angelo and Mary C. Geraci
Liber FSR 79 Folio 436
- 1944: Angelo and Mary C. Geraci to Bernard and Robert Green
Liber JHH 312 Folio 128

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1323

199-201 Main Street
name of property
Anne Arundel County, MD
county and state

- =====
- 1947: Bernard and Robert Green to James Green and Ida Green
Liber JHH 426 Folio 297
- 1951: James Green and Ida Green to Eugene and Victoria, Robert
S. and Frances Cloud
Liber JHH 613 Folio 264
Robert S. Cloud died and Frances married Joseph Parker
- 1972: Eugene W. Cloud and Victoria A. Cloud to Frances Louise
Parker
Liber 2488 Folio 391
- 1989: Frances Louise Parker to Shirley D. Williams
Liber 4818 Folio 811



Tax Map of Annapolis, Maryland
Map 4-6



AA-1323, AA-1324, AA-1325
199-207 MAIN STREET
ANNAPOLIS, MARYLAND
TRACERIES
MAY 1994
MARYLAND SHPO
FACADE, LOOKING WEST
1/5



AA-1323; AA-1324; AA-1325

199-207 MAIN STREET

ANNAPOLIS, MD

TRACERIES

MAY 1994

MD SHPO

SW ELEVATION

VIEW LOOKING NE

2/5



New York
Sports Shop

RON C

JEWELRY

YES WE'RE
OPEN

AA-1323

199-201 MAIN STREET
ANNAPOLIS, MARYLAND

TRACERIES

MAY 1994

MARYLAND SHPO

FACADE, LOOKING WEST

3/5



AA-1323

199-201 MAIN STREET
ANNAPOLIS, MD

TRACERIES

MAY 1994

MD SHPO

SW ELEVATION

VIEW LOOKING NE

4/5



AA-1323

199-201 MAIN STREET

ANNAPOLIS, MD

TRACERIES

MAY 1994

MD SHPD

NW ELEVATION

VIEW LOOKING EAST

5/5

MARYLAND HISTORICAL TRUST
 21 STATE CIRCLE
 SHAW HOUSE
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET
 Individual Structure Survey Form

SURVEY NUMBER: <u>AA 1323</u>
NEGATIVE FILE NUMBER:
UTM REFERENCES: Zone/Easting/Northing
U.S.G.S. QUAD. MAP:
PRESENT FORMAL NAME:
ORIGINAL FORMAL NAME:
PRESENT USE: <u>Comm/Apts</u>
ORIGINAL USE: <u>Comm/Apts</u>
ARCHITECT/ENGINEER:
BUILDER/CONTRACTOR:
PHYSICAL CONDITION OF STRUCTURE: Excellent () Good (X) Fair () Poor: ()
THEME:
STYLE: <u>Queen Anne Commercial</u>
DATE BUILT: <u>c1880</u>

COUNTY: <u>Anne Arundel</u>
TOWN: <u>Annapolis</u>
LOCATION: <u>199 Main St.</u>
COMMON NAME: <u>Rainbow Cleaners</u>
FUNCTIONAL TYPE: <u>COMM Map32 Par253</u>
OWNER: <u>Parket Frances L</u> ADDRESS: <u>1995 Fairfax Rd</u> <u>Annapolis, MD 21401</u>
ACCESSIBILITY TO PUBLIC: Yes (X) No () Restricted ()
LEVEL OF SIGNIFICANCE: Local (✓) State () National ()

GENERAL DESCRIPTION:

Structural System

- Foundation: Stone () Brick (X) Concrete () Concrete Block ()
- Wall Structure
 - Wood Frame: Post and Beam () Balloon (X)
 - Wood Bearing Masonry: Brick () Stone () Concrete () Concrete Block ()
 - Iron () D. Steel () E. Other:
- Wall Covering: Clapboard () Board and Batten () Wood Shingle () Shiplap ()
 Novelty () Stucco () Sheet Metal () Aluminum () Asphalt Shingle ()
 Brick Veneer () Stone Veneer () Asbestos Shingle (X)
 Bonding Pattern: _____ Other: _____
- Roof Structure
 - Truss: Wood (X) Iron () Steel () Concrete ()
 - Other:
- Roof Covering: Slate () Wood Shingle () Asphalt Shingle (X) Sheet Metal ()
 Built Up () Rolled () Tile () Other:
- Engineering Structure:
- Other:

Appendages: Porches () Towers () Cupolas () Dormers (X) Chimneys () Sheds () Ells (X)
 Wings () Other:

Roof Style: Gable () Hip () Shed () Flat (X) Mansard (X) Gambrel () Jerkinhead ()
 Saw Tooth () With Monitor () With Bellcast () With Parapet () With False Front ()
 Other: Inset Second Floor

Number of Stories: 3

Number of Bays: 3

Approximate Dimensions: 15 x 55

Entrance Location: R & L

THREAT TO STRUCTURE: No Threat () Zoning () Roads () Development () Deterioration () Alteration () Other:	LOCAL ATTITUDES: Positive () Negative () Mixed () Other:
--	---

24-1357
ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

Large pedimented dormer on Mansard roof, with triple window, molded cornice and curb; blind facade with round arch opening hiding triple window at second floor; bracketed cornice over first floor shop front, which is later.

RELATED STRUCTURES: (Describe)


Part of 199-207 Main

STATEMENT OF SIGNIFICANCE:

One of a row of three visually interesting late 19thC Commercial row, impressive because of scale and second floor screen wall, important to streetscape.

REFERENCES:

MAP: (Indicate North In Circle)



SURROUNDING ENVIRONMENT:

Open Lane()Woodland()Scattered Buildings()
Moderately Built Up()Densely-Built Up(x)
Residential()Commercial(x)
Agricultural()Industrial()
Roadside Strip Development()
Other:

RECORDED BY:

Russell Wright

ORGANIZATION:


Historic Annapolis, Inc

DATE RECORDED:


Aug 1983




AA-1323
ANNAPOLIS HIST. DIST.




ST. JOHN'S STREET



BLADEN STREET




NORTHWEST STREET




CATHEDRAL STREET



COLLEGE



CHURCH CIRCLE




SCHOOL ST.



DUKE




STREET



SHAW

SOUTH

STREET




ACTON

CHARLES

STREET

WASHINGTON



WEST



ST.



199 Main

AA 1323

Annapolis, Anne Arundel County
Russell Wright July, 1982
Maryland Historical Trust,
Annapolis, Maryland

NW Elevation/camera facing SE