

CAPSULE SUMMARY
34-36 East Street
AA-1809

The pair of buildings at 32 and 34-36 East Street are located on property that was originally part of the large tract of land associated with the Brice House. The dwellings, constructed between 1903 and 1905 atop a stone wall retaining wall enclosing the eastern edge of the 18th-century Brice House property, illustrate the subdivision of the once large and prominent 18th-century Annapolis estates into smaller parcels in the 19th century, and the subsequent development of these subdivisions.

The 2-1/2-story, three-bay frame dwellings are identical in form and detail to one another and, though distinct for their raised configuration, reflect a two-story, three-bay form of architecture that is common to the residential buildings on East Street. The dwelling at 34-36 East Street is located on the northwest side of East Street at the intersection of Martin Street. Presented in a vernacular manner and set upon a raised brick foundation, the frame dwelling is clad with a smooth stucco finish and is covered with a gable roof with a central dormer window and central chimney. A two-story ell, original to the house, spans almost the entire rear elevation of the dwelling, while a single-story porch addition, raised upon a high foundation, extends across two of the three bays of the facade.

Originally constructed as rental property, the building at 34-36 East Street has been owner-occupied since 1912 when it was sold independent of 32 East Street.

MARYLAND HISTORICAL TRUST
MD INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY

Inventory No. AA-1809

=====

1. Name of Property

=====

historic name _____

common/other name 34-36 East Street

=====

2. Location

=====

street & number 34-36 East Street not for publication

city or town Annapolis vicinity

state Maryland code MD county Anne Arundel code 003

zip code 21041

=====

3. State/Federal Agency Certification

N/A

=====

4. National Park Service Certification

N/A

=====

5. Classification

=====

Ownership of Property (Check all that apply)

- private
 public-local
 public-State
 public-Federal

Category of Property (Check only one box)

- building(s)
 district
 site
 structure
 object

Number of Resources within Property

Contributing Noncontributing

<u>1</u>	<u> </u>	buildings
<u> </u>	<u> </u>	sites
<u> </u>	<u> </u>	structures
<u> </u>	<u> </u>	objects
<u>1</u>	<u> </u>	Total

Is this property listed in the National Register?

Yes Name of Listing Annapolis Historic District
No

Maryland Inventory of Historic Properties
Annapolis Survey
34-36 East Street
Anne Arundel County, Maryland

Inventory No. AA-1809
Page 2

=====
6. Function or Use
=====

Historic Functions (Enter categories from instructions)

Cat: Domestic Sub: Single Dwelling

Current Functions (Enter categories from instructions)

Cat: Domestic Sub: Single Dwelling

=====
7. Description
=====

Architectural Classification (Enter categories from instructions)

Vernacular

Materials (Enter categories from instructions)

foundation Parged brick

roof Gable: asphalt shingles

walls Stucco over brick

other _____

Narrative Description (Describe the historic and current condition of the property.)

See Continuation Sheet No. 7-1

=====
8. Statement of Significance
=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties
Annapolis Survey
34-36 East Street
Anne Arundel County, Maryland

Inventory No. AA-1809
Page 4

=====
Areas of Significance (Enter categories from instructions)

Architecture

Period of Significance 1903-1905

Significant Dates 1903-1905

Significant Person (Complete if Criterion B is marked above)

Cultural Affiliation undefined

Architect/Builder unknown

Narrative Statement of Significance (Explain the significance of the property.)

See Continuation Sheet No. 8-1

Maryland Inventory of Historic Properties
Annapolis Survey
34-36 East Street
Anne Arundel County, Maryland

Inventory No. AA-1809
Page 5

=====
9. Major Bibliographical References
=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Anderson, Elizabeth. *Annapolis, A Walk Through History*. Centerville, MD: Tidewater Publishers, 1984.

Anne Arundel County Assessment Records. 1876-1896; 1896-1905. Maryland State Archives. Record Group C35.

Anne Arundel County Land Records. Anne Arundel County Courthouse and Maryland State Archives, Annapolis, Maryland.

Papenfuse, Edward and Jane McWilliams. "Southern Urban Society after the Revolution: Annapolis, Maryland, 1782-1786." Final Report for NEH Grant #H69-0-178, Historic Annapolis Foundation, 1969.

Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1897, 1903, 1908, 1913, 1921, 1930, 1954.

Southern Map Company, *Map of Annapolis*, Baltimore, MD, 1905.

=====
10. Geographical Data
=====

Acreage of Property less than one acre

Verbal Boundary Description (Describe the boundaries of the property.)

The property designated as 34-36 East Street is located on Parcel 1288 as indicated on Tax Map 4-6.

Boundary Justification (Explain why the boundaries were selected.)

The building located at 34-36 East Street has been associated with Parcel 1288 since its construction in 1902-1905.

=====
11. Form Prepared By
=====

name/title L. Trieschmann & K. Williams, Architectural Historians
organization Traceries date May 1, 1995
street & number 5420 Western Avenue telephone 301/656-5283
city or town Chevy Chase state MD zip code 20815
=====

12. Property Owner
=====

name Carlo Tripodi and F. Tripodi
street & number 34-36 East Street telephone _____
city or town Annapolis state MD zip code 21401
=====

Section 7 Page 1

34-36 East Street
name of property
Annapolis, Maryland
county and state

=====

The pair of attached dwellings located at 32 and 34-36 East Street were constructed between 1903 and 1905¹ atop a stone wall enclosing the eastern edge of the 18th-century Brice House property. The 2-1/2-story, three-bay, frame dwellings are identical in form and detail to one another and, though distinct for their raised configuration, reflect a two-story, three-bay form of architecture that is common to the residential buildings on East Street.

EXTERIOR

The dwelling at 34-36 East Street is one of a pair of attached dwellings located on the northwest side of East Street at the intersection of Martin Street. It is a 2-1/2-story, three-bay, side-passage frame structure, clad with a smooth stucco finish and set upon a raised brick foundation. The dwelling is covered with a gable roof with a central dormer window and central chimney. A two-story ell, original to the house, spans almost the entire rear elevation of the dwelling, while a single-story porch addition (post-1954), raised upon a high foundation, extends across two of the three bays of the facade.

The south facade of the dwelling is divided into three equal bays on the first and second stories and has an English basement built into the raised foundation and located under the first-story porch. The raised foundation level is constructed of brick, parged with stucco on the facade. Only the west end of this foundation level is exposed, as the foundation supporting the porch abuts the foundation and extends across the two eastern bays of the house. A small, two-light fixed window is located in the exposed western end bay of the foundation wall. The entrance to the English basement is reached through a door opening located at the foundation level under the raised porch.

The first story, raised upon the high foundation and reached by the porch set upon a parged concrete block foundation, consists of a side-entry and two 6/6 windows. The entry is fitted with a wood and glass replacement door with a single-light transom above. The

¹ According to the 1903 Sanborn Map, the site of 32-34 East Street was unimproved. In 1905, when the division of Martin's estate was completed, Lot 11 had been improved by the erection of the duplex presently on the site. The construction of the buildings by 1905 is further documented by the *Map of Annapolis, Maryland* published by the Southern Map Company in 1905.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1809

Section 7 Page 2

34-36 East Street
name of property
Annapolis, Maryland
county and state

=====

door and window immediately next to it retains the original square-edged wood casing and molded lintel, while the other window has square-edged aluminum trim covering the original. The two-bay porch, built after 1954, has a hipped roof, supported by turned columns, and a balustrade with square balusters. The porch itself features a beaded board ceiling and a wood floor.

The second story has three 6/6 windows. All of the original window trim on this story is covered with aluminum replacement trim. All of the first and second story windows have shutters.

A boxed wood cornice with an ogee cap is visually supported by four equally spaced wood brackets. A central pedimented dormer is located on center of the south slope of the gable. The dormer is fitted with a 2/2 window and has side walls clad with asphalt shingles.

The west side elevation of the dwelling extends along a narrow brick passage separating this duplex from the attached flankers of the Brice house next door and includes both the side wall of the main block of the house and the side wall of the rear ell. The main block of the house, two bays deep, is lit by one window on each level. The first and second stories have 6/6 windows, while the sash in the attic level window in the gable end is not visible. The west side wall of the rear ell of the house has a door and window on the first story and two windows on the second story. Though the windows here are 6/6, they appear to be interior dividers or "snap-in" muntins. The windows all have aluminum trim surrounding the original wood trim.

The north (rear) elevation of the house includes the north wall of the rear ell and a narrow, exposed bay on the main block of the house. Both wall surfaces are clad with a smooth stucco finish. The exposed bay of the main block has a 6/6 window on both the first and second stories with aluminum window trim. The rear ell has two bays of 6/6 windows on the second story and a single window on the first story. Ghosting of a second window on this first story indicates that it was originally lit with two openings.

The interior of the dwelling was not accessible for survey.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1809

Section 8 Page 1

34-36 East Street
name of property
Annapolis, Maryland
county and state

=====
The pair of buildings at 32 and 34-36 East Street, erected between 1903 and 1905, are located on property that was originally part of the large tract of land associated with Brice House at 42 East Street. The history of the attached dwelling illustrates the subdivision of the once large and prominent 18th century Annapolis properties into smaller parcels in the 19th century, and the subsequent development of these subdivisions. Originally constructed as rental property, the building at 34-36 East Street has been owner-occupied since 1912 when it was sold independent of 32 East Street.

SITE HISTORY

The building known as 34 East Street is located on a small portion of property originally owned by Captain John Brice and designated as Lot 94 on the Stoddert Map of 1718. Listed as a gentleman, merchant, and planter, John Brice immigrated to Annapolis about 1698 from England. Following Brice's death in 1713, his will devised all land and improvements to his wife, Sarah Worthington Brice.² When Sarah Brice died in 1729, the land was transferred to her eldest son, John Brice, Jr.

John Brice, Jr. (1705-1766) served as city alderman, vestryman for St. Anne's Church from 1758-1759, member of the Council of the Province of Maryland, and one of the Judges of Assize for the Western Shore.³ Having inherited the vacant property at the intersection of Prince George and East streets, John Brice, Jr. began planning the construction of the Georgian-style mansion known today as the Brice House at 42 East Street. The *Maryland Gazette* documents in 1761 advertisements placed by Brice for contractors to build a two-story dwelling with a stone cellar.⁴

When Brice, Jr. died in September 1766, Lot 94 "which came to me by descent from my father" and Lot 103 "plus bricks, lime, stone, timber for building a dwelling on those lots" was devised to his

² Will Records of Anne Arundel County, Liber L 13 Folio 589.

³ Robert Harry McIntire. *Annapolis, Maryland Families*. (Baltimore, MD: Gateway Press, Inc., 1980), p 86.

⁴ *The Maryland Gazette*, March 5, 1761.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1809

Section 8 Page 2

34-36 East Street
name of property
Annapolis, Maryland
county and state

=====

son, James Brice.⁵ James Brice (1746-1801) documented battles of the Revolutionary War in which he was engaged as an aide to George Washington.⁶ Brice served as Mayor of Annapolis in 1782 and 1788, a member of the Maryland Council of Safety, and a lieutenant in the Anne Arundel County militia. He also served as Acting Governor of Maryland in 1791-1792.

Following John Brice Jr.'s death, James Brice proceeded with the construction of the 33-room mansion as planned by his father. James Brice kept detailed records of construction which took place between 1766 and 1774, detailing the cost of the shingles, planks, lathe, hair, stone, bricks, and nails. His accounts list the names and the wages of each bricklayer, mason, carpenter, joiner, and servant who worked for him during the construction period.⁷ According to the Federal Direct Tax of 1798, James Brice was charged with a brick dwelling with two wings, a brick kitchen measuring 32 x 14 feet, a stable, and two small houses on two acres, assessed at \$1800.⁸

When James Brice died intestate in 1801, his nephew Nicholas Carroll Brice was appointed administrator. Prior to 1869, the Brice Family Heirs conveyed all of Lot 94, including the Brice House to William Martin.⁹ Martin died in 1869, leaving his Annapolis property to his son, Thomas E. Martin. Thomas Ennalls Martin (1811-1902)¹⁰ was the editor and publisher of the *Snow Hill Shield* and the *Maryland Gazette*. Martin served as Mayor of

⁵ Will Records of Anne Arundel County, Liber L 34 Folio 243.

⁶ McIntire, p 86.

⁷ Elizabeth Anderson. *Annapolis, A Walk Through History*. (Centerville, MD: Tidewater Publishers, 1984), p 92.

⁸ Federal Direct Tax of 1798, Folio 2.

⁹ This information is based on the fact that, according to the land records, at William Martin's death in 1869, he bequeathed the property to his son, Thomas E. Martin.

¹⁰ According to McIntire, *Annapolis Maryland Families*, p 450, Thomas Ennalls Martin was the son of Thomas Martin from Trappe, Maryland. However, according to Equity Case 2438 involving the division of Thomas E. Martin's estate in 1902, Thomas Ennalls Martin was the son of William Martin. McIntire provides no information on William Martin.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1809

Section 8 Page 3

34-36 East Street
name of property
Annapolis, Maryland
county and state

=====
Annapolis from 1879 to 1783. Martin lived in the Brice House with his family until his death in 1902, at which time Lot 94 was divided among his two surviving children and granddaughter. At the time of his death, Lot 94 "consisted of a large brick house, consisting of two wings on East and Prince George streets and grounds attached, a new frame dwelling recently erected on Prince George Street for his son Charles, and four frame dwelling erected on Martin Street, with ground rents of \$192 per year."¹¹ The gross value of the estate was assessed at \$165,000.

The heirs of Thomas Martin who wished to divide the property equally broke it up into a series of separate lots. Sarah Louise Martin Robb received the wings and colonnade of the Brice House on Lots 8 and 10, in addition to three lot on Martin Street. Claire Martin, the daughter of Charles Martin, received the frame dwelling on Prince George Street constructed for her father on Lot 7, and the four Martin Street dwellings. Robert E. Martin received the main block of the Brice House on Lot 9 and Lot 11 on East Street.

PROPERTY HISTORY

Robert E. Martin conveyed Lots 9 and 11 to his sister, Sarah Louise Martin Robb in 1905. According to the deed of sale, the property included buildings; however, the deed does not clearly specify which buildings existed at the time of the sale. A *Map of Annapolis*, published by the Southern Map Company, indicates that by 1905, the duplex at 32-34 East Street did in fact exist on Lot 94. It appears that the buildings were constructed between 1903 and 1905 by either Robert E. Martin prior to selling in 1905, or by S. Louise Robb immediately upon receipt of the land. The duplex was built atop a high foundation so as to incorporate part of a wall bordering the Brice property into the new buildings. Though sympathetic in overall form to the earlier mid and late-19th century dwellings found along East Street, this frame duplex is unique on the street for its high foundation--the result of incorporating an existing retaining wall into its structure. It is also distinguished by its prominent site overlooking East Street at its intersection with Martin Street.

¹¹Equity Case 2438, Equity Liber Gw 45 Folio 344.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1809

Section 8 Page 4

34-36 East Street
name of property
Annapolis, Maryland
county and state

=====

BUILDING HISTORY

S. Louise Robb immediately sold the Brice House in its entirety, but retained all of Lot 11 until 1910. At that time, Robb sold the dwelling at 32 East Street, while holding onto its twin at 34-36 East Street. In 1912, Thomas Linthicum, Jr. bought the dwelling at 34-36 East Street. Linthicum (1871-1922) served as an alderman, and postmaster from 1914 to 1922. By 1916, Linthicum defaulted on the mortgage and was forced to sell the property. The notice of the public sale was advertised in the *Evening Capital* and by handbills. Withdrawn from public sale for insufficient bids, the building at 34 East Street was purchased by Daniel J. and Daisy A. Dunne for \$2,200 at a private sale.

Two years after the death of Daniel J. Dunne in 1935, Daisy Dunne conveyed one-half interest in the single-family dwelling to her sister, Alberta Aurin. The sisters resided together in the dwelling until 1954, when Daisy Dunne died. Alberta Aurin retained full ownership until 1960, when she sold the property at 34 East Street to its present owners, Carlo and Fortunata Tripodi. The Italian-born Carlo Tripodi operated a shoe repair on Main Street.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1809

34-36 East Street
name of property
Annapolis, Maryland
county and state

=====

HISTORIC CONTEXT:

Geographic Organization: Western Shore

Chronological/Development Period (s):

Industrial/Urban Dominance, 1870-1930

Prehistoric/Historic Period Theme (s):

Architecture, Landscape Architecture and
Community Planning

Resource Type(s)

Category: Building

Historic Environment: Urban

Historic Function (s): Domestic/Single Dwelling

Known Design Source: unknown

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1809

34-36 East Street
name of property
Annapolis, Maryland
county and state

=====
Chain of Title for 34-36 East Street:

1766-1773: Colonel James Brice owned property

1801: Nicholas Carroll Brice owned property

pre 1860s: Brice Heirs to William Martin

January 1, 1869: William Martin devised to son Thomas E. Martin

April 20, 1902: Thomas E. Martin bequeathed to children, Robert E. Martin and S. Louise Robb, and infant child, Clare Louise Martin, of Charles R. Martin, his deceased son

May 16, 1902: Equity Case 2438: Robert E. Martin and S. Louise Robb versus Clare Louise Martin, infant, and Daniel R. Randall, Trustee
Land Records of Anne Arundel County,
Equity Liber GW 45 Folio 344

November 15, 1905: Robert E. Martin to S. Louise Robb
Land Records of Anne Arundel County,
Liber GW 49 Folio 87

July 11, 1912: S. Louise Robb to Thomas Linthicum
Land Records of Anne Arundel County,
Liber GW 94 Folio 262

April 20, 1916: James W. Owens, Attorney for Thomas Linthicum's defaulted mortgage, to Daniel J. and Daisy A. Dunne
Equity Case 4047
Land Records of Anne Arundel County,
Liber GW 127 Folio 325

September 11, 1935: Daniel J. Dunne bequeathed to wife, Daisy A. Dunne

July 1, 1937: Daisy A. Dunne to George B. Woelfel, Trustee for immediate reconveyance
Land Records of Anne Arundel County,
Liber FAM 166 Folio 289

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-1809

34-36 East Street
name of property
Annapolis, Maryland
county and state

=====

- July 1, 1937: George B. Woelfel, Trustee, to Bertie Aurin and Daisy A. Dunne
Land Records of Anne Arundel County,
Liber FAM 166 Folio 290
- September 26, 1954: Daisy A. Dunne bequeathed half interest
to sister Bertie Aurin
- October 18, 1960: Bertie Aurin to Carlo Tripodi and F.
Tripodi
Land Records of Anne Arundel County,
Liber 1432 Folio 314



AA-1809

34 EAST STREET
ANNAPOLIS, MD

TRACERIES
APRIL 1995

MARYLAND SHPO

FACADE, VIEW LOOKING NORTHEAST
1 OF 5



AA-1809
34 EAST STREET
ANNAPOLIS, MD
TRACERIES
APRIL 1995
MARYLAND SHPO
FACADE, VIEW LOOKING NORTHEAST
2 OF 5



AA-1809
34 EAST STREET
ANNAPOLIS, MD
TRACERIES
APRIL 1995
MARYLAND SHPO
NORTHWEST ELEVATION OF REAR
ELL, VIEW LOOKING EAST
5 OF 5



AA-1809
34 EAST ST
ANNAPOLIS, MD
TRALERIES
APRIL 1995
MARYLAND SHPO
NORTH ELEVATION, VIEW LOOKING SE
3 OF 5



AA-1809
34 EAST STREET
ANNAPOLIS, MD

TRACERIES

APRIL 1995

MARYLAND SHPO

NORTH CORNER OF REAR ELL. VIEW LOOKING EAST
4 OF 5

MARYLAND HISTORICAL TRUST
 21 STATE CIRCLE
 SHAW HOUSE
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET
 Individual Structure Survey Form

SURVEY NUMBER: <u>AA 1809</u>
NEGATIVE FILE NUMBER:
UTM REFERENCES: Zone/Easting/Northing
U.S.G.S. QUAD. MAP:
PRESENT FORMAL NAME:
ORIGINAL FORMAL NAME:
PRESENT USE: SF Res/Shoe Repair
ORIGINAL USE: SF Res
ARCHITECT/ENGINEER:
BUILDER/CONTRACTOR:
PHYSICAL CONDITION OF STRUCTURE: Excellent () Good (X) Fair () Poor: ()
THEME:
STYLE: Vernacular (Annapolis Federal)
DATE BUILT: 1908-1913

COUNTY: Anne Arundel
TOWN: Annapolis
LOCATION: 34 East Street
COMMON NAME:
FUNCTIONAL TYPE: Res Map 34 Par 24
OWNER: Carlo & F. Tripodi
ADDRESS: 34 East Street Annapolis, MD 21401
ACCESSIBILITY TO PUBLIC: Yes (X) No () Restricted ()
LEVEL OF SIGNIFICANCE: Local (X) State () National ()

GENERAL DESCRIPTION:

Structural System

- Foundation: Stone () Brick (X) Concrete () Concrete Block ()
- Wall Structure
 - Wood Frame: Post and Beam () Balloon (X)
 - Wood Bearing Masonry: Brick () Stone () Concrete () Concrete Block ()
 - Iron () D. Steel () E. Other:
- Wall Covering: Clapboard () Board and Batten () Wood Shingle () Shiplap ()
 Novelty () Stucco (X) Sheet Metal () Aluminum () Asphalt Shingle ()
 Brick Veneer () Stone Veneer () Asbestos Shingle ()
 Bonding Pattern: Other:
- Roof Structure
 - Truss: Wood (X) Iron () Steel () Concrete ()
 - Other:
- Roof Covering: Slate () Wood Shingle () Asphalt Shingle (X) Sheet Metal ()
 Built Up () Rolled () Tile () Other:
- Engineering Structure:
- Other:

Appendages: Porches (X) Towers () Cupolas () Dormers (X) Chimneys (X) Sheds () Ells (X)
 Wings () Other:

Roof Style: Gable (X) Hip () Shed () Flat () Mansard () Gambrel () Jerkinhead ()
 Saw Tooth () With Monitor () With Bellcast () With Parapet () With False Front ()
 Other:

Number of Stories: 2 1/2
 Number of Bays: 3
 Approximate Dimensions: 15 x 50

Entrance Location: Right

THREAT TO STRUCTURE: No Threat (X) Zoning () Roads () Development () Deterioration () Alteration () Other:	LOCAL ATTITUDES: Positive () Negative () Mixed () Other:
--	---

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

Pedimented dormer; bracketed cornice; molded window and transom lit door caps; two-bay porch with slender turned square columns; lower level of porch infilled.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

Good example of Vernacular Annapolis Federal in scale with Brice House to the west and contributing to the streetscape.

REFERENCES:

MAP: (Indicate North In Circle)




SURROUNDING ENVIRONMENT:

- Open Lane()Woodland()Scattered Buildings()
- Moderately Built Up()Densely-Built Up(✓)
- Residential()Commercial()
- Agricultural()Industrial()
- Roadside Strip Development()
- Other:

RECORDED BY: Russell Wright

ORGANIZATION: Historic Annapolis, Inc

DATE RECORDED: Aug. 1983



AA 1809
ANNAPOLIS HIST. DIST.



34 East

AA 1809

Annapolis, Anne Arundel County

Russell Wright July, 1982

Maryland Historical Trust,

Annapolis, Maryland

sw Elevation/camera facing NE