

### **Capsule Summary of 118 Conduit Street (AA-425)**

The house at 118 Conduit Street occupies a site on the south side of Conduit Street between Duke of Gloucester Street and Union Street, but closer to Union Street. The property was originally part of a larger tract of land that was subdivided and cut through, first by Conduit Street between 1877 and 1880 and later, by Union Street in 1890. The house at 118 Conduit Street was built after the extension of Conduit Street, but before 1880, when the then-owner of the property is listed in the U.S. Census Records as living at that address. It is one of six houses, now designated 114-128 Conduit Street, which were erected on the street immediately following its dedication.

The side-passage-plan house at 118 Conduit Street is a 2-1/2-story, three-bay frame building with some Italianate details, including a bracketed wood cornice on the front and a projecting window bay on the eastern side. The house was originally set back from the front of the lot, but now, since the addition of the front porch in the mid-20th century, fronts directly onto the public sidewalk and has no frontyard setback. It is covered with a gable roof with a central chimney stack and is clad with cedar shingles over the original weatherboard siding. A two-story wing, currently serving as a rental apartment, was added to the house between 1897 and 1903.

The house at 118 Conduit Street was built during the late 19th century as a result of the new-cut Conduit Street. Its construction, along with adjacent building activity, provides important insight into the residential development patterns and growth of this part of the City of Annapolis during the mid- to late 19th century.

MARYLAND HISTORICAL TRUST  
MD INVENTORY OF HISTORIC PROPERTIES  
ANNAPOLIS SURVEY

Inventory No. AA-425

1. Name of Property

historic name \_\_\_\_\_  
other names 118 Conduit Street

2. Location

street & number 118 Conduit Street not for publication \_\_\_  
city or town Annapolis vicinity \_\_\_\_\_  
state MD code \_\_\_\_\_ county \_\_\_\_\_ code \_\_\_  
zip code 21401

3. State/Federal Agency Certification N/A

4. National Park Service Certification N/A

5. Classification

Ownership of Property (Check all that apply)

- private  
 public-local  
 public-State  
 public-Federal

Category of Property (Check only one box)

- building(s)  
 district  
 site  
 structure  
 object

Number of Resources within Property

Contributing		Noncontributing	
<u>1</u>	_____	_____	buildings
_____	_____	_____	sites
_____	_____	_____	structures
_____	_____	_____	objects
<u>1</u>	_____	_____	Total

Is this property listed in the National Register?

Yes  Name of Listing Annapolis Historic District  
No \_\_\_\_\_

Maryland Inventory of Historic Properties  
Annapolis Survey  
118 Conduit Street  
Anne Arundel County, Maryland

Inventory No. AA-425  
(Page 2)

=====

6. Function or Use

=====

Historic Functions (Enter categories from instructions)

Cat: Domestic Sub: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Current Functions (Enter categories from instructions)

Cat: Domestic Sub: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

=====

7. Description

=====

Architectural Classification (Enter categories from instructions)

Vernacular  
\_\_\_\_\_  
\_\_\_\_\_

Materials (Enter categories from instructions)

foundation Brick  
roof Asphalt Shingles  
walls Cedar Shingles  
other \_\_\_\_\_  
\_\_\_\_\_

Narrative Description (Describe the historic and current condition of the property.) See Continuation Sheet No. 7-1

=====

8. Statement of Significance

=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties  
Annapolis Survey  
118 Conduit Street  
Anne Arundel County, Maryland

Inventory No. AA-425  
(Page 4)

=====  
Areas of Significance (Enter categories from instructions)

Architecture  
\_\_\_\_\_  
\_\_\_\_\_

Period of Significance 1877-1880  
\_\_\_\_\_  
\_\_\_\_\_

Significant Dates 1877-1880  
\_\_\_\_\_  
\_\_\_\_\_

Significant Person (Complete if Criterion B is marked above)  
\_\_\_\_\_

Cultural Affiliation \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Architect/Builder unknown  
\_\_\_\_\_  
\_\_\_\_\_

Narrative Statement of Significance (Explain the significance of the property.) See Continuation Sheet No. 8-1

Maryland Inventory of Historic Properties  
Annapolis Survey  
118 Conduit Street  
Anne Arundel County, Maryland

Inventory No. AA-425  
(Page 5)

---

---

9. Major Bibliographical References

---

---

(Cite the books, articles, legal records, and other sources used in preparing this form.)

**Articles, Books, Published and Unpublished Sources**

Anderson, Elizabeth B. Annapolis: A Walk Through History.  
(Centreville, MD: Tidewater Publishers, 1984.

Annapolis Historic District. National Register of Historic Places  
Inventory-Nomination Form. 1984.

Anne Arundel County Assessment Records. 1876-1896. Maryland State  
Archives. Record Group C35.

Anne Arundel County Land Records. Anne Arundel County Courthouse  
and Maryland State Archives, Annapolis, Maryland.

Anne Arundel County Records of Incorporation [Deed of Dedication  
for the extension of Conduit Street]. Liber SH 13, Folio 138-140.  
Anne Arundel County Courthouse, Annapolis, Maryland

The Maryland Comprehensive Historic Preservation Plan. Maryland  
Historical Trust. Department of Economic and Community  
Development, June 1986.

Papenfuse, Edward. "Southern Urban Society after the Revolution:  
Annapolis, Maryland, 1782-1786." Final Report for NEH Grant #H69-  
0-178, Historic Annapolis Foundation, 1969.

"Historic Customhouse Inventory Form," n.d., Historic Annapolis  
Foundation.

Record Group 29 "Records of the Bureau of the Census." 1900, 1910  
and 1920 Census; Anne Arundel County, Maryland.

**Maps and Drawings**

Hopkins, G.M. Map of Annapolis, 1877.  
Map of Annapolis, Southern Map Company, Baltimore, MD., 1905.  
Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1897, 1903, 1908,  
1913, 1921, 1930, 1954.

**Prints and Photographs**

Warren, Mame. "The Annapolis I Remember Collection." Maryland  
State Archives. Negative Number SC 2140-364.

Maryland Inventory of Historic Properties  
Annapolis Survey  
118 Conduit Street  
Anne Arundel County, Maryland

Inventory No. AA-425  
(Page 6)

=====  
10. Geographical Data  
=====

Acreage of Property 3,981 square feet

Verbal Boundary Description (Describe the boundaries of the property.)

The property at 118 Conduit Street comprises Parcel 694 on Tax Map 32.

Boundary Justification (Explain why the boundaries were selected.)

Parcel 694 has historically been associated with 118 Conduit Street since its construction.

=====  
11. Form Prepared By  
=====

name/title Kim Williams/Architectural Historian  
organization TRACERIES date January 22, 1993  
street & number 1606 20th St., N.W. telephone (202) 232-6870  
city or town Washington, D.C. state     zip code 20009

=====  
12. Property Owner  
=====

name Marion S. Borsodi  
street & number 118 Conduit Street telephone (410) 263-3576  
city or town Annapolis state MD zip code 21401  
=====

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
ANNAPOLIS SURVEY  
CONTINUATION SHEET

Inventory No. AA-425

Section 7 Page 1

118 Conduit Street  
name of property  
Annapolis, MD  
county and state

=====

Built between 1877-1880, the house at 118 Conduit Street is located on the southern side of Conduit Street, near the intersection with Union Street. It is sited on a residential block of primarily free-standing and attached dwellings of similar size and scale that were also built during the late 19th century. The house itself is a free-standing structure separated from its western neighbor at 116 Conduit Street by approximately 11 feet and from its eastern neighbor by approximately 20 feet. An original ornate wrought iron railing encloses the side yards from the street.<sup>1</sup> An original wrought iron gate on the western side allows access to the side walk laid in brick and leads to the rear yard.

The side-passage-plan house at 118 Conduit Street is a 2-1/2-story, three-bay frame building with some Italianate details, including a bracketed wood cornice on the front and a projecting window bay on the eastern side. The house was originally set back from the front of the lot, but now, since the addition of the front porch in the mid-20th century, fronts directly onto the public sidewalk and has no frontyard setback. It is covered with a gable roof with a central chimney stack and is clad with cedar shingles over the original weatherboard siding. A two-story wing, currently serving as a rental apartment, was added to the house between 1897 and 1903. It extends off of the rear and wraps around the eastern side of the house.

The house is similar in size and scale to the other houses along Conduit Street, and was built concurrently with the group of six buildings located towards this end the street. The house is especially similar in detail to its two neighbors at 116 and 120 Conduit Street; although the builder remains undocumented, it appears that these three houses may have been built by the same builder.

Divided into three narrow bays, the front elevation consists, on the first floor, of a side-passage entry door and two, long and narrow windows, and on the second floor, by three slightly shorter window openings located directly above those on the first. Two dormer windows with large, overhanging eaves project from the wide

---

<sup>1</sup> An historic photograph of 118 Conduit Street shows the original wrought iron fence in its entirety before the addition of the front porch interrupted it. Mame Warren, "I Remember Collection," Maryland State Archives, SC-2140-364.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
ANNAPOLIS SURVEY  
CONTINUATION SHEET

Inventory No. AA-425

Section 7 Page 2

118 Conduit Street

name of property

Annapolis, MD

county and state

=====

gable of the main roof. The windows on both the first and second floor are surrounded by simple architraves with a slightly projecting cornice and contain 2/2 sash. The dormers have shorter, segmental-arched openings with 2/2 windows. The entry with its two-light transom is similarly surrounded by an architrave with a slightly projecting cornice. The entry door itself is a wood and glass replacement door.

The house was originally a flat-fronted dwelling, until in the period between 1913 and 1921, a porch was built across the front of the house. This hipped roof porch, set upon a brick pier foundation, has three slender wood columns. A simple balustrade extends between two of the three porch columns.<sup>2</sup>

The east and west side elevations present rather austere wall surfaces. Only two narrow windows, located towards the rear of the west elevation, pierce the entire wall surface. The east elevation is similarly unarticulated, save for a polygonal window bay located towards the front of the house. The window bay is a single-story and has windows on its three planar surfaces. Each window contains 2/2-light, double-hung sash.

The rear of the house opens onto a long and narrow yard and includes a two-story rear wing that wraps around the east side of the house. Originally a single-story rear wing that housed the kitchen/dining area, this space was raised, in two phases, to two full stories. The first addition, made to accommodate a second floor bathroom, occurred above the kitchen proper by 1913. The second addition, above the dining area and made to accommodate a bedroom, was built ca. 1920.<sup>3</sup>

Originally built as a single-family residence, the house was

---

<sup>2</sup> An historic photograph from the Mame Warren, "I Remember Collection" of 118 Conduit Street shows the house without the front porch.

<sup>3</sup> Mrs. Borsodi, the current owner of the property was born in the house. The second story above the kitchen was built as her bedroom when she was a child and although she can't remember the exact date, she thinks it was ca. 1920.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
ANNAPOLIS SURVEY  
CONTINUATION SHEET

Inventory No. AA-425

Section 7 Page 3

118 Conduit Street  
name of property  
Annapolis, MD  
county and state

=====

converted into two separate apartments in the 1960s or 1970s.<sup>4</sup> The current owner occupies the first floor apartment, while a tenant occupies the second floor level. This second floor apartment is entered through an entry door located on the front of the wrap-around rear wing.

The first floor features a modified side-passage, double-parlor plan. The narrow hallway opens off of the outside door and leads directly back to the large rear room or parlor. A single door opening off of the west side wall of the hall leads into the front room, currently serving as a bedroom. The square room is enlarged and lighted by the polygonal window bay located against the east wall. The wood floors, molded baseboard and molded door and window trim are all original.

A door on the north wall of the bedroom opens onto the rear parlor. This is a large living space with a fireplace located against the northern wall. The fireplace, located on center of the house and against the wall that is shared by the front room, probably served the front room as well, although no evidence remains. The current owner who was born in the house has no recollection of a fireplace serving this front room. The mantle to the fireplace in the rear room is a plain wood mantle with a projecting mantle piece. The southern wall of this parlor leads directly into the rear kitchen space, while a door leading to the basement opens off of the west side wall.

The rear kitchen is treated quite differently from the main section of the house and also is quite different from the other rear wings of the houses on Conduit Street. In particular, this wing differs in shape, size and interior details. The wing was originally one-story tall, as opposed to two, is square in plan as opposed to rectangular, and wraps around the side of the house instead of extending directly off of the back elevation of the house.

The interior of the kitchen features beaded board wainscoting not found elsewhere in the house, and simple, flat trim around the doors and windows that is unlike the molded trim found in the rest

---

<sup>4</sup> Although Mrs. Borsodi cannot remember the exact date, she knows that her father converted the single-family residence into two apartments in either the 1960s or 1970s.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
ANNAPOLIS SURVEY  
CONTINUATION SHEET

Inventory No. AA-425

Section 7 Page 4

118 Conduit Street  
name of property  
Annapolis, MD  
county and state

=====

of the house. The kitchen has a unornamented quality to it that is not found in any of the other kitchens on the block. The space itself is actually divided into two: a narrow room along the east side of the space was originally the kitchen proper, while the larger area accommodates a breakfast/dining room. However, the narrow kitchen area was divided into two to allow for a bathroom, while the seating area came to house much of the kitchen appliances. The second story additions occurred first, over the kitchen property, and then, over the dining/eating area.

The second floor of the house is currently rented out and was not accessible. According to the owner, however, the second floor has three rooms and a kitchenette and bathroom and the attic level is one large open space that is used for storage.

The basement level, reached from a door off of the rear room, is a full basement with brick floors and walls only under this rear room; a dirt crawl space extends off of the basement towards the rear and front of the house.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
ANNAPOLIS SURVEY  
CONTINUATION SHEET

Inventory No. AA-425

Section 8 Page 1

118 Conduit Street  
name of property  
Annapolis, MD  
county and state

=====  
The house at 118 Conduit Street occupies a site on the south side of Conduit Street between Duke of Gloucester Street and Union Street, but closer to Union Street. The property was originally part of a larger tract of land that was subdivided and cut through, first by Conduit Street between 1877 and 1880 and later, by Union Street in 1890. The house at 118 Conduit Street was built after the extension of Conduit Street, but before 1880, when it is listed in the U.S. Census Records.

The property now designated 118 Conduit Street was originally part of a large tract of land, designated Lot 35 on the Stoddert Map of 1718, and owned at that time by William Bladen, and later his son Thomas. In 1725 the land was sold to Benjamin Tasker. Upon Benjamin's death in 1768, the land went to his wife Anna, and in 1775, it was passed to their grandson Daniel Dulaney, Jr. In 1781, Daniel Dulaney's estate was sold. Part of Lot 35, on which 118 Conduit Street now stands, was sold to Col. John Stewart as a nominal purchaser for Nathaniel Ramsey. In 1793, Charles Wallace purchased the property from Nathaniel Ramsey. After Wallace's death, the property was sold by Nicholas Brewer, trustee in the Chancery Case involving Wallace's will to Edward Williams.

In the 66 year period between 1793 and 1859, the property passed through several hands, until eventually it was purchased by George Wells. George Wells, a prominent local resident who was state senator in 1854 and 1856, President of Farmers Bank of Annapolis, chief head of the Annapolis and Elkridge Railroad and Warden of St. Anne's Church, owned both halves of Stoddert Lot 35, as well as adjoining property. Towards the end of his life, George Wells fell into bankruptcy and his lands were sold by the bank to recover his debt. In 1878, William H. Thompson purchased a portion of Wells' estate from Alexander Randall, who was acting as Trustee for George Wells and the Farmer's National Bank. Thompson purchased the land that is currently designated 118-124 Conduit Street.

Prior to 1877, Conduit Street ran for a single block between Main Street and Duke of Gloucester Street. Named for the fact that in the 18th century it provided a passage, or conduit, from Main Street to Duke of Gloucester Street, Conduit Street was extended 1877-1878 to Spa Creek in order to provide access to new lots located behind Market Street. Cut at an angle to the already existing block of Conduit Street, the new stretch of Conduit Street began on the southwest side of Duke of Gloucester Street and ran at an angle perpendicular to it and parallel to Market Street. At

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
ANNAPOLIS SURVEY  
CONTINUATION SHEET

Inventory No. AA-425

Section 8 Page 2

118 Conduit Street  
name of property  
Annapolis, MD  
county and state

=====

this time, no cross street existed between Duke of Gloucester Street and Spa Creek. In 1890, Union Street, a one-block street, was cut between Conduit and Market Streets, bisecting the large and narrow block that had been created by the extension of Conduit Street to Spa Creek.

Prior to the extension of Conduit Street, only scattered development existed between Duke of Gloucester Street and Spa Creek. According to Gray's Map of Annapolis, 1877, a row of buildings aligned the southwest side of Duke of Gloucester Street and a few individual buildings were located on the northwest side of Market Street. No buildings within the interior of the square are indicated on the map. After Conduit Street was extended, 1877-1878, but before 1885, according to the Sanborn Map of 1885, a group of six buildings, identified as dwellings on the map, were erected on the new stretch of Conduit Street. The house at 118 Conduit Street is one of the two freestanding buildings located in the middle of this row. Although this house does not appear on the historic maps until 1885, census record research indicates that it was erected before 1880 when the house was occupied.

Bought by William H. Thompson in 1878, the property was then sold in 1884 to John M. Gesner.<sup>5</sup> According to U.S. Census records, Gesner, a musician in the Naval Academy Band, lived at the house with his wife, his daughter and two sons. One of his sons worked as a blacksmith, while his daughter worked as a clerk in a store.

In 1910, Gesner sold the property to Charles and Kathryn P. Shearman. Charles, an English-born singer, immigrated to America in 1905 and was naturalized a U.S. citizen in 1910. Charles lived at the house with his wife, two sons and daughter.<sup>6</sup> After the death of his wife, Kathryn, Charles Shearman remarried. In his

---

<sup>5</sup> Tax books indicate that John Gesner was assessed \$700.00 for a frame house on Conduit Street as early as 1879. However, the deed indicates that Gesner did not buy this property until 1884. The census records for 1880 indicate that John Gesner lived in an unnumbered house on Conduit Street with his family. The conflict in documents prevents a clear understanding of the property at this point. However, it is certain that the house was erected between 1877 and 1880 and maybe as early as 1879.

<sup>6</sup> Mr. Shearman's daughter, Marion Borsodi, who was born in the house is the current owner of the property today.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
ANNAPOLIS SURVEY  
CONTINUATION SHEET

Inventory No. AA-425

Section 8 Page 3

118 Conduit Street  
name of property  
Annapolis, MD  
county and state

=====

will, Charles left the property to his second wife, Alice Larnia, for life to be conveyed, at her death, to his daughter, Marion. In 1975, Marion Borsodi bought the property from her step-mother and moved back to the house in which she was born. Marion Borsodi currently owns and occupies the house.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
ANNAPOLIS SURVEY  
CONTINUATION SHEET

Inventory No. AA-425

Section \_\_\_\_\_ Page \_\_\_\_\_

118 Conduit Street  
name of property  
Annapolis, MD  
county and state

=====

**Historic Period Theme:** Architecture, Landscape Architecture & Community Planning

**Geographic Organization:** Western Shore

**Chronological/Developmental Period:** Industrial/Urban Dominance

**Resource Type(s):** Standing Structures

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
ANNAPOLIS SURVEY  
CONTINUATION SHEET

Inventory No. AA-425

Section \_\_\_\_\_ Page \_\_\_\_\_


118 Conduit Street  
name of property  
Annapolis, MD  
county and state

=====

**Chain of Title for 118 Conduit Street**

- 1878: George Wells to Alexander Randall, Trustee. Randall is give the power to sell Wells' land in two mortgages between Wells and the Farmer's National Bank of Annapolis. Liber SH 10 Folio 488 and 490. Alexander Randall is named Trustee in Liber SH 10 Folio 544.
- 1878: Alexander Randall, Trustee to William H. Thompson  
Liber SH 13 Folio 222
- 1884: William H. and Jane A. Thompson to John M. Gesner  
Liber SH 23 Folio 532
- 1910: John M. and Mary N. Gesner to Charles H. and Kathryn P. Shearman  
Liber GW 78 Folio 2
- 1975: Alice Lavinia Shearman Dove (formerly Alice Lavinia Shearman) and Marion S. Borsodi to Allan C. Westcott  
Liber 2749 Folio 434
- 1975: Allan C. Westcott to Marion S. Borsodi and Mary Lorna Cahall  
Liber 2749 Folio 436
- 1981: Richard S. Cahall, Trustee to Marion S. Borsodi and Mary Lornal Cahall.  
Liber 3396 Folio 553

NO CONDUIT IN  
FIRST FLOOR



STAIRS  
BASEMENT

Bathroom

CONDUIT STREET



A4-425

MARYLAND HISTORICAL TRUST  
 21 STATE CIRCLE  
 SHAW HOUSE  
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET  
 Individual Structure Survey Form

SURVEY NUMBER: <u>AA 425</u>
NEGATIVE FILE NUMBER:
UTM REFERENCES: Zone/Easting/Northing
U.S.G.S. QUAD. MAP:
PRESENT FORMAL NAME:
ORIGINAL FORMAL NAME:
PRESENT USE: SF Res
ORIGINAL USE: SF Res
ARCHITECT/ENGINEER:
BUILDER/CONTRACTOR:
PHYSICAL CONDITION OF STRUCTURE: Excellent ( ) Good (X) Fair ( ) Poor: ( )
THEME:
STYLE: Vernacular - Annapolis Federal
DATE BUILT: 1885-1891

COUNTY: Anne Arundel
TOWN: Annapolis
LOCATION: 118 Conduit Street
COMMON NAME:
FUNCTIONAL TYPE: Res Map 32 Par 194
OWNER: Mary L. Cahall ADDRESS: 1404 Samar Street Beltsville, MD 20705
ACCESSIBILITY TO PUBLIC: Yes (X) No ( ) Restricted ( )
LEVEL OF SIGNIFICANCE: Local (✓) State ( ) National ( )

GENERAL DESCRIPTION:

Structural System

- Foundation: Stone ( ) Brick (X) Concrete ( ) Concrete Block ( )
- Wall Structure
  - Wood Frame: Post and Beam ( ) Balloon (X)
  - Wood Bearing Masonry: Brick ( ) Stone ( ) Concrete ( ) Concrete Block ( )
  - Iron ( ) D. Steel ( ) E. Other:
- Wall Covering: Clapboard ( ) Board and Batten ( ) Wood Shingle (X) Shiplap ( )  
 Novelty ( ) Stucco ( ) Sheet Metal ( ) Aluminum ( ) Asphalt Shingle ( )  
 Brick Veneer ( ) Stone Veneer ( ) Asbestos Shingle ( )  
 Bonding Pattern: Other:
- Roof Structure
  - Truss: Wood (X) Iron ( ) Steel ( ) Concrete ( )
  - Other:
- Roof Covering: Slate ( ) Wood Shingle ( ) Asphalt Shingle ( ) Sheet Metal (X)  
 Built Up ( ) Rolled ( ) Tile ( ) Other:
- Engineering Structure:
- Other:

Appendages: Porches (X) Towers ( ) Cupolas ( ) Dormers (X) Chimneys (X) Sheds ( ) Ells (X)  
 Wings ( ) Other: Bay at east side wall

Roof Style: Gable (X) Hip ( ) Shed ( ) Flat ( ) Mansard ( ) Gambrel ( ) Jerkinhead ( )  
 Saw Tooth ( ) With Monitor ( ) With Bellcast ( ) With Parapet ( ) With False Front ( )  
 Other:

Number of Stories: 2 1/2  
 Number of Bays: 3 x 3 Entrance Location: Right  
 Approximate Dimensions: 15 x 40

THREAT TO STRUCTURE: No Threat (X) Zoning ( ) Roads ( ) Development ( ) Deterioration ( ) Alteration ( ) Other:
--

LOCAL ATTITUDES: Positive ( ) Negative ( ) Mixed ( ) Other:
---

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

AA-425

Two gabled dormers with later trim, original elliptical sash; good cornice with modillions and frieze; molded window and transom lit door caps; one story bay unit at front bay of left elevation; full width hipped roof porch on Tuscan columns.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

Good Vernacular Annapolis Federal despite alterations to roof dormers; good use of materials; contributes to streetscape.

REFERENCES:

MAP: (Indicate North In Circle)



SURROUNDING ENVIRONMENT:

Open Lane( ) Woodland( ) Scattered Buildings( )  
Moderately Built Up() Densely Built Up( )  
Residential( ) Commercial( )  
Agricultural( ) Industrial( )  
Roadside Strip Development( )  
Other:

RECORDED BY:

Russell Wright

ORGANIZATION:

Historic Annapolis, Inc

DATE RECORDED:

Aug. 1983

0204252509


Form 10-445  
(5/62)

<p>1. STATE Annapolis, Maryland          COUNTY          TOWN VICINITY          STREET NO. 118 Conduit Street</p> <p>ORIGINAL OWNER          ORIGINAL USE residence          PRESENT OWNER Chas. H. Sherman          PRESENT USE residence          WALL CONSTRUCTION wood shingle          NO. OF STORIES two plus dormer attic</p>	<p>HISTORIC AMERICAN BUILDINGS SURVEY          INVENTORY</p> <p>2. NAME</p> <p>DATE OR PERIOD Late 19th C.          STYLE 19th C. Annapolis residential          ARCHITECT          BUILDER</p> <p>3. FOR LIBRARY OF CONGRESS USE</p>
<p>4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION OPEN TO PUBLIC NO</p> <p>118 Conduit Street is a slightly larger version of 116 though brown shingle. Identical columned porch and 2/2 windows. The cornice has two small brackets and a row of modillions. The dormers are rather unique; the windows are 2/2 with elliptical tops, but the triangular gable roof is proportionately very large and extends over the edges and covers the whole dormer. 118 has a nice small yard. Needs only proper maintenance; close to other buildings of same scale and size.</p>	
<p>5. PHYSICAL CONDITION OF STRUCTURE</p>	<p>good</p>
<p>6. LOCATION MAP (Plan Optional)</p> <p>9. PUBLISHED SOURCES (Author, Title, Pages)          INTERVIEWS, RECORDS, PHOTOS, ETC.</p>	<p>7. PHOTOGRAPH</p> <p>9. NAME, ADDRESS AND TITLE OF RECORDER          William D. Morgan          Columbia University          New York City</p> <p>DATE OF RECORD July 25, 1967</p>




SUPPLEMENTAL INFORMATION AND PHOTOGRAPHS MAY BE ADDED ON SHEET OF SAME SIZE







AA-425  
 City of Annapolis  
 Property Tax Map Number 32  
 Maryland Department of Assessments and Taxation  
 Revised 1991  
 Scale: 1"=200'



AA 425  
ANNAPOLIS HIST. DIST.





Warren, Mame. The Annapolis I  
Remember Collection. Record Group  
SC2140-364. Annapolis, Maryland;  
Maryland State Archives. ND.



AA-425

118 Conduit Street

Anne Arundel, MD

groceries

December 1992

Maryland SHPO

Northwest elevation

1/7



NO  
PARKING  
THIS SIDE  
OF STREET

TOW AWAY  
ZONE

AA-425  
118 Conduit Street  
Annapolis, MD  
Traceries  
January 1993  
Maryland SHPO  
View of Northeast elevation  
2/7



AA-425

118 Conduit Street

Anne Arundel, MD

Faceries

December 1992

Maryland SHPO

Detail of 2nd floor former windows on  
northwest elevation

3/7



AA-425

118 Conduit Street

Annapolis, MD

Traceries

January 1993

Maryland SHPO

View of Southeast elevation

4/7



AA-425

118 Conduit Street

Annapolis, MD

Traceries

January 1993

Maryland SHPO

Detail of iron fence.

5/7



AA 425  
118 Conduit Street  
Annapolis, MD  
Traceries

January 1993  
Maryland SHPO  
interior view of southeast room  
4/7



118 Conduit Street AA-425  
Annapolis, MD.

Traceries

January 1993

Maryland SHPO

Interior view of middle room

9/17



AA-425

PHOTOGRAPH BY  
WILLIAM D. MORGAN  
118 Conduit St.  
VII/25/67

527



118 Conduit

AA 425

Annapolis, Anne Arundel County

Russell Wright July, 1982

Maryland Historical Trust,

Annapolis, Maryland

NE Elevation/camera facing SW

118 CONDUIT