

CAPSULE SUMMARY
George Heath House (AA-524)
201 Hanover Street

The Italianate-style dwelling at 201 Hanover Street was constructed between 1869 to 1876 by property owner George Heath, inventor of the tumble gates and patent locks used in the construction of the Erie Canal. Clad with a stucco finish, the house is constructed of oyster shells with concrete, representing an early use of this material for domestic building purposes. Heath devised the dwelling, together with the lot at 199 Hanover Street, to his daughter Mary Casler and granddaughter Annette Casler Horton. Casler proceeded to improve the property by constructing rental housing at 199, 203 and 205 Hanover Street, while residing at 201 Hanover Street, which remained in Heath family until 1927. In 1954, building was converted into three apartments and, by 1965, was renovated to again serve as a single-family dwelling.

The two-story, three-bay house was designed in an Italianate style, characterized by long and narrow 2/2 windows with window hoods and a wide-eaved roof. It is set upon a raised basement, separated from the first story by a watertable, and is covered with a low hipped roof, sheathed with standing seam metal. The roof features a central cupola and two brick chimneys -- one interior fireplace stack and one brick stovepipe stack. The original lot was subdivided and the former garage associated with the property was substantially modified to serve as a two-story dwelling.

MARYLAND HISTORICAL TRUST
MD INVENTORY OF HISTORIC PROPERTIES

Inventory No. AA-524

=====

1. Name of Property

=====

historic name George Heath House
common/other name _____

=====

2. Location

=====

street & number 201 Hanover Street not for publication _____
city or town Annapolis vicinity _____ state Maryland code MD
county Anne Arundel code 003 zip code 21401

=====

3. State/Federal Agency Certification N/A

=====

4. National Park Service Certification N/A

=====

5. Classification

=====

Ownership of Property (Check all that apply)

- private
- public-local
- public-State
- public-Federal

Category of Property (Check only one box)

- building(s)
- district
- site
- structure
- object

Number of Resources within Property

Contributing		Noncontributing	
<u>1</u>	_____	_____	buildings
_____	_____	_____	sites
_____	_____	_____	structures
_____	_____	_____	objects
<u>1</u>	_____	_____	Total

Is this property listed in the National Register?

Yes Name of Listing Annapolis Historic District
No _____

Maryland Inventory of Historic Properties
George Heath House
201 Hanover Street
Annapolis, Maryland

Inventory No. AA-524
Page 2

=====
6. Function or Use
=====

Historic Functions (Enter categories from instructions)

Cat: DOMESTIC Sub: Single Dwelling
DOMESTIC Multiple Dwelling

Current Functions (Enter categories from instructions)

Cat: EDUCATION Sub: School-Related

=====
7. Description
=====

Architectural Classification (Enter categories from instructions)

Italianate

Materials (Enter categories from instructions)

foundation Concrete

roof Hipped: Standing Seam Metal

walls Stucco: Oyster shells, Lime

other _____

Narrative Description (Describe the historic and current condition of the property.)

See Continuation Sheet No. 7-1

=====
8. Statement of Significance
=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties
George Heath House
201 Hanover Street
Annapolis, Maryland

Inventory No. AA-524
Page 4

=====
Areas of Significance (Enter categories from instructions)

Architecture

Period of Significance 1869-1954

Significant Dates 1869-1876
1954-1965

Significant Person (Complete if Criterion B is marked above)

Cultural Affiliation Undefined

Architect/Builder Unknown

Narrative Statement of Significance (Explain the significance of the property.)

See Continuation Sheet No. 8-1

Maryland Inventory of Historic Properties
George Heath House
201 Hanover Street
Annapolis, Maryland

Inventory No. AA-524
Page 5

=====
9. Major Bibliographical References
=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Anne Arundel County Land and Will Records. Anne Arundel County Courthouse and Maryland State Archives, Annapolis, Maryland.

Archives of Maryland, XXXVIII, "Act for Keeping Good Rules and Orders," 1696.

McIntire, Robert Harry, Annapolis Maryland Families. Baltimore, MD: Gateway Press, Inc., 1980.

Papenfuse, Edward and Jane McWilliams. "Southern Urban Society After the Revolution: Annapolis, Maryland, 1782-1786." Final Report for NEH Grant #H69-0-178, Historic Annapolis Foundation, 1969.

Record Group 29, "Records of the Bureau of the Census." 1880, 1900, 1910, and 1920 Census; Anne Arundel County, Maryland.

Warren, Marion E. and Mame Warren, The Train's Done Been and Gone, Annapolis, MD: M.E. Warren, 1976.

Maps and Drawings

Magnus, Charles. Bird's Eye View of the City of Annapolis, 1864, Reproduced 1967.

Sachse, Edward. Bird's Eye View of the City of Annapolis, circa 1858. Maryland Hall of Records, MdHR G 1213-349.

Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1903, 1908, 1913, 1921, 1930, and 1954 updated.

Maryland Inventory of Historic Properties
George Heath House
201 Hanover Street
Annapolis, Maryland

Inventory No. AA-524
Page 6

=====
10. Geographical Data
=====

Acreeage of Property 2794 Square Feet

Verbal Boundary Description (Describe the boundaries of the property.)

The property designated as 201 Hanover Street is located on Parcel 1386 as shown on Grid 11, Map 4 in the City of Annapolis.

Boundary Justification (Explain why the boundaries were selected.)

The building has been historically associated with this property since its construction in the period between 1869 and 1876.

=====
11. Form Prepared By
=====

name/title L. Trieschmann & K. Williams, Architectural Historians
organization Traceries date February 2, 1998
street & number 5420 Western Avenue telephone 301/656-5283
city or town Chevy Chase state MD zip code 20815

=====
12. Property Owner
=====

name Annapolis Baptist Union; Alumni Association, Inc.
street & number P.O. Box 242 telephone _____
city or town Annapolis state MD zip code 21404
=====

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

Section 7 Page 1

George Heath House
name of property
Annapolis, Maryland
county and state

=====
The two-story, three-bay house at 201 Hanover Street was built between 1869 and 1876 in an Italianate style, characterized by long and narrow 2/2 windows with window hoods and a wide-eaved roof. Clad with a stucco finish, the house is constructed of oyster shells with lime and oyster shell aggregate. Consequently, it represents an early use of this material for domestic building purposes. It is set upon a raised basement, separated from the first story by a watertable, and is covered with a low hipped roof, sheathed with standing seam metal. The roof features a central cupola and two brick chimneys -- one interior fireplace stack and one brick, stovepipe stack. An original wrought iron fence and gate delineate the perimeter of the front yard, while a tall picket fence at the back separates the house from what was historically part of its rear yard and garage structure. The original lot was subdivided and the former garage associated with 201 Hanover Street was substantially modified to serve as a two-story dwelling.

The facade (northeast elevation) facing Hanover Street is divided into three bays. The first story consists of a pedimented entry porch and door located in the northwestern end bay and two 2/2 segmental-arched windows with window hoods and stone sills. The entry porch is raised upon concrete pier walls and is reached by a flight of stone steps. Pairs of extremely attenuated wood columns support a broad pediment and its standing seam metal gable roof. Double exterior doors with glazed upper panels and a broad, segmental arched transom spanning the pair, lead into an entry narthex which then leads to two interior replacement doors and separate offices. The window hoods are segmentally arched with a recessed central panel and corner blocks with label molds beneath them. The hood moldings appear to be of masonry and are clad with a stucco finish.

The second story consists of three segmentally arched 2/2 windows, similarly featuring window hoods and stone sills. The basement level consists of one pair of square-shaped 2/2 casement windows, similarly having a window hood and stone sill, and an English basement door, located under the steps leading to the main entry. The basement level door, partially sunk beneath ground is reached by a flight of brick steps leading from the side alley to the door. The door, set within the masonry with a window hood, has a glazed upper panel over a lower wood panel. This door may have originally been a window converted into a door.

The low hipped roof of the house, which rises above the second story windows, has wide boxed eaves supported by paired, exposed rafter ends. These exposed rafters, similar to those found next

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

Section 7 Page 2

George Heath House
name of property
Annapolis, Maryland
county and state

=====

door at 199 Hanover Street (AA-1103), are not common and less ornate than the typical Italianate bracketed cornice.

The southeast elevation facing the alley between 199 and 201 Hanover Street is four bays deep on all three levels (basement, first and second stories). The first and second stories have four symmetrically aligned 2/2 rectangular windows, set within segmental-arched surrounds and featuring window hood moldings. Here, the window sills are wood, as opposed to stone. The basement level similarly consists of four 2/2 windows; however, the windows are set deep into the concrete walls and have no trim or window hoods, though screens with mitred joints are placed in front of the window flush with the wall surface.

The northwest side elevation, facing a driveway between 201 and 205 Hanover Street is less well lit with only two 2/2 windows in the two rear bays on the first story and several, small square openings with single-light casements at the second story level.

The southwest elevation facing the rear yard has a contemporary and make-shift, double-story porch appended to the stuccoed rear wall. The porch has a half-hipped roof supported by square wood posts on both levels. A spiral wooden stair is located at the northwestern end of the porch and provides access to the two levels. The rear wall of the house has been altered and consists of three door openings on the first story and two doors on the second story. The first story has two single wood and glass replacement doors located in the southeastern end and a double, wood and glass door in the opposite end. An original, four-paneled wood door is leaning against the exterior wall on the first story. The second story has two single door openings leading to the second story porch. The basement retains the only original door -- a four-paneled wood door with recessed lower panels and glazed upper panels.

Surrounding the rear yard of 201 Hanover Street is a tall, wood picket fence. Behind the fence, is another dwelling reached by the drive leading between 199 and 201 Hanover Street. This house is a two-story gable-roofed dwelling with stuccoed wall surfaces which appears from maps to have incorporated the two-story garage that was historically associated with 201 Hanover Street. The back building, nor the interior of 201 Hanover Street were accessible for survey.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

Section 8 Page 1

George Heath House
name of property
Annapolis, Maryland
county and state

=====
The Italianate-style dwelling at 201 Hanover Street was constructed in the period between 1869 to 1876 by property owner George Heath, the inventor of the tumble gates and patent locks of the Erie Canal.¹ Clad with a stucco finish, the house is constructed of oyster shells with concrete, representing an early use of this material for domestic building purposes. Heath devised the dwelling, together with the lot at 199 Hanover Street, to his daughter Mary Casler and granddaughter Annette Casler Horton. Casler proceeded to improve the property by constructing rental housing at 199, 203 and 205 Hanover Street, while residing at 201 Hanover Street. The concrete dwelling remained in Heath family until 1927. In 1954, building was converted into three apartments and, by 1965, was renovated again to serve the Adams family as a single-family dwelling.

PROPERTY HISTORY

The property on which the building at 201 Hanover Street is sited was historically owned by Captain Thomas Gassaway (1684-1739), who started his career as a storekeeper for Perkins, Buchanan, & Brown. At the time of his death in 1739, Gassaway owned only a portion of Parcel 25. The parcel, bounded by King George Street, Maryland Avenue, Hanover Street, and Governor Street, was divided into twenty equally sized lots denoted A through W. The Gassaway heirs retained ownership of five of the lots (B, H, I, G, L, and M) until the 1760s and 1770s. Now designated as 203-207 Hanover Street, Lot I was the first of the Gassaway tracts to be sold. Lot H, which included the present property known as 195-201 Hanover Street, was conveyed months later to Daniel of St. Thomas Jenifer. The sale also included Lots G and D to the southeast (now property of the United States Naval Academy).

By the summer of 1772, Jenifer was in possession of Lots B, H, D, I, G, L, and M, thus, reuniting the lots originally owned by Gassaway in 1739. Jenifer was one of the most important individuals in the influential Province of Maryland prior to the Revolutionary War and, in the later events leading to the adoption of the Constitution of the United States. Jenifer, however, appears never to have resided in the Hanover Street property, selling Lots B, H, and I within months to local merchant and

¹ George Heath purchased the unimproved lot in 1869. By 1876, Mary Casler is occupying a dwelling on the property for which she is assessed \$1,800.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

Section 8 Page 2

George Heath House
name of property
Annapolis, Maryland
county and state

=====

importer, Anthony Stewart.

Believing his future destroyed following the burning of his cargo ship, the Peggy Stewart, Anthony Stewart left Annapolis for Nova Scotia. His wife and children remained, eventually defaulting on the mortgage and transferring the Hanover Street property back to Daniel of St. Thomas Jenifer in 1779. In May 1783, Thomas Stone became the owner and occupant of the grand house and Lots B, H, I, G, L, and M. One of the four signers of the Declaration of Independence from Maryland, Stone died only a few years after obtaining ownership. Consequently, the vast parcel was ordered to be sold by the executors of the estate, M.J. Stone and G.R. Brown. Purchased by William Harwood, and confirmed by Daniel of St. Thomas Jenifer in 1801, the property remained in the hands of the Harwood family until 1864. Alexander Randall and Joseph H. Nichols were appointed trustees by the Chancellor to sell the real estate of General Richard Harwood of Thomas to Robert Welch of Ben. The vast property, which stretched from Hanover Street to King George Street and Maryland Avenue, was then immediately reconveyed by Welch to his son, Charles, for \$4,000.

Residing in the Peggy Stewart House at 207 Hanover Street, Charles Sellman Welch was an alderman and Judge of the Orphans Court for Anne Arundel County. By the late 1860s, Welch and his wife Ann Rebecca Welch began to subdivide and individually convey portions of the property fronting on Hanover Street to the southeast of his dwelling.

BUILDING HISTORY

On January 1, 1869, George Heath of Onondaga County, New York purchased the unimproved rectangular lots at 199 and 201 Hanover Street from Welch for \$750. Born in 1802, Heath was the inventor of the tumble gates and patent locks used in the construction of the Erie Canal.² Now a permanent resident of Annapolis, Heath had the imposing Italianate-style dwelling at 201 Hanover Street constructed between 1869 and 1876. The building, constructed on concrete foundation, served as Heath's primary residence until his death in 1879. A two-story porch, constructed of brick and wood frame, connected the northwest elevation of the dwelling with those

² Robert Harry McIntire, Annapolis Maryland Families. (Baltimore, MD: Gateway Press, Inc., 1980), p. 316.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

Section 8 Page 3

George Heath House
name of property
Annapolis, Maryland
county and state

=====

of 203 and 205 Hanover Street. The porch was open on the first story and enclosed with brick on the second. Based on the Sanborn Fire Insurance Maps of Annapolis, Heath also had a two-story, hipped roof garage/stable erected in the same oyster shell concrete at the rear of the property.

According to his last will and testament, Heath devised ownership of the vacant lot at 199 Hanover Street in 1876 to his eldest daughter, Mary. Born in Little Falls, NY, Mary Heath married Marcus Casler in 1830. Casler, also originally from Little Falls, NY, was a captain in the 121st New York Volunteers during the Civil War, later working as a clerk at the United States Naval Academy.³

Title of the dwelling at 201 Hanover Street was bequeathed to Heath's granddaughter, Annette Heath Casler. Affectionately known as Nettie, Casler was born in New York about 1856. With her marriage in 1884 to Frederick Horton of Albany, NY, Nettie Casler transferred title of the Italianate style dwelling to her mother, Mary Casler. The deed of sale stated "...which house and lot was conveyed to me by my grandfather George Heath by deed." It further stated that Mary Casler was "...to have and to hold the above described premises during her natural life, and at her death, the said property to be equally devised between her three children, viz: Nettie H., Moreau M. and George H. Casler."⁴

As documented by tax assessment records, while residing at 201 Hanover Street, Mary Casler had the fashionable Italianate-style dwelling at 199 Hanover Street erected in 1882 for use as rental property. She was charged with one frame dwelling, valued at \$1,200, at 199 Hanover Street in 1882. By 1886, Casler was being assessed for a single concrete dwelling at 201 Hanover Street, valued at \$3,024; a single concrete dwelling at 203 Hanover Street, valued at \$1,764; and a concrete house at 205 Hanover Street, valued at \$1,764; as well as the frame dwelling at 199 Hanover Street. The census records for 1880 and 1900 indicate that Mary Casler and several of her children lived at 201 Hanover Street, while leasing the other three dwellings.

Between 1901 and 1903, over half of the block on which 201 Hanover Street was constructed had been purchased by the United States

³ McIntire, p. 124.

⁴ Land Records of Anne Arundel County, Liber SH 23 Folio 122.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

Section 8 Page 4

George Heath House
name of property
Annapolis, Maryland
county and state

=====

Naval Academy for future expansions. All of the wood frame and brick dwellings, the majority of which had been erected between 1844 and 1891, were razed. By 1913, a security fence was constructed directly to the southeast of 195 Hanover Street (AA-1101) and 198 King George Street (AA-1130) to separate the town from the school, thereby obscuring the circa 1908 dwellings erected by the Naval Academy.

Despite the death of Mary Casler in 1904, the Casler family retained ownership of the properties at 199 Hanover Street until 1921, and 201 Hanover Street until 1927.⁵ As many of the heirs had returned to live in New York, both of the dwellings in Annapolis were utilized as rental housing prior to the sales. A widower, Frederick Horton conveyed title of the dwelling at 201 Hanover Street to Florence Nelson Tardy and Walter B. Tardy in 1927.

Born in Arkansas in 1875, Walter Benjamin Tardy relocated to Annapolis from Longview, TX. Tardy, a graduate of the United States Naval Academy (class of 1898), retired as a Lieutenant Commander in 1918. Florence Tardy was born in Washington, DC about 1877. The Tardy family, which included three children, resided in the dwelling at 205 Hanover Street, leasing 201 Hanover Street in 1928 to L.B. Austin. Although the Tardy family retained ownership, the city directory for 1949 lists Mrs. Anne T. Cupp as occupant of the dwelling.

In January 1954, widow Florence Tardy conveyed 201 Hanover Street to Edward and Renee Taliaferro. Based on the city directories, it appears that the Taliaferros renovated the single-family dwelling to function as multiple-family housing. The directory for 1928 lists three individuals, Gene H. Miller, Marie Antoinette Jordon, and Marie P. Parlett, as residing in the building at 201 Hanover Street. By 1956, they had conveyed ownership to the Quintus Corporation, which continued to maintain the three apartments until 1965. The building was purchased that year by David Gregg Adams, Jr. and his wife, Lucie Foster Adams.

The Adams family returned the building to its original function as a single-family dwelling in the summer of 1965. The dwelling was occupied by the Adams family until 1982, when the children of David

⁵ The dwellings at 203 and 205 Hanover Street were razed, and therefore no deed research was conducted to determine when the Casler family conveyed title of the properties.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

Section 8 Page 5

George Heath House
name of property
Annapolis, Maryland
county and state

=====

and Lucie Adams conveyed it to the Annapolis Baptist Student Union, Alumni Association. As the current owners of the building, the Annapolis Baptist Student Union uses the structure as office and meeting space. The rear garage has since been converted into the single-family dwelling.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

George Heath House
name of property
Annapolis, Maryland
county and state

=====

HISTORIC CONTEXT:

Geographic Organization: Western Shore

Chronological/Development Period (s):

Industrial/Urban Dominance (1870-1930)
Modern Period (1930-present)

Prehistoric/Historic Period Theme (s):

Architecture, Landscape Architecture, and
Community Planning

RESOURCE TYPE(S)

Category: Building

Historic Environment: Urban

Historic Function (s): DOMESTIC/Single Dwelling
DOMESTIC/Multiple Dwelling
EDUCATION/School-Related

Known Design Source: Unknown

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

George Heath House
name of property
Annapolis, Maryland
county and state

=====
Chain of Title for 201 Hanover Street:

April 1772: John Stoughton Harmonson to Daniel of St.
Thomas Jenifer
Provincial Court Records
Liber IB 3 Folio 282

July 1772: Daniel of St. Thomas Jenifer to Anthony
Stewart
Provincial Court Records
Liber DD 5 Folio 335

1779: Stewart to Daniel of St. Thomas Jenifer
Land Records of Anne Arundel County,
Liber NH 1 Folio 85

May 30, 1783: Daniel of St. Thomas Jenifer to Thomas
Stone
Land Records of Anne Arundel County,
Liber NH 11 Folio 295

October 1787: Thomas Stone died; property ordered to be
sold by executors M.J. Stone and G.R.
Brown
Will Records of Charles County
Liber AH 9 Folio 459

1801: J.M. and Margaret Daniel and T. and
Mildred Daniel to Thomas Harwood
Land Records of Anne Arundel County
Liber NH 11 Folio 348

June 16, 1853: Alexander Randall and Joseph H.
Nicholson, Esquire, as Trustees for the
estate of General Richard Harwood to
Robert Welch of Ben
Land Records of Anne Arundel County,
Liber NHG 2 Folio 604

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

George Heath House

name of property

Annapolis, Maryland

county and state

=====

June 14, 1864:	Robert Welch of Ben to son Charles Welch Land Records of Anne Arundel County, Liber NHG 12 Folio 337
January 1, 1869:	Charles S. and Ann Rebecca Welch, and Sally Welch, wife of Robert Welch of Ben, to George Heath Land Records of Anne Arundel County, Liber SH 3 Folio 208
January 1, 1869:	Charles S. and Ann Rebecca Welch to George Heath Land Records of Anne Arundel County, Liber SH 3 Folio 206
September 9, 1879:	George Heath to granddaughter, Nettie H. Casler Land Records of Anne Arundel County, Liber SH 14 Folio 579
February 6, 1884:	Nettie H. Casler to mother, Mary H. Casler Land Records of Anne Arundel County, Liber SH 23 Folio 122
December 17, 1924:	Nicholas H. Green and George E. Rullman, Trustees, to Florence Nelson Tardy and Walter B. Tardy Equity Case 4924 Land Records of Anne Arundel County, Liber WNW 91 Folio 373
June 15, 1925:	Nicholas H. Green and George E. Rullman, Trustees, to Frederick Horton Equity Case 4924 Land Records of Anne Arundel County, Liber WNW 99 Folio 73
August 24, 1927:	Frederick Horton, widower, to Florence Nelson Tardy and Walter B. Tardy Land Records of Anne Arundel County, Liber FSR 23 Folio 151

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-524

George Heath House
name of property
Annapolis, Maryland
county and state


=====

January 28, 1954: Florence Nelson Tardy, widow, to Edward Henry Hugh Taliaferro and Renee Florence Camille Taliaferro
Land Records of Anne Arundel County,
Liber JHH 810 Folio 246

November 5, 1956: Edward Henry Hugh Taliaferro and Renee Florence Camille Taliaferro to the Quintus Corporation
Land Records of Anne Arundel County,
Liber GTC 1077 Folio 143

June 30, 1965: The Quintus Corporation to David Gregg Adams, Jr. and Lucie Foster Adams
Land Records of Anne Arundel County,
Liber 1877 Folio 23

November 1, 1982: Elizabeth R. Adams and Walter D. Wysocki, by David G. Adams, their attorney; David Gregg Adams, Jr. and Lucie Foster Adams, and Elizabeth R. Dasms, by David G. Adams, make payable to Lucie F. Adams as agent to Annapolis Baptist Student Union; Alumni Association, Inc.
Land Records of Anne Arundel County
Liber 3531 Folio 232



INSET
1" = 100'

AA-524
201 HANOVER ST

UNITED STATES NAVAL ACADEMY
P. 1400



SEE INSET,
1" = 100'

MAP OF ANNAPOLIS, No. 4-6
Maryland Department of Assessments and Taxation
1967; Revised 1991
Scale 1' = 200'



AA-52A
201 HANOVER STREET
ANNAPOLIS, MD
TRACERIES
MARCH 1998
MD SHPO
VIEW LOOKING SW
1 OF 4



AA-52A
201 HANOVER STREET
ANNAPOLIS, MD
TRACERIES
MARCH 1998
MD SHPO
VIEW LOOKING WEST
2 OF 4



AA-524

201 HANOVER ST
ANNAPOLIS, MD

TRALERIES

MARCH 1998

MD SHPO

VIEW LOOKING NE

3 OF 4



AA-524

201 HANGOVER ST REAR

ANNAPOLIS, MD

TRAILERIES

MAY 1998

MD SHPO

FORMER GARAGE AT REAR, LOOKING WEST

4 OF 4

MARYLAND HISTORICAL TRUST
 21 STATE CIRCLE
 SHAW HOUSE
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET
 Individual Structure Survey Form

SURVEY NUMBER: <u>AA 524</u>
NEGATIVE FILE NUMBER:
UTM REFERENCES: Zone/Easting/Northing
U.S.G.S. QUAD. MAP:
PRESENT FORMAL NAME:
ORIGINAL FORMAL NAME:
PRESENT USE: <u>Apa rtments</u>
ORIGINAL USE: <u>SF Res</u>
ARCHITECT/ENGINEER:
BUILDER/CONTRACTOR:
PHYSICAL CONDITION OF STRUCTURE: Excellent (X) Good () Fair () Poor: ()
THEME:
STYLE: <u>Italianate</u>
DATE BUILT: <u>1897-1903</u>

COUNTY: <u>Anne Arundel</u>
TOWN: <u>Annapolis</u>
LOCATION: <u>201 Hanover</u>
COMMON NAME:
FUNCTIONAL TYPE: <u>RES</u> <u>Map 34 Par 126</u>
OWNER: <u>Adams David G Jr & Lucie F</u>
ADDRESS: <u>107 Scot Dr.</u> <u>Annapolis, MD 21401</u>
ACCESSIBILITY TO PUBLIC: Yes (X) No () Restricted ()
LEVEL OF SIGNIFICANCE: Local (✓) State () National ()

GENERAL DESCRIPTION:

Structural System

1. Foundation: Stone () Brick (X) Concrete () Concrete Block ()
2. Wall Structure
 - A. Wood Frame: Post and Beam () Balloon (X)
 - B. Wood Bearing Masonry: Brick () Stone () Concrete () Concrete Block ()
 - C. Iron () D. Steel () E. Other:
3. Wall Covering: Clapboard () Board and Batten () Wood Shingle () Shiplap ()
 Novelty () Stucco (X) Sheet Metal () Aluminum () Asphalt Shingle ()
 Brick Veneer () Stone Veneer () Asbestos Shingle ()
 Bonding Pattern: Other:
4. Roof Structure
 - A. Truss: Wood (X) Iron () Steel () Concrete ()
 - B. Other:
5. Roof Covering: Slate () Wood Shingle () Asphalt Shingle (X) Sheet Metal ()
 Built Up () Rolled () Tile () Other:
6. Engineering Structure:
7. Other:

Appendages: Porches (X) Towers () Cupolas () Dormers () Chimneys () Sheds () Ells (X)
 Wings () Other:

Roof Style: Gable () Hip (X) Shed () Flat () Mansard () Gambrel () Jerkinhead ()
 Saw Tooth () With Monitor () With Bellcast () With Parapet () With False Front ()
 Other:

Number of Stories: 2
 Number of Bays: 3 x 2
 Approximate Dimensions: 35 x 50

Entrance Location: Right

THREAT TO STRUCTURE: No Threat (X) Zoning () Roads () Development () Deterioration () Alteration () Other:
--

LOCAL ATTITUDES: Positive () Negative () Mixed () Other:

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

AA-524

Bracketed cornice; elliptical windows with cast iron drip molds, 2/2 sash; pedimented porch with clustered columns; double doors with full transom; tabby foundation.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

Good example of Italianate Victorian, important as a type and important to streetscape.

REFERENCES:

MAP: (Indicate North In Circle)



SURROUNDING ENVIRONMENT:

Open Lane() Woodland() Scattered Buildings()
Moderately Built Up(X) Densely-Built Up()
Residential(X) Commercial()
Agricultural() Industrial()
Roadside Strip Development()
Other:

RECORDED BY:

Russell Wright

ORGANIZATION:

Historic Annapolis, Inc

DATE RECORDED:

Aug. 1983

0205242504

Form 10-445
(5/62)

1. STATE Annapolis, Maryland COUNTY TOWN VICINITY STREET NO. 201 Hanover Street ORIGINAL OWNER ORIGINAL USE residence PRESENT OWNER ADAMS PRESENT USE residence WALL CONSTRUCTION stucco/Tabby foundation NO. OF STORIES two	HISTORIC AMERICAN BUILDINGS SURVEY INVENTORY
	2. NAME DATE OR PERIOD Mid 19th C. STYLE Victorian ARCHITECT BUILDER

4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION	OPEN TO PUBLIC no
--	-------------------

201 Hanover Street is a square Victorian town house. 2/2 windows with their round drip moldings give the house an Italianate feeling; the overhanging roof with simplified brackets makes the house appear almost Moorish revival, very much like old Naval Academy sick bay or much like some of Henry Austin's houses in New Haven, Connecticut. There is a pedimented porch with very slender groups of square columns. Only "Moorish" example extant in Annapolis.

SUPPLEMENTAL INFORMATION AND PHOTOGRAPHS MAY BE ADDED ON SHEET OF SAME SIZE

5. PHYSICAL CONDITION OF STRUCTURE



good

6. LOCATION MAP (Plan Optional)

7. PHOTOGRAPH


8. PUBLISHED SOURCES (Author, Title, Pages)
INTERVIEWS, RECORDS, PHOTOS, ETC.

9. NAME, ADDRESS AND TITLE OF RECORDER

H.A. Inc reports: 3 Ancient Blocks.

William D. Morgan
Columbia University
New York City

DATE OF RECORD August 21, 1967



MARYLAND

AVENUE

GEORGE STREET

STREET

RCLE

FRANCIS ST.

CORNHILL STREET

FLEET STREET

PINKNEY STREET

EAST STREET

MARKET ST.

MARTIN

RANDALL STREET

COMPRISE

AA 524
ANNAPOLIS HIST. DIST.

SCALE IN FEET
0 50 100 200 300 400 500





AA-524

918



201 Hanover

AA 524

Annapolis, Anne Arundel County

Russell Wright July, 1982

Maryland Historical Trust,

Annapolis, Maryland

NW elevation/camera position SE