

Capsule Summary of 117-119 Main Street (AA-543)

Originally built ca. 1850, the building at 117-119 Main Street was historically part of a row of three, similarly designed and attached tenements. This row, designed in a vernacular federal style and designated 117-119-121 Main Street, stood on the site until the mid-20th century. At that time, the northeast end section of the group was demolished, and the two remaining sections were renovated and merged into the single, cohesive structure designated 117-119 Main Street. A modern infill building occupies the site of the demolished tenement. Constructed on property leased from Benjamin Tasker, the building survives as one of the few vernacular Federal style tenement houses located within the market and waterfront area of 19th-century Annapolis.

Set on the southwest side of Main Street, mid-block between Conduit and Green Streets, the building currently appears as a two-story, four-bay frame structure covered with a gable roof, clad with standing seam metal. A chimney which originally projected from the center of the building (between the two tenements) has been dismantled, although evidence of the chimney stack can be seen in the repairs to the roof cladding on the southwest end. A two-story ell projects from the northern half of the southwest elevation of the original building, while a single-story concrete block addition, L-shaped in plan, abuts the rear wall of the original building and the ell. These rear additions are not visible from the public domain on the exterior.

MARYLAND HISTORICAL TRUST
MD INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY

Inventory No. AA-543

=====

1. Name of Property

=====

historic name _____

other names 62 Main or Church Street

=====

2. Location

=====

street & number 117-119 Main Street not for publication _____

city or town Annapolis vicinity _____

state Maryland code _____ county Anne Arundel code _____

zip code 21401

=====

3. State/Federal Agency Certification

N/A

=====

4. National Park Service Certification

N/A

=====

5. Classification

=====

Ownership of Property (Check all that apply)

- private
 public-local
 public-State
 public-Federal

Category of Property (Check only one box)

- building(s)
 district
 site
 structure
 object

Number of Resources within Property

Contributing Noncontributing

<u>1</u>	_____	buildings
_____	_____	sites
_____	_____	structures
_____	_____	objects
<u>1</u>	_____	Total

Is this property listed in the National Register?

Yes Name of Listing Annapolis Historic District

No _____

=====
6. Function or Use
=====

Historic Functions (Enter categories from instructions)

Cat: Commerce/Trade

Sub: Store

Domestic

Dwelling

Current Functions (Enter categories from instructions)

Cat: Commerce/Trade

Sub: Store

=====
7. Description
=====

Architectural Classification (Enter categories from instructions)

Federal

Materials (Enter categories from instructions)

foundation Not visible

roof Standing seam metal

walls Stucco over weatherboard

other _____

Narrative Description (Describe the historic and current condition of the property.) See Continuation Sheet No. 7-1

=====
8. Statement of Significance
=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties
Annapolis Survey
117-119 Main Street
Anne Arundel County, Maryland

Inventory No. AA-543
Page 4

=====
Areas of Significance (Enter categories from instructions)

Architecture

Period of Significance ca. 1850

Significant Dates ca. 1850

Significant Person (Complete if Criterion B is marked above)

Cultural Affiliation _____

Architect/Builder unknown

Narrative Statement of Significance (Explain the significance of the property.) See Continuation Sheet No. 8-1

=====
9. Major Bibliographical References
=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Articles, Books, Published and Unpublished Resources

Anderson, Elizabeth B. Annapolis: A Walk Through History.
Centreville, MD: Tidewater Publishers, 1984.

Anne Arundel County Assessment Records. 1876-1896; 1896-1905.
Maryland State Archives. Record Group C35.

Anne Arundel County Land Records. Anne Arundel County Courthouse
and Maryland State Archives, Annapolis, Maryland.

Baltz, Shirley. The Quays of the City, An Account of the Bustling
Eighteenth Century Port of Annapolis. Annapolis, MD: The Liberty
Tree, Ltd., 1975.

Cromley, Elizabeth and Stephen Calloway. The Elements of Style, A
Practical Encyclopedia of Interior Architectural Details. New
York: Simon and Schuster, 1991.

Jennings, Jan and Herbert Gottfried. American Vernacular Design,
1870-1940. New York: Van Nostrand Reinhold Company, 1985.

----- . American Vernacular Interior Architecture,
1870-1940. Ames, IW: Iowa State University
Press, 1988.

Longstreth, Richard. The Buildings of Main Street. Washington,
D.C.: The Preservation Press, 1987.

Lounsbury, Carl R. An Illustrated Glossary of Early Southern
Architecture and Landscape. New York: Oxford University Press,
1994.

The Maryland Comprehensive Historic Preservation Plan. Maryland
Historical Trust. Department of Economic and Community
Development, June 1986.

McAlester, Virginia and Lee McAlester. A Field Guide to American
Houses. New York: Alfred A. Knopf, 1985.

McIntire, Robert Harry. Annapolis Maryland Families. Baltimore:
Gateway Press, Inc., 1979.

Maryland Inventory of Historic Properties
Annapolis Survey
117-119 Main Street
Anne Arundel County, Maryland

Inventory No. AA-543
Page 6

=====
National Register Bulletin: How to Complete the National Register
Registration Form 16A. Washington, D.C.: National Park Service,
1991.

Papenfuse, Edward. In Pursuit of Profit, The Annapolis Merchants
in the Era of the American Revolution, 1763-1805. Baltimore, MD:
The Johns Hopkins University Press, 1975.

----- . "Southern Urban Society after the Revolution:
Annapolis, Maryland, 1782-1786." Final Report for NEH Grant
#H69-0-178, Historic Annapolis Foundation, 1969.

Radoff, Morris L. Buildings of the State of Maryland at Annapolis
Publication No. 9. Annapolis, MD: The Hall of Records Commission,
1954.

Record Group 29 "Records of the Bureau of the Census." 1900, 1910
and 1920 Census; Anne Arundel County, Maryland.

Warfield, J.D. The Founders of Anne Arundel and Howard Counties,
Maryland. Westminster, MD: Family Line Publications, 1990.

Warren, Mame. Then Again...Annapolis, 1900-1965. Annapolis, MD:
Time Exposure Limited, 1990.

Maps and Drawings

Bird's Eye View of the City of Annapolis, Charles Magnus, 1864,
Reproduced, 1967. Bird's Eye View of the City of Annapolis, Edward
Sachse, ca. 1858. (Maryland Hall of Records, MdHR G 1213-349)
Church Circle, Annapolis, MD, ca. 1790. Watercolor by C. Milburn.
Gray's New Map of Annapolis, Anne Arundel County, MD., 1877.
Hopkins, G.M. Map of Annapolis, 1878.
Map of Annapolis, Southern Map Company, Baltimore, MD., 1905.
Plan of Annapolis, Geo. H. Shafer, 25 July 1718.
Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1897, 1903, 1908,
1913, 1921, 1930, 1954.

Photographs

Hayman Collection, 1920ca-1930ca. Record Group SC1406. Annapolis,
Maryland: Maryland State Archives.

Mame Warren Collection, 1859-1910. Record Group SC985. Annapolis,
Maryland: Maryland State Archives.

Photographic Collection at the Historic Annapolis Foundation.

=====
City Directories

Mullin-Kille and Capital-Gazette City Directory of Annapolis, MD.
Ohio: Mullin-Kille; Evening Capital; and the Maryland
Gazette, 1949.

Polk's City Directory of Annapolis, MD. New York: R.L. Polk and
Co., 1928, 1954.

=====
10. Geographical Data
=====
Acreage of Property less than 1 acre

Verbal Boundary Description (Describe the boundaries of the
property.)

The property designated as 117-119 Main Street occupies Parcel 780
on Tax Map 4-6.

Boundary Justification (Explain why the boundaries were selected.)

This parcel has been associated with the property since the
construction of the building on the site in the early- to mid-19th
century.

=====
11. Form Prepared By
=====
name/title Kim Williams & L. Trieschmann/Architectural Historians
organization Traceries date June 01, 1994
street & number 5420 Western Avenue telephone (301) 656-5283
city or town Chevy Chase state MD zip code 20815
=====

12. Property Owner
=====
name Sike and Nancy J. Sharigan c/o Fran O'Brien's
street & number 113 Main Street telephone _____
city or town Annapolis state MD zip code 21401
=====

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-543

Section 7 Page 1 117-119 Main Street
name of property
Anne Arundel County, MD
county and state

=====
Originally built ca. 1850, the building at 117-119 Main Street was historically part of a row of three, similarly designed and attached tenements. This row, designed in a vernacular federal style and designated 117-119-121 Main Street, stood on the site until the mid-20th century. At that time, the northeast end section of the group was demolished, and the two remaining sections were renovated and merged into the single, cohesive structure designated 117-119 Main Street. A modern infill building occupies the site of the demolished tenement.

Set on the southwest side of Main Street, mid-block between Conduit and Green Streets, the building currently appears as a two-story, four-bay frame structure covered with a gable roof, clad with standing seam metal. A chimney which originally projected from the center of the building (between the two tenements) has been dismantled, although evidence of the chimney stack can be seen in the repairs to the roof cladding on the southwest end. A two-story ell projects from the northern half of the southwest elevation of the original building, while a single-story concrete block addition, L-shaped in plan, abuts the rear wall of the original building and the ell. These rear additions are not visible from the public domain on the exterior.

The southwest elevation, facing Main Street, consists of two side-passage entry doors, a storefront and four bays of windows on the second story. The two, side-passage entries occupy the far northern and southern end bays. The northern end entry features a six-light, wood panelled replacement door and leads to the second story of the building (designated 119 Main Street). The southern entry with its vertical board wood door, opens onto an enclosed passageway leading to the rear of the building.

The storefront spans the two central bays of the building, extending from one side-passage entry to the other. The storefront is articulated by a recessed bay window, with two entry doors that provide access to the first floor. The entry doors are all-glass replacement doors with wood surrounds. The polygonal show windows on either side of the doors are set upon a granite foundation, covered with stucco, and feature large plateglass windows. A narrow half-hipped roof cantilevers from the wall extending across the commercial storefront.

The second story of the building has four bays of 6/1 replacement windows with flat architrave surrounds. The windows are not grouped in pairs, but as two sets of two windows, distinguished by

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY Inventory No. AA-543
CONTINUATION SHEET

Section 7 Page 2 117-119 Main Street
name of property
Anne Arundel County, MD
county and state

=====

a wider wall surface between the two groups. This window configuration, as well as the dismantled central chimney, confirms that although considered a single building today, it was historically two distinct and separate spaces.

A cursory inspection of the first floor public space reveals that the interior of the building has been renovated; no original interior architectural details remain. Several interior walls on the first floor of the building have been removed, creating a single commercial space.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-543

Section 8 Page 1 117-119 Main Street
name of property
Anne Arundel County, MD
county and state

=====
Built circa 1850,¹ the building at 117-119 Main Street was originally constructed as three separate tenement houses, designated 117-119-121 Main Street.² Constructed on property leased from Benjamin Tasker, the building survives as one of the few vernacular Federal style tenement houses located within the market and waterfront area of 19th-century Annapolis.

The land on which 117-119 Main Street is sited was historically part of Lot 28 on the Stoddert Map of Annapolis and was owned for most of the 18th century by the estate of Benjamin Tasker, one time Mayor of Annapolis. Upon the death of Tasker in 1766, Daniel Dulany of Baltimore was appointed administrator of the leased properties. Correspondence between John Ridout and Daniel Dulany, dating from 1781, documents the collection of rents by Ridout for Dulany from four individuals leasing property "near the docks." In a letter dated May 10, 1785, Ridout informs Dulany "...that Major Jenifer has notified by advertisement that he shall on the 17 of this month sell as confiscated property at public vendue, one-fifth share of the houses, etc. lots near the dock in this city, which belonged to Mr. Tasker."³ The property, confiscated by the State, included the lots leased by Mrs. Ann Gaither and by Francis Fairbrothers, in addition to the shop and house rented to Thomas Graham.⁴

Chancery Papers #2016 document that the above mentioned property was purchased at public auction by Frederick Green following the death of Daniel Dulany in 1797. In 1798, Green petitioned the State of Maryland stating that:

"...your petitioner under the idea that the said lott joined upon Church Street and that a house now in the tenure and

¹The building seems to appear on the 1858 Sachse Print, although it has not been positively identified.

² Although the chain of title may include the portion of the building located at 121 Main Street, the following history only addresses 117-119 Main Street, as 121 Main Street was demolished after 1954 and the deeds of conveyance were not investigated in this survey.

³John Ridout to Daniel Dulany, May 10, 1785. (Ridout Papers #324, Hall of Records).

⁴Lot History, Parcel 12, Section II and III, Lot 27. (Historic Annapolis Foundation, Inc.).

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY Inventory No. AA-543
CONTINUATION SHEET

Section 8 Page 2 117-119 Main Street
name of property
Anne Arundel County, MD
county and state

=====

occupation of John Roe stood upon part of the said lott...."

The petition further stated that the said lot "was cut off by the public ground laid out for a custom house lott and that the house...stands on the said public ground...."⁵ Following a resurvey, the court decreed to void the sale and returned the money with interest to Green. In 1800, the same one-fifth portion of Lot 27 was again sold by the State of Maryland to Allen Quynn for L105.⁶

In 1813, Ann Ogle, the daughter of Benjamin Tasker's wife, petitioned the courts stating that Tasker owned:

"...a lot #27 in the city of Annapolis, a part of which was leased to Mrs. Ann Gaither by the aforesaid Benjamin Tasker for a term of 99 years, renewable forever...that the said executrix [Anne Tasker] by her last will, appointed the late Daniel Dulany, her executor, on who it devolved to complete the execution of the will of the aforesaid Benjamin Tasker, but he, the said Daniel Dulany, departed this life without completing the same and the said land...remained unsold."⁷

Following the petition, Samuel Ridout and Richard T. Lowndes were appointed Trustees of the estate of Tasker. The Trustees reported that on February 27, 1813 "...part of lot 27, except for the land leased to Ann Gaither, but including the portion sold to Allen Quynn," was sold to John Munroe on behalf of John Smith for \$316.00.⁸

In 1829, "...all that part of lot 27 lying 49 feet on the south side of Church Street, whereon John Smith, Jr. now dwells" was conveyed by John Smith, Sr. to his son, John Smith, Jr., as payment

⁵Chancery Papers 2016, recorded in Liber 39 Folio 391. Frederick Green versus State of Maryland.

⁶Liber NH 10 Folio 225

⁷Chancery Court Case 3921, recorded in Liber 84 Folio 341. (Anne Ogle versus Benjamin Tasker's Estate).

⁸Liber WSG 5 Folio 168

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY Inventory No. AA-543
CONTINUATION SHEET

Section 8 Page 3 117-119 Main Street
name of property
Anne Arundel County, MD
county and state

=====

for part of a \$2,486.81 debt.⁹

Anne Munroe purchased the portion of the lot retained by John Smith Sr. in 1822 and in 1836 gained ownership of the remaining portion from John Smith, Jr., thus acquiring the entire lot.¹⁰ When Anne Munroe died about 1848, the property was conveyed by her heirs to Ezekeil J. Stansbury, the husband of her daughter, Rebecca Anne Munroe.¹¹ Dr. Ezekeil J. Stansbury, born in 1802, operated a drug store on Main Street.

Lewis Tydings, who owned the property in the early 19th century, conveyed sections of Lot 27 to Joseph Parkinson and his son, William N., from 1847 through 1863. It was during this period that the buildings known as 117-119-121 Main Street was constructed as tenement housing.

In 1875, the property was devised to the only daughter of William N. Parkinson, Mary Ann Parkinson and her husband John Sprigg Sullivan. Sullivan, born in 1831, was a carpenter and worked as Superintendent of the State House and grounds.¹² The 1880 Census records show that the entire building was occupied by the Sullivan family. Although this cannot be proved, this information indicates that Sullivan, a carpenter, may have built the tenements on the site. The census records for 1900 indicate that 117 Main Street was leased by Grandville Everson, a painter originally from Washington, D.C., and his family. The tenement at 119 Main Street was owned and occupied by Mary Jane Sullivan and her daughter Mary E. Sullivan, who worked as a sales lady. John Ridout Sullivan and his family owned and occupied the tenement at 121 Main Street. John Sullivan, born in 1860, was a painter who also served as sheriff, clerk to Mayor and Council, secretary to the State Senate, and Assistant Superintendent of Public Buildings.¹³

⁹Liber WSG 14 Folio 555

¹⁰Liber WSG 8 Folio 388 and WSG 20 Folio 466.

¹¹Liber JHN 3 Folio 307

¹²McIntire, p. 538 and 686.

¹³McIntire, p. 686.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-543

Section 8 Page 4

117-119 Main Street
name of property
Anne Arundel County, MD
county and state

=====
Prior to the death of Mary Jane Sullivan in 1922, John Ridout Sullivan, her son, petitioned the courts for his interest in the property. The courts appointed a Trustees, Nicholas H. Green to sell the 31 by 160 feet lot. It was purchased by J. Clayton Brewer for \$3,900.00.¹⁴ The same day, Brewer conveyed the building to Hyman and Lena Reichel, who renovated the dwellings into commercial space.¹⁵

According to the city directory for 1928-1929, the building was occupied by Jack Cohen, who sold general merchandise. In 1930, the Reichels sold 117-119-121 Main Street to Jack and Yetta Cohen.¹⁶ The city directories for 1949 and 1954 indicate that Jack Cohen continued to operate his general store on the first floor of the building, while residing on the second floor. The Sanborn maps from 1930 and 1954 indicate that the two setions, 117 and 119, were merged into a single space. The Sanborn maps also indicate the separation, and subsequent demolition, of 121 Main Street. Cohen sold 117-119 Main Street in 1980 to Sike and Nancy J. Sharigan, the present owners.¹⁷ The entire building currently is leased to La Belle Cezanne, a jewelry store.

¹⁴Equity Case 4469; Liber WNW 49 Folio 1.

¹⁵Liber WNW 42 Folio 499

¹⁶Liber FSR 65 Folio 385

¹⁷Liber 3303 Folio 195

=====
MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY Inventory No. AA-543
CONTINUATION SHEET

117-119 Main Street
name of property
Anne Arundel County, MD
county and state
=====

Historic Period Theme: Architecture, Landscape Architecture
and Community Planning

Geographic Organization: Western Shore

Chronological/Developmental Period: Agricultural-
Industrial Transition,
1815-1870

Resource Type(s): Standing Structure

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-543

117-119 Main Street
name of property
Anne Arundel County, MD
county and state

=====
Chain of Title for 117-119 Main Street:

- 1760s: Benjamin Tasker leases property to Ann Gaither and Francis Fairbrothers
- 1798: Property in Equity, Chancery Papers 2016
Frederick Green versus State of Maryland
- 1813: Property in Equity, Chancery Papers 3921
Anne Ogle versus estate of Benjamin Tasker
Samuel Ridout and Richard T. Lowndes appointed Trustees
Liber 84 Folio 341
- 1813: Samuel Ridout and Richard T. Lowndes to John Munroe on
behalf of John Smith
Liber WSG 5 Folio 168
- 1822: John Smith, Sr. to Anne Munroe
Liber WSG 8 Folio 388
- 1829: John Smith, Sr. to John Smith, Jr.
Portion of property
Liber WSG 14 Folio 555
- 1836: John Smith, Jr. to Anne Munroe
Remaining portion of property
Liber WSG 20 Folio 466
- 1848: Heirs of Anne Munroe to Ezekeil J. Stansbury.
Liber JHN 3 Folio 307
- 1857: Lewis Tydings to William Parkinson
One-half of house
Liber NHG 6 Folio 305
- 1863: Lewis Tydings to William Parkinson
Liber NHG 11 Folio 651
- 1875: Parkinson devised to daughter, Mary J. Sullivan.
- 1921: Nicholas H. Green, Trustee, to J. Clayton Brewer
Equity Case 4469, John Ridout Sullivan, et al, versus
Mary Jane Sullivan, et al
Liber WNW 49 Folio 1


MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-543

117-119 Main Street
name of property
Anne Arundel County, MD
county and state

=====

1921:	J. Clayton Brewer to Hyman and Lena Reichel Liber WNW 42 Folio 499
1930:	Hyman and Lena Reichel to Jack and Yetta Cohen Liber FSR 65 Folio 385
1980:	Jack and Yetta Cohen to Sike and Nancy J. Sharigan Liber 3303 Folio 195




AA-543

Tax Map of Annapolis, Maryland
Map 4-6



Main Street, August 1948
MdHR G 1804-82

AA-543



AA-543

Main Street, no date

Annapolis Book (Annapolis:


Main Street, looking West from Market Place,
Annapolis, Md.



109 111 113-45
new one


Main Street, no date
Historic Annapolis Photograph
Collection

AA-543



AA-543


Main Street
Historic Annapolis Foundation, Inc.
MIF-3063



20
21/15 #

AA-543

Main Street, no date
Historic Annapolis Photograph



101-151 Main Street, no date
Historic Annapolis Photographic
Collection

AA-543



 *La Belle Cezanne*

AA-543
117-119 MAIN STREET
ANNAPOLIS, MARYLAND
TRACERIES
MAY 1994
MARYLAND SHPO
FACADE, LOOKING SW
1/1

MARYLAND HISTORICAL TRUST
 21 STATE CIRCLE
 SHAW HOUSE
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET
 Individual Structure Survey Form

SURVEY NUMBER: <u>AA 543</u>	
NEGATIVE FILE NUMBER:	
UTM REFERENCES: Zone/Easting/Northing	
U.S.G.S. QUAD. MAP:	
PRESENT FORMAL NAME:	
ORIGINAL FORMAL NAME:	
PRESENT USE: Retail/Vacant Above	
ORIGINAL USE: Retail/Res	
ARCHITECT/ENGINEER:	
BUILDER/CONTRACTOR:	
PHYSICAL CONDITION OF STRUCTURE: Excellent () Good (X) Fair () Poor: ()	
THEME:	
STYLE: Vernacular	
DATE BUILT: E-M 19th c.	

COUNTY: Anne Arundel
TOWN: Annapolis
LOCATION: 117-119 Main
COMMON NAME: McBride Gallery
FUNCTIONAL TYPE: Map 32 Par 281
OWNER: Sharigan, Sike & Nancy J
ADDRESS: % Fran O'Brien/113 Main St. Annapolis, MD 21401
ACCESSIBILITY TO PUBLIC: Yes (X) No () Restricted ()
LEVEL OF SIGNIFICANCE: Local (✓) State () National ()

GENERAL DESCRIPTION:

Structural System

- Foundation: Stone () Brick (X) Concrete () Concrete Block ()
- Wall Structure
 - Wood Frame: Post and Beam () Balloon ()
 - Wood Bearing Masonry: Brick (X) Stone () Concrete () Concrete Block ()
 - Iron () D. Steel () E. Other:
- Wall Covering: Clapboard () Board and Batten () Wood Shingle () Shiplap () Novelty () Stucco () Sheet Metal () Aluminum () Asphalt Shingle () Brick Veneer (X) Stone Veneer () Asbestos Shingle () Bonding Pattern: Other:
- Roof Structure
 - Truss: Wood (X) Iron () Steel () Concrete ()
 - Other:
- Roof Covering: Slate () Wood Shingle () Asphalt Shingle () Sheet Metal (X) Built Up () Rolled () Tile () Other:
- Engineering Structure:
- Other:

Appendages: Porches () Towers () Cupolas () Dormers () Chimneys () Sheds () Ells () Wings () Other:

Roof Style: Gable () Hip () Shed () Flat () Mansard () Gambrel () Jerkinhead () Saw Tooth () With Monitor () With Bellcast () With Parapet () With False Front () Other:

Number of Stories: 2

Number of Bays: 4 Entrance Location: _____

Approximate Dimensions: 30 x 30 with Rear 30 x 40

THREAT TO STRUCTURE: No Threat (X) Zoning () Roads () Development () Deterioration () Alteration () Other:
--

LOCAL ATTITUDES: Positive () Negative () Mixed () Other:

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

AA-543

Simple wood cornice at standing seam metal roof, later shop front of acceptable design, later door in right bay.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

Minor example of 19thC Commercial style, contributing through scale and roof line to streetscape.

REFERENCES:

MAP: (Indicate North In Circle)



SURROUNDING ENVIRONMENT:

Open Lane() Woodland() Scattered Buildings()
Moderately Built Up() Densely-Built Up()
Residential() Commercial()
Agricultural() Industrial()
Roadside Strip Development()
Other:

RECORDED BY:

Russell Wright

ORGANIZATION:

Historic Annapolis, Inc

DATE RECORDED:

AUG. 1983

Form 10-445
(3/62)

1. STATE Annapolis, Maryland COUNTY TOWN VICINITY STREET NO. 117 - 119 Main Street ORIGINAL OWNER ORIGINAL USE commercial PRESENT OWNER PRESENT USE Jack's Store WALL CONSTRUCTION stucco NO. OF STORIES two plus attic	HISTORIC AMERICAN BUILDINGS SURVEY INVENTORY 2. NAME DATE OR PERIOD Early-Mid 19th C. STYLE 19th C. commercial ARCHITECT BUILDER 3. FOR LIBRARY OF CONGRESS USE
---	--

4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION OPEN TO PUBLIC **yes**

Though not an outstanding piece of architecture, 117 - 119 Main Street does have the scale, plus certain features of similar buildings, to the east of (111, 109, 107, etc.). Aside from the metal roof, there is a simple wood cornice and four small 2nd storey windows (orig. 6/6) all above a relatively undecorated street level. Possibly brick worth removing the stucco for. Restoration would involve very little to develop this building's potential.


SUPPLEMENTAL INFORMATION AND PHOTOGRAPHS MAY BE ADDED ON SHEET OF SAME SIZE

5. PHYSICAL CONDITION OF STRUCTURE **good**





6. LOCATION MAP (Plan Optional) 7. PHOTOGRAPH

8. PUBLISHED SOURCES (Author, Title, Pages) INTERVIEWS, RECORDS, PHOTOS, ETC.	9. NAME, ADDRESS AND TITLE OF RECORDER William D. Morgan Columbia University New York City DATE OF RECORD July 11, 1967
--	---



AA 543
ANNAPOLIS HIST. DIST.





McBRIDE GALLERY

ASHLEY'S
THE SHIRT FOOT

1757-0216

AR

117-119 Main

AA 543

Annapolis, Anne Arundel County

Russell Wright July, 1982

Maryland Historical Trust,

Annapolis, Maryland

NWElevation/camera facing SE