

Capsule Summary of 220-222 Main Street (AA-585)

The building at 220-222 Main Street was constructed in the years between 1927 and 1930 on the northeast side of Main Street. Replacing a single-family dwelling that dated from the early 19th century, the commercial building was constructed by Gertrude and John Walton.

Although built as a single structure, the low-lying and horizontal, one-story building is divided into two stores, designated on the exterior by a two, recessed cant entries. L-shaped in plan, the building is constructed of five-course American bond brick set upon a poured concrete foundation. The double-wide commercial facade, divided by three brick piers on granite blocks, is composed of all-stretcher bond pressed brick. Approximately forty feet wide, the building is covered with a flat roof with a brick parapet wall and features Craftsman-like details, such as the recessed brick panels. The building is an example of the 20th-century commercial style that replaced the 18th and 19th century domestic architecture along Main Street.

MARYLAND HISTORICAL TRUST
MD INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY

Inventory No. AA-585

=====

1. Name of Property

=====

historic name _____

other names _____

=====

2. Location

=====

street & number 220-222 Main Street not for publication _____

city or town Annapolis vicinity _____

state Maryland code _____ county Anne Arundel code _____

zip code 21401

=====

3. State/Federal Agency Certification N/A

=====

4. National Park Service Certification N/A

=====

5. Classification

=====

Ownership of Property (Check all that apply)

- private
 public-local
 public-State
 public-Federal

Category of Property (Check only one box)

- building(s)
 district
 site
 structure
 object

Number of Resources within Property

Contributing	Noncontributing	
<u>1</u>	_____	buildings
_____	_____	sites
_____	_____	structures
_____	_____	objects
<u>1</u>	_____	Total

Is this property listed in the National Register?

Yes Name of Listing Annapolis Historic District
No _____

Maryland Inventory of Historic Properties
Annapolis Survey
220-222 Main Street
Anne Arundel County, Maryland

Inventory No. AA-585
Page 2

=====
6. Function or Use
=====

Historic Functions (Enter categories from instructions)

Cat: Commerce/Trade

Sub: Store

Current Functions (Enter categories from instructions)

Cat: Commerce/Trade

Sub: Store

=====
7. Description
=====

Architectural Classification (Enter categories from instructions)

Commercial Classical

Materials (Enter categories from instructions)

foundation Poured Concrete

roof Not visible

walls Five-course American bond brick

All-stretcher bond brick

other _____

Narrative Description (Describe the historic and current condition of the property.) See Continuation Sheet No. 7-1

=====
8. Statement of Significance
=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties
Annapolis Survey
220-222 Main Street
Anne Arundel County, Maryland

Inventory No. AA-585
Page 4

=====
Areas of Significance (Enter categories from instructions)

Architecture

Period of Significance 1927-1930

Significant Dates 1927-1930

Significant Person (Complete if Criterion B is marked above)

Cultural Affiliation _____

Architect/Builder unknown

Narrative Statement of Significance (Explain the significance of the property.) See Continuation Sheet No. 8-1

=====
9. Major Bibliographical References
=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Articles, Books, Published and Unpublished Resources

Anderson, Elizabeth B. Annapolis: A Walk Through History.
Centreville, MD: Tidewater Publishers, 1984.

Anne Arundel County Assessment Records. 1876-1896; 1896-1905.
Maryland State Archives. Record Group C35.

Anne Arundel County Land Records. Anne Arundel County Courthouse
and Maryland State Archives, Annapolis, Maryland.

Baltz, Shirley. The Quays of the City, An Account of the Bustling
Eighteenth Century Port of Annapolis. Annapolis, MD: The Liberty
Tree, Ltd., 1975.

Cromley, Elizabeth and Stephen Calloway. The Elements of Style, A
Practical Encyclopedia of Interior Architectural Details. New
York: Simon and Schuster, 1991.

Jennings, Jan and Herbert Gottfried. American Vernacular Design,
1870-1940. New York: Van Nostrand Reinhold Company, 1985.

----- . American Vernacular Interior Architecture,
1870-1940. Ames, IW: Iowa State University
Press, 1988.

Longstreth, Richard. The Buildings of Main Street. Washington,
D.C.: The Preservation Press, 1987.

Lounsbury, Carl R. An Illustrated Glossary of Early Southern
Architecture and Landscape. New York: Oxford University Press,
1994.

The Maryland Comprehensive Historic Preservation Plan. Maryland
Historical Trust. Department of Economic and Community
Development, June 1986.

McAlester, Virginia and Lee McAlester. A Field Guide to American
Houses. New York: Alfred A. Knopf, 1985.

McIntire, Robert Harry. Annapolis Maryland Families. Baltimore:
Gateway Press, Inc., 1979.

Maryland Inventory of Historic Properties
Annapolis Survey
220-222 Main Street
Anne Arundel County, Maryland

Inventory No. AA-585
Page 6

=====
National Register Bulletin: How to Complete the National Register
Registration Form 16A. Washington, D.C.: National Park Service,
1991.

Papenfuse, Edward. In Pursuit of Profit, The Annapolis Merchants
in the Era of the American Revolution, 1763-1805. Baltimore, MD:
The Johns Hopkins University Press, 1975.

----- . "Southern Urban Society after the Revolution:
Annapolis, Maryland, 1782-1786." Final Report for NEH Grant
#H69-0-178, Historic Annapolis Foundation, 1969.

Radoff, Morris L. Buildings of the State of Maryland at Annapolis
Publication No. 9. Annapolis, MD: The Hall of Records Commission,
1954.

Record Group 29 "Records of the Bureau of the Census." 1900, 1910
and 1920 Census; Anne Arundel County, Maryland.

Warfield, J.D. The Founders of Anne Arundel and Howard Counties,
Maryland. Westminster, MD: Family Line Publications, 1990.

Warren, Mame. Then Again...Annapolis, 1900-1965. Annapolis, MD:
Time Exposure Limited, 1990.

Maps and Drawings

Bird's Eye View of the City of Annapolis, Charles Magnus, 1864,
Reproduced, 1967. Bird's Eye View of the City of Annapolis, Edward
Sachse, ca. 1858. (Maryland Hall of Records, MdHR G 1213-349)
Church Circle, Annapolis, MD, ca. 1790. Watercolor by C. Milburn.
Gray's New Map of Annapolis, Anne Arundel County, MD., 1877.
Hopkins, G.M. Map of Annapolis, 1878.
Map of Annapolis, Southern Map Company, Baltimore, MD., 1905.
Plan of Annapolis, Geo. H. Shafer, 25 July 1718.
Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1897, 1903, 1908,
1913, 1921, 1930, 1954.

Photographs

Hayman Collection, 1920ca-1930ca. Record Group SC1406. Annapolis,
Maryland: Maryland State Archives.

Mame Warren Collection, 1859-1910. Record Group SC985. Annapolis,
Maryland: Maryland State Archives.

Photographic Collection at the Historic Annapolis Foundation.

Maryland Inventory of Historic Properties
Annapolis Survey
220-222 Main Street
Anne Arundel County, Maryland

Inventory No. AA-585
Page 7

=====
City Directories

Mullin-Kille and Capital-Gazette City Directory of Annapolis, MD.
Ohio: Mullin-Kille; Evening Capital; and the Maryland
Gazette, 1949.

Polk's City Directory of Annapolis, MD. New York: R.L. Polk and
Co., 1928, 1954.

=====
10. Geographical Data
=====

Acreage of Property less than 1 acre

Verbal Boundary Description (Describe the boundaries of the
property.)

The property designated as 220-222 Main Street occupies Parcel 810
on Tax Map 4-6.

Boundary Justification (Explain why the boundaries were selected.)

Parcel 810 has been associated with the property since the
construction of the building on the site between 1927 and 1930.

=====
11. Form Prepared By
=====

name/title Kim Williams & L. Trieschmann/Architectural Historians
organization Traceries date June 24, 1994
street & number 5420 Western Avenue telephone (301) 656-5283
city or town Chevy Chase state MD zip code 20815
=====

12. Property Owner
=====

name Mark Eisner, Jr.
street & number 329 Dewey Drive telephone _____
city or town Annapolis state MD zip code 21401
=====

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-585

Section 7 Page 1

220-222 Main Street

name of property

Anne Arundel County, MD

county and state

=====
Built between 1927 and 1930,¹ the low-lying and horizontal one-story building at 220-222 Main Street is located on the northeast side of Main Street just south of Church Circle. Although built as a single structure, the building is divided into two stores, designated on the exterior by a two, recessed cant entries. The building is an example of the 20th-century commercial style that replaced the domestic architecture of the 18th and 19th centuries along Main Street.

L-shaped in plan, the building is constructed of five-course American bond brick set upon a poured concrete foundation. The double-wide commercial facade, divided by three brick piers on granite blocks, is composed of all-stretcher bond pressed brick. Approximately forty feet wide, the facade has a continuous cornice that projects below the brick parapet. The ogee-molded cornice, made of hollow-metal sheets, is ornamented with large fluted cavetto-like brackets. Double-wide awnings have been applied to the facade within the flat frieze. The brick parapet has two rectangular panels and is capped by a row of bull headers. The flat roof is capped on the side elevations by clay tiles. A brick chimney projects from the northeastern corner of the building.

The facade of the building, fronting on Main Street, consists of two recessed cant storefront entries, symmetrically exhibiting a two-part organization with show windows and commercial entries. The show windows, flush with the facade, are set upon stuccoed wooden boards that are pierced by geometric Craftsmen-style ventilation grates. The large panes of glass are trimmed with molded copper mullions. Large single panes of glass, creating a transom, cap the show windows. The entry floor is comprised of hexagon ceramic mosaics with a contrasting square joint border. The ceiling of the entry, which extend into the show windows, is covered with pressed metal sheets that have a floral-in-square pattern. The single wood and glass doors are topped by a large square transom and have molded surrounds.

The southeast elevation, visible above the one-story infill structure located at 216 Main Street, extends to the rear of the 1 School Street. The elevation has no visible openings or infills.

¹ A two-story brick and frame dwelling house, last mentioned in a 1927 deed (Liber FSR 11 Folio 255), historically stood on the site. The Sanborn Maps for 1930 indicate that the dwelling had been demolished and replaced by the present 20th-century commercial style building.

Section 7 Page 2 220-222 Main Street
name of property
Anne Arundel County, MD
county and state

=====

The northwest elevation, fronting the four-foot alley, has three window openings that have been infilled and covered with metal security bars. The rear of the building is not visible.

The interior of the building, renovated in 1976, consists of two separate commercial spaces with rear offices and a full basement. The original wood floors have been covered with carpeting in the space at 222 Main Street, and recently exposed in 220 Main Street. The northwest wall of 222 Main Street exhibits the placement of the original window openings that are now covered with plaster. The ceiling of both spaces is covered with pressed tin that has a square-in-square pattern, convex molding, and a textured filler. The ceiling is edged with an elongated egg and dart cornice.

According to the Sanborn Maps from 1930 and 1954, the interior of the building was open, creating one commercial store. Examination of the central interior wall where the drywall meets the ceiling beam indicates its later construction.

The basement of the space at 222 Main Street, now used as storage, is accessible by wooden stairs located within the rear offices. The basement has poured concrete walls and a cement floor. The space is divided by a hollow-tile wall with a tin-coated hanging door. Located within the southwest wall is another door that is suggested to provide access to the underground tunnels of the city. The basement of the space at 220 Main Street was not examined.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY Inventory No. AA-585
CONTINUATION SHEET

Section 8 Page 1 220-222 Main Street
name of property
Anne Arundel County, MD
county and state

=====

The building at 220-222 Main Street was constructed in the years between 1927 and 1930 on the northeast side of Main Street. Replacing a single-family dwelling that dated from the early 19th century, the commercial building was constructed by Gertrude and John Walton. The building stands, essentially unaltered, as an example of the impact of 20th century commercial construction on the historically commercial/domestic Main Street of Annapolis.

The land on which 220-222 Main Street stands was historically associated with Lot 73, as seen on the Stoddert Map of 1718. The large triangular plot of land was owned in the early 1720s by Margaret and John Steele, who conveyed it to Robert Johnson in 1722. Johnson constructed a dwelling on the property, which was enlarged in 1745 by George Johnson. Throughout the 18th century the property was devised and conveyed several times amongst the Johnson family. The 1798 Federal Direct Tax indicates that the property contained a frame house on Church Street, assessed at \$400.00, and a brick house on School Street, assessed at \$800.00.²

By 1808, the lot was conveyed by order of the Chancery Court to Charles Wallace, a prominent merchant and builder of the State House. The deed of sale states that the Church Street dwelling was leased by Richard Harwood, while the brick dwelling on School Street was occupied by John Johnson.³ Within a matter of days the property fronting on Church Street was conveyed to Elizabeth Thompson for \$133.00. Just three years later, Thompson purchased the remained of the lot from John Johnson, who had relocated to Prince George's County.

Following the death of Elizabeth Thompson, the entire parcel, containing the frame dwelling on Church Street and the brick dwelling on School Street, was bequeathed to Eleanor Thompson. In 1874, Alicia A. Stewart, Mariana Bennett, Dennis C. Thompson, and others conveyed the property to Rose S. Cowman, the daughter of George H. and Martha Bond (von Swearinger) Shafer. Rose Shafer Cowman, born in Washington County about 1838, attended the Peabody and Boston Conservatories.⁴

²Federal Direct Tax, folder 10 and 11.

³Chancery Court Accounts, Liber 47 Folio 320

⁴McIntire, p. 162.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY Inventory No. AA-585
CONTINUATION SHEET

Section 8 Page 2 220-222 Main Street
name of property
Anne Arundel County, MD
county and state

=====

By the 1880s, Cowman transferred the property to a trust, maintained by J. Wirt Randall. Randall conveyed it to George Hawkins Williams and Elizabeth Dorsey in 1884. Williams, following an exchange of interest with Dorsey, received ownership of the frame dwelling fronting on Church Street. After several years of ownership, Williams conveyed the property designated later as 220-222 Main Street back to the Shafer family.

George H. Shafer devised the dwelling to his sisters, Rose S. Cowman, Martha Ann Shafer, M. Antoinette Shafer, and his niece Marcia Bond Beck in 1906. Following several transfers of interest, the property was fully conveyed by M. Antoinette Shafer to her niece Rosa Bond Cowman in 1925.

The single-family dwelling was conveyed by Cowman to Gertrude M. and James Alphonsus Walton in 1927. James Walton, born in 1872, was the president of the County Commissioner from 1913-1923, president of the Annapolis Banking and Trust from 1917-1934, and county treasurer from 1940-1945. His wife, Gertrude Mary, was born in 1886 to James and Mary Anne (Woods) Farrell.⁵ The Waltons demolished the single-family frame dwelling that had stood on the site since the early 19th century, replacing it with the present double-wide, brick-front commercial building. According to the city directory for 1949 and 1954, the building was occupied by the Parsons Company, a clothing store for women. The Sanborn Maps show that the building contained a single commercial store although it had a double-wide entry.

By 1965, the property was under the ownership of 101 Hopkins Place, later known as Hilton Village, Incorporated. During this period the interior of the building was divided, creating two separate stores. In 1976, the property was sold to Mark Eisner, Jr., who currently owns the building. Although the building is for sale, the shop at 220 Main Street is presently leased by a women's clothing shop, while the owner maintains a shop in the space designated as 222 Main Street .

⁵McIntire, p. 230 and 734.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-585

220-222 Main Street
name of property
Anne Arundel County, MD
county and state

=====

Historic Period Theme: Architecture, Landscape Architecture
and Community Planning

Geographic Organization: Western Shore

Chronological/Developmental Period: Industrial/Urban Dominance,
1870-1930

Resource Type(s): Standing Structure

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-585

220 Main Street
name of property
Anne Arundel County, MD
county and state

=====
Chain of Title for 220 Main Street:

- 1722: Margaret Mercier and husband, John Steele, to Robert Johnson
Liber B Folio 94
- 1745: Cornelius Brooksby II conveyed an addition 10 feet to George Johnson, son of Robert Johnson
Liber RB 2 Folio 167
- 1751: Sewell and Mary Long with George Johnson, clear title to George Johnson
Liber RB 3 Folio 403
- 1758: George Johnson died, bequeathing property to wife, Mary, and daughter, Rebecca, and sons, Robert and John.
Inventory Liber 67 Folio 528
- 1773: Robert Johnson died, bequeathing his interest in property to wife, Ann, and sons, George, John, and Robert
Will Liber 39 Folio 241
- 1801: George Johnson's 1/3 interest in property inherited from father, Robert Johnson, to be sold
Chancery Court Accounts 47 Folio 320
- 1808: Robert Denny, appointed to sell to Charles Wallace
Liber NH 14 folio 485
- 1808: Charles Wallace to Elizabeth Thompson
1/3 interest in portion of property
Liber NH'14 Folio 487
- 1811: John Johnson to Elizabeth Thompson
2/3 interest in property inherited from father, Robert Johnson
Liber WSG 1 Folio 235

MARYLAND INVENTORY OF HISTORIC PROPERTIES
ANNAPOLIS SURVEY
CONTINUATION SHEET

Inventory No. AA-585

220 Main Street
name of property
Anne Arundel County, MD
county and state

=====

- Will of Elizabeth Thompson devises property to Mrs. Eleanor Thompson
- 1874: Heirs of Eleanor Thompson to Rose S. Cowman
Liber SH 9 Folio 34
- 1883: Rose S. Cowman to J. Wirt Randall, Trustee
Liber SH 22 Folio 165
- 1884: J. Wirt Randall to George Hawkins Williams
Liber SH 24 Folio 108
- 1885: Elizabeth Dorsey exchanged property with George Hawkins Williams
Portion of property containing a two-story brick and frame dwelling
Liber SH 26 Folio 90
- 1887: George Hawkins Williams to George H. Shafer
Liber SH 31 Folio 453
- 1906: George Hawkins Williams devised to Martha Ann Shafer, M. Antoinette Shafer, Rose S. Cowman, and Marcia Bond Beck
- 1906-1925: M. Antoinette Shafer received full ownership from Martha Ann Shafer, and Marcia Bond Beck
Liber GW 49 Folio 121
Liber GW 50 Folio 61
Will Liber OBD 1 Folio 121
- 1925: M. Antoinette Shafer to Rosa B. Cowman
Liber WNW 102 Folio 399
- 1927: Rosa Bond Cowman to Gertrude M. and James Alphonsus Walton
Liber FSR 11 Folio 255
- 1965: Gertrude M. Walton to 101 Hopkins Place
Liber LNP 1885 Folio 462
- 1976: Hilton Village, Inc., formerly 101 Hoplins Place, to Mark Eisner, Jr.
Liber 2857 Folio 350



AA-585

220 MAIN STREET

ANNAPOLIS, MD

TRACERIES

MAY 1994

MD SHPO

SW ELEVATION

VIEW LOOKING NE

1/9



AA-585

220 MAIN STREET
ANNAPOLIS, MD

TRACERIES

MAY 1994

MD SHPO

DETAIL OF END BRACKET AND PARAPET WALL

2/9



AA-585
220 MAIN STREET
ANNAPOLIS, MD
TRACERIES
MAY 1994
MD SHPO
NW ELEVATION
VIEW LOOKING EAST

3/9



AA-585
220 MAIN STREET
ANNAPOLIS, MD
TRACERIES
MAY 1994
MD SHPO
RECESSED ENTRY

4/9



AA-585
220 MAIN STREET
ANNAPOLIS, MD

TRACERIES

MAY 1994

MD SHPO


ENTRY TRANSOM LOOKING ONTO PRESSED
TIN CEILING

5/9



AA-585
220 MAIN STREET
ANNAPOLIS, MD
TRACERIES
MAY 1994
MD SHPO
SE ELEVATION
VIEW LOOKING NORTH

6/9



AA-585
220 MAIN STREET
ANNAPOLIS, MD
TRACERIES
MAY 1994
MD SHPD
PRESSED TIN CEILING
7/9



AA-585

220 MAIN STREET
ANNAPOLIS, MD

TRACERIES

MAY 1994

MD SHPO

PRESSED TIN CEILING

8/9



AA-585
220 MAIN STREET
ANNAPOLIS, MD

TRALERIES

MAY 1994

MD SHPO

BASEMENT, HANGING TROLLEY DOOR

9/9

MARYLAND HISTORICAL TRUST
 21 STATE CIRCLE
 SHAW HOUSE
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET
 Individual Structure Survey Form

SURVEY NUMBER: AA 589
NEGATIVE FILE NUMBER:
UTM REFERENCES: Zone/Easting/Northing
U.S.G.S. QUAD. MAP:
PRESENT FORMAL NAME:
ORIGINAL FORMAL NAME:
PRESENT USE: <u>Retail</u>
ORIGINAL USE: <u>Retail</u>
ARCHITECT/ENGINEER:
BUILDER/CONTRACTOR:
PHYSICAL CONDITION OF STRUCTURE: Excellent () Good (X) Fair () Poor: ()
THEME:
STYLE: <u>Commercial</u>
DATE BUILT: <u>1909-1913</u>

COUNTY: <u>Anne Arundel</u>
TOWN: <u>Annapolis</u>
LOCATION: <u>220-222 Main Street</u>
COMMON NAME:
FUNCTIONAL TYPE: <u>Comm Map 32 Par 315</u>
OWNER: <u>Mark Eisner, Jr.</u>
ADDRESS: <u>329 Dewey Dr.</u> <u>Annapolis, MD 21401</u>
ACCESSIBILITY TO PUBLIC: Yes (X) No () Restricted ()
LEVEL OF SIGNIFICANCE: Local (✓) State () National () <input checked="" type="radio"/>

GENERAL DESCRIPTION:

Structural System

1. Foundation: Stone () Brick (X) Concrete () Concrete Block ()
2. Wall Structure
 - A. Wood Frame: Post and Beam () Balloon ()
 - B. Wood Bearing Masonry: Brick (X) Stone () Concrete () Concrete Block ()
 - C. Iron () D. Steel () E. Other:
3. Wall Covering: Clapboard () Board and Batten () Wood Shingle () Shiplap ()
 Novelty () Stucco () Sheet Metal () Aluminum () Asphalt Shingle ()
 Brick Veneer (X) Stone Veneer () Asbestos Shingle ()
 Bonding Pattern: Common Other:
4. Roof Structure
 - A. Truss: Wood (X) Iron () Steel () Concrete ()
 - B. Other:
5. Roof Covering: Slate () Wood Shingle () Asphalt Shingle () Sheet Metal ()
 Built Up (X) Rolled () Tile () Other:
6. Engineering Structure:
7. Other:

Appendages: Porches () Towers () Cupolas () Dormers () Chimneys () Sheds () Ells (X)
 Wings () Other:

Roof Style: Gable () Hip () Shed () Flat (X) Mansard () Gambrel () Jerkinhead ()
 Saw Tooth () With Monitor () With Bellcast () With Parapet () With False Front ()
 Other:

Number of Stories: 1

Number of Bays: 6

Entrance Location: 2nd & 5th Bays

Approximate Dimensions: 40 x 50

Rt. Half Rear Addition = 20 x 35

THREAT TO STRUCTURE:

No Threat (X) Zoning () Roads ()
 Development () Deterioration ()
 Alteration () Other:

LOCAL ATTITUDES:

Positive () Negative ()
 Mixed () Other:

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

AA-585

Paneled parapet wall of pressed buff brick, with full width cornice at first floor level with end consoles; first floor probably original and is good example of type.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

Modest example of early 20th small scale Commercial style, with period storefront and good cornice. Contributes to streetscape despite its low mass and scale.

REFERENCES:

MAP: (Indicate North In Circle)



SURROUNDING ENVIRONMENT:

Open Lane() Woodland() Scattered Buildings()
Moderately Built Up() Densely-Built Up(✓)
Residential() Commercial()
Agricultural() Industrial()
Roadside Strip Development()
Other:

RECORDED BY:

Russell Wright

ORGANIZATION:

Historic Annapolis, Inc

DATE RECORDED:

Aug. 1983

AA-585

6205851611

Form 10-445
(5/62)

<p>1. STATE Annapolis, Maryland COUNTY TOWN VICINITY STREET NO. 220 Main Street</p> <p>ORIGINAL OWNER ORIGINAL USE commercial PRESENT OWNER PRESENT USE store, Door Store WALL CONSTRUCTION brick NO. OF STORIES one</p>	<p>HISTORIC AMERICAN BUILDINGS SURVEY INVENTORY</p> <p>2. NAME</p> <p>DATE OR PERIOD Late 19th Century STYLE Simple 19th C. commercial ARCHITECT BUILDER</p> <p>3. FOR LIBRARY OF CONGRESS USE</p>
--	--

4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION OPEN TO PUBLIC **yes**

A typical example of simple 19th C. commercial, 220 Main is red brick with a false front (boomtown front) of yellow brick extended about 4' above roof level. On the false part of front is an extended wood cornice with 2 brackets. Above it are two raised brick panels. Otherwise the building is plain. Has two recessed entrances with typical glass and window arrangement. Though not outstanding of itself, such low buildings are important here as they reveal interesting backs of buildings on School St., State Circle, and the State House itself.



5. PHYSICAL CONDITION OF STRUCTURE Endangered Interior Exterior **Good**




<p>6. LOCATION MAP (Plan Optional)</p> <p>8. PUBLISHED SOURCES (Author, Title, Pages) INTERVIEWS, RECORDS, PHOTOS, ETC.</p>	<p>7. PHOTOGRAPH</p> <p>9. NAME, ADDRESS AND TITLE OF RECORDER</p> <p>William D. Morgan Columbia University New York City, N.Y.</p> <p>DATE OF RECORD July 5, 1967</p>
--	--


SUPPLEMENTAL INFORMATION AND PHOTOGRAPHS MAY BE ADDED ON SHEET OF SAME SIZE




AA 585
ANNAPOLIS HIST. DIST.



ST. JOHN'S STREET



BLADEN STREET




NORTHWEST STREET




CATHEDRAL STREET

COLLEGE



STATE CIRCLE

DUKE



STREET

STREET

WASHINGTON

STREET

MARKIN ST.

WATER ST.

CITY GATE LANE

STREET

DEAN STREET

SHAW ST.

SHAW

SOUTH

STREET

CHARLES

STREET

ACTON



220-222 Main

AA 585

Annapolis, Anne Arundel County

Russell Wright

July, 1982

Maryland Historical Trust,

Annapolis, Maryland

sw Elevation/camera facing NE



220-222 Main

AA 585

Annapolis, Anne Arundel County

Russell Wright July, 1982

Maryland Historical Trust,

Annapolis, Maryland

sw Elevation/camera facing NE