

CAPSULE SUMMARY
196 Prince George Street
(AA-660)

The pair of dwellings at 196 and 198 Prince George Street was constructed in 1891-1893 for property owner Joseph S.M. Basil. Zealously involved in residential speculative development, Basil subdivided the property on Prince George Street, erecting two almost identical dwellings. Retaining the building at 198 Prince George Street for his own use, Basil sold the newly completed building at 196 Prince George Street to a Benjamin F. Russell, listed in the U.S. Census as a laundry man. The building was sold numerous times during the 20th century, generally serving as rental property.

The house is a quaint, but deceptively large, 2-1/2-story frame structure characterized by its urban Queen Anne massing and detail, including projecting bay windows, gables, and dormer. Set upon a raised brick foundation, the main block of the house is covered with a false mansard roof with a projecting gable and a shed roof dormer located in the half-story. Although the main block of the house is only three bays deep, a long, contemporaneous rear wing makes this seemingly modest-sized house quite expansive.

The dwelling retains much of its original exterior and interior detailing, and stands along with 198 Prince George Street, as an excellent example of the Queen Anne style of architecture.

MARYLAND HISTORICAL TRUST
MD INVENTORY OF HISTORIC PROPERTIES

Inventory No. AA-660

=====

1. Name of Property

=====

historic name _____
common/other name _____

=====

2. Location

=====

street & number 196 Prince George Street not for publication _____
city or town Annapolis vicinity _____ state Maryland code MD
county Anne Arundel code 003 zip code 21401

=====

3. State/Federal Agency Certification N/A

=====

4. National Park Service Certification N/A

=====

5. Classification

=====

Ownership of Property (Check all that apply)

- private
- public-local
- public-State
- public-Federal

Category of Property (Check only one box)

- building(s)
- district
- site
- structure
- object

Number of Resources within Property

Contributing		Noncontributing	
<u>1</u>	_____	_____	buildings
_____	_____	_____	sites
_____	_____	_____	structures
_____	_____	_____	objects
<u>1</u>	_____	<u>0</u>	Total

Is this property listed in the National Register?

Yes Name of Listing Annapolis Historic District
No _____

=====
6. Function or Use
=====

Historic Functions (Enter categories from instructions)

Cat: Domestic Sub: Single Dwelling

Current Functions (Enter categories from instructions)

Cat: Domestic Sub: Single Dwelling
Commerce/Trade Professional

=====
7. Description
=====

Architectural Classification (Enter categories from instructions)

Queen Anne

Materials (Enter categories from instructions)

foundation Brick
roof Wood Shingles
walls Wood: German Siding
other _____

Narrative Description (Describe the historic and current condition of the property.)

See Continuation Sheet No. 7-1

=====
8. Statement of Significance
=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

Maryland Inventory of Historic Properties
196 Prince George Street
Annapolis, Maryland

Inventory No. AA-660
Page 4

=====
Areas of Significance (Enter categories from instructions)

Architecture

Period of Significance 1891-1893

Significant Dates 1891-1893

Significant Person (Complete if Criterion B is marked above)

Cultural Affiliation Undefined

Architect/Builder Unknown

Narrative Statement of Significance (Explain the significance of the property.)

See Continuation Sheet No. 8-1

=====
9. Major Bibliographical References
=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Anne Arundel County Land Records. Anne Arundel County Courthouse and Maryland State Archives, Annapolis, Maryland.

Papenfuse, Edward. *In Pursuit of Profit, The Annapolis Merchants in the Era of the American Revolution, 1763-1805.* Baltimore, MD: The Johns Hopkins University Press, 1975.

Papenfuse, Edward and Jane McWilliams. "Southern Urban Society after the Revolution: Annapolis, Maryland, 1782-1786." Final Report for NEH Grant #H69-0-178, Historic Annapolis Foundation, 1969.

Record Group 29 "Records of the Bureau of the Census." 1880, 1900, 1910 and 1920 Census; Anne Arundel County, Maryland.

Maps and Drawings

Bird's Eye View of the City of Annapolis, Charles Magnus, 1864, Reproduced, 1967. *Bird's Eye View of the City of Annapolis*, Edward Sachse, ca. 1858. (Maryland Hall of Records, MdHR G 1213-349)

Sanborn Fire Insurance Maps, 1885, 1891, 1896, 1897, 1903, 1908, 1913, 1921, 1930, 1954.

=====
10. Geographical Data
=====

Acreage of Property Less than one acre

Verbal Boundary Description (Describe the boundaries of the property.)

The building at 196 Prince George Street is located on Parcel 1351 as designated on Tax Map 4-6.

Boundary Justification (Explain why the boundaries were selected.)

The building has been historically associated with Parcel 1351 since the building's construction in 1891-1893.

=====
11. Form Prepared By
=====

name/title L. Trieschmann & K. Williams, Architectural Historians
organization Traceries date May 20, 1996
street & number 5420 Western Avenue telephone 301/656-5283
city or town Chevy Chase state MD zip code 20815
=====

12. Property Owner
=====

name Edward W. Washburn and Gay P. Crowther
street & number 196 Prince George Street telephone _____
city or town Annapolis state MD zip code 21401
=====

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-660

Section 7 Page 1

196 Prince George Street
name of property
Annapolis, Maryland
county and state

=====

The detached Queen Anne-style dwelling at 196 Prince George Street located on the northern side of the street between East Street and Maryland Avenue in downtown Annapolis was erected between 1891 and 1893. It was built, along with 198 Prince George Street (AA-1224), as one of two almost identical dwellings, and is similar to another pair across the street. The house is a quaint, but deceptively large, 2-1/2-story frame structure characterized by its urban Queen Anne massing and detail, including projecting bays, gables, and dormers. Set upon a raised brick foundation, the main block of the house is covered with a false mansard roof with a projecting gable and a shed roof dormer located in the half-story. Although the main block of the house is only three bays deep, a long, contemporaneous rear wing makes this seemingly modest-sized house quite expansive.

EXTERIOR DESCRIPTION:

The principal facade, facing Prince George Street, features a two-story polygonal bay with three windows in each wall of the bay, and a side-passage entry. The walls of the frame house are clad with narrow German siding, while the front elevation of the false mansard is sheathed with slate shingles. A brick chimney projects off-center of the sloped roof behind the false mansard. A three-story frame wing at the rear of the house was originally a two-story wing built at the time of construction. Between 1913 and 1921, the wing was raised one story and has since been altered by the addition of new windows and French doors.

The facade (southwest elevation) is divided into two unequal bays, including a side-passage entry bay and a two-story, polygonal, projecting window bay. The side entry is located in the first story, set slightly above ground level and is reached by a wooden stair. A shed roof supported by wooden brackets shelters the entry door. A wood panelled replacement door sits within the original surround, which is further ornamented by the original ten-light transom and bracketed hold molding. The first story of the two-story bay has three 1/1 windows in each wall surface with original square-edged trim. A plain, wide frieze runs across the window lintels and forms the frieze of the shed roof over the main entry.

The second story consists of a single window in the western bay and three windows in the projecting bay. All of these windows have the identical, square-edged trim with a projecting lintel. A plain frieze, together with a projecting boxed wood cornice with

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-660

Section 7 Page 2

196 Prince George Street
name of property
Annapolis, Maryland
county and state

=====
modillions and dentils, divides the principal stories of the house from the half-story, which is actually a full third story on the interior.

The half-story consists of a wide projecting gable above the projecting bay and a single window over the western bay. The gable is steeply pitched with a raked cornice and cornerboards. A triple window with square-edged surrounds is set within the gable. The center opening has a Queen Anne style window with multi-lights-over-a-single-light sash. The upper sash has 12 small square lights bordering a larger, central light. The narrower side windows each have 8-lights over a single light. The single dormer in the western bay has a sloped shed roof and a similar configuration of multiple square lights bordering a larger central light in the upper sash and a single-light lower sash.

The northwest side elevation, which faces a small passage between this house and its twin at 198 Prince George Street, has no openings. The wall is clad in asbestos shingles.

The southeast side elevation of the main block of the house is three bays deep and clad with weatherboard siding. Single 2/2 windows are located in all three bays of the first story and in the upper stories in the two front bays. All of the windows share the identical square-edged window trim with a projecting lintel.

A three-story rear wing projects from the northeast (rear) wall of the main block, leaving one bay of the main block exposed. The second and third stories of this exposed bay have 2/2 sash with square-edged trim and projecting lintels.

The rear ell is frame construction, set upon a brick foundation and featuring a second story open porch. The wing is covered with a sloped roof and clad with a combination of German and weatherboard siding. The rear elevation of the wing has contemporary window openings including double French doors on the first and second stories and four eight-light casements on the third story.

INTERIOR DESCRIPTION:

The interior of the house has a side-passage, two-room deep plan with some minor modifications. The opening between the narrow side hall and the front parlor has been widened, forming a segmentally arched entry that is ornamented by Doric columns. The wall between

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-660

Section 7 Page 3

196 Prince George Street
name of property
Annapolis, Maryland
county and state

=====

the side hall and the rear parlor has been pierced by narrow, elongated openings that provided additional light into the space. Similarly, the walls between the front and rear parlor have been removed, leaving the central chimney breast as the division between these two rooms.

The exterior door of the house opens into a small, enclosed entry vestibule which in turn, opens into the side stair hall. The entry vestibule is approximately 3 feet x 3 feet and has a floor with small octagonal tiles of various colors forming a decorative pattern. The tiles are a variety of blues, greens, and oranges in color. The wall of the vestibule is papered with an embossed paper with a floral pattern and the baseboards are marble. The door between the vestibule and the side stair hall is not original.

The stair hall is a narrow space that extends the width of the main block of the building. The hall has its original wood floors and high baseboard with ogee cap. The straight-flight stair is High Victorian in detail, characterized by a turned newel post set upon a high square baseblock and featuring a square wood cap with incised wood ornament and a round finial. The balusters are turned and stringer brackets ornament the wall.

The front parlor (living room) is entered from the stair hall through the wide, contemporary arched opening. A chimney breast which separates the front parlor from the rear parlor is centered on the rear wall. It is ornamented by a High Victorian mantel which is not original to the house. The mantle has narrow Tuscan-like pilasters ornamenting a cushioned frieze and cavetto molded shelf. The face of the mantel is marble with a brick hearth and fireback. Above the shelf is a mirror adorned with carved cabinet doors, lattice work, and spindles. All of the wood floors, baseboard, and molded window casings are original.

The rear parlor (dining room) similarly has a Victorian-era mantel, which is not original to the house. The wood mantel is similarly detailed with pilasters, projecting shelf, and mirror. The room, with its original floors, baseboard, and casings, has been altered by the addition of a small bathroom and closet, as well as a butler's "pass-through" between the dining room and kitchen wing. This "pass-through" was originally a built-in cabinet and features beaded walls and sliding doors. The kitchen, located in the rear wing, retains no historic fabric.

The second floor of the main block of the house retains its

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-660

Section 7 Page 4

196 Prince George Street
name of property
Annapolis, Maryland
county and state

=====
original side-hall, two-room configuration, but has been altered to accommodate a large bathroom and laundry room. The typical trim on the second floor is pilaster casing with a molded backband.

The third floor of the main block consists of the side hall and two rooms. The front room was originally two small rooms, but has been opened to form one large room. The rear room has been altered with contemporary furnishings, including built-in bookshelves. The typical trim on the third floor is bull's eye cornerblocks with molded pilaster casings. A skylight above the stair hall has also been added to allow more light into the house.

The rear wing has a bedroom on the second floor that opens to a balcony, and an office on the third floor.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-660

Section 8 Page 1

196 Prince George Street
name of property
Annapolis, Maryland
county and state

=====
The pair of dwellings at 196 and 198 Prince George Street were constructed in 1891-1893 by property owner Joseph S.M. Basil. Zealously involved in the construction of dwellings for use as rental property, Basil subdivided the land on Prince George Street, erecting two almost identical dwellings. Retaining the building at 198 Prince George Street for his own use, Basil sold the newly completed 196 Prince George Street to laundry-man Benjamin F. Russell. The building was sold numerous times during the 20th century, being owner-occupied or leased. Despite the change of owners, the dwelling retains much of its original exterior detailing, and stands along with 198 Prince George Street, as an excellent example of the Queen Anne style of architecture.

SITE HISTORY

Designated as Lot 92 on the Stoddert Map of 1718, the property located at 196 Prince George Street was one of the final parcels of the Hammond-Harwood estate to be subdivided. Historically the estate belonged to Matthias Hammond, who in 1774 began to construct a five-part plan townhouse at what is now 19 Maryland Avenue. Hammond's Square, stretching from King George Street to Prince George Street and down to William Paca's wall on the east, was one of the largest single holdings in town. Matthias Hammond never lived in the house, which was completed in 1776 to the designs of architect William Buckland. Upon his death the property was willed to his nephews, who sold it in 1810 to Ninan Pinkney, Sr. Pinkney in turn sold the house to Judge Jeremiah Townley Chase in 1811.

Judge Chase gave the house to his daughter Frances Townley Chase Loockerman, who lived there with her family until her death in 1857. It was inherited by her daughter, Hester Anne Loockerman Harwood. Hester Anne and her husband, William Harwood, began to subdivide the property in the early 1860s. In 1870, the property which would eventually contain 196 and 198 Prince George Street was conveyed by the Harwoods to Solomon Phillips for \$1590. After the death of Phillips, by 1887, the property was purchased by Joseph S.M. Basil for \$1200. The deed of conveyance clearly states that at the time of the sale the property, which measured 20 feet by 120 feet, was vacant and unimproved.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-660

Section 8 Page 2

196 Prince George Street
name of property
Annapolis, Maryland
county and state

=====

BUILDING HISTORY

Joseph S.M. Basil (1833-1899) was a lumber and hardware merchant with a store on Main Street, and a grocer with a store at the Market Space. He was responsible for the construction of numerous dwellings on Fleet and Prince George streets which he used as rental property.

By 1891-1893, Basil proceeded to construct the buildings at 196 and 198 Prince George Street. Upon completion, the Queen Anne style dwelling at 196 Prince George Street was sold to Benjamin T. Russell, while 198 Prince George Street was retained by Basil for his own use.

According to the census records for 1900, Russell was born in 1859 and was employed as a laundry man. In 1902, Russell and his wife Catherine, sold the building for \$4,200 to Frederick W. Kipper. John W. Martin purchased the single dwelling in 1909 from the estate of the deceased Frederick Kipper. Martin, a wholesaler of fish, crabs and oysters, sold the building just one year prior to his death in 1925. It was purchased by Rosa and Elsie Meade, the daughters of John Flemmon Meade of West River, Maryland. In 1948, they transferred one-third interest in the property to Elsie Elizabeth Layden, the daughter of Elsie Meade.

After having lived in the dwelling at 196 Prince George Street for just over fifty years, the Meade sisters conveyed it to Donald W. Sharp and Patricia B. Holden. The Historic Annapolis Foundation, which had purchased the dwelling at 194 Prince George Street for its office space, obtained an easement for the building in 1976. In 1978, Donald Sharp conveyed the structure to Stephen and Christina Krug. In 1988, Christina and Stephen Krug conveyed 196 Prince George Street to the present owners, Edward W. Washburn and Gay P. Crowther. The couple renovated the interior of the building and landscaped the property. Gay Crowther operates an architectural landscape company on the third floor of the building, which she occupies with her husband and son.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-660

196 Prince George Street
name of property
Annapolis, Maryland
county and state

=====
HISTORIC CONTEXT:

Geographic Organization: Western Shore

Chronological/Development Period (s):

Industrial/Urban Dominance, 1870-1930

Prehistoric/Historic Period Theme (s):

Architecture, Landscape Architecture, and
Community Planning

RESOURCE TYPE(S)

Category: Building

Historic Environment: Urban

Historic Function (s): Domestic: Single Dwelling
Commerce/Trade: Professional

Known Design Source: Unknown

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-660

196 Prince George Street
name of property
Annapolis, Maryland
county and state

=====
Chain of Title for 196 Prince George Street:

- 1718: James Parrock, executor of Benjamin Fordham,
to Thomas Bordley
Provincial Court Deed
Liber IB 2 Folio 498
- 1726: Thomas Bordley devised Lots 92, 93, 104, and
105 to sons John and Thomas
Will Records of Anne Arundel County
Liber 19 Folio 99
- 1747: Thomas Bordley, II devised interest to brother
John Bordley
Will Records of Anne Arundel County
Liber 25 Folio 310
- 1757: John Bordley of Kent County devised to wife
Isabella Bordley
Will Records of Anne Arundel County
Liber 31 Folio 212
- 1761: Isabella Bordley Stevenson and husband William
Stevenson of Kent County to Robert Sterling
Lots 92, 93, 104, and 105
Provincial Court Deeds
Liber BB 2 Folio 563
- February 1762: Title cleared by Robert Sterling to William
Stevenson
Provincial Court Deeds
Liber BB 2 Folio 601
- March 1762: William Stevenson to Thomas Johnson, Jr.
Lots 92, 93, 104, and 105 with improvements
Provincial Court Deeds
Liber B Folio 276
- 1763: Thomas Johnson, Jr. to William Paca
Lots 93 and 104 with improvements
Provincial Court Deeds
Liber BB 2 Folio 797

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-660

196 Prince George Street
name of property
Annapolis, Maryland
county and state

- =====
- 1763: Thomas Johnson, Jr. to Edward Lloyd
Lots 92 and 105 with improvements
Provincial Court Deeds
Liber BB 3 Folio 77
- 1772: Edward Lloyd to Matthias Hammond
Lots 92 and 105 in exchange for Lot 90
Land Records of Anne Arundel County
Liber IB 3 Folio 405
- 1774: Denton Hammond to Matthias Hammond
Lots 91 and 106
Land Records of Anne Arundel County
Liber IB 4 Folio 361
- 1786: Matthias Hammond devised to nephew John
Hammond
- 1789: John Hammond to brother Philip Hammond
Land Records of Anne Arundel County
Liber NH 5 Folio 122
- 1810: Philip Hammond to Ninan Pinkney
Land Records of Anne Arundel County
Liber NH 15 Folio 619
- 1811: Ninan Pinkney to J.T. Chase
Land Records of Anne Arundel County
Liber WSG 1 Folio 141
- 1853: Chase to daughter, Frances Townley Lookerman
Liber SH 5 Folio 277
- November 20, 1870: William Harwood, Trustee for Solomon Phillips
and Hester Ann Lookerman Harwood, to Solomon
Phillips
Equity Case: Sale of Townley Lookerman Estate
Land Records of Anne Arundel County,
Liber SH 5 Folio 118
- May 28, 1887: Frank Stockett and John Wirt Randall, Trustees
for Solomon Phillips, to Joseph S.M. Basil
Equity Case 957: George Heath versus Waldo O.
Bigelow
Land Records of Anne Arundel County
Liber SH 30 Folio 606

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. AA-660

196 Prince George Street
name of property
Annapolis, Maryland
county and state

=====
August 2, 1893: Joseph S.M. Basil to Benjamin F. Russell and
Katherine Alice Russell
Land Records of Anne Arundel County
Liber SH 44 Folio 310

August 20, 1902: Catherine A. and Benjamin F. Russell to
Frederick W. Kipper
Land Records of Anne Arundel County,
Liber GW 25 Folio 497

May 8, 1909: James R. Brashers, Trustee for estate of
Frederick W. Kipper to John W. Martin
Will Records of Anne Arundel County,
Liber RID 1 Folio 164
Land Records of Anne Arundel County,
Liber GW 70 Folio 436


June 17, 1924: John W. Martin to Rosa and Elsie V. Meade
Land Records of Anne Arundel County,
Liber WNW 93 Folio 270

May 26, 1948: Rosa and Elsie V. Meade to Eugene M. Childs,
Trustee
Land Records of Anne Arundel County,
Liber JHH 475 Folio 10

May 26, 1948: Eugene M. Childs, Trustee to Elsie V.M.
Layden, Elsie Elizabeth Layden, and Rosa I.
Meade
Land Records of Anne Arundel County,
Liber JHH 475 Folio 12


December 1, 1975: Elsie V.M. Layden, Elsie Elizabeth Layden, and
Rosa I. Meade to Donald W. Sharp and Patricia
B. Holden
Land Records of Anne Arundel County,
Liber 2812 Folio 220

April 7, 1976: Donald W. Sharp and Patricia B. Holden to
Historic Annapolis, Inc.
Land Records of Anne Arundel County,
Liber 2850 Folio 236



196 PRINCE GEORGE ST

↖ N
NOT TO SCALE



AA-660

MAP OF ANNAPOLIS, No.4-6
 Maryland Department of Assessments and Taxation
 1967; Revised 1991
 Scale 1' = 200'



AA-660; AA-1224
196-198 PR GEORGE ST
ANNAPOLIS, MD
TRACERIES
APRIL 1996
MD SHPO
SW ELEVATION
1 OF 6



AA-660
196 PRINCE GEORGE ST
ANNAPOLIS, MD
TRACERIE'S
APRIL 1996
MD SHPO
SW ELEVATION
2 OF 6



AA-660

196 PRINCE GEORGE ST

ANNAPOLIS, MD

TRACERIES

APRIL 1996

MD SHPO

SE ELEVATION

3 OF 6



AA-660

196 PRINCE GEORGE ST

ANNAPOLIS, MD

TRACERIES

APRIL 1996

MD SHPO

NE ELEVATION

4 OF 6



AA-660

196 PRINCE GEORGE ST
ANNAPOLIS, MD

TRACERIES

APRIL 1996

MD SHPO

INTERIOR, VIEW FROM FRONT PARLOR LOOKING TOWARDS
REAR

5 OF 6



AA-660

196 PRINCE GEORGE ST

ANNAPOLIS, MD

TRACERIE'S

APRIL 1996

MD SHPO

INTERIOR, 2ND FLOOR STAIR HALL

6 OF 6

MARYLAND HISTORICAL TRUST
 21 STATE CIRCLE
 SHAW HOUSE
 ANNAPOLIS, MARYLAND 21401

HISTORIC SITES SURVEY FIELD SHEET
 Individual Structure Survey Form

SURVEY NUMBER: <u>AA 660</u>
NEGATIVE FILE NUMBER:
UTM REFERENCES: Zone/Easting/Northing
U.S.G.S. QUAD. MAP:
PRESENT FORMAL NAME:
ORIGINAL FORMAL NAME:
PRESENT USE: <u>Apartments</u>
ORIGINAL USE: <u>SF Res</u>
ARCHITECT/ENGINEER:
BUILDER/CONTRACTOR:
PHYSICAL CONDITION OF STRUCTURE: Excellent (<input checked="" type="checkbox"/>) Good () Fair () Poor: ()
THEME:
STYLE: <u>Edwardian Vernacular</u>
DATE BUILT: <u>1892-1897</u>

COUNTY: <u>Anne Arundel</u>
TOWN: <u>Annapolis</u>
LOCATION: <u>196 Prince George</u>
COMMON NAME:
FUNCTIONAL TYPE: <u>Res Map 34 Par 88</u>
OWNER: <u>Stephen J. & Christiane Krug</u>
ADDRESS: <u>196 Prince George</u> <u>Annapolis, MD 21401</u>
ACCESSIBILITY TO PUBLIC: Yes (<input checked="" type="checkbox"/>) No () Restricted ()
LEVEL OF SIGNIFICANCE: Local (<input checked="" type="checkbox"/>) State () National (<input type="checkbox"/>)

GENERAL DESCRIPTION:

Structural System

1. Foundation: Stone () Brick () Concrete () Concrete Block ()
2. Wall Structure
 - A. Wood Frame: Post and Beam () Balloon ()
 - B. Wood Bearing Masonry: Brick () Stone () Concrete () Concrete Block ()
 - C. Iron () D. Steel () E. Other:
3. Wall Covering: Clapboard () Board and Batten () Wood Shingle () Shiplap ()
 Novelty () Stucco () Sheet Metal () Aluminum () Asphalt Shingle ()
 Brick Veneer () Stone Veneer () Asbestos Shingle ()
 Bonding Pattern: _____ Other: _____
4. Roof Structure
 - A. Truss: Wood () Iron () Steel () Concrete ()
 - B. Other:
5. Roof Covering: Slate () Wood Shingle () Asphalt Shingle () Sheet Metal ()
 Built Up () Rolled () Tile () Other: _____
6. Engineering Structure:
7. Other:

Appendages: Porches () Towers () Cupolas () Dormers () Chimneys () Sheds () Ells ()
 Wings () Other:

Roof Style: Gable () Hip () Shed () Flat () Mansard () Gambrel () Jerkinhead ()
 Saw Tooth () With Monitor () With Bellcast () With Parapet () With False Front ()
 Other: Wall gable at right

Number of Stories: 3
 Number of Bays: 2
 Approximate Dimensions: 18 x 60

Entrance Location: Left

THREAT TO STRUCTURE: No Threat (<input checked="" type="checkbox"/>) Zoning () Roads () Development () Deterioration () Alteration () Other:
--

LOCAL ATTITUDES: Positive () Negative () Mixed () Other:

ADDITIONAL ARCHITECTURAL OR STRUCTURAL DESCRIPTION:

AA-660

Mansard roof with cross gable over two story breakfront and gabled dormer, bracketed cornice, molded rakes, molded caps at all windows and transom lit door, entrance in inset at left bay, with roof supported by deep sawn bracket, the frieze of the porch continuing across the bay as a belt course.


RELATED STRUCTURES: (Describe)

STATEMENT OF SIGNIFICANCE:

Excellent example of the eclectic Victorian, with good detailing, important to streetscape.

REFERENCES:

MAP: (Indicate North In Circle)



SURROUNDING ENVIRONMENT:

- Open Lane()Woodland()Scattered Buildings()
- Moderately Built Up()Densely-Built Up(✓)
- Residential()Commercial()
- Agricultural()Industrial()
- Roadside Strip Development()
- Other:

RECORDED BY:

Russell Wright

ORGANIZATION:

Historic Annapolis, Inc

DATE RECORDED:

Aug. 1983

AA-660 ✓

0106602604

Form 10-445
(5/62)

1. STATE Annapolis, Maryland COUNTY TOWN VICINITY STREET NO. 196, 198 Prince George Street ORIGINAL OWNER ORIGINAL USE residences PRESENT OWNER PRESENT USE residences WALL CONSTRUCTION clapboard NO. OF STORIES three	HISTORIC AMERICAN BUILDINGS SURVEY INVENTORY
	2. NAME DATE OR PERIOD Late 19th C. STYLE Victorian ARCHITECT BUILDER
	3. FOR LIBRARY OF CONGRESS USE

4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION OPEN TO PUBLIC **no**

These two buildings, almost identical, are almost identical with 146 Charles Street and were probably built by the same builder, perhaps for speculation. Though not outstanding they do add a picturesque quality to the street and may be an "Annapolis type." (197 and 199 are also of this type, 199 being almost identical.)



5. PHYSICAL CONDITION OF STRUCTURE **E**

6. LOCATION MAP (Plan Optional)


8. PUBLISHED SOURCES (Author, Title, Pages)
INTERVIEWS, RECORDS, PHOTOS, ETC.

7. PHOTOGRAPH

9. NAME, ADDRESS AND TITLE OF RECORDER
William D. Morgan
Columbia University
New York City

DATE OF RECORD **August 17, 1967**

SUPPLEMENTAL INFORMATION AND PHOTOGRAPHS MAY BE ADDED ON SHEET OF SAME SIZE



MARYLAND

AVENUE

GEORGE

STREET

GEORGE STREET

STREET

MARKET SP.

MARTIN

RANDALL STREET

AA 660
ANNAPOLIS HIST. DIST.

SCALE IN FEET
0 50 100 200 300 400 500





196 Prince George

AA 660

Annapolis, Anne Arundel County

Russell Wright July, 1982

Maryland Historical Trust,

Annapolis, Maryland

sw Elevation/camera facing NE