

BA 1989

HUNTER HOUSE-STIFFLER HOUSE

1896

PARKTON

PRIVATE

The Hunter House is an attractive, L-shaped, two-story plus attic house in a simplified Queen Anne style, with a full width porch, and some jerkinhead roofing. The house is covered with white aluminum siding. The dwelling was built by or for Thomas C. and Rose J. Hunter, who bought two of the Harris-Fishel lots on Calder Avenue in 1896 and were found with a "new frame dwelling" in the same year's tax ledger. The house was owned by William N. Krout from 1920 to 1924; Krout was also owner of the now extinct White Hall Roller Mill. Pleasant A. Stiffler bought the house in 1924. In 1959, Mrs. Stiffler sold to the trustees of the Parke Memorial Methodist Church next-door, which needed the rear lot of the dwelling in which to expand a proposed educational building.

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC HUNTER HOUSE

AND/OR COMMON
Stiffler House

2 LOCATION

STREET & NUMBER
18,912 York Road

CITY, TOWN Parkton VICINITY OF 2nd CONGRESSIONAL DISTRICT

STATE Maryland COUNTY Baltimore County

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL <input type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER:

4 OWNER OF PROPERTY

NAME PARKE MEMORIAL METHODIST CHURCH, INC. Telephone #: 329-6070

STREET & NUMBER
18,908 York Road

CITY, TOWN Parkton VICINITY OF STATE, zip code Maryland 21120

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC. County Courts Building

Liber #: WJR 3528
Folio #: 215

STREET & NUMBER
401 Bosley Avenue

CITY, TOWN Towson STATE Maryland 21204

6 REPRESENTATION IN EXISTING SURVEYS

TITLE NONE

DATE
___FEDERAL ___STATE ___COUNTY ___LOCAL

DEPOSITORY FOR SURVEY RECORDS

CITY, TOWN STATE

<input checked="" type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input checked="" type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Stiffler or Hunter House is an L-shaped, two-story plus attic frame house in a simplified Queen Anne style. The main block is two bays wide, set under a gabled roof, with a full-width, one-story, shed-roofed porch. The "L" portion of the house projects toward the street past the porch and presents a three-surfaced bay, sheltered on the street end by a jerkinhead roof section.

The main entrance door off the porch has a plate glass panel and it is topped by a transom, flanked by sidelights. Two windows open onto the porch, both almost floor-to-ceiling types, one set in the main block to the left of the door (or to the south), the other located in the south wall of the bay that projects toward the street. The door is centrally located in the overall house.

The porch deck is supported by a foundation of field-stone laid as uncoursed rubble. Two porch posts, machined into both square and round cross-sections support the roof and are decorated with simple scroll brackets. Balusters in the porch railing are slender, machine-turned in decorative forms.

The bay windows are mixed sash types, with older, 2-over-2 types facing the street and 1-over-1 types in the side surfaces. In this projecting bay, there are false windows at attic level under the slopes of the jerkinhead roofing.

In the second story of the main facade, the two windows facing the street are 2-over-2 types similar to others in the house.

The south (or left) end of the house contains two bays, also with the same kind of 2-over-2 windows at each story plus two rectangular windows of one light each at attic level in the gable peak.

The north facade is two bays deep, with four windows, 2-over-2 in format like the others.

Chimneys are found in the south end of the main block (an inside end-chimney) and in the ridge line of the "L" there is an internal chimney that emerges just forward (streetward or east) of the ridge line of the main block. Both chimneys have corbelled caps.

The entire house has been covered with white aluminum

CONTINUE ON SEPARATE SHEET IF NECESSARY

(continued)

BA-1989

CONTINUATION SHEET NO. 1, ITEM 7, PAGE 2

HUNTER HOUSE

siding.

Roofing material is light green rubber or asphalt tile. Foundation is uncoursed fieldstone. Rectangular cellar windows appear in both bays of the south end of the house.

This is one of the best-looking houses in Parkton, well-maintained by the church located immediately to the south.

Parke Church, which was at that time putting up an educational building. The dwelling house on this site has been preserved, although its deep rear lot provided space for the school structure and parking. (10)

NOTES:

1. Baltimore County Deeds, JWS 178:518.
2. B.C. Deeds, JWS 178:518 (Plat).
3. B.C. Deeds, LMB 191:461.
4. B.C. Deeds, WPC LMB 219:105.
5. Tax Ledger, District 7, 1918, Entry #273-54.
6. B.C. Deeds, JWS 169:315.
7. B.C. Deeds, WPC 422:486.
8. Tax Ledger, District 7, 1918, f. 611.
9. B.C. Deeds, WPC 595:4.
10. B.C. Deeds, WJR 3528:215. Also, Committee on History, Parke Memorial United Methodist Church 1888-1978 (Parkton, 1978), p. 11.

ADDENDA

The Baltimore County Union reported on January 23, 1897:

PARKTON, N.C.R.R.—The new residence for Mr. Thomas Hunter is rapidly nearing completion and he expects to occupy it next week. Mr. Wm. F. Stiffler was the contractor and builder and deserves much credit for the expeditious manner in which the work was done."

Baltimore County Deeds, Plats, and Tax Ledgers.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATAACREAGE OF NOMINATED PROPERTY 77 square perches (0.48 ac.)**VERBAL BOUNDARY DESCRIPTION**

Beginning in centerline of Calder Avenue -
 N4W 71 feet along Calder Avenue
 S76E 328 feet to York Road
 S14-1/2W 66-2/3 feet along York Road
 N76W 304 feet to Calder Avenue

(Tax Map 17 P216)

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE NONE COUNTY NONE

STATE NONE COUNTY NONE

11 FORM PREPARED BY

NAME / TITLE

John W. McGrain, Sites Surveyor

ORGANIZATION

Baltimore County Office of Planning and Zoning

DATE

May 26, 1980

STREET & NUMBER

401 Bosley Avenue

TELEPHONE

494-3495

CITY OR TOWN

Towson

STATE

Maryland 21204

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.


The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
 The Shaw House, 21 State Circle
 Annapolis, Maryland 21401
 (301) 267-1438

HUNTER HOUSE

BA 1989

U.S.G.S. 7.5 Minute Quad
NEW FREEDOM



REFORD) 663 II SW E 1:24 000
 40° NE REFORD 2.6 MI
 BALTIMORE (NORTH AVE) 22 MI
 2310 000 FEET (MSL)
 159mm E
 WHITE HALL C



ROAD CLASSIFICATION

Heavy duty	—————	Light duty
Medium-duty	- - - - -	Unimproved dirt
	⊖	○
	U.S. Route	State Route

NEW FREEDOM, M

N3937.5--W7637.5/

1958
PHOTOREVISED 197
AMS 5663 II NW SERIES

MARYLAND
 compiled by the Geological
 Survey from 1974. This



HUNTER HOUSE BA 1989
Baltimore County, Maryland
J. McGrain, March 1980
Neg. located at MHT
Mian (east) and s. facades fr. SE



HUNTER HOUSE

BA 1989

Baltimore County, Maryland

J. McGrain, March 1980

Neg. located at MHT

South facade, SE corner