

**MARYLAND HISTORICAL TRUST  
NR-ELIGIBILITY REVIEW FORM**

NR Eligible: yes \_\_\_  
no \_\_\_

Property Name: Stiltz-Bevan House Inventory Number: BA-2025

Address: 17006 York Road City: Parkton Zip Code: 21120

County: Baltimore USGS Topographic Map: Hereford, MD

Owner: Stanley A. Cohn and Karen P. Cohn

Tax Parcel Number: 245 Tax Map Number: 22 Tax Account ID Number: \_\_\_\_\_

Project: Hereford Tower Project Agency: FCC

Site visit by MHT Staff:  no  yes Name: \_\_\_\_\_ Date: \_\_\_\_\_

Eligibility recommended  Eligibility not recommended

Criteria:  A  B  C  D Considerations:  A  B  C  D  E  F  G  None

Is the property located within a historic district?  no  yes Name of district: \_\_\_\_\_

Is district listed?  no  yes Determined eligible?  no  yes District Inventory Number: \_\_\_\_\_

Documentation on the property/district is presented in: MIHP form; Rotenstein 2000

**Description of Property and Eligibility Determination:** *(Use continuation sheet if necessary and attach map and photo)*

The Stiltz-Bevan House is a 2½-story brick two-part commercial block constructed on a masonry wall foundation. The double house has a symmetrical six-bay façade and full length shed roof bracketed porch. The side-gabled roof and gable dormer are clad by standing seam metal. The windows are wood double-hung sash (9/6 and 6/6 lights) and are highlighted by brick jack arches and wood shutters. There are three-light transoms over both front doors. The building currently is used by two businesses and there is a surfaced parking lot in the rear (west). West of the house and parking lot is a hewn V-notched log stable with a standing seam metal gable roof and board-and-batten siding.

The Stiltz-Bevan House was built between 1832 and 1840, according to the MIHP form completed in 1980. Built by Nicholas Stiltz, the building was used as a store and residence as early as 1876. This property is an excellent example of a nineteenth century two-part commercial block and is further complemented by the intact log barn. This property appears to be eligible for listing in the National Register of Historic Places under Criteria A because it is a surviving example of nineteenth century commerce stimulated and supported by the advent of the York Turnpike. The property also appears to be eligible for listing in the National Register of Historic Places under Criterion C as an outstanding example of nineteenth century mixed commercial-residential architecture.

Prepared by: David S. Rotenstein

Date Prepared: 09/07/2000

<b>MARYLAND HISTORICAL TRUST REVIEW</b>	
Eligibility recommended <input type="checkbox"/>	Eligibility not recommended <input checked="" type="checkbox"/>
Criteria: <input type="checkbox"/> A <input type="checkbox"/> B <input checked="" type="checkbox"/> C <input type="checkbox"/> D	Considerations: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input checked="" type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G <input type="checkbox"/> None
Comments: _____	
_____ Reviewer, Office of Preservation Services	_____ Date
_____ Reviewer, NR program	_____ Date



# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. BA-2025

### 1. Name of Property (indicate preferred name)

historic Stiltz-Bevan House

other \_\_\_\_\_

### 2. Location

street and number 17006 York Road \_\_\_\_\_ not for publication

city, town Parkton \_\_\_\_\_ vicinity

county Baltimore

### 3. Owner of Property (give names and mailing addresses of all owners)

name Stanley A. Cohn and Karen P. Cohn

street and number 17004 York Road telephone \_\_\_\_\_

city, town Parkton state MD zip code 21120

### 4. Location of Legal Description

courthouse, registry of deeds, etc. Baltimore County Courthouse tax map and parcel: 22-245

city, town Towson liber 6357 folio 530

### 5. Primary Location of Additional Data

- Contributing Resource in National Register District  
 Contributing Resource in Local Historic District  
 Determined Eligible for the National Register/Maryland Register  
 Determined Ineligible for the National Register/Maryland Register  
 Recorded by HABS/HAER  
 Historic Structure Report or Research Report at MHT  
 Other: \_\_\_\_\_

### 6. Classification

Category	Ownership	Current Function	Resource Count	
			Contributing	Noncontributing
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture	<input type="checkbox"/> landscape	<input type="checkbox"/> buildings
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input checked="" type="checkbox"/> commerce/trade	<input type="checkbox"/> recreation/culture	<input type="checkbox"/> sites
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	<input type="checkbox"/> religion	<input type="checkbox"/> structures
<input type="checkbox"/> site		<input type="checkbox"/> domestic	<input type="checkbox"/> social	<input type="checkbox"/> objects
<input type="checkbox"/> object		<input type="checkbox"/> education	<input type="checkbox"/> transportation	<input type="checkbox"/> Total
		<input type="checkbox"/> funerary	<input type="checkbox"/> work in progress	
		<input type="checkbox"/> government	<input type="checkbox"/> unknown	
		<input type="checkbox"/> health care	<input type="checkbox"/> vacant/not in use	
		<input type="checkbox"/> industry	<input type="checkbox"/> other:	
				<b>Number of Contributing Resources previously listed in the Inventory</b>
				<u>1</u>

---

## 7. Description

Inventory No. BA-2025

---

### Condition

<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins
<input type="checkbox"/> fair	<input checked="" type="checkbox"/> altered

---

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

The Stiltz-Bevan House is a 2½-story brick two-part commercial block constructed on a masonry wall foundation. The double house has a symmetrical six-bay façade and full length shed roof bracketed porch. The side-gabled roof and gable dormer are clad by standing seam metal. The windows are wood double-hung sash (9/6 and 6/6 lights) and are highlighted by brick jack arches and wood shutters. There are three-light transoms over both front doors.

The building currently is used by two businesses and there is a surfaced parking lot in the rear (west). West of the house and parking lot is a hewn V-notched log stable with a standing seam metal gable roof and board-and-batten siding.

## 8. Significance

Inventory No. BA-2025

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	philosophy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	religion
<input type="checkbox"/> 2000-	<input checked="" type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	other:

Specific dates

Architect

Construction dates ca. 1832-1840

Builder

Evaluation for:

National Register

Maryland Register

not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance reports, complete evaluation on a DOE Form - see manual.)

The Stiltz-Bevan House was built between 1832 and 1840, according to the MIHP form completed in 1980. Built by Nicholas Stiltz, the building was used as a store and residence as early as 1876. This property is an excellent example of a nineteenth century two-part commercial block and is further complemented by the intact log barn. This property appears to be eligible for listing in the National Register of Historic Places under Criteria A because it is a surviving example of nineteenth century commerce stimulated and supported by the advent of the York Turnpike. The property also appears to be eligible for listing in the National Register of Historic Places under Criterion C as an outstanding example of nineteenth century mixed commercial-residential architecture.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. BA-2025

Name Stiltz-Bevan House

Continuation Sheet

Number 8 Page 1

---

## HISTORIC CONTEXT

### MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization:

Chronological/Developmental Period(s):

Historic Period Theme(s):

Resource Type:

Category:

Historic Environment

Historic Function(s) and Use(s):

Known Design Source:

---

## 9. Major Bibliographical References

Inventory No. BA-2025

---

Baltimore County Council (1991); Brooks, N. A., and E. G. Rockel (1979); Clemens and Clemens (1983); McGrain (1980)

---

## 10. Geographical Data

---

Acreage of surveyed property	<u>32,670 sq. ft.</u>		
Acreage of historical setting	<u>32,670 sq. ft.</u>		
Quadrangle name	<u>Hereford, MD</u>	Quadrangle scale	<u>1:24,000</u>

---

### Verbal boundary description and justification

The boundaries for this property conform to the tax parcel boundary: Map 22, Parcel 245.

---

## 11. Form Prepared By


---

name/title	David S. Rotenstein, Ph.D./Historian		
organization	URS/Dames & Moore	date	09/07/2000
street and number	7101 Wisconsin Avenue, Suite 700	telephone	301-652-221
city or town	Bethesda	state MD	zipcode 20814-4870

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust  
DHCD/DHCP  
100 Community Place  
Crownsville MD 21032  
410-514-7600





BA-2025

1/5

Stiltz-Bevan House

17006 York Road

Baltimore County, Maryland

David S. Rotenstein

8/22/2000

MD SHPO

View of the Stiltz-Bevan House,  
to the west, from across York Road.

035 NNNN 00 22 00



BA-2025

2/5


Stiltz-Bewan House  
Baltimore County, Maryland  
David S. Rotenstein

8/22/2000

MD SHPO

View of the rear of the Stiltz-Bewan  
House, to the east.

025 NNNN 09.23.00



BA-2025

3/5

Stiltz-Bevan House

17006 York Road

Baltimore County, Maryland

David S. Rotenstein

8/22/2000

MD SHPO

View of barn west of the Stiltz-Bevan  
House, to the southeast.

044 NNNN -- 09.06.00



BA-2025

4/5

Stiltz-Bevan House

17006 York Road

Baltimore County, Maryland

David S. Rotenstein

8/22/2000

MD SHPO

View of barn west of the Stiltz-Bevan  
House, to the southwest.

09.06.00

NNNN

044



BA-2025

5/5

Stiltz-Bevan House

17006 York Road

Baltimore County, Maryland

David S. Rotenstein

8/22/2000

MD SHPO

Barn on Stiltz-Bevan House parcel,  
detail of corner notching.

044 NNNN-09.06.00

BA 2025

STILTZ-BEVAN HOUSE

1832-1840

HEREFORD

PRIVATE

This 2-½ story brick house is one of the earliest town structures, built by Nicholas Stiltz on a lot subdivided by Dr. Ashton Alexander in 1832. Stiltz, who also owned the Foster-Masemore Mill, sold this lot for \$700, a substantial sum, to Ann Bevan in 1840. The house can be found on the 1850 Sidney map. The 1876 tax ledger would suggest that owner Rachel Fell kept a store there. This brick duplex, 32 by 28 feet in the 1918 tax ledger, is one of the most prominent Hereford structures, vernacular in style, reflecting the mixed Maryland and Pennsylvania traditions, with full-width front porch, six bays across. A slanted line in the brickwork of the north end would suggest that the north half of the house was once shed-roofed. The main roof is now gabled, sheathed with standing-seam metal. A frame rear wing produces an L-shaped overall plan. The house is squeezed close to its adjoining town structures. The north end wall is a blank expanse of brick.

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

**1 NAME**

HISTORIC **STILTZ-BEVAN HOUSE**

AND/OR COMMON

**2 LOCATION**

STREET & NUMBER

**17,006 York Road**

CITY, TOWN

**Hereford**

\_\_\_ VICINITY OF

CONGRESSIONAL DISTRICT

**2nd**

STATE

**Maryland**

COUNTY

**Baltimore County**

**3 CLASSIFICATION**

**CATEGORY**

- DISTRICT
- BUILDING(S)
- STRUCTURE
- SITE
- OBJECT

**OWNERSHIP**

- PUBLIC
- PRIVATE
- BOTH
- PUBLIC ACQUISITION**
- IN PROCESS
- BEING CONSIDERED

**STATUS**

- OCCUPIED
- UNOCCUPIED
- WORK IN PROGRESS
- ACCESSIBLE**
- YES: RESTRICTED
- YES: UNRESTRICTED
- NO

**PRESENT USE**

- AGRICULTURE
- COMMERICAL
- EDUCATIONAL
- ENTERTAINMENT
- GOVERNMENT
- INDUSTRIAL
- MILITARY
- MUSEUM
- PARK
- PRIVATE RESIDENCE
- RELIGIOUS
- SCIENTIFIC
- TRANSPORTATION
- OTHER:

**4 OWNER OF PROPERTY**

NAME

**Richard J. Leitch**

Telephone #: **727-5512**

STREET & NUMBER

**17,006 York Road**

CITY, TOWN

**Parkton**

\_\_\_ VICINITY OF

STATE, zip code

**Maryland 21120**

**5 LOCATION OF LEGAL DESCRIPTION**

COURTHOUSE,

REGISTRY OF DEEDS, ETC. **County Courts Building**

Liber #: **EHK JR. 5722**

Folio #: **380**

STREET & NUMBER

**401 Bosley Avenue**

CITY, TOWN

**Towson**

STATE

**Maryland 21204**

**6 REPRESENTATION IN EXISTING SURVEYS**

TITLE

**NONE**

DATE

\_\_\_ FEDERAL \_\_\_ STATE \_\_\_ COUNTY \_\_\_ LOCAL

DEPOSITORY FOR SURVEY RECORDS

CITY, TOWN

STATE

**7 DESCRIPTION**

<b>CONDITION</b>		<b>CHECK ONE</b>	<b>CHECK ONE</b>
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED      DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

**DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE**

The Stiltz-Bevan House is a 2-1/2-story brick duplex in the Maryland-Pennsylvania vernacular tradition, one of the solid town houses that give character to Hereford. Both half houses have centrally located doors and center-hall plans. The house is fairly imposing. Its main block has totally blank end walls, set on a stone foundation. The porch is moderately high, now reached by four broad steps of poured concrete, with three iron handrails. There is a full-width shed-roofed front porch, supported by five square posts of tapering design, five across the front, plus two recessed posts as at the rear corners. The posts are decorated with wood scroll brackets. Concrete piers support the posts. The porch is railed with square balusters and the street-side spaces under the deck are filled in with latticework supported by panels. The north and south ends of the porch are solid concrete walls.

Six bays open onto the porch, and each center door is flanked by a pair of double-hung sash windows with 6-over-6 lights and louvered shutters. The front doors are paneled, without window lights, and are set under rectangular transoms and protected by mismatching contemporary storm doors.

The four bays at second-story level on the main facade contain windows set directly over the windows on the porch level. These too are 6-over-6 types, fitted with shutters. All windows have brick jack arches.

The main roof is gabled, of standing-seam sheet metal like the porch roof, and there is one dormer, located in the center bay of the southern duplex, presumably the survival of a matched set of dormers. The dormer contains one double-hung sash window of 6-over-6 layout. There are two mismatching inside end chimneys. On the south end, the chimney is broad, with a corbeled cap; at the north end, the chimney is square, protected by a flat cover over the flue.

The house has a frame and clapboard rear wing, three bays deep, which provides an L-shaped plan. This wing has a shed roof, and its eaves merge with the eaves of the main roof. This wing is vernacular, if not functional, in style. Each half house contains three bedrooms.

In the blank north end-wall of the main block is a line of bricks running at a slant from the cornice of the main facade toward the rear of the house; this pattern would sug-

CONTINUE ON SEPARATE SHEET IF NECESSARY

(continued)

CONTINUATION SHEET NO. 1, ITEM 7, PAGE 2 STILTZ-BEVAN HOUSE

gest that the north half of the house once was a shed-roofed appendage, probably a grocery store, that was later raised to full height with the section to the south.

**8 SIGNIFICANCE**

STILTZ-BEVAN HOUSE

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION		
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE		
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN		
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER		
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION		
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)		
		<input type="checkbox"/> INVENTION				

SPECIFIC DATES 1832-1840

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

In August 1832, Dr. Ashton Alexander, a resident of Baltimore City, who was parceling out the former Merryman tract, Hereford Resurveyed, into town lots, sold 50 square perches to Nicholas Stiltz. This deed stated that the doctor's wife, Sarah R. Alexander, was daughter of the late John Merryman; the deed also mentioned the "village of Hereford" and referenced Green Alley, the rear access to the lots that front on the westside of York Road north of Mount Carmel Road. (1)

Nicholas Stiltz owned numerous properties and he came to own the Foster Mill, 2 miles NW of Hereford. The 1833 tax ledger fails to show his small town lot, or to indicate whether there was a house on it but, in early 1840, Stiltz and his wife and Martha Green conveyed the property to Ann Bevan, widow, delivering the deed to Joseph Bevan. The deed described the tract as Lot 4 and the \$730 price tag suggests that the substantial brick house of the present stood at that time. (2) It is not possible to identify this particular lot in all the various Stiltz holdings on the 1841 assessor's field book.

Mrs. Bevan is shown as owner on the 1850 map by J. C. Sidney and that year she deeded to Thomas Taft for \$1200. (3) The 1852 Assessment listed Thomas Taft with \$1200 in improvements plus \$1000 in Dry Goods and Groceries. (4)

In 1871, Laura A. and Mollie F. Taft, who had become tenants in common, agreed to partition the property and sold the 50 square perches to Rachel Fell for \$10. (5) The 1876 Assessor's Field Book showed that Rachel Fell owned 23-1/4 acres at Hereford and also had \$1000 stock in trade, "store goods." (6) The 1877 atlas showed the house as the third square north of the corner, and the 1878 State Directory listed Rachel Fell among the seven dealers in "General Merchandise" at Hereford. (7) She sold in 1887 for \$2000 to Solomon B. Foster. (8) Foster and wife, Mary Ann, described as residents of Woodberry conveyed the place to Jarrett N. Turnbaugh in 1896. (9) Turnbaugh appears in the 1896 tax ledger with the same 23-plus acres previously owned by Rachel Fell and the house was described as a "brick dwelling" worth

CONTINUATION SHEET NO. 1, ITEM 8, PAGE 2 STILTZ-BEVAN HOUSE

\$1100. There was also a frame barn (\$300) and "Out Buildings" worth \$125. (10)

Jarrett N. Turnbaugh died in 1904 and his widow, Melvina, married Joshua Armacost. The 1918 tax ledger showed the house as two stories, 28 by 32 feet, valued at \$914. There was one outbuilding worth \$25. (11)

Following a lawsuit in 1946, the property was sold at auction and passed to Carroll H. Hollingshead and wife. (12)

Subsequent owners were George G. and Betty Jane Litz (1974) and Richard J. Leitch (1977). (13) In 1980, the property, considerably improved in recent years, was on the real estate market, described as "zoned for business," a likely place for professional offices. (14)

## NOTES:

1. Baltimore City Deeds, AI 220:248.
2. Baltimore City Deeds, TK 306:361.
3. Baltimore City Deeds, AWB 441:49.
4. 1852 Assessment, District 7 (Hall of Records #8256).
5. Baltimore County Deeds, EHA 74:564.
6. Tax Ledger, 1876, District 7, n.p.
7. J. Frank Lewis & Co., Maryland Directory (Baltimore, 1878), p. 530.
8. B.C. Deeds, JWS 165:430.
9. B.C. Deeds, LMB 220:167.
10. Tax Ledger, 1896, District 7, Entry #587-134.
11. Tax Ledger, 1918, District 7, f. 408.
12. B.C. Deeds, RJS 1511:318.
13. B.C. Deeds EHK JR. 5443:859 and EHK JR. 5722:380.
14. Homes & Land North and Northeast of Baltimore, February 1980, p. 17.

**9 MAJOR BIBLIOGRAPHICAL REFERENCES**

STILTZ-BEVAN HOUSE

Baltimore County Deed Books and Tax Ledgers.

CONTINUE ON SEPARATE SHEET IF NECESSARY

**10 GEOGRAPHICAL DATA**

ACREAGE OF NOMINATED PROPERTY 50 sq. perches (0.31 ac.)

**VERBAL BOUNDARY DESCRIPTION**

Rectangular parcel fronting 74.25 feet on westside of York Road, running back at depth of 198 feet to Green Alley.

**LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES**

STATE NONE COUNTY NONE

STATE NONE COUNTY NONE

**11 FORM PREPARED BY**

NAME / TITLE

John W. McGrain, Sites Surveyor

ORGANIZATION

Baltimore County Office of Planning and Zoning

DATE

March 14, 1980

STREET & NUMBER

401 Bosley Avenue

TELEPHONE

494-3495

CITY OR TOWN

Towson

STATE

Maryland 21204


The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust  
The Shaw House, 21 State Circle  
Annapolis, Maryland 21401  
(301) 267-1438

UNITED STATES  
DEPARTMENT OF THE ARMY  
ENGINEERS  
(3 11 NW  
FREEDOM)

STILTZ-BEVAN HOUSE BA 2025  
U.S.G.S. 7.56 Minute Quad  
HEREFORD





STILTZ-BEVAN HOUSE      BA 2025  
Baltimore County, Maryland  
J. McGrain, MARCH 1979  
Neg. located at MHT  
Main (E) & north facades



STILTZ-BEVAN HOUSE      BA 2025  
Baltimore County, Maryland  
J. McGrain, OCT 1979  
Neg. located at MHT  
Main (E) facade from NE



STILTZ-BEVAN HOUSE      BA 2025  
Baltimore County, Maryland  
J. McGrain,      MARCH 1979  
Neg. located at MHT  
Main (E) & south facades



STILTZ-BEVAN HOUSE - STABLE  
Baltimore Co., MD. BA 2025  
J. McGrain, OCT 1979  
Neg located at MHT  
SW corner from Green Alley (SW)