

United States Department of the Interior  
National Park Service

BA-2306

For NPS use only

National Register of Historic Places  
Inventory—Nomination Form

received

date entered

See instructions in *How to Complete National Register Forms*  
Type all entries—complete applicable sections

1. Name

historic School No. 2, District 1, Catonsville; St. Mark's School

and or common Old Catonsville High School (preferred)

2. Location

street & number 20 Winters Lane N/A not for publication

city, town Catonsville N/A vicinity of Third Congressional District

state Maryland code 24 county Baltimore code 005

3. Classification

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input checked="" type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input type="checkbox"/> private residence
<input type="checkbox"/> site	<b>Public Acquisition</b>	<b>Accessible</b>	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input checked="" type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	<input checked="" type="checkbox"/> other: vacant

4. Owner of Property

name Gilbert E. South, Principal Partner  
Winters Lane Partnership

street & number 2 Winters Lane

city, town Catonsville N/A vicinity of state Maryland 21228

5. Location of Legal Description

courthouse, registry of deeds, etc. Baltimore County Courts Building

street & number 401 Bosley Avenue

city, town Towson state Maryland 21204

6. Representation in Existing Surveys

title Maryland Historical Trust  
Historic Sites Inventory has this property been determined eligible?  yes  no

date February 1987  federal  state  county  local

depository for survey records Maryland Historical Trust

city, town Annapolis state Maryland 21401

# 7. Description

BA-2306

<b>Condition</b>		<b>Check one</b>	<b>Check one</b>
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date <u>N/A</u>
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

### Describe the present and original (if known) physical appearance

Number of Resources

Contributing	Noncontributing
<u>1</u>	<u>0</u> buildings
<u>0</u>	<u>0</u> sites
<u>0</u>	<u>0</u> structures
<u>0</u>	<u>0</u> objects
<u>1</u>	<u>0</u> Total

Number of previously listed National Register properties included in this nomination: 0

Original and historic functions and uses: educational

### DESCRIPTION SUMMARY

Located at the N.E. corner of Winter's Lane and Melrose Avenue, only a short distance from Frederick Road, the old Catonsville High School remains intact within the scale and context of a quiet neighborhood. The masonry schoolhouse prominently occupies its site among mature hardwood trees and comprised of a one-story, single bay structure (1878) and a three story, four bay addition (1899). The buildings are immediately recognizable to be school by virtue of the ample provisions for light and ventilation featured at each elevation and by the location of the entrances which are centered at each of the four elevations except the north, which occurs at the interface of the one and three story building portions. In appearance, the buildings are unified by the use of matching materials and detailing of stone foundation walls, brick masonry walls and shingled gable ends. On the interior, the various rooms and their configurations remain intact with original interior finish materials, where exposed, in very good condition. Some floor, wall and ceiling surfaces have been concealed by relatively recent coverings such as carpet, tile and paneling and over time there have been modernizations made to plumbing, electrical and heating systems.

For General Description, see Continuation Sheet No. 1

United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetSection number 7 Page 1Old Catonsville High School  
Baltimore County, Maryland**GENERAL DESCRIPTION:**

The one-story portion is situated at the street corner and upon approaching the site, presents a simple rectangular aspect that is easily perceived to be single bay. The granite foundation walls are randomly coursed up to a cut sill course at floor level, above which, brick masonry extends to the roof line in common bond. There is a belt course of turned brick which occurs between the window openings at the height of the jack arched heads. The double hung wood windows have bull nose frame sections and are evenly spaced along each wall. The roof features slate shingle gables with wooden attic louvers and a pair of large, double hung ten over ten windows at each end. Closer observations reveal perforated rake boards, beaded soffits and moulded detailing at the gable ends. A third slate shingle gable features a half-round fan light occurring above the west entry door which is flanked at each side by six over six double hung sidelights extending from the door head down to a railing height sill. The raised six panel door appears to be a fairly recent replacement. The exterior, with the exception of the door and the asphalt shingle roof, appears to have a high level of integrity of character.

On the interior, the roof structure exposes half-circle timber frames beneath a sloped pilaster ceiling. The room volume is allowed light and ventilation from above by the gable windows, however a fiber tile ceiling presently conceals this area, reducing it to an attic. Around the room perimeter there are eight over eight double hung windows along each of the four plaster walls with beaded wainscot extending from sill height to floor level. Original hard pine strip floors are concealed beneath composition tile. The one-story portion is connected to the three-story building by a pair of five panel doors, one at each side of a partial partition constructed of beaded tongue and groove. The partition is open across most of the room but separates the present attic space. At the exterior entry door, the partition forms a vestibule with a pair of five panel doors. Door and window casings are plain. An intersecting gable roof meeting the west wall of the three story portion connects the two building portions.

The three-story portion presents a vertical and more complex aspect that is not immediately comprehensible upon approaching the building. The perimeter walls jog in and out to define classroom bays which feature vertically aligned groups of large double-hung windows at each floor level. The classroom bays extend above and interrupt the general roof line with wood shingle gables that occur in right-angled pairs at three corners of the building. The south west corner features an open belfry complete with bell, hip roof, flemish eaves and a wind vane. At the north elevation there is a recent metal stair extending from grade to the third floor where one window opening has been modified, probably recently, for a door. Similarly at the east elevation, there is a deteriorated exterior wooden stair which accesses four classrooms, each with a

United States Department of the Interior  
National Park Service

BA-2306

## National Register of Historic Places Continuation Sheet

Section number 7 Page 2

modified window/door installation. The north and south primary building entries feature vestibules with interior and exterior door pairs. Both exterior door pairs have been replaced with steel doors set in the original bull nose wood frame. The interior five panel wood door pairs are set with double hung sidelights and transom frames. With the exception of the steel doors and tile floor finish, the entries appear to be the original construction.

The basement is half above grade with windows at each wall. The stone and brick foundation walls are exposed except t the northeast and southeast bays which are concealed in deteriorating fiber board. The northeast bay is partitioned for toilet rooms with a terrazzo floor. The southeast bay has strip pine flooring evidencing moisture damage and poor quality interior wood sheet partitions. A fairly recent oil-fired boiler is located at the northwest bay. The southwest portion of the basement contains the original wood stair, presently carpeted, and two cast iron coal furnaces located to either side. The ceilings are plaster throughout and floors are concrete except as noted above. Situated at the east wall between the north and south bays, there is an entry area to the exterior and access up to the first floor by a narrow wooden stair. The five panel entry door and double hung sidelight with beaded sill panel survive in poor condition.

There are three high-ceiling classrooms each, on the first and second floors within the three story portion with generous provisions for light and ventilation. The classrooms are oriented to the building corners allowing for two exterior walls provided with groups of large two over two double hung windows and two interior walls with blackboards. There are two masonry ventilation shafts integral with an interior wall of each classroom that extend from the ground floor to the attic where a section of the hip roof is provided with open eaves. The shafts are equipped with a patent air control device and ventilation grills at classrooms. These controls are labeled "Isaac D. Smead & Co., Toledo, Ohio, Smead's Patent. August 1, 1882." Also, there are operable nine light transoms above five panel classroom doors which communicate to a short, wide hallway and stair. The wood strip floors and plaster ceilings of the classrooms have been overlaid with tile, however the continuous baseboard, picture moulding and plain castings remain. The hall and stairs are carpeted with wood sheet paneling occurring at wall areas of the hall. Cloakrooms are adjacent to and finished as the classroom.

# 8. Significance

BA-2306

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> architecture	<input checked="" type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

**Specific dates** 1878-1910      **Builder/Architect** Henry R. Davis

**Statement of Significance (in one paragraph)**      Applicable Criteria: A  
Applicable Exceptions: none  
Significance Evaluated: local

### SIGNIFICANCE SUMMARY:

The Old Catonsville High School is important for association with the development of Catonsville, a suburb of Baltimore. Built in 1878 and enlarged in 1898, this brick structure was erected to accommodate the educational needs of an expanding community. In the last half of the nineteenth century the Catonsville area (Baltimore County has no incorporated towns) grew rapidly, particularly with the start of the Baltimore and Catonsville Passenger Railway in 1862. The area population nearly doubled in this period. The county school commission responded to this growth first by building the 1838 section on to an earlier frame structure and then replacing the frame building with a brick building in 1898. The Old Catonsville High School represents the beginning and intermediate stage of advanced education in Catonsville at the turn of the century. In 1885 the school was designated a high school. By 1910, however, the faculty was too small to meet the demand and a new school was erected. In 1910, the property was sold to the Catholic Church.

United States Department of the Interior  
National Park Service

## National Register of Historic Places Continuation Sheet

Section number 8 Page 1

Old Catonsville High School  
Baltimore County, Maryland

### CONTEXT:

Old Catonsville High School is the most elaborate historic educational buildings surviving intact in Baltimore County. There is a small, two room, Davis-designed school at 2007 Old Frederick Road that is now used as a dwelling. Another brick school survives on the Old Hanover Road at Woodenburg-Boring, but is strictly vernacular in architecture. The Rayville School on Middletown Road at the north end of the county still has a louvered cupola set in the ridge line of the roof. The surviving Ashland school, designed by the Davis firm, shares some interior finish treatments with the Catonsville High School, but lacks a tower. Pikesville's now demolished brick school was very plain. The first Reisterstown high school was brick, originally built for the privately operated Franklin Academy; it was architecturally unimposing, looking much like an L-shaped brick house with a small cupola. Only the Old Catonsville High School has the distinctive tower and belfry.

Early development of Catonsville begins with the eighteenth century Baltimore Iron Works Company whose vast land holdings included an area known as "Frederickstadt". In 1810 the company properties were divided among members, of whom, Charles Carroll conveyed his portion to his son-in-law, Richard Caton. Settlement occurred by the subsequent division of this property into lots in the proximity of, and with access to, the established through fare traffic of Frederick Turnpike. The construction of a new road north to Franklinton created an intersection with Frederick Turnpike and encouraged commerce. St. Timothy's Hall and other professionally staffed educational institutions existed in the area and by 1850 Catonsville existed as a village.<sup>1</sup>

Previous to the 1848 Maryland Assembly's passage of "An Act to Establish Public Schools in Baltimore County", attempts to establish public schools had been unsuccessful as conditions had favored home instruction, apprenticeship, private tutoring, education abroad or a formal academy education. The new law provided for a Board of School Commissioners comprised of a representative from each election district who were charged to locate and establish schools, employ teachers, procure supplies and report annually to the County

<sup>1</sup>Brooks, Neal A., Rockel, Eric G., Hughes, William, **A History of Baltimore County**, Friends of the Towson Library, Inc., Towson, Maryland, 1979, pp. 298-9.

United States Department of the Interior  
National Park Service

BA-2306

National Register of Historic Places  
Continuation SheetSection number 8 Page 2 Old Catonsville High School  
Baltimore County, Maryland

Commissioners. Shortly thereafter, in 1849, a one acre lot on Winter's Lane was conditionally donated to the County Commissioners by John Gittings as the site for Public School Number Two District One, Catonsville.<sup>2</sup>

There were 60 schools in Baltimore County in 1849 with a total of 1,858 pupils in attendance. The School Commissioners described conditions of schoolhouses in 1856 as "generally small, old, and dilapidated buildings, relics of the olden time, and totally unfit for the purposes of education; only a small number can be considered ordinary, none good- and of furniture there is nothing worthy of the name." A log structure, approximately 18 feet square, provided with front and back doors, a fireplace, pupil benches, a writing shelf along two walls and without ceiling or plastering may be considered the model for 46 of 99 schoolhouses then in use. Other facilities included rooms in private dwellings, church basements, frame, stone or masonry buildings originally intended for other uses. The 1857 Catonsville School of 35 pupils was conducted by one teacher in a church basement.<sup>3</sup>

The School Commissioners Annual Report for 1859 states, "Perhaps no provision for common school education has been so neglected as the proper construction and ventilation of schoolhouses. Shelter and warmth have heretofore been considered the only requisites. No such thing as a ventilator in a schoolhouse of the olden time could be found..." Commissioned by the County, the architects Thomas and James Dixon prepared plans for standardized frame buildings, modulated according to size and cost. The School commissioners reported "The general design of the houses is simple, but in appearance they are neat and comfortable, and some of them are ornaments to the neighborhoods. Much attention has been paid to lighting and ventilation." The designs had satisfied the basic requirements for a classroom facility and established the schoolhouse as a recognizable and functionally specific building type within the neighborhood context.<sup>4</sup>

By 1859 Catonsville contained 4 taverns, 12 rum mills, 6 stores, 2 blacksmiths, 2 wheel wrights, 4 shoe shops, a harness maker and a public schoolhouse. "The house is frame, built by plan No. 2. The building is 24 x 36 feet, with a vestibule. The ceiling is 12 feet high to the square, with

<sup>2</sup>Crewe, Amy C., **No Backward Step Was Taken**, Teachers Association of Baltimore County, Maryland, Inc., 1949. pp. 20, 27; Baltimore County Deeds, AWB 433:487

<sup>3</sup>Crew, Amy C., **No Backward Step Was Taken**, Teachers Association of Baltimore County, Maryland, Inc., 1949. pp. 22; Annual Report of the Board of School Commissioners, Baltimore County, 1857.

<sup>4</sup>Crewe, Amy C., **No Backward Step Was Taken**, Teachers Association of Baltimore County, Maryland, Inc., 1949. pp. 23-4.

United States Department of the Interior  
National Park Service

BA-2306

**National Register of Historic Places  
Continuation Sheet**Section number 8 Page 3Old Catonsville High School  
Baltimore County, Maryland

the centre raised 3 feet above the square. The contract was awarded to George A. Nagle at \$650, but he agreed to build the house for \$600, relying upon the people in the neighborhood to pay him the balance of fifty dollars." There were thirty pupils and a teacher to use the new house.<sup>5</sup>

The concern for the physical schoolhouse was only a part of the problem facing the early school system. Geographically dispersed facilities conducted the matters of education in a rather self-styled fashion in the absence of centralized control. Reverend Libertus Van Bokkelen, who founded and directed St. Timothy's Hall, later served as Baltimore County School Commissioner from 1859 to 1865. Van Bokkelen initiated a "temporary normal school" which assembled the county's teachers. The Annual Report for 1860 states, "The five days during which this normal class convened, did more to awaken the zeal of its members, and give new life and energy to our Public School System, than could have been accomplished by any other method." Concluding the week of the normal class, teachers were examined and certified either Second or First Grade, in accordance with subject matter. Appointed as State Superintendent of Public Instruction in 1864, Van Bokkelen introduced strategies to uniformly organize the school system and outlined a "Plan for the Classification of Pupils in Mixed Ungraded Schools (through the Sixth Grade)" in 1866. In 1873 Baltimore County School Commissioners adopted a "Schedule of Studies for Ungraded Schools and the Lower Classes of Grade Schools (through the Sixth Grade)" and reported that "...Schoolhouse No. 2, at Catonsville, has been enlarged by the addition of two rooms, each 24 x 18 feet. This house will now accommodate one hundred and fifty pupils." The original design of county school buildings previously established the schoolhouse to be a single classroom simply sized for a number of general pupils. The rigors of teaching diverse courses to increased pupil numbers, grouped by achievement grades, demanded the physical accommodation that was afforded by duplicating the basic building unit and dividing that space into secondary units.<sup>6</sup>

Catonsville's development as a suburb of Baltimore City is attributable to accessibility, at first by turnpike, and later by railroad. The Baltimore and Catonsville Passenger Railway offered commuter service to the public on August 5, 1862, enhancing commerce and development. Catonsville continued to develop

<sup>5</sup>Brooks, Neal A., Rockel, Eric G., Hughes, William, **A History of Baltimore County**, Friends of the Towson Library, Inc., Towson, Maryland, 1979, pp. 299; Annual Report of the School Commissioners for the Year Ending December 31, 1859, pp. 9.

<sup>6</sup>Crewe, Amy C., **No Backward Step Was Taken**, Teachers Association of Baltimore County, Maryland, Inc., 1949. pp. 26, 32, 41; Report of the School Commissioners of Baltimore County, Maryland for the Scholastic Year Ending June 30th, 1873, pp. 3.

United States Department of the Interior  
National Park Service

BA-2306

National Register of Historic Places  
Continuation SheetSection number 8 Page 4Old Catonsville High School  
Baltimore County, Maryland

through the 70s as evidenced by the need to enlarge the schoolhouse within six years of the previous addition. The Annual Report for 1878 says, "The addition to the schoolhouse 2, district 1, is built of brick, one story in height and contains two rooms, contract price \$2,745. It is located in Catonsville, a short distance from the turnpike. The old building is frame containing three classrooms, originally built in 1859 and enlarged in 1872. The building was in need of repairs, the classrooms small and crowded to double their capacities, yet the patrons did not complain, and their patience has been rewarded by one of the handsomest two-room schoolhouses in the State. The building will now accommodate over two hundred and fifty pupils." In 1881 the County School Commissioners declared the facility a High School, as entitled by having one permanent assistant or more and three grades above the sixth. The county educational system had attained administrative and supervisory sophistication while the schoolhouse, renamed a high school, remained an accumulation of ad-on classrooms.

The 1880's were times of community organization in Catonsville coinciding with intensified development. The **Argus**, a local newspaper began publication, water and gas services became available, fire, police and health officials came into existence. Well-to-do Baltimoreans built impressive summer residences and speculative housing development intensified. The Catonsville Improvement Association formed an effective legislation committee to lobby at County level enabling Delegates to the Legislature to pass bills for the building of schoolhouses without consulting the School Board. Catonsville news, as reported 1898 in the **Maryland Journal**, states, "The plans for the new schoolhouse have been completed by architect H. R. Davis. The contract for the erection of the building will be awarded as soon as possible. The building will be erected on part of the old site. The brick part of the present building will be left standing and will be utilized in connection with the new building. It is expected that the frame portion of the present building will be moved..."<sup>8</sup>

Regionally, social structure was increasingly affected by conditions generated by developing industries, agricultural methods, transportation and communication. Increased population migrating to the city and the rapid

<sup>7</sup>Brooks, Neal A., Rockel, Eric G., Hughes, William, **A History of Baltimore County**, Friends of the Towson Library, Inc., Towson, Maryland, 1979, pp. 302, 305; Board of County School Commissioners, September 30, 1878, pp. 13; Crewe, Amy C., **No Backward Step Was Taken**, Teachers Association of Baltimore County, Maryland, Inc., 1949. pp. 52.

<sup>8</sup>Brooks, Neal A., Rockel, Eric G., Hughes, William, **A History of Baltimore County**, Friends of the Towson Library, Inc., Towson, Maryland, 1979, pp. 304-5; "Maryland Journal", July 30, 1898.

United States Department of the Interior  
National Park Service

BA-2306

## National Register of Historic Places Continuation Sheet

Section number 8 Page 5

expansion of suburbs demanded a solution for the small and geographically dispersed schools which had become inadequate for the number of pupils and impractical in terms of the logistics of administration, staffing and building maintenance. The education profession sought to consolidate schools by convincing the public of the need for modern and centrally located buildings. Survey of the new site and plans for a modern building were in process in 1909 and construction followed in 1910 and 1911. The Archdiocese of Baltimore purchased the old property from the County board of School Commissioners in March, 1910 and used the building as a Catholic elementary school and meeting hall. A new parish school was opened in 1950 and between 1950 and 1979 the building functioned as a place for meetings for various parish groups. The factors which induced the development of the old public school facility are responsible for its abandonment.<sup>9</sup>

The surviving building complex is representative of beginning and intermediate stages of school building development. The ne story portion is an example of the original one room schoolhouse partitioned to accommodate two classrooms. The three story building vertically echoes the plan of clustered frame classrooms as evidenced by the irregular foundation walls compared with the Annual Report accounts of previous additions. The relationship of classrooms remained similar though provision for vertical circulation oriented the classroom to the building's corners and consolidated the ad hoc classroom configurations into a single building. The interior wall common to adjacent classrooms incorporated the latest advances in heat and ventilation technology allowing vertical air shafts to deliver conditioned air to the classroom from patent furnaces featuring jacketed construction.

<sup>9</sup>Crewe, Amy C., **No Backward Step Was Taken**, Teachers Association of Baltimore County, Maryland, Inc., 1949. pp. 64, 97; Annual Reports of the Board of Education, 1909-11; Baltimore County Deeds, WPC 357-152; Law Offices of Gallagher, Evelius and Jones, correspondence dated 7-22-86.

# 9. Major Bibliographical References

BA-2306

See Footnotes under Section 8.

# 10. Geographical Data

Acreeage of nominated property .526 acre

Quadrangle name Baltimore West, MD

Quadrangle scale 1:24000

UTM References

A	<u>1</u> <u>8</u>	<u>3</u> <u>5</u> <u>0</u> <u>2</u> <u>4</u> <u>0</u>	<u>4</u> <u>3</u> <u>4</u> <u>18</u> <u>2</u> <u>18</u> <u>10</u>
	Zone	Easting	Northing

B			
	Zone	Easting	Northing

C			
	Zone	Easting	Northing

D			
	Zone	Easting	Northing

E			
	Zone	Easting	Northing

F			
	Zone	Easting	Northing

G			
	Zone	Easting	Northing

H			
	Zone	Easting	Northing

**Verbal boundary description and justification** Beginning at a stone marked 106 and running thence, North 35 West 40 perches, North 55 East 11½ perches South 35, East 10 perches, South 55 West 10 perches, South 35 East 30½ to the turnpike, thence to the beginning. (from original deed)

List all states and counties for properties overlapping state or county boundaries

state	N/A	code	county	code
-------	-----	------	--------	------

state	code	county	code
-------	------	--------	------

# 11. Form Prepared By

name/title Harry Parker

organization David S. Shull, A.I.A. Architects date 29 September 1986

street & number 518 South Hanover Street telephone (301) 332 0128

city or town Baltimore state Maryland 21201

# 12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national  state  local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature *J. M. A. L.* 7-29-87

title STATE HISTORIC PRESERVATION OFFICER date

For NPS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

Attest:

date

Chief of Registration

NATIONAL PARK SERVICE  
STATE REVIEW SHEET

BA-2306

Historic Preservation Certification Application--Part I

St. Marks School

Property: OLD CATONSVILLE HIGH SCHOOL, CATONSVILLE, MD.

Historic District: PENDING INDIVIDUAL

~~11-18-86~~ Date initial application received by State \_\_\_\_\_ Date additional information

~~11-18-86~~ Date complete information received by State \_\_\_\_\_ requested by State

\_\_\_\_\_ Date of this transmittal to NPS

\_\_\_\_\_ Inspection of property by State staff?  no \_\_\_\_\_ yes Date: \_\_\_\_\_

There is adequate documentation enclosed to evaluate the historic character and integrity of this property.

\_\_\_\_\_ There is insufficient documentation to evaluate the property adequately. The application is missing the following items: \_\_\_\_\_

Reasonable efforts, described below, have been made to obtain this information. Copies of the information requests are enclosed.

1	This property involves:	
	<input type="checkbox"/> Extensive loss of historic fabric	<input type="checkbox"/> Obscured or covered elevation(s)
	<input type="checkbox"/> Substantial alterations over time	<input type="checkbox"/> Moved property
	<input checked="" type="checkbox"/> Preliminary determination of listing for district	<input type="checkbox"/> State recommendation inconsistent with NR documentation
	<input checked="" type="checkbox"/> for individual property	<input type="checkbox"/> Recommendation different than the applicant's request

Complete one section below as appropriate.

(1)  The property  contributes \_\_\_\_\_ does not contribute to the historic significance of this district in:  
 location  design  setting  materials  workmanship  feeling and association  
Property is mentioned in the NR documentation in Section \_\_\_\_\_, page \_\_\_\_\_.

(2) \_\_\_\_\_ For properties less than 50 years old:  
\_\_\_\_\_ the historical merits of the district (the periods and areas of significance) are documented in the National Register nomination form or district documentation on file as less than 50 years old, justifying the certification of this property's contribution.  
\_\_\_\_\_ the strong historical or architectural merit of this property as described in the National Register nomination form or district documentation on file justifies its certification as contributing.  
\_\_\_\_\_ there is insufficient justification to consider this property contributing to the district on the basis of its individual architectural or historical merits or the significance of the district does not extend up to and including the latest 50 year period.  
Briefly explain how Standard (3) applies to this property's individual merits or its significance in relationship to the significant qualities and characteristics of the district.

(3) For preliminary determinations:  
A. The status of the nomination for the property/historic district:  
\_\_\_\_\_ Nomination has already been submitted to State review board, and if reviewed by the board, nomination will be forwarded to the NPS within a reasonable period of time. (Draft nomination is enclosed.)  
\_\_\_\_\_ Nomination was submitted to the NPS on \_\_\_\_\_.  
 Nomination will be submitted to the State review board within twelve months.  
\_\_\_\_\_ Nomination process likely will be completed within thirty months.  
\_\_\_\_\_ Other; explain: \_\_\_\_\_

B. Evaluation of the property:  
 Property  is individually eligible and meets National Register Criteria for Evaluation  
\_\_\_\_\_ Property is located within a potential registered district that meets National Register Criteria for Evaluation  
 A \_\_\_\_\_ B \_\_\_\_\_ C \_\_\_\_\_ D Exceptions:

(4) The property is located in a registered district, is outside the period(s) and/or area(s) of significance as documented in the NR nomination and:  
\_\_\_\_\_ appears to contribute to the expanded significance of the district. Enclosed is the revised nomination documentation.  
\_\_\_\_\_ does not appear to contribute to the period(s) and/or area(s) of significance of the district.

sections below for all properties:

Description of district including the period(s) and area(s) of significance as described in the National Register documentation or documentation on file (except for preliminary determination of individual listing).

N/A

Period(s) of significance: \_\_\_\_\_ Section \_\_\_\_\_, page \_\_\_\_\_.

Description of the property documenting current condition.

SEE ATTACHED NOMINATION FORM.

Retains sufficient integrity?  Yes  No  
Statement of significance of the property

SEE ATTACHED NOMINATION FORM

State Official Recommendation:

4

This application for the above-named property has been reviewed by MICHAEL DAY, a professionally qualified architect, architectural historian, or historian on my staff.

The property is included within the boundaries of a registered historic district, contributes to the significance of the district, and is a "certified historic structure" for the purpose of rehabilitation.

The property is included within the boundaries of a registered historic district, contributes to the significance of the district, and is a "certified historic structure" for a charitable contribution for conservation purposed in accordance with the Tax Treatment Extension Act of 1980.

The property does not contribute to the significance of the above-named district.

The property appears to meet the National Register Criteria for Evaluation and will likely be nominated.

The property does not appear to meet the National Register Criteria for Evaluation and will not be nominated.

The property appears to contribute to the significance of a:

potential historic district which appears to meet the National Register Criteria For Evaluation and will likely be nominated.

registered historic district but is outside the period(s) and area(s) of significance as documented in the National Register nomination or district documentation on file with the NPS. Revised nomination or district documentation is enclosed.

The property should be denied a preliminary determination that it could qualify as a certified historic structure.

Insufficient documentation has been provided to evaluate the structure.

Detailed NPS review recommended  Precedent setting case  Forwarded without recommendation

Date: 12-1-86

State Official Signature: 

HISTORIC PRESERVATION CERTIFICATION APPLICATION  
PART 1 - EVALUATION OF SIGNIFICANCE

BA-2306

NPS Office Use Only

Project Number:

Instructions: Read the instructions carefully before completing application. No certification will be made unless a completed application form has been received. Use typewriter or print clearly in black ink. If additional space is needed, use continuation sheets or attach blank sheets.

1. Name of property: Old Catonsville High School

Address of property: 20 Winters Lane

City Catonsville County Baltimore State Maryland Zip Code 21228

Name of historic district: N/A

National Register district  certified state or local district  potential historic district

2. Check nature of request:

- certification that the building contributes to the significance of the above-named historic district for the purpose of rehabilitation.
- certification that the structure or building and, where appropriate, the land area on which such a structure or building is located contributes to the significance of the above-named historic district for a charitable contribution for conservation purposes.
- certification that the building does not contribute to the significance of the above-named district.
- preliminary determination for individual listing in the National Register.
- preliminary determination that a building located within a potential historic district contributes to the significance of the district.
- preliminary determination that a building outside the period or area of significance contributes to the significance of the district.

3. Authorized project contact:

Name David S. Shull A.I.A. Architects Title Architect

Street 518 S. Hanover Street City Baltimore

State Maryland Zip 21201 Telephone Number (during day): 301-332-0128

4. Owner:

Name Winters Lane Partnership

Street 10B Winters Lane City Baltimore

State Maryland Zip 21228 Telephone Number (during day): 301-744-1667

I hereby attest that the information I have provided is, to the best of my knowledge, correct, and that I own the above-named property.

Owner's Signature W. Brent Sauterbock Date 10/2/86

Social Security Number or Taxpayer Identification Number 52-1420066

NPS Office Use Only

The National Park Service has reviewed the "Historic Preservation Certification Application - Part 1" for the above-named property and hereby determines that the property:

- contributes to the significance of the above-named district and is a "certified historic structure" for the purpose of rehabilitation.
- contributes to the significance of the above-named district and is a "certified historic structure" for a charitable contribution for conservation purposes in accordance with the Tax Treatment Extension Act of 1980.
- does not contribute to the significance of the above-named district.

Preliminary Determinations:

- appears to meet the National Register Criteria for Evaluation and will likely be listed in the National Register of Historic Places if nominated by the State Historic Preservation Officer according to the procedures set forth in 36 CFR Part 60.
- does not appear to meet the National Register Criteria for Evaluation and will likely not be listed in the National Register.
- appears to contribute to the significance of a potential historic district, which will likely be listed in the National Register of Historic Places if nominated by the State Historic Preservation Officer.
- appears to contribute to the significance of a registered historic district but is outside the period or area of significance as documented in the National Register nomination or district documentation on file with the NPS.
- does not appear to qualify as a certified historic structure.

HISTORIC PRESERVATION  
CERTIFICATION APPLICATION-

NPS Office Use Only

BA-2306

Old Catonsville High School

Property Name

20 Winters Lane, Catonsville, MD

Property Address

Winters Lane Partnership 52-1420066

Owner Name/Social Security or Taxpayer ID Number

Project Number:

5. Description of physical appearance:

See Attached

Date of Construction: 1878 Source of Data: Annual Report of the Board of School

Date(s) of Alteration(s): 1898 Commissioners, Baltimore County, 9-30-1878

Has building been moved?  yes  no. If so, when?

6. Statement of significance:

See Attached

7. Photographs and maps.

Attach photographs and maps to application.

Continuation sheets attached:  yes  no







SECOND FLOOR PLAN

REVISIONS

SEAL

Blank space for project notes or additional information.

SKEL & RUTHERFORD  
MECHANICAL/ELECTRICAL  
ENGINEERS  
2125 MARYLAND AVE.  
BALTIMORE, MD 21218

DAVID S. SHILL AIA  
ARCHITECTS  
518 S. HARBOUR STREET  
BALTIMORE, MD 21201  
(XO) 332-0128


DRAWN BY

DATE

SHEET NO. OF


BA-2306

OLD CATONSVILLE HIGH SCHOOL  
20 Winters Lane  
Catonsville, Maryland




BA-2306  
 Old Catonsville  
 High School  
 BA-2306  
 Baltimore Co.  
 Maryland

18/350240/4348280



(SAVAGE)  
 2062 III NE

Mapped by the Army Map Service  
 Edited and published by the Geological Survey  
 Control by USGS, USC&GS, USCE, and City of Baltimore  
 Topography from aerial photographs by photogrammetric methods  
 Aerial photographs taken 1943. Field checked 1944  
 Culture revised by the Geological Survey 1953  
 Hydrography from USC&GS Chart 545 (1942)  
 Polyconic projection. 1927 North American datum  
 10,000-foot grid based on Maryland coordinate system.  
 1000-meter Universal Transverse Mercator grid ticks,  
 zone 18, shown in blue  
 Red tint indicates areas in which only landmark buildings are shown



UTM GRID AND 1974 MAGNETIC NORTH DECLINATION AT CENTER OF SHEET



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

3. south elevation, view to N.W.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

1. west elevation



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

48. Ground floor N.E. toilet room, view to S.E.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

2. south elevation, view to N.E.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

44. Ground floor view to N.W.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

47. S.E. room, view to S.

Ground floor



BA-2306


OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

45. Ground floor view to N.E.

oil fired boiler



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

46. Ground floor S.E. room



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

40. Ground floor/1st floor at south entry  
view to N.E.



OLD CATONSVILLE HIGH SCHOOL

BA-2306

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

42. Ground floor furance front (1 of 2)



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

43. Ground floor furance front (2 of 2)

view to S.W.



BA-2306 -00

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

41. stair, view to S.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

36. 1st floor N.E. classroom



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

37. 1st floor N.W. classroom



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

39. 1st floor stair, view to south entrance




BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

38. typical moulding & casing



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

32. classroom (1-story), ventilation grill

1st floor



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

33. 1st floor hall, view to E.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

35. 1st floor S.E. classroom.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

34. 1st floor hall, view to N.E.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

28. 1st floor hall & stair, view to S.W.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

29. 1st floor hall, view to W.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

31. 1st floor classroom (1-story), typical  
window



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

30. 1st floor classroom (1-story), view to S.E.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

24. 2nd floor N.E. classroom



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

25. N.E. classroom, 2nd floor



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

27. 1st floor stair landing, view S. to  
windows



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

26. 1st floor stair landing, view N. up to 2nd  
floor



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

20. 2nd floor S.E. classroom



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

21.2nd floor S.E. classroom, view N. to hall





BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

23. 2nd floor S.E. classroom, west wall detail  
ventilation control



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

22. S.E. classroom, view to west, 2nd floor  
ventilation grills & control



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

16. 2nd floor hall, view to east



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

17. 2nd floor hall, veiw to N.E.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

19. 2nd floor, S.E. classroom



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

18.2nd floor, typical coat room



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

12. 2nd floor hall, view to west



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

13. 2nd floor hall & stair, view to south



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

14. 2nd floor stair detail



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

15. 2nd floor stair detail



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

8. north & west elevation, view to S.E.



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

9. north elevation, view up at 1st story gable



OLD CATONSVILLE HIGH SCHOOL

BA-2306

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

11. north elevation, entry detail



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

10. north elevation, entry



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

4. typical exterior masonry detail



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

5. east elevation

OLD CATONSVILLE HIGH SCHOOL



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

7. north elevation



BA-2306

OLD CATONSVILLE HIGH SCHOOL

20 Winters Lane, Baltimore County, Maryland

Photo- David S. Shull A.I.A. Architects 9-22-86

6. east & north elevation, view to S.W.