

**MARYLAND HISTORICAL TRUST
DETERMINATION OF ELIGIBILITY FORM**

NR Eligible: yes
no

Property Name: Ehrhardt-Rude Property Inventory Number: BA-3006
 Address: 8012 Windsor Mill Rd. City: Baltimore Zip Code: 21244-1300
 County: Baltimore USGS Topographic Map: Ellicott City
 Owner: Helen M. Ehrhardt Is the property being evaluated a district? yes
 Tax Parcel Number: 46 Tax Map Number: 87 Tax Account ID Number: 0205320000
 Project: _____ Agency: _____
 Site visit by MHT Staff: no yes Name: _____ Date: _____
 Is the property located within a historic district? yes no

If the property is within a district District Inventory Number: _____
 NR-listed district yes Eligible district yes District Name: _____
 Preparer's Recommendation: Contributing resource yes no Non-contributing but eligible in another context

If the property is not within a district (or the property is a district)
 Preparer's Recommendation: Eligible yes no

Criteria: A B C D Considerations: A B C D E F G None

Documentation on the property/district is presented in:

Description of Property and Eligibility Determination: *(Use continuation sheet if necessary and attach map and photo)*

The property is a vernacular wood frame dwelling on a large sloping grassy lot with mature trees and shrubs throughout. The house faces southwest toward Windsor Mill Rd. The salt-box section on the rear of the house appears to be the initial period of construction. This one-and-a-half story section is topped by a salt-box roof and features an exterior-end brick chimney clad with stucco. A shed-roof enclosed porch is located on the northwest elevation of this addition. The second period of construction is the single-pile section, which stands two stories high and measures three bays across. This section dates to the mid-to late 19th century. Both sections rest on a solid random rubble stone foundation and are clad with asbestos shingles. The two-story section has one interior-end brick chimney above the side gabled asphalt shingle roof. Features of the dwelling include thin square-edged wood surrounds and sill, a boxed wood cornice and overhanging eaves. A third addition, circa late 19th century, is located on the northwest elevation. This section, constructed of random-rubble stone, is one story in height and two bays wide. Two historic and three non-historic secondary buildings are associated with this property. (MHT Inventory #BA-3006)

As the above description states, this is an unexceptional vernacular property located in western Baltimore County. Both the original c.1835 salt-box and the later two story addition have been significantly altered in the 20th century. The salt-box became

MARYLAND HISTORICAL TRUST REVIEW	
Eligibility recommended <input checked="" type="checkbox"/>	Eligibility not recommended <input type="checkbox"/>
Criteria: <input checked="" type="checkbox"/> A <input type="checkbox"/> B <input checked="" type="checkbox"/> C <input type="checkbox"/> D	Considerations: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G <input type="checkbox"/> None
Comments: <u>Retains sufficient integrity to represent 19th-century farm complex.</u>	
<u>[Signature]</u> Reviewer, Office of Preservation Services	<u>11/7/03</u> Date
<u>[Signature]</u> Reviewer, NR Program	<u>11/17/03</u> Date

MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM

Continuation Sheet No. 1

BA-3006

the kitchen for the entire house and the two-story addition was used as living space. The third addition is now used as a mechanical room and contains the furnace for the building.

While the two-story addition still features its original windows, replacement units have been installed in the kitchen. As the kitchen is the oldest portion of the house, it has undergone the most change. A bulkheaded beam runs the length of the room and may represent an early-enclosed porch. A small vestibule has been added to the entrance. A large sink and coal stove were added in the early 20th century. The kitchen was again modernized in the 1960s. Some original features remain including the small spiral staircase leading up to the small space above the kitchen and the fireplace behind the cook stove.


While these remaining details are significant, the overall property is not an excellent example of vernacular architecture. The asbestos shingles on the exterior, replacement windows in the kitchen, and use of the stone addition as a furnace room have all significantly impacted the houses historic fabric. Part of the significance of this property is the fact that this has been in the Ehrhardt family since 1894. While a chain of title this direct is significant, it seems that there is nobody in the family willing or able to maintain this property at this time. In addition, other more representative vernacular farm structures can be found throughout Baltimore County. The building immediately across the street is a better-preserved example of a mid to late 19th century farmhouse.

Although this property is representative of a nineteenth century farm, the numerous non-historic modifications that are present do not warrant its listing on the National Register.

Prepared by: Adam Blumenthal

Date Prepared: 10/13/03


BA-3006



0 0.3 0.6 0.9 1.2 1.5 km
 0 0.2 0.4 0.6 0.8 1 mi
 Map center is UTM 18 348061E 4355935N (NAD27)
Ellicott City quadrangle
 Projection is UTM Zone 18 NAD83 Datum

M*
 G
 M=-11.105
 G=-1.118

BA-3006
Ehrhardt-Rude Property
Baltimore County
Ellicott City Quad





MIHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Adam Blumenthal

10/14/03

MD SHPO

View West on Windsor Mills Rd.

1/16

ART-2611 <No. 36A>017
355 28** * + 2 N N-3 02 (042)0



MIHP BA-3006
Ehrhardt-Rude Property
Paltimore County, MD
Adam Blumenthal

10/14/03

MD SHPO

South Facade

2/16

ART-2611
355 78**
<No. 13A>B11
N N N-3 14 (B42)@



MHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Blumenthal

10/14/03

ART-2611 <No. 12A>01B N N N-3-12 <042>@ 355 78**

MD SHPO

South Façade

3/16

Professional
PAPER
STUDIOS

10/14/03

10/14/03



MIHP BA-3006

Ehrhardt - Rude Property

Baltimore County, MD

Photographer: Aden Blunthel

10/14/03

MD S4PO

East Façade

4/16

ART-2611 <No. 11A>09
355 78** N N N-1-23-<042>@



MIHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Blumenthal

11/11/03

MD SHPO

East Facade, detail

5/16

ART-2611
355 78**
<NO. 10A>000
N N N-2-11 <042>@

PROFESSIONAL PHOTOGRAPHER
FOR CONSTRUCTION



MIHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Blumenthal

10/14/03

MD SHPO

North Facade, chimney

6/16

ART-2611 *55 78**
<No. 9A>07
N N N-3 04 <042>@

NO NOT COPY
PROHIBIDA LA REPRODUCCION

PROHIBIDA LA REPRODUCCION
NO NOT COPY



MIHP BA 3006

Richard-Rude Property

Baltimore County, MD

Photographer: Adam Blumenthal

10/14/03

MD SHPO

West Facade

7/16

ART-2611 <No. 6A>006
355 78** N N N-4 02 <042>@

Kodak Professional
PAPER PAPER
DO NOT COPY
KOPIEREN NIET



MLHP BA-3006

Ehrhardt-Rude Property
Baltimore County, MD

Photographer: Adam Blumenthal

10/14/53

MD SHPO

South facade

8/16

ART-2611
355 78**
<No. 4A>004
N N N-4 12 (042) ©



MHP BA 3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Blumenthal

10/14/03

MD SHPO

South facade, detail stone addition

9/16

ART-2611 <No. 5A>005 N N N-3 22 (042) ©
355 78**

PROFESSIONAL IMAGES ARE
PROTECTED BY COPYRIGHT
PAPER



MHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Blumthal

10/14/03

ART-2611 <No. 3A>003
355 78** N N N-2 18 <042>0

MD SHPO

Basement floor, main house

10/16

Professional
PAPER



MHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Blumenthal

10/14/03

MD SHPO

Basement ceiling, main house

11/16

ART-2611 <No. 2A>002
355 78** * N N N-3 36 <042>@



TOMATOES

MIHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Blumenthal

10/14/03

MD SHPO

Basement ceiling, main house

12/16

ART-2611 <No. 1A>001
355 28** N N N-1 22 <042>@



MIHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Blumenthal

10/14/03

MD SHPO

Kitchen sink

13/16

ART-2611 <No. 15A>012
355 28** N N N-9 32 (042)@



MHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Bhattachal

10/14/03

MD SHPO

Kitchen stove, blocking fireplace

1/4/16

ART-2611 <No. 16A>013
355 78** - N N N-5 23 <042>0

Copyright © 2003 Kodak Professional
All rights reserved. No part of this publication may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Kodak Professional.

Kodak Professional
PAPER
DO NOT COPY
REPRODUCTION



MIHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Blumenthal

10/14/03

MD SHPO

Smoke house, north elevation

15/16

ART-2611 <No. 21A>015
355 28** N N N-1-03 <042>©

PROFESSIONAL PHOTOGRAPHER
COPYRIGHT PROTECTION
DIRECT COPY



MIHP BA-3006

Ehrhardt-Rude Property

Baltimore County, MD

Photographer: Adam Blumenthal

10/14/02

MD SHPC

Smokehouse, East elevation

10/16

ART-2611 *** N N N-2 05 (0422)@
<No. 20A>014

DO NOT COPY
FOR REPRODUCTION
WITHOUT PERMISSION
OF THE STATE HISTORICAL
ARCHIVES

CAPSULE SUMMARY
BA-3006
Ehrhardt-Rude House
8012 Windsor Mill Road
Circa 1830
Private

Three families have resided at this location on Windsor Mill Road since its construction circa 1830. This vernacular frame dwelling was built by Abraham Jessop circa 1830. The Hook family purchased the property in 1838 and members resided here for approximately fifty-four years. The Ehrhardt family has owned this property for just under one hundred years, since 1874. Windsor Mill Road extends from the village of Powhattan to Court Road, just south of Randalstown. The Ehrhardt-Rude dwelling is one of the oldest remaining vernacular dwellings along this section of Windsor Mill Road.

Sited close to the road, this vernacular wood frame dwelling, circa 1830, sits on a large sloping grassy lot with mature trees and shrubs throughout. The house faces southwest towards Windsor Mill Road. The salt box section on the rear of the house, appears to be the initial period of construction. This one-and-a-half-story section is topped a salt-box roof and features an exterior-end brick chimney clad with stucco. A shed-roof enclosed porch is located on the northwest elevation of this addition. The second period of construction is the single-pile section, which stands two stories high and measures three bays across. This section dates to the mid- to late-19th century. Both sections rest on a solid random-rubble stone foundation and is clad with asbestos shingles. The two-story section has one interior-end brick chimney above the side-gable asphalt-shingle roof. Features of the dwelling include thin square-edged wood surrounds and sill, a boxed wood cornice and overhanging eaves. A third addition, circa late 19th century, is located on the northwest elevation. This section, constructed of random-rubble stone, is one story in height and two bays wide. Two historic and three non-historic secondary buildings are associated with this property.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. BA-3006

1. Name of Property (indicate preferred name)

historic Ehrhardt-Rude House

other

2. Location

street and number 8012 Windsor Mill Road not for publication

city, town Baltimore vicinity

county Baltimore County

3. Owner of Property (give names and mailing addresses of all owners)

name Helen M. Ehrhardt

street and number 8012 Windsor Mill Rod telephone not available

city, town Baltimore state MD zip code 21244-1300

4. Location of Legal Description

courthouse, registry of deeds, etc. Baltimore County Courthouse tax map and parcel: 87, 46

city, town Towson liber 14771 folio 605

5. Primary Location of Additional Data

- Contributing Resource in National Register District
- Contributing Resource in Local Historic District
- Determined Eligible for the National Register/Maryland Register
- Determined Ineligible for the National Register/Maryland Register
- Recorded by HABS/HAER
- Historic Structure Report or Research Report
- Other

6. Classification

Category	Ownership	Current Function	Resource Count	
			Contributing	Noncontributing
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> agriculture		
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	<u>2</u>	<u>3</u> buildings
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense		sites
<input type="checkbox"/> site		<input checked="" type="checkbox"/> domestic	<u>1</u>	structures
<input type="checkbox"/> object		<input type="checkbox"/> education		objects
		<input type="checkbox"/> funerary	<u>3</u>	Total
		<input type="checkbox"/> government		
		<input type="checkbox"/> health care		
		<input type="checkbox"/> industry		
		<input type="checkbox"/> landscape		
		<input type="checkbox"/> recreation/culture		
		<input type="checkbox"/> religion		
		<input type="checkbox"/> social		
		<input type="checkbox"/> transportation		
		<input type="checkbox"/> work in progress		
		<input type="checkbox"/> unknown		
		<input type="checkbox"/> vacant/not in use		
		<input type="checkbox"/> other:		
			Number of Contributing Resources previously listed in the Inventory	
			<u>1</u>	

7. Description

Inventory No. BA-3006

Condition

- | | |
|--|---------------------------------------|
| <input type="checkbox"/> excellent | <input type="checkbox"/> deteriorated |
| <input type="checkbox"/> good | <input type="checkbox"/> ruins |
| <input checked="" type="checkbox"/> fair | <input type="checkbox"/> altered |

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

Sited close to the road, this vernacular wood frame dwelling sits on a large sloping grassy lot with mature trees and shrubs throughout. The house faces southwest towards Windsor Mill Road. The salt box section on the rear of the house, appears to be the initial period of construction. This one-and-a-half-story section is topped a salt-box roof and features an exterior-end brick chimney clad with stucco. A shed-roof enclosed porch is located on the northwest elevation of this addition. The second period of construction is the single-pile section, which stands two stories high and measures three bays across. This section dates to the mid- to late-19th century. Both sections rest on a solid random-rubble stone foundation and is clad with asbestos shingles. The two-story section has one interior-end brick chimney above the side-gable asphalt-shingle roof. Features of the dwelling include thin square-edged wood surrounds and sill, a boxed wood cornice and overhanging eaves. A third addition, circa late 19th century, is located on the northwest elevation. This section, constructed of random-rubble stone, is one story in height and two bays wide. Two historic and three non-historic secondary buildings are associated with this property.

EXTERIOR

The façade of the dwelling features a central entrance flanked by two 6/6 wood sash windows. The entry contains a single-leaf 2-light 2-panel wood door. The second story has two 2/2 wood sash windows. Covering the full-width of the first story is a half-hipped replacement porch. The porch is supported with square wood posts and pilasters with lace-like brackets. A concrete foundation replaced the original porch deck. The southwest elevation of the shed-roof stone addition is two bays wide with one 6/6 wood sash window and a recessed off-center entry. The entrance holds a single-leaf vertical-board door and the window is supported with a square-edged wood sill.

The southeast elevation is pierced by one opening, a 6/6 wood sash window on the first story. A bulk-head entrance on this elevation provides access to the basement. The southeast elevation of the rear addition is one story high and two bays deep. A 6/6 wood sash window and a single-leaf 2-light wood paneled door pierce this elevation.

One 6/6 wood sash window on both the first and second story of the main block is visible on the northeast elevation. On the salt-box addition is the exterior-end shouldered brick chimney. Flanking the chimney in the upper story are 2-light wood awning windows. One replacement 1/1 wood sash window pierces the northeast elevation of the enclosed porch.

SECONDARY BUILDINGS

Close to the house is a 1920s board-and-batten shed standing one story high and one bay wide. It rests on a solid random-rubble stone foundation and is capped with a front-gable roof clad with asphalt shingles. One 6-light awning window pierces the side elevation. The roof features overhanging eaves. Sited away from the house to the north are two outbuildings, a granary and a tractor shed. The wood frame 1930s granary, is one story high and one bay wide and is clad with vertical-board siding. It is capped with a front-gable roof covered with corrugated-sheet metal, and rests on brick piers. The center entry holds a vertical-board wood door. The 1960s tractor shed stands one story high and measures five bays across. It is clad with vertical-board siding and has a post-in-ground foundation. Next, is a 1960s wood-frame chicken coop clad with horizontal-board siding resting on a cinderblock piers foundation. It is capped with a off-center gable roof covered with corrugated-sheet metal. A 1960s tobacco barn, sited to the northeast of the dwelling, is wood frame and clad with vertical-board siding. It is capped with a gambrel roof covered with standing-seam metal.

8. Significance

Inventory No. BA-3006

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime industry	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other:

Specific dates 1835 ca. Architect/Builder unknown

Construction dates 1835 ca.

Evaluation for:

National Register

Maryland Register

not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance reports, complete evaluation on a DOE Form - see manual.)

SIGNIFICANCE STATEMENT

Three families have resided at this location on Windsor Mill Road since its construction. This vernacular frame dwelling was built by Abraham Jessop circa 1830. The Hook family purchased the property in 1838 and members resided here for approximately fifty-four years. The Ehrhardt family has owned this property for just under one hundred years, since 1874. Windsor Mill Road extends from the village of Powhattan to Court Road, just south of Randalstown. The Ehrhardt-Rude dwelling is one of the oldest remaining vernacular dwellings along this section of Windsor Mill Road.

HISTORY

The Ehrhardt-Rude house is located at 8012 Windsor Mill Road near the historic village of Rockdale in the Second District of Baltimore County. The Second District is located west of Baltimore City and borders Howard and Carroll Counties. It is bounded on the south by the First District, on the east by the Third District, and on the north by the Fourth District. This section of Baltimore County is known for its granite and chrome mining. According to the Hopkins Atlas, the Second District was one of the most flourishing and rapidly growing places in the County. In 1881, the population was 3760, up slightly from 3127 in 1870. North of Windsor Mill Road is the town of Rockdale. A small village in 1881, with a population of 200, Rockdale is located along Liberty turnpike, now called Liberty Road.(1) Liberty Road connects Frederick to downtown Baltimore City at Reisterstown Road.

According to tax records of 1823, Abraham Jessop had \$40 worth on his land. For \$600, Joseph Hook bought 66 acres of land from Abraham Jessop in 1838. The land transaction included parts of three tracts of land, Timber Neck, Arey Hills, and Pleasant Springs to total sixty-six acres of land. The deed mentions buildings and other improvements to be included within the sale. This suggests that the vernacular dwelling at 8012 Windsor Mill Road was built between 1823 and 1838.

Vernacular buildings tend to have little to no stylistic detailing and are typically constructed by local builders with locally available tools and materials. Vernacular architecture accounts for the majority of the built environment and reflects the traditions of society, rather than the whims of the architect.(2) Throughout Baltimore County, there are a number of vernacular frame houses from this period. Commonly, these dwellings are two stories in height, single-pile with side gable roofs. This continuity of form is a result of folk architecture and the reliance on constructing forms that had been built by the previous generation.

Joseph Hook resided on Windsor Mill Road from 1838 until his death in 1874. He is noted on the Sidney Atlas of 1850 at this residence on the west side of Ben's Run.(3) In Hook's last will and testament, his children received his estate. The Hopkins Atlas of 1877 shows Mrs. J.A. Macken(4) on Windsor Road just south of Rockdale.(5) Daughter of Joseph Hook, Mrs. J.A. Machen,

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No BA-3006

Name Ehrhardt-Rude House

Continuation Sheet

Number 8 Page 1

was the wife of Joshua A. Machen. Joshua and Catherine Machen died in the early 1890s. In 1894, Charles Ehrhardt purchased the property from Catherine Machen's executors. A member of the Ehrhardt family continues to own this property.

ENDNOTES

1. J. Thomas Scharf, *History of Baltimore City and County From the Earliest Period to the Present Day: Including Biographical Sketches of Their Representative Men* (Philadelphia, PA: Louis H. Everts, 1881. Reprinted by Higginson Book Company, Salem, MA), pp. 830, 832.
2. Dell Upton and John Michael Vlach, editors, *Common Places: Readings in American Vernacular Architecture*, (Athens, GA: The University of Georgia Press, 1986), pp. xv-xvi.
3. J.C. Sidney, *Map of the City and County of Baltimore, Maryland, from Original Surveys* (Baltimore, MD: James M. Stephens, 1850).
4. The deed books spell this name as Machen, whereas the 1877 map spells it Macken.
5. *Atlas of Baltimore County, Maryland* (Philadelphia: G.M. Hopkins, 1877).

CHAIN OF TITLE

- | | |
|-------------------|---|
| February 7, 1838 | Abraham Jessop to Joseph Hook
Land Records of Baltimore County
Liber TK 277 Folio 272 |
| 1874 | Joseph Hook to William A. Hook and Johnsey Hook, executors
Will Records of Baltimore County
Liber BWA 4 Folio 319 |
| 1874 | Catherine M. Machen, daughter of Joseph Hook,
and Joshua A. Machen, husband, received property circa 1874
Catherine M. Machen left property to Joshua A. Machen |
| 1891 | Joshua A. Machen to Catherine Machen
Will Records of Baltimore County
Liber BWA 9 Folio 382 |
| 1892 | Catherine M. Machen to John H. Machen and Howard E. Machen, executors
Will Records of Baltimore County
Liber BWA 10 Folio 22 |
| November 21, 1894 | John H. Machen and Howard E. Machen, executors to Catherine Machen, to Charles Ehrhardt
Land Records of Baltimore County
Liber LBM 207 Folio 480 |
| December 9, 1899 | Charles and Augusta Ehrhardt to William and Paul Ehrhardt (sons)
Land Records of Baltimore County
Liber NBM 243 Folio 132 |

Maryland Historical Trust
Maryland Inventory of
Historic Properties Form

Inventory No BA-3006

Name Ehrhardt-Rude House

Continuation Sheet

Number 8 Page 2

August 26, 1928	William Ehrhardt to Mary Ehrhardt Land Records of Baltimore County Liber WJP 25 Folio 256
November 3, 1953	Lillian A. Kelly, Trustee to Mary Ehrhardt to Carl W. and Minnie Ehrhardt Land Records of Baltimore County Liber GLB 2384 Folio 503
February 18, 1999	Carl W. Ehrhardt to Helen M. Ehrhardt Land Records of Baltimore County Liber 13533 Folio 638
October 23, 2000	Helen M. Ehrhardt to Helen M. Ehrhardt Land Records of Baltimore County Liber 14771 Folio 605

9. Major Bibliographical References

Inventory No. BA-3006

See continuation sheet.

10. Geographical Data

Acreage of surveyed property 53.69 acres

Acreage of historical setting 60 acres

Quadrangle name Ellicott City

Quadrangle scale 1:24,000

Verbal boundary description and justification

The Ehrhardt-Rude house is located at 8012 Windsor Mill Road near Hebbville in the Second District of Baltimore County. It has historically been associated with tax map 87 parcel 46 since its construction.

11. Form Prepared By

name/title K. Baynard, Architectural Historian

organization E.H.T. Traceries

date 9/11/02

street and number 1121 Fifth Street, NW

telephone 202/393-1199

city or town Washington

state DC zip code 20001

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: **Maryland Historical Trust**
DHCD/DHCP
100 Community Place
Crownsville MD 21032
410-514-7600

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. BA-3006

Name Ehrhardt-Rude House

Continuation Sheet

Number 9 Page 1

Atlas of Baltimore County, Maryland. Philadelphia, PA: G. M. Hopkins, 1877.

Baltimore County Historic Inventory.

Brooks, Neal A. and Eric G. Rockel. A History of Baltimore County. Towson, MD: Friends of the Towson Library, Inc., 1979.

Map of Baltimore County. Philadelphia, PA: G. W. Bromley, 1915.


Scharf, J. Thomas. History of Baltimore City and County From the Earliest Period to the Present Day: Including Biographical Sketches of Their Representative Men. Philadelphia, PA: Louis H. Everts, 1881. Reprinted by Higginson Book Company, Salem, MA.

Sidney, J. C. Map of the City and County of Baltimore, Maryland, from Original Surveys. Baltimore, MD: James M. Stephens, 1850.

ELLICOTT CITY QUADRANGLE
MARYLAND
7.5 MINUTE SERIES (TOPOGRAPHIC)

5662 1 NW
(COCKEYSVILLE)

47°30' 346 347 348 870 000 FEET 76°45' 39°22'30"



BA-3006
Ehrhardt-Rude House
8012 Windsor Mill Road
Ellicott City USGS Quad Map
Baltimore County

MILFORD 0.6 MI.
BALTIMORE (CIVIC CENTER) 9 MI.

4354



BA-3006

EHRHARDT-RUDE HOUSE

8012 WINDSOR MILL ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MDSHPO

HOUSE, SOUTHWEST ELEVATION

1 OF 4



BA-3006

EHRHARDT-RUDE HOUSE

8012 WINDSOR MILL ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

OUTBUILDINGS, VIEW LOOKING NORTH

2 OF 4



BA-3006

EHRHARDT-RUDE HOUSE

8012 WINDSOR MILL ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

OUTBUILDINGS, VIEW LOOKING NORTH

3 OF 4



BA-3006

EHRHARDT-RUDE HOUSE

8012 WINDSOR MILL ROAD

BALTIMORE COUNTY, MD

TRACERIES

9/2002

MD SHPO

OUTBUILDING, VIEW LOOKING NORTHEAST

4 OF 4