

BA-3078

10517 Liberty Road
Randallstown vic.
Private
c. 1875-1910

The house at 10517 Liberty Road faces north toward the road and is a 2 ½-story, two-bay by a four-bay frame structure with aluminum siding. It has an ell plan with cross-gabled roofs that have asphalt shingles. On the north elevation, the first story east bay is a three-sided bay window and the west bay is a doorway with sidelights and a transom. There is a one-story porch that wraps around part of both sides of the ell and has a hip roof with asphalt shingles, round posts with large jig-sawn brackets, and drop pendants in the center of each pair of posts. The west bay of the porch, where the steps are located, has a gable added to the roof with stick work in it. The second story has a two-over-two sash in both the east and west bays. The gable end has wood shingles, some of the courses having staggered butts. There is also a jig-sawn bargeboard with spindle work here. Just west of, and behind, the gable is a dormer window with a jerkin head gable. On the east elevation, the north-center bay is a three-sided, two-story projecting bay window with a one-over-one sash in each side of both stories. Above it is a gable end with the same shingles as the north gable. The west elevation also has a gable that is identical to the gable on the north elevation. The interior has a side passage plan with a room behind the passage and a room behind the front room.

The Baltimore County Public Library's Legacy website includes photographs of the house at 10517 Liberty Road, which it calls the Albert H. Callow House, and states that it was built c. May 1872 and served as the rectory for Holy Family Catholic Church from

1903 to 1918. In that year the house was sold to Elden E. and Elizabeth W. Conrey, the parents of the current owner. According to the owner, Ms. Scott, the family lived in the house for all but a few years, when they moved to North Carolina. The 1877 Hopkins *Atlas* shows a house in the general vicinity, though it is not certain the building shown is the existing house. J. I. Holbrook occupied the house shown. The 1898 Bromley *Atlas* shows what is apparently the house, with the name "Calough" associated with it. This is probably a phonetic version of Callow by a mapmaker who did not know the correct spelling. Unfortunately, nothing more could be discovered about the house due to errors in state and county records. The house is typical of a national style that was popular c. 1875-1910, featuring a "T" or "L" plan with a projecting center section with a porch that wrapped around all three sides of that center section. The house represents the switch from traditional vernacular forms to national influences in building, which by this time had spread from urban and suburban areas to rural locations such as this one. It appears in many respects to be a pattern book house, though no immediate source could be located, and retains much of its original detail.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. BA-3078

1. Name of Property (indicate preferred name)

historic

other A. H. Callow House

2. Location

street and number 10517 Liberty Road not for publication

city, town Randallstown X vicinity

county Baltimore County

3. Owner of Property (give names and mailing addresses of all owners)

name Mrs. James R. Scott

street and number 10517 Liberty Road telephone 410-922-6717

city, town Randallstown state MD zip code 21133

4. Location of Legal Description

courthouse, registry of deeds, etc. Baltimore County Courthouse tax map and parcel: 66-83

city, town Towson liber folio

5. Primary Location of Additional Data

- Contributing Resource in National Register District
- Contributing Resource in Local Historic District
- Determined Eligible for the National Register/Maryland Register
- Determined Ineligible for the National Register/Maryland Register
- Recorded by HABS/HAER
- Historic Structure Report or Research Report
- Other _____

6. Classification

Category	Ownership	Current Function	Resource Count	
			Contributing	Noncontributing
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture		
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	<u> 1 </u>	<u> 0 </u> buildings
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	<u> 0 </u>	<u> 0 </u> sites
<input type="checkbox"/> site		<input checked="" type="checkbox"/> domestic	<u> 0 </u>	<u> 0 </u> structures
<input type="checkbox"/> object		<input type="checkbox"/> education	<u> 0 </u>	<u> 0 </u> objects
		<input type="checkbox"/> funerary	<u> 1 </u>	<u> 0 </u> Total
		<input type="checkbox"/> government		
		<input type="checkbox"/> health care		
		<input type="checkbox"/> industry		
		<input type="checkbox"/> landscape		
		<input type="checkbox"/> recreation/culture		
		<input type="checkbox"/> religion		
		<input type="checkbox"/> social		
		<input type="checkbox"/> transportation		
		<input type="checkbox"/> work in progress		
		<input type="checkbox"/> unknown		
		<input type="checkbox"/> vacant/not in use		
		<input type="checkbox"/> other:		
			Number of Contributing Resources previously listed in the Inventory	
			<u> 0 </u>	

7. Description

Inventory No. BA-3078

Condition

<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins
<input type="checkbox"/> fair	<input type="checkbox"/> altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

The house at 10517 Liberty Road faces north toward the road and is a 2 ½-story, two-bay by a four-bay frame structure with aluminum siding. It has an ell plan with cross-gabled roofs that have asphalt shingles. On the north elevation, the first story east bay is a three-sided bay window with a one-over-one sash with exterior blinds in each side. The west bay is a doorway with sidelights of three lights each, and a transom. There is a one-story porch that wraps around part of both sides of the ell and has a hip roof with asphalt shingles, round posts with large jig-sawn brackets, and drop pendants in the center of each pair of posts. These pendants join the brackets together. The railings have turned balusters. The west bay of the porch, where the steps are located, has a gable added to the roof with stick work in it. The second story has a two-over-two sash in both the east and west bays. The gable end has wood shingles, some of the courses having staggered butts. There is also a jig-sawn bargeboard with spindle work here. Just west of, and behind, the gable is a dormer window with a jerkin head gable. It has a diamond sash with four lights, and the jerkin head projects forward above this sash. There is an interior brick chimney on the west side of this dormer.

On the east elevation, the north-center bay is a three-sided, two-story projecting bay window with a one-over-one sash in each side of both stories. Above it is a gable end with the same shingles as the north gable. The bargeboard is missing, as it came down in a storm according to the owner. The north bay has no opening on the first story and a one-over-one sash on the second story. The south bay has a one-over-one sash on both the first and second stories. The south-center bay has a door on the first story and a one-story, one-bay porch with a shed roof and the same details as the north porch. This porch is now enclosed with windows.

The first story of the west elevation has a diamond Queen Anne sash in the north bay, a one-over-one sash in the north-center bay, and a new enclosed porch covering the two south bays. There is a door in the center of the east two bays in the house. The second story has four one-over-one sash, and there is a similar sash set between the north and north-center bays, between the first and second stories. Above the north-center bay is a gable that is identical to the gable on the north elevation.

The interior has a side passage plan with a room behind the passage and a room behind the front room. The flooring throughout is random-width pine that runs north-south. The passage has a two-run stair on the west with a closed stringer, turned balusters, and a square, paneled newel post. The interior doors have four panels and two-light transoms. The architrave is symmetrical, with a double bead in the center and an ogee to each side, and there are bulls-eye corner blocks. The east room has a fireplace on the west elevation, with a wood mantel that has crossetted architrave, a pulvinated frieze, and an ovolo and cavetto bed mould.

In the center of the front lawn is a large cast iron urn that replaces the original urn that was stolen circa 1995. The base beneath the urn is original, and is also cast iron, but is filled with concrete.

8. Significance

Inventory No. BA-3078

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philospohy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime industry	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other:

Specific dates n/a

Architect/Builder n/a

Construction dates n/a

Evaluation for:

National Register

Maryland Register

not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance reports, complete evaluation on a DOE Form - see manual.)

The Baltimore County Public Library's Legacy website includes photographs of the house at 10517 Liberty Road, which it calls the Albert H. Callow House, and states that it was built c. May 1872 and served as the rectory for Holy Family Catholic Church from 1903 to 1918. In that year the house was sold to Elden E. and Elizabeth W. Conrey, the parents of the current owner. According to the owner, Ms. Scott, the family lived in the house for all but a few years, when they moved to North Carolina. The 1877 Hopkins Atlas shows a house in the general vicinity, though it is not certain the building shown is the existing house. J. I. Holbrook occupied the house shown. The 1898 Bromley Atlas shows what is apparently the house, with the name "Calough" associated with it. This is probably a phonetic version of Callow by a mapmaker who did not know the correct spelling. The 1915 Bromley Atlas does not have any name with it, perhaps because it was church property. Unfortunately, nothing more could be discovered about the house due to errors in state and county records. State records for this house actually refer to the wrong deed, it being the deed for a farm on Moore's Chapel Road that Elizabeth Conrey purchased in 1934, after the death of her husband the previous year. According to the assessments and taxation office, Mrs. Conrey still owns the farm, though her daughter says it was sold in the 1960s and Mrs. Conrey died many years ago. A search of the grantee indexes for the period 1917 - 1920 turned up no mention of Elden Conrey, and an assignment of mortgage involving Elizabeth Conrey in 1934 could not be located in the mortgage or deed records, even though it is listed in the indexes. It therefore seems that there is no legal record to show that the Conreys purchased the property. Ms. Scott has copies of deeds at her bank, but as yet had not made them available. The house is typical of a national style that was popular c. 1875-1910, featuring a "T" or "L" plan with a projecting center section with a porch that wrapped around all three sides of that center section. It seems more likely to have been built after 1885, though this is not certain. The mantel suggests a twentieth-century date, but is probably an alteration by the Conrey family. The house represents the switch from traditional vernacular forms to national influences in building, which by this time had spread from urban and suburban areas to rural locations such as this one. It appears in many respects to be a pattern book house, though no immediate source could be located, and retains much of its original detail. (1)

Notes:

(1) G. M. Hopkins, Atlas of Baltimore County, Maryland (Philadelphia, 1877). G. W. Bromley, Atlas of Baltimore County, Maryland (Philadelphia, 1898, 1915).

9. Major Bibliographical References

Inventory No. BA-3078

See continuation sheet.

10. Geographical Data

Acreage of surveyed property 1.98 A.

Acreage of historical setting 1.98 A.

Quadrangle name Reisterstown

Quadrangle scale 1:24000

Verbal boundary description and justification

The boundaries include the entire parcel.

11. Form Prepared By

name/title Kenneth M. Short

organization _____ date 01/29/2003

street and number 610 Regester Ave. telephone 410-377-4953

city or town Baltimore state MD zip code 21212-1915

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville MD 21032
410-514-7600

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. BA-3078

Name

Continuation Sheet

Number 9 Page 1

See endnotes


MERLIN Online Map

Base Maps

3.75' Quarter Quad Grid



Reisterstown Quad 7.5' Topo



N 191330.98m E 413495.36m



Coordinates at center of image in Maryland State Plane, NAD 1983 meters

© Copyright 2002, Maryland Department of Natural Resources, www.mdmerlin.net
Created with TNTserver™ from Microlimages, Inc

BA-3078

10517 Liberty Rd.



BA - 3078

10517 Liberty Rd
Balto Co, MD

Ken Short

Dec. 2002

MD SHPO

N. & W. eLeus

1/2



BA-3078

10517 Liberty Rd

Balto. Co, MD

Ken Short

Dec. 2002

MD SHPO

E. & N. eleus

2/2