

CAPSULE SUMMARY

BA-384

Affinity

11544 Long Green Pike

Glen Arm, Baltimore County

Circa 1800 ca.

Private

Constructed circa 1800, Affinity is located between the historic villages of Long Green and Greenwood in the Eleventh District of Baltimore County. By 1850, the land that would become the town of Long Green was still largely rural and traversed primarily by rolling farmland. A general store and post office were located along Manor Road south of Long Green Pike's terminus at Manor Road. By 1877, however, Long Green Pike had been extended past Manor Road and the town of Long Green, which was also known as Unionville, was centered on that intersection. A store was sited on the northwest corner of the intersection of Long Green Pike and Manor Road. By the late 1870s, much of the land, although it remained rural in character, had been subdivided for use as smaller farms. Affinity is denoted on the 1850 Sidney Atlas as the property of J. Burton who is denoted on the 1877 Hopkins Atlas with 48 acres. By 1915 W.M. & S.M. Wisnom are owners of the property and the map denotes 97 acres with their property.

Facing northwest, this vernacular dwelling is surrounded by trees and shrubs on a sloping grassy lot. Sited away from the road, a paved driveway leads to the house. Standing two-and-a-half stories high, this side-gable dwelling is constructed of random-rubble stone clad with stucco. This four-bay wide dwelling was constructed in several phases. The original house appears to three bays wide with a one-bay wide addition to the side. Rising above the asphalt-shingle roof are two interior-end brick chimneys with corbeled caps. The center entry contains a single-leaf wood 12-light door. The windows are 6/6 wood sash with square wood sills. Above the roof are two non-historic gable dormers, each with a single 6/6 wood-sash window. One story in height, the full-width porch is capped with a flat roof and supported with square wood posts. The roof features overhanging eaves and a vinyl encased soffit. A two-and-a-half story ell addition was constructed on the rear elevation. A one-story shed roof addition was constructed in the angle of the ell. Six historic buildings and one non-historic structure are associated with this property.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. BA-384

1. Name of Property (indicate preferred name)

historic Affinity

other

2. Location

street and number 11544 Long Green Pike not for publication

city, town Glen Arm vicinity

county Baltimore County

3. Owner of Property (give names and mailing addresses of all owners)

name William A. Koegel

street and number 766 Old Hammonds Ferry Road telephone Not Available

city, town Linthicum state MD zip code 21090-1359

4. Location of Legal Description

courthouse, registry of deeds, etc. Baltimore County Courthouse tax map and parcel: 62, 95

city, town Towson liber N/A folio N/A

5. Primary Location of Additional Data

- Contributing Resource in National Register District
- Contributing Resource in Local Historic District
- Determined Eligible for the National Register/Maryland Register
- Determined Ineligible for the National Register/Maryland Register
- Recorded by HABS/HAER
- Historic Structure Report or Research Report
- Other

6. Classification

Category	Ownership	Current Function	Resource Count	
			Contributing	Noncontributing
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> agriculture		
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	7	
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense		
<input type="checkbox"/> site		<input checked="" type="checkbox"/> domestic		1
<input type="checkbox"/> object		<input type="checkbox"/> education		
		<input type="checkbox"/> funerary	7	1
		<input type="checkbox"/> government		
		<input type="checkbox"/> health care		
		<input type="checkbox"/> industry		
		<input type="checkbox"/> landscape		
		<input type="checkbox"/> recreation/culture		
		<input type="checkbox"/> religion		
		<input type="checkbox"/> social		
		<input type="checkbox"/> transportation		
		<input type="checkbox"/> work in progress		
		<input type="checkbox"/> unknown		
		<input type="checkbox"/> vacant/not in use		
		<input type="checkbox"/> other:		
			Number of Contributing Resources previously listed in the Inventory	
			1	

7. Description

Inventory No. BA-384

Condition

<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins
<input type="checkbox"/> fair	<input type="checkbox"/> altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

Facing northwest, this vernacular dwelling is surrounded by trees and shrubs on a sloping grassy lot. Sited away from the road, a paved driveway leads to the house. Standing two-and-a-half stories high, this side-gable dwelling is constructed of random-rubble stone clad with stucco. This four-bay wide dwelling was constructed in several phases. The original house appears to three bays wide with a one-bay wide addition to the side. Rising above the asphalt-shingle roof are two interior-end brick chimneys with corbeled caps. The center entry contains a single-leaf wood 12-light door. The windows are 6/6 wood sash with square wood sills. Above the roof are two non-historic gable dormers, each with a single 6/6 wood-sash window. One story in height, the full-width porch is capped with a flat roof and supported with square wood posts. The roof features overhanging eaves and an vinyl encased soffit. A two-and-a-half story ell addition was constructed on the rear elevation. A one-story shed roof addition was constructed in the angle of the ell. Six historic buildings and one non-historic structure are associated with this property.

One story high and one bay wide, the spring house, dating circa 1820 is constructed of random-rubble stone and is capped with a side gable roof. The roof is covered with corrugated-sheet metal. The wood-frame privy, circa 1920, is clad with board-and-batten siding and rests on a random-rubble stone foundation. It is capped with a pyramidal asphalt-shingle roof. This double-crib drive-in barn, circa 1920, is a two-story wood-frame building clad with board-and-batten siding. It rests on a random-rubble stone foundation, and is covered with a front-gable roof sheathed with corrugated-sheet metal. The bank barn, circa 1900, sits on a solid random-rubble stone foundation and is clad with vertical-board siding. The side gable roof is clad with corrugated-sheet metal. Dating to circa 1920, the remodeled garage is constructed of concrete blocks and wood frame. One exterior-side concrete block chimney rises above the side gable roof. The roof is covered with asphalt shingles and features exposed roof rafters and overhanging eaves. A 1930s concrete block barn has a front-gable roof clad with standing-seam metal. The gable is clad with wood shingles. One non-historic silo is concrete stave with a dome roof.

8. Significance

Inventory No. BA-384

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime industry	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other:

Specific dates 1800 ca. Architect/Builder unknown

Construction dates 1800 ca.

Evaluation for:

National Register Maryland Register not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance reports, complete evaluation on a DOE Form - see manual.)

Constructed circa 1800, Affinity is located between the historic villages of Long Green and Greenwood in the Eleventh District of Baltimore County. The Eleventh District is described by Scharf as being the next to largest district in the county with a population of 4,581 in 1881.(1) The district is bounded by Harford County on the east, the Tenth District on the northwest, the Ninth District on the west, the Fourteenth District on the southwest, and the Fifteenth District on the south.

By 1850, the land that would become the town of Long Green was still largely rural and traversed primarily by rolling farmland. A general store and post office were located along Manor Road south of Long Green Pike's terminus at Manor Road.(2) By 1877, however, Long Green Pike had been extended past Manor Road and the town of Long Green, which was also known as Unionville, was centered on that intersection. A store was sited on the northwest corner of the intersection of Long Green Pike and Manor Road. In addition, several churches and a schoolhouse were located in and around the community. By the late 1870s, much of the land, although it remained rural in character, had been subdivided for use as smaller farms.(3) The village of Greenwood is located on the Harford turnpike, where Long Green Road branches off. In 1881, the population of Greenwood was 100 people. At this time, a Methodist Episcopal Church and a schoolhouse were located in the village of Greenwood.(4) Long Green continued to develop slowly through the early 20th century, and by 1915, several additional residences were built along the two main roads.(5) Long Green has retained its rural, agrarian character through the late 20th century.

Affinity is denoted on the 1850 Sidney Atlas as the property of J. Burton.(6) At this time, the Friendship School is located nearby. John W. Burton is denoted on the 1877 Hopkins Atlas with 48 acres. At this location, Burton had an address with the Greenwood Post Office. He is listed as a patron to the Hopkins Atlas, which denotes him as a Blacksmith, born in Maryland, and settled in the area in 1822.(7) By 1915 W.M. & S.M. Wisnom are owners of the property and the map denotes 97 acres with their property.(8)

ENDNOTES

1. J. Thomas Scharf, History of Baltimore City and County from the Earliest Period to the Present Day: Including Biographical Sketches of Their Representative Men (Philadelphia, PA: Louis H. Everts, 1881), p. 916.
2. J.C. Sidney, Map of the City and County of Baltimore, Maryland, from Original Surveys (Baltimore, MD: James M. Stephens, 1850).
3. Atlas of Baltimore County, Maryland (Philadelphia, PA: G. M. Hopkins, 1877).
4. Scharf, p. 918.

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No BA-384

Name Affinity

Continuation Sheet

Number 8 Page 1

5. Map of Baltimore County (Philadelphia, PA: G. W. Bromley, 1915).

6. Sidney Atlas, 1850.

7. Hopkins Atlas, 1877.

8. Bromley Atlas, 1915.

9. Major Bibliographical References

Inventory No. BA-384

See continuation sheet.

10. Geographical Data

Acreage of surveyed property 98.85 acres

Acreage of historical setting 97 acres

Quadrangle name White Marsh

Quadrangle scale 1:24,000

Verbal boundary description and justification

Affinity is located at 11544 Long Greek Pike near the historic village of Long Green in the Eighth District of Baltimore County. It has historically been associated with tax map 62 parcel 95.

11. Form Prepared By

name/title K. Baynard & J. Riggle, Architectural Historian

organization E.H.T. Traceries

date 9/9/02

street and number 1121 5th Street, NW

telephone 202/393-1199

city or town Washington

state DC zip code 20001

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville MD 21032
410-514-7600

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. BA-384

Name Affinity

Continuation Sheet

Number 9 Page 1

Atlas of Baltimore County, Maryland. Philadelphia, PA: G. M. Hopkins, 1877.


Baltimore County Historic Inventory.

Brooks, Neal A. and Eric G. Rockel. A History of Baltimore County. Towson, MD: Friends of the Towson Library, Inc., 1979.

Map of Baltimore County. Philadelphia, PA: G. W. Bromley, 1915.

Scharf, J. Thomas. History of Baltimore City and County From the Earliest Period to the Present Day: Including Biographical Sketches of Their Representative Men. Philadelphia, PA: Louis H. Everts, 1881. Reprinted by Higginson Book Company, Salem, MA.

Sidney, J. C. Map of the City and County of Baltimore, Maryland, from Original Surveys. Baltimore, MD: James M. Stephens, 1850.



BA - 384
 Affinity
 11544 Long Green Pike
 White Marsh USGS Quad Map
 Baltimore County

BA CA



BA-384

AFFINITY

11544 LONG GREEN PIKE

BALTIMORE COUNTY, MD

TRACERIES

8/2002

MD SHPO

HOUSE, NORTHEAST ELEVATION

1 OF 5



BA-384

AFFINITY

11544 LONG GREEN PIKE

BALTIMORE COUNTY, MD

TRACERIES

8/2002

MD SHPO

HOUSE, SOUTH CORNER

2 OF 5



BA-384

AFFINITY

11544 LONG GREEN PIKE

BALTIMORE COUNTY, MD

TRACERIES

8/2002

MD SHPO

BARN, GARAGE, SILO, VIEW LOOKING SOUTHEAST

3 OF 5



BA-384

AFFINITY

11544 LONG GREEN PIKE

BALTIMORE COUNTY, MD

TRACERIES

8/2002

MD SHPO

CORN CRIB AND OUTHOUSE, VIEW LOOKING
EAST

4 OF 5



BA-384

AFFINITY

11544 LONG GREEN PIKE

BALTIMORE COUNTY, MD

TRACERIES

8/2002

MD SHPO

SPRING HOUSE, VIEW LOOKING SOUTHWEST

5 OF 5