

**CAPSULE SUMMARY**

**BA-475**

**Mallonee School**

**4408 Mt. Carmel Road**

**Hampstead, Baltimore County**

**Circa 1865**

**Private**

The Mallonee School is located in the historic village of Armacost and is associated with the town of Hampstead in the Fifth District of Baltimore County. Armacost started out as a crossroads community in the last half of the 19<sup>th</sup> century when after the turn of the 20<sup>th</sup> century it gained the name Armacost. According to the 1915 atlas it was served by a school, and had a sawmill to the east. The Fifth District is located in the northwest corner of Baltimore County and is historically known for its abundant waterpower and timber that spurred construction of sawmills, paper mills, and flour mills, making this an industrial region of the county. Located along Mt. Carmel Road, this school was constructed circa 1865. Although an exact date of construction for the school has not been determined, historic maps and architectural evidence support a circa 1865 date. The school is denoted (without a specific name) on the 1877 Hopkins Atlas and the 1915 Bromley Atlas.

The Mallonee Schoolhouse is located on a rural grassy lot slightly sloping surrounded by several mature trees and shrubs with a gravel driveway leading to the house. A chain link fence lines the front yard and a rock wall connects the rear of the house to the separate garage. The school, now a single dwelling, rests on a solid coursed stone foundation and is one-and-a-half stories in height and three bays wide. The original German weatherboard siding is covered with simulated brick asphalt shingle siding. A one-story wrap-around porch supported with replacement square wood posts is seen on the facade. The side elevation of the porch features six 4-light wood awning windows. The façade is pierced with two 2/2 double-hung wood sash windows and two 1/1 double-hung vinyl sash windows. There are two replacement single-leaf wood paneled-with-fanlight doors on the façade. Rising above the front gable roof is one exterior-end capped brick chimney. There are two historic outbuildings associated with this property, a garage and shed.



---

## 7. Description

Inventory No. BA-475

---

### Condition

excellent       deteriorated  
 good             ruins  
 fair               altered

---

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

The Mallonee Schoolhouse is located on a rural grassy lot slightly sloping surrounded by several mature trees and shrubs with a gravel driveway leading to the house. A chain link fence lines the front yard and a rock wall connects the rear of the house to the separate garage. The school, now a single dwelling, rests on a solid coursed stone foundation and is one-and-a-half stories in height and three bays wide. The original German weatherboard siding is covered with simulated brick asphalt shingle siding. A one-story wrap-around porch supported with replacement square wood posts is seen on the facade. The side elevation of the porch features six 4-light wood awning windows. The façade is pierced with two 2/2 double-hung wood sash windows and two 1/1 double-hung vinyl sash windows. There are two replacement single-leaf wood paneled-with-fanlight doors on the façade. Rising above the front gable roof is one exterior-end capped brick chimney.

There are two historic outbuildings associated with this property. First, is a one-story high two bay wide circa 1940 garage in fair condition. It is wood frame clad with vertical boards and the foundation is not visible. The façade has a single-leaf wood paneled-with-lights door and one paneled-with-lights wood roll-up door. The front gable roof is clad with asphalt shingles. The roof features overhanging eaves. Next to the garage is a circa 1940 wood frame shed. It is one-story high and one bay wide and is clad with vertical boards. No foundation is visible and the shed roof is covered with rolled asphalt.

# 8. Significance

Inventory No. BA-475

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input checked="" type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other:

**Specific dates** 1865 ca. **Architect/Builder** Unknown

**Construction dates** 1865 ca.

Evaluation for:

National Register                       Maryland Register                       not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

The Mallonee School is located in the historic village of Armacost and is associated with the town of Hampstead in the Fifth District of Baltimore County. Armacost started out as a crossroads community in the last half of the 19<sup>th</sup> century when after the turn of the 20<sup>th</sup> century it gained the name Armacost. According to the 1915 atlas it was served by a school, and had a sawmill to the east. The Fifth District is located in the northwest corner of Baltimore County and is historically known for its abundant waterpower and timber that spurred construction of sawmills, paper mills, and flour mills, making this an industrial region of the county. Located along Mt. Carmel Road, this school was constructed circa 1865. Although an exact date of construction for the school has not been determined, historic maps and architectural evidence support a circa 1865 date. The school is denoted (without a specific name) on the 1877 Hopkins Atlas and the 1915 Bromley Atlas.

---

## 9. Major Bibliographical References

---

Inventory No. BA-475

*Atlas of Baltimore County, Maryland.* Philadelphia, PA: G. M. Hopkins, 1877.

Baltimore County Historic Inventory.

Brooks, Neal A. and Eric G. Rockel. *A History of Baltimore County.* Towson, MD: Friends of the Towson Library, Inc., 1979.

*Map of Baltimore County.* Philadelphia, PA: G. W. Bromley, 1915.

Scharf, J. Thomas. *History of Baltimore City and County From the Earliest Period to the Present Day: Including Biographical Sketches of Their Representative Men.* Philadelphia, PA: Louis H. Everts, 1881. Reprinted by Higginson Book Company, Salem, MA.

Sidney, J. C. *Map of the City and County of Baltimore, Maryland, from Original Surveys.* Baltimore, MD: James M. Stephens, 1850.

---

## 10. Geographical Data

---

Acreeage of surveyed property	<u>.90 Acre</u>
Acreeage of historical setting	<u>Unknown</u>
Quadrangle name	<u>Hampstead</u>

Quadrangle scale: 1:24,000

---

### Verbal boundary description and justification

The Mallonee School constructed circa 1865 is located at 4408 Mt. Carmel Road in Hampstead in the Fifth District of Baltimore County, and has been associated with the historic village of Mt. Carmel. It has been historically associated with tax map 15, parcel 95 since its construction.

---

## 11. Form Prepared by

---

name/title	R. Weidlich and K. Baynard, Architectural Historians		
organization	EHT Traceries, Incorporated	date	March 19, 2002
street & number	1121 5th Street NW	telephone	202.393.1199
city or town	Washington	state	DC

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust  
DHCD/DHCP  
100 Community Place  
Crownsville, MD 21032-2023  
410-514-7600


UNITED STATES  
DEPARTMENT OF THE ARMY  
CORPS OF ENGINEERS

5663 III NE  
(LINEBORO)

345 1.5 MI. TO END OF MD. 25 47°30'

347

**BA #: 475**  
**Mallonee School**  
**4408 Mount Carmel Road**  
**Hampstead**  
**Hampstead USGS Quad Map**  
**Baltimore County**





BA-475

SCHOOL, 4408 MOUNT CARMEL ROAD

BALTIMORE COUNTY, MD

TRACERIES

3/2002

MHT

SCHOOL, SOUTHWEST ELEVATION

1 OF 4



BA-475

SCHOOL, 4408 MOUNT CARMEL ROAD

BALTIMORE COUNTY, MD

TRACERIES

3/2002

MHT

SCHOOL, NORTHWEST ELEVATION

2 OF 4



BA-475

SCHOOL, 4408 MOUNT CARMEL ROAD

BALTIMORE COUNTY, MD

TRACERIES

3/2002

MHT

SCHOOL, SOUTHEAST ELEVATION

3 OF 4



BA-475

SCHOOL, 4408 MOUNT CARMEL ROAD

BALTIMORE COUNTY, MD

TRACERIES

3/2002

MHT

SCHOOL, VIEW LOOKING NORTHEAST

4 OF 4