

**MARYLAND HISTORICAL TRUST
DETERMINATION OF ELIGIBILITY FORM**

NR Eligible: yes no

Property Name: St. Paul's Episcopal Church Inventory Number: CT-818
 Address: 25 Church Street Historic district: yes no
 City: Prince Frederick Zip Code: 20678 County: Calvert
 USGS Quadrangle(s): Prince Frederick
 Property Owner: St. Paul's Episcopal Church Tax Account ID Number: 035901
 Tax Map Parcel Number(s): 138 Tax Map Number: 24
 Project: MD 231 at MD 765A Community Enhancement and Safety Agency: Maryland State Highway Administration
 Agency Prepared By: Parsons Brinckerhoff
 Preparer's Name: G. Blanchard K. Britt Date Prepared: 5/1/2014
 Documentation is presented in: Maryland Historic Sites Inventory Form for CT-818
 Preparer's Eligibility Recommendation: Eligibility recommended Eligibility not recommended
 Criteria: A B C D Considerations: A B C D E F G
Complete if the property is a contributing or non-contributing resource to a NR district/property:
 Name of the District/Property: _____
 Inventory Number: _____ Eligible: yes Listed: yes
 Site visit by MHT Staff yes no Name: _____ Date: _____

Description of Property and Justification: *(Please attach map and photo)*

Architectural Description

St. Paul's Episcopal Church is a modest church with a harmonious design indicative of mid-nineteenth-century rural sacred architecture in Maryland. The gable-front brick church has a nave plan and is oriented to the northwest, facing Church Street in Prince Frederick. It was built in 1841, with the bell tower added in 1885. The cemetery appears to date to the 1860s.

The original building's facade is three bays with tall, thin round-arch windows in the outer bays. The church is clad in red bricks laid in a running bond pattern. A stained glass rosette window is present in the gable area, but is obscured by the bell tower. Brick corbelling and modest gable returns accentuate the gable end. The facade is dominated by a centrally placed steeple and bell tower that were added in 1885. The tower is supported on an enclosed, projecting, single-story entrance vestibule with a round-arched entrance in the central bay; double doors fit within the opening, which is articulated with brick stretchers accentuating the top of the round arch. Tall thin round arched stained glass windows are present on the sides of the vestibule. The brick on the vestibule is laid in an American bond pattern. The vestibule is topped with a wood-shingle-clad hip roof and the tower ascends above. The tower features Victorian-era decorative elements including shaped arches, excised decorative woodwork, fish-scale shingles, incised ornament, and also a dentil course. Classical columns support the tower above arched openings. Inset round arches

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended Eligibility not recommended
 Criteria: A B C D Considerations: A B C D E F G

MHT Comments:

John Zalunski
 Reviewer, Office of Preservation Services
Blanty
 Reviewer, National Register Program

6/6/2014
 Date
6/12/14
 Date

contain louvers for ventilation. The wood-shingle-clad steeple rises from an angular base and culminates in a point that is topped by a budded or Apostles cross.

The northeast and southwest side elevations are identical and are simply adorned with three evenly spaced round-arch stained glass windows. The tops of the arches are articulated with brick stretchers.

The southeast elevation (rear) contains the apse; however, it has been obscured by a 1981 addition. The rear originally appeared to be covered in stucco with a molded cornice. The apse was not full-height but was incorporated into the building with a gable-on-hip roof form. A thin, round-arch window with multiple panes is found on each side elevation of the apse.

The 1981 addition imitates this roof form, with a louvered vent in the gable. The addition is executed in brick of a slightly different color laid in running bond. A series of round-arch windows are found on rear of the addition, and round-arch doors are on the northeast and southwest sides.

The gable roof and the hip-on-gable roofs of the apse and addition are all clad in asphalt shingles.

The cemetery features grave markers from various eras. Markers are generally modest; no markers are sculptural or artistic. Mature plantings are present and include magnolia and holly trees and evergreen shrubs. A brick walkway leads from the parking lot in front of the church and a cast-iron fence with an ornate gate extends along the front of the church lot. A new and large church center/parish house is located to the historic church's southwest.

St. Paul's Episcopal Church History

St. Paul's Episcopal Church, located at Church Street in Prince Frederick has deep roots in the community. Since 1841, the site has been a place of worship. The Church of England was established in Calvert County in the 1690s, and by the 1790s, the Episcopal Church was established in America. As Prince Frederick grew and the county seat was established there, the need for a church became apparent to local officials. In 1840-1841, church officials organized a new Episcopal parish, electing a vestry and selecting the name of St. Paul's for the parish.

In 1841, the congregation let the contract to build the present church building. Bricks were fired in a kiln located on the site. The first services were held on Christmas Day in 1842. Work continued in 1844 with a new foundation and painting occurring. The Right Reverend William R. Whittingham consecrated the church in 1848. In 1856, church records indicate that the sanctuary was "repaired and remodeled." Significant alterations occurred in 1885, when the steeple and bell were added and the church was "repaired and otherwise beautified," according to congregation records. Maintenance in 1892 included a new course of brick applied to the exterior, and two years later a wall was underpinned and built up to the windows for stabilization. In 1903, the chancel was expanded to form an area for the font. Interior alterations continued in the new century, with installation of the altar window in 1909; a central sanctuary aisle placed in 1915; new flooring installed in 1918; and electric lights put in place in 1921. In 1981, a rear addition was placed on the church.

In 1856, the congregation purchased a rectory and 90-acre glebe. A fire swept through Prince Frederick in March 1882, and the courthouse was destroyed. The rectory temporarily served as courthouse space until a second fire destroyed it in September of the same year, although the church building was spared. A new rectory was constructed the following year. In 1930, a third rectory building was completed. A parish hall was completed in 1937; it was used for religious education and as a space for fellowship. In 1992, the congregation raised more than \$1 million to build the Parish House, a large meeting and banquet space for both parishioners and the community. The area surveyed for this assessment included 2.25 acres.

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended _____ Eligibility not recommended _____
Criteria: ___ A ___ B ___ C ___ D Considerations: ___ A ___ B ___ C ___ D ___ E ___ F ___ G

MHT Comments:

Reviewer, Office of Preservation Services

Date

Reviewer, National Register Program

Date

Prince Frederick and Calvert County History

Established in 1654, Calvert County is bordered by the Chesapeake Bay to the east and the Patuxent River to the west and south. Today, the county encompasses 413 square miles of land. "A History of Calvert County" states that the county extended north and northwest of its present boundaries when established, including present-day Prince George's County in its entirety. In 1658, the Prince George's County region was separated from Calvert County.

Calvert County's early settlers recognized the region's suitability for growing tobacco and tobacco cultivation emerged as the county's driving economic force in the late seventeenth century. In turn, this impacted many aspects of life in Calvert County, including its social structure and physical development. Slaves worked on tobacco plantations and the crop became so integral to life in the county that residents used the plant's leaves for currency. Residential and agrarian growth initially occurred along the county's shorelines and riverbanks, and transportation centers for shipping tobacco via the region's waterways developed instead of roads. With little need for a central market, towns did not rapidly develop and growth within the county's central region. Poor roads, along with the county's location on the Calvert Peninsula, left Calvert County isolated for many years.

According to "The County Courthouses and Records of Maryland," the original county seat was likely itinerant, but a legislative report from March 23, 1697/98 first mentions a Calvert County courthouse. Calvert County established this first courthouse at Calvertown, located on the county's western side at Battle Creek, but many residents found this location inconvenient. After repeated complaints about the location and the courthouse's declining condition, the Assembly relocated the county seat. In 1722, an act establishing the county seat on a centrally located tract of unsettled land passed. This land, known as William's Old Field, was renamed Prince Fredericktown and later Prince Frederick for King George I's eldest son. (Within this historic context, the town will be referred to as Prince Frederick, its present name.) The Assembly did not appropriate sufficient funding to build the courthouse and jail until 1725, Prince Frederick's official year of establishment.

Early settlement patterns occurred along the water. However, prior to Prince Frederick's 1725 establishment, several Calvert County residents built homes in the central region and landowners established lots in this central region. William Kidd and John Critchard completed the first Prince Frederick courthouse and nearby jail in 1732. From this site, Prince Frederick's Main Street (present-day MD 765A) and downtown evolved. After Kidd and Critchard completed the courthouse and jail, local landowners laid out plots of land for homes in Prince Frederick during the 1730s. Small wooden buildings were constructed around the courthouse over time. These buildings in town primarily housed various merchants and law offices. Due to tobacco's dominance and the region's plantation-based economy, Prince Frederick's early residents and those living in the county seat's vicinity lived on large tracts of farmland. Residents came to town to shop for supplies, socialize, or attend court.

According to "The County Courthouse and Records of Maryland," Prince Frederick's first courthouse burned during a fire in 1748. Calvert County built a second courthouse, a brick building likely the same size as the first, on the site that year. Census data indicates that 3,788 Caucasian residents lived in Calvert County in 1800, but information for Prince Frederick's total population is not available. British forces burned Prince Frederick's second courthouse, along with several homes in the town, during the War of 1812. Anticipating the British forces' arrival, officials and residents removed the county records prior to the fire. Thus, Calvert County's records dating to the Colonial era were saved. Maryland's General Assembly did not authorize funding to repair and rebuild Prince Frederick's courthouse until 1816 and Calvert County completed the town's third courthouse in 1819. During the period after the attack on Prince Frederick, a new law office opened in town.

Referenced in the newspaper article "From Humble Origins: The Birth of Prince Frederick and Calvert County," an 1824 survey maps shows Prince Frederick's location at the intersection of two roads. The map only identifies the courthouse and two buildings

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended _____ Eligibility not recommended _____
 Criteria: ___ A ___ B ___ C ___ D Considerations: ___ A ___ B ___ C ___ D ___ E ___ F ___ G

MHT Comments:

 Reviewer, Office of Preservation Services

 Date

 Reviewer, National Register Program

 Date

opposite it on Main Street (MD 765A) in the town's center. These two roads, like those throughout Calvert County, were unpaved. Prince Frederick did not benefit from hard surface roads until the early twentieth century. Prior to 1830, the town's first post office was constructed. An 1835 newspaper advertisement also mentions a large building's existence, operating as a tavern, and likely Prince Frederick's first hotel.

Though census data pertaining to Prince Frederick is not available for the 1840s, an 1840 Calvert County map indicates that 2,895 Caucasians, 1,474 free African Americans, and 4,170 slaves (9,229 residents total) lived in the county at that time. According to this data, between 1800 and 1840, the number of Caucasian citizens living in Calvert County declined. However, Prince Frederick's population was large enough for residents to justify building a church in town. Many residents disliked traveling south to Port Republic to attend church. On March 1, 1841, residents organized Prince Frederick's first congregation, St. Paul's Episcopal Church. Dr. James Duke oversaw construction the following year and builders completed the one-and-one-half story brick building in late 1842. St. Paul's Episcopal Church (CT-818) remains in its original location on present-day Church Street.

Prince Frederick experienced marginal growth during the following decades. An 1850 account specifically mentions the town's courthouse, St. Paul's Episcopal Church, an inn, lawyer's office, post office, and several homes. During the 1860s, the Civil War and slavery's end briefly interrupted Prince Frederick's economy and social order. Several plantations throughout the county were ceased to operate, but many freed slaves were employed as farm hands or tenant farmers after the war. Ultimately, the Civil War did not affect tobacco's standing as southern Maryland's primary cash crop and life in Prince Frederick and Calvert County returned to normal after the war. Farmers also continued growing wheat, another major cash crop, and orchards were common throughout the county.

Simultaneously, discussion and planning began in 1861 to develop a railroad connecting Baltimore with the harbor at Drum Point in southeastern Calvert County. The proposed Baltimore & Drum Point Railroad (CT-1295) would pass directly through Prince Frederick's town center. According to "Documentation of The Baltimore & Drum Point Railroad," the railroad's presence would have dramatically affected Prince Frederick's social and economic fabric in the late nineteenth and early twentieth century, a region long isolated by poor roads and bodies of water. An 1866 USGS map illustrates moderate growth since 1850; the map notes ten buildings in Prince Frederick's town center, including the courthouse.

In 1868, the Baltimore & Drum Point Railroad received its charter. Before the railroad's construction began, the majority of Prince Frederick burned during a devastating, accidental fire in 1882. An incident account and record, noting buildings destroyed, reveals Prince Frederick's moderate development since 1866. According to "Minutes and Proceedings of the Orphans' Court of Calvert County, Maryland," Prince Frederick's "Methodist Episcopal Church and Parsonage, Courthouse, Shoe shop, Journal Office, a large store, property of J. W. Shemwell & Bro., a large and fine hotel, property of D.R. Magruder, a dwelling house occupied by Silas R. King, and the law offices of Joseph A. Wilson, John P. Briscoe, C.S. Parran, and John B. Gray" were destroyed during the fire. In total, fourteen of the town's eighteen buildings burned, along with deeds, wills, and court records. Sommerville Sollers, the county clerk, saved some documents. Two extant buildings, the St. Paul's Episcopal Church and a Dowell family home (CT-739), survived the fire. Calvert County established a temporary courthouse in St. Paul's unoccupied rectory. Several months later on June 27, 1882, the church's rectory burned in a fire, likely caused by foul play, and records burned. According to "A History of Calvert County, Maryland," Prince Frederick and Calvert County documents dated prior to 1882 do not exist.

Calvert County built Prince Frederick's fourth courthouse on the same site; the March 1882 fire did not damage the previous courthouse's brick frame. During rebuilding, the Hotel Calvert was also constructed on Main Street (MD 765A), opposite and east of the courthouse. The hotel replaced the Brentford House, Prince Frederick's inn before the fire. In 1891, after years of legal battles and funding issues, the railroad company abandoned the Baltimore & Drum Point Railroad project. Though laborers prepared 25 miles of railroad bed by 1891, tracks were never laid. Due to the great fire and the railroad project's stoppage, Prince

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended _____ Eligibility not recommended _____
 Criteria: ___ A ___ B ___ C ___ D Considerations: ___ A ___ B ___ C ___ D ___ E ___ F ___ G

MHT Comments:

 Reviewer, Office of Preservation Services Date

 Reviewer, National Register Program Date

Frederick never experienced rapid growth or expansion during the late nineteenth and early twentieth century.

The 1986 newspaper article, "Shades of Old Prince Frederick," explains that local residents founded a Prince Frederick Development Company in 1894, "for the creation and maintenance of reading and lecture rooms in Prince Frederick." The same year, the company constructed a two-story Town Hall building on the lot located directly southeast of the courthouse. The first known photograph from the period after Prince Frederick burned, taken southwest of the small town, shows the Town Hall, young trees and shrubs, and narrow dirt roads lined by split-rail fences. Clapboard-clad one and two-story buildings surround the courthouse, the largest and only brick building. Typical of late-nineteenth and early-twentieth century rural communities, there were a variety of I-house and gable-ell buildings. A turn-of-the-century account confirms that lawyers' offices, a local newspaper office, and a cobbler's shop occupied small buildings in Prince Frederick.

Calvert County's population rose from 9,229 in 1840 to 10,223 in 1900. Despite this marginal population growth, a 1901 map identifies several buildings along the road leading southwestward toward the Patuxent River (MD 231) from the town's center. The map also notes several buildings, likely residences, further south on Main Street (MD 765A) Prince Frederick expanded, albeit slowly, during the early twentieth century. The 1907 Maryland Geological Survey's Calvert County Survey indicates that Solomons was the county's largest town, not Prince Frederick; however, because it was the county seat, Prince Frederick continued to hold a prominent place within the county. Photographs from 1908 show that a one-story, gable-front building in Prince Frederick housed the county's first bank. A one-story, gable-front building also housed the town's school. In 1910, the town's name was officially changed from Prince Fredericktown to Prince Frederick. The county's population reached 10,325 in 1910.

During the 1910s, the Maryland State Roads Commission (SRC) sought to improve road conditions statewide, attempting to utilize modern methods and materials to improve transportation. Prior to 1911, the SRC began preparing the existing dirt road connecting Owings in Calvert County with Prince Frederick. Originally named MD 2 after the SRC improved it, the road between Owings and Prince Frederick was a portion of the 84-mile-long road that extended between Baltimore and Solomons Island in southern Calvert County. MD 2 passed through Prince Frederick as the town's Main Street, today MD 765A. Covered in gravel, the SRC completed MD 2 in 1915 and it was Prince Frederick's first hard-surface road and state road.

Built between 1914 and 1916, Calvert County constructed a new courthouse on Main Street on the same lot. This building's lawn is the site of the town's previous courthouses, but the 1916 building was set back from the street with a chain-link fence encompassing the grounds. The two-story brick courthouse featured Neoclassical-style elements, including a prominent gable pediment supported by two-story columns. A photograph collection from 1917 offers additional information about the town's appearance from this time. Businesses and offices concentrated around the courthouse tended to flank Main Street directly, whereas the residences are set back from the street, having lots enclosed by picket or split-rail fences. A picket fence also enclosed the Hotel Calvert's lot.

One of Prince Frederick's most prominent citizens, the widely respected Louis Goldstein, was born in Calvert County in 1913. His father owned the Prince Frederick Department Store, later renamed Goldstein's Department Store, and he worked there as a boy, developing an affinity for dealing with both people and numbers. The younger Goldstein entered politics immediately after serving in the U.S. Marine Corps during World War II and completing law school, serving first in Maryland's General Assembly, and later as the state comptroller from 1959 until his death in 1998.

Prince Frederick gradually became more modernized during the 1920s and 30s, but Calvert County experienced little change in population. In 1920, the county's population was 9,744 and in 1930, the county's population declined to 9,528. During the 1920s, officials established the town's first volunteer fire department and high school. The two-story building constructed for the high school also housed Prince Frederick's elementary school in one of its rooms. Prince Frederick's high school later absorbed two

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended _____ Eligibility not recommended _____
Criteria: ___ A ___ B ___ C ___ D Considerations: ___ A ___ B ___ C ___ D ___ E ___ F ___ G

MHT Comments:

Reviewer, Office of Preservation Services

Date

Reviewer, National Register Program

Date

other area high schools, becoming Calvert County High School. Due to segregation, African American students attended the Colored Industrial School, a Rosenwald school completed in 1921 and enlarged in 1924; the building is extant and is located on Armory Road.

Sanborn Fire Insurance Maps and city directories do not exist for Prince Frederick and the lack of courthouse records presents challenges to research. However, many local residents have provided important oral histories, recounting their memories of growing up in Prince Frederick. Local resident Arthur Wilson Dowell gave his personal account of the town in his book, "Growing Up in Prince Frederick During the 1920's & 30's." Dowell's book includes a sketch map showing a concentration of businesses surrounding the courthouse on Main Street (MD 765A). These businesses include various shops, lawyers' offices, doctors' offices, motor companies, the Calvert Journal newspaper office, a fire station, butcher, restaurant, library, bank, and hotels. Homes were primarily located north of the courthouse and business district, as well as further south on Main Street.

After the Eastern Shore Public Service Company ran a line from the Eastern Shore during the 1930s, the company introduced electricity to Prince Frederick for the first time. In 1939, the Southern Maryland Electric Cooperative began offering electricity service on a larger scale throughout Calvert County. According to the 1974 Baltimore Sun article "Prince Frederick Inevitably Will Be 'A Different Place,'" the town's population barely exceeded 300 during the 1930s and 40s. Local author and newspaperman Hulbert Footner said, "Calvert is the least populated, the least improved, the least opulent, and is generally termed the least progressive county in Maryland, but I like it," regarding the county in 1942. However, World War II ushered in major changes for Prince Frederick and Calvert County. Between 1941 and 1945, the U.S. Navy and the U.S. Marine Corps established several training and testing bases at Solomons Island in southern Calvert County, introducing an influx of people to the region and new jobs for local residents. Between 1940 and 1950, the county's population increased from 10,484 to 12,100, but Calvert County's farming industry also began to decline the late 1940s and 1950s, following a nationwide trend of increased white-collar and industrial jobs in the post-war economy.

In 1951, the SRC completed a bypass, diverting traffic around the center of Prince Frederick from Main Street (MD 765A). During the 1960s, the bypass and extant portions of MD 2 were transitioned into the MD 2-4 dual highway, introducing change and development to the town and county; commercial strip malls soon populated the area around downtown Prince Frederick. The four-lane highway carried traffic from Washington, DC, through Prince Frederick, to southern Calvert County. In the mid-1970s, Calvert Cliffs Nuclear Power Plant was established approximately sixteen miles south of Prince Frederick. Downtown Prince Frederick's appearance also changed quite a bit during the same time period when the present-day Calvert County Services Building was constructed in 1974. Since then, other historic buildings on Main Street have been demolished; in most cases, new construction or parking lots now occupy these spaces. Other historic residential buildings have been altered, many for commercial uses.

Significance Evaluation

St. Paul's Episcopal Church was evaluated for listing in the National Register of Historic Places (NRHP) under Criteria A, B, and C using guidelines set forth in the NRHP Bulletin "How to Apply the National Register Criteria for Evaluation." The property was previously surveyed by the Maryland Historical Trust (MHT) in 1986. Correspondence between MHT and the Maryland State Highway Administration dated December 14, 1995 states that the church is individually eligible for listing in the NRHP. However, a determination of eligibility was never completed for the property.

The church is not eligible under Criterion A. Research has not shown the building to be associated with events or trends important in history. Therefore, the property is not eligible under Criterion A.

MARYLAND HISTORICAL TRUST REVIEW	
Eligibility recommended _____	Eligibility not recommended _____
Criteria: ___ A ___ B ___ C ___ D	Considerations: ___ A ___ B ___ C ___ D ___ E ___ F ___ G
MHT Comments:	
_____	_____
Reviewer, Office of Preservation Services	Date
_____	_____
Reviewer, National Register Program	Date

The building is not eligible under Criterion B. Research has not shown the building to be associated with people important in history. Therefore, the property is not eligible under Criterion B.

The building is eligible under Criterion C. St. Paul's Episcopal Church is eligible as an early example of sacred architecture in Calvert County and as one of the oldest buildings in Prince Frederick. It demonstrates an early design austerity that was altered with Victorian-era decorative techniques. Therefore, the building is eligible under Criterion C.

The property was not evaluated under Criterion D for this assessment.

St. Paul's Episcopal Church is also eligible under Criterion Consideration A because the church is eligible for its architectural merit. The cemetery is included within the historic property boundary but is not required to meet Criterion Consideration D because the church is the primary resource being nominated. The cemetery is being included as part of the church's setting.

Therefore, St. Paul's Episcopal Church is eligible for listing in the NRHP. It retains integrity of location, design, materials, workmanship, feeling, and association. The integrity of setting has been diminished by surrounding new construction, but remains sufficient for NRHP listing.

Boundary Description

The historic property boundary for St. Paul's Episcopal Church includes its tax parcel (map 24, parcel 138) with the exception of the new Parish Hall buildings located to the southwest of the historic church. The parking lot in front of the church is on a separate parcel and is not included. Please see the attached map for the boundary.

Boundary Justification

St. Paul's Episcopal Church historic property boundary includes the eligible church building and the surrounding cemetery and landscape. The boundary encompasses all of the historic components of the church, cemetery, and historic landscape.

Works Consulted

- Arnett, Earl. "Prince Frederick Will Be A 'Different Place.'" The Baltimore Sun, May 17, 1974.
- "The Baltimore Afro-American." October 15, 1957. Prince Frederick Vertical File, Calvert County Historical Society.
- Baugh, Annesley Bond. "I Remember... When Ox carts Were Commonplace." The Baltimore Sun, June 26, 1960.
- Bond, James A. C. "Historical Account of the Removal of the Court House." Calvert Independent, January 4, 1968.
- Briscoe, Betty. "Dedication September 20, 1970." Calvert Independent. Prince Frederick Vertical File, Calvert County Historical Society.
- . "Gone But Not Forgotten." Calvert Independent, February 19, 1970.
- Calvert County, Maryland. "1840 Map with Census Figures." Accessed March 3, 2014. <http://calvertgis.co.cal.md.us/historic/pages/1009.html>.

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended _____ Eligibility not recommended _____
 Criteria: ___ A ___ B ___ C ___ D Considerations: ___ A ___ B ___ C ___ D ___ E ___ F ___ G

MHT Comments:

_____	_____
Reviewer, Office of Preservation Services	Date
_____	_____
Reviewer, National Register Program	Date

---. "History of Calvert County, Maryland." Accessed February 24, 2014. <http://md-calvertcounty.civicplus.com/index.aspx?nid=214>.

---. "Prince Frederick' Quadrangle." Accessed March 3, 2014. <http://calvertgis.co.cal.md.us/historic/pages/PF1901.html>.

Calvert High School. "Patapeake: Calvert High School." Prince Frederick: Patapeake Staff, 1956.

---. "Patapeake: Calvert High School." Prince Frederick: Patapeake Staff, 1960.

---. "Patapeake: Calvert High School." Prince Frederick: Patapeake Staff, 1961.

Cole, Hannah L. "Documentation of the Baltimore and Drum Point Railroad Calvert County, Maryland (CT-1295)." 2010.

Dowell, Arthur Wilson. "Growing Up In Prince Frederick During the 1920's and 30's." Prince Frederick: A.W. Dowell, 1999.

Forstall, Richard L. "Population of Counties by Decennial Census: 1900 to 1990." Accessed February 27, 2014. "<http://www.census.gov/population/cencounts/md190090.txt>"

"Fire At Prince Frederick." The Baltimore Sun, July 29, 1941.

Gibb, James G. "Railroad Ghosts." New Bay Times, May 19-June 1, 1999.

Gibb, James G. and Paula F. Mask. "A Road Without Rails: The Baltimore and Drum Point Railroad, 1868-1891," The Calvert Historian (1990): 27-39.

Gottlieb, Robin. "The Promise of Prince Frederick." Chesapeake Life, Winter 1998/99.

Gray, Carter T. "Calvert County." Charleston: Arcadia, 2000.

Hutchins, Ailene. "From Humble Origins: The Birth of Prince Frederick and Calvert County." The Calvert Recorder, February 27, 2002.

---. "Shades of Old Prince Frederick." The Calvert Historian (1986): 33-35.

---. "Then and Now." Prince Frederick Recorder, August 5, 1976.

---. "The Calvert County Courthouse has Seen Many Changes Since Early Days." The Calvert Independent, July 28, 2004.

---. "Prince Frederick, The County Seat with its Days of Trials and Tribulations." The Calvert Independent, November 16, 2005.

Hutchins, Ailene W., and David Mohler. "An Album of Old Prince Frederick, Maryland." Chesapeake Country Life, July 1981.

Janofsky, Michael. "Louis Goldstein, 85, Maryland Comptroller." The New York Times, July 7, 1988.

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended _____

Eligibility not recommended _____

Criteria: ___ A ___ B ___ C ___ D Considerations: ___ A ___ B ___ C ___ D ___ E ___ F ___ G

MHT Comments:

Reviewer, Office of Preservation Services

Date

Reviewer, National Register Program

Date

Maryland State Roads Commission. "First, Second, Third, and Fourth Annual Reports of the State Roads Commission For the Years 1908, 1909, 1910, and 1911 to the General Assembly of Maryland." Baltimore: 1912.

---. "Report of the State Roads Commission of Maryland. Operating Report for the Fiscal Years 1951-1952. Fiscal Report for the Fiscal Years 1951-1952." Baltimore: 1952.

"A Maryland Village In Ashes." The Baltimore Sun, March 7, 1882.

Miller, Benjamin L., Jay A. Bonsteel, William Henry Alexander, Frederick Haynes Newell, L. A. Bauer, F. W. Besley, and Maryland Geological Survey. "Prince George's County." Baltimore: The Johns Hopkins Press, 1911.

"Minutes and Proceedings of the Orphans' Court of Calvert County, Maryland." 1882. March 14. Prince Frederick Vertical File, Calvert County Historical Society.

"Prince Frederick North End. Plat 4252." 1940. June 14. Prince Frederick Vertical File, Calvert County Historical Society.

Radoff, Morris L. "The County Courthouses and Records of Maryland: Part One: The Courthouses." Annapolis: The Hall of Records Commission, 1960.

Radoff, Morris L., Gust Skordas, and Phebe R. Jacobsen. "The County Courthouses and Records of Maryland: Part Two: The Records." Annapolis: The Hall of Records Commission, 1963.

"The Recent Fire At Prince Frederick." The Baltimore Sun, March 11, 1882.

Scisco, Louis Dow. "Calvert County Court Houses and Records." Maryland Historical Magazine XXVII (1932): 36-41.

Shattuck, George Burbank, Benjamin L. Miller, Jay A. Bonsteel, R. T. Avon Burke, Charles F. Von Herrmann, Nathan Clifford Grover, L. A. Bauer, Hugh McCollum Curran, and Maryland Geological Survey. "Calvert County." Baltimore: The Johns Hopkins Press, 1907.


St. Paul's Episcopal Church. "History." Accessed March 3, 2014. http://www.stpaulspf.org/?page_id=20.

Stein, Charles Francis. "A History of Calvert County, Maryland." Baltimore: Calvert County Historical Society, 1960.

Sunderman, Anne. "The Money Crop: Calvert County After the Tobacco Buyout." Crownsville: Maryland Historical Trust, 2004.


Warner, Paul S. "What's In a Name? In Southern Maryland, A Lot." Calvert Recorder, February 17, 2012.

MARYLAND HISTORICAL TRUST REVIEW	
Eligibility recommended _____	Eligibility not recommended _____
Criteria: ___ A ___ B ___ C ___ D	Considerations: ___ A ___ B ___ C ___ D ___ E ___ F ___ G
MHT Comments:	
_____	_____
Reviewer, Office of Preservation Services	Date
_____	_____
Reviewer, National Register Program	Date



 Historic Property Boundary

USGS 7.5 Minute Series 1:24000 Topographic Quadrangle: Prince Frederick (1993)



CT-818
St. Paul's Episcopal Church

25 Church Street
Prince Frederick, Calvert County, MD
Parcel ID: 24-138, former 24-140, 24-893
(Map-Parcel)



-  Historic Property Boundary
-  Parcels Annotated with Map-Parcel-Block-Lot-Section (Calvert County GIS)

Coordinate System: NAD 1983 StatePlane Maryland FIPS 1900




Photo Log

CT-818, St. Paul's Episcopal Church

All printed photographs were created using HP 100 Gray Photo Cartridge and HP Premium Plus Photo Paper, Soft Gloss.

CT-0818_2014-02-12_01

Facade with bell tower, view to the southeast

CT-0818_2014-02-12_02

Facade and side elevation, view to the southeast

CT-0818_2014-02-12_03


Rear and side elevations, view to the southwest

CT-0818_2014-02-12_04

Landscape elements including iron gate, view to the northeast

CT-0818_2014-02-12_05

Cemetery, view to the south



CT-818

St. Paul's Episcopal Church

Calvert County, MD

S. Foell

2/2014

MD SHPO

Facade with bell tower, view to the
Southeast

1/5



CT- 818

St. Paul's Episcopal Church

Calvert County, MD

S. Foell

2/2014

MDSHPD

Facade and side elevation, view to the
Southeast

2/5



CT-818

St. Paul's Episcopal Church

Calvert County, MD

S. Foell

2/2014

MD SHPO

Rear and side elevations, view to the
south east

3/5



CT-818

St. Paul's Episcopal Church

Calvert County, MD

S. Foell

2/2014

MD SHPO

Landscape elements including iron gate,
view to the northeast

4/5



CT-818

St. Paul's Episcopal Church

Calvert County, MD

S. Foell

2/2014

MD SHPO

Cemetery, view to the south

315

7. Description

Survey No. CT-818

Condition		Check one	Check one	
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

This brick nave-plan church faces northwest. The structure is four bays long with round-headed arched windows and corbelled brick cornices. The unbroken stretcher bond may be a veneer. The rectangular apse on the rear of the church is now surrounded by a modern brick addition. Stained glass windows were added at various times around the turn of the century. The original configuration of the facade included three bays surmounted by a rose window in the gable. These features have been obscured by the added tower. The five-course American bond brick base of this tower has a dentillated cornice and a hipped roof. The surmounting wooden section has a pierced and sawn balustrade, chamfered posts, wood shingled and louvred lantern, and a wood shingled polygonal steeple.

The cemetery was first used before the Civil War. The entire church yard is enclosed by a c. 1890's Gothic iron fence.

8. Significance

Survey No. CT-818

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input checked="" type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates 1841, 1885 **Builder/Architect**

check: Applicable Criteria: A B C D
 and/or
 Applicable Exception: A B C D E F G
 Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

The traditional date of construction for this church is 1841. The front tower was added in 1885. Despite protestations to the contrary, the church has been heavily worked over in this century. The donor for the tower was Charles S. Parran. The brick addition to the back of the church was made in 1981.

Directed historical research would more firmly establish the historical significance of this site.

9. Major Bibliographical References

Survey No. CT-818

10. Geographical Data

Acreege of nominated property _____

Quadrangle name Prince Frederick, MD

Quadrangle scale 1:24000

UTM References do NOT complete UTM references

A
 Zone Easting Northing

B
 Zone Easting Northing

C

D

E

F

G

H

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code

state	code	county	code

11. Form Prepared By

name/title	Camille Wells		
organization	MHT/Calvert Planning Department	date	September 30, 1986
street & number	Courthouse, Main Street	telephone	(301) 535-2348
city or town	Prince Frederick	state	Maryland 20678

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.


The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
 Shaw House
 21 State Circle
 Annapolis, Maryland 21401
 (301) 269-2438



PRINCE FREDERICK
CALVERT COUNTY MAP #29
ENLARGEMENT 3 of 3
CT-818

Prince Frederick Properties



PRINCE FREDERICK QUAD



Ct-818 St. Paul's Episcopal
Church
Highway 231
Prince Frederick

Camille Wells
view from the north

9/86

Gt-818