

CARR-1451

William Hush House
Eldersburg (vicinity)

c. 1900

Summary:

The William Hush House was part of the Ireland Family Farm for much of the nineteenth century. The 1877 atlas does not indicate a dwelling at this site. The Ireland's sold the property to Hush in 1897 for \$1,400, and it probably had few improvements, though apparently did have at least one. According to a former owner, the main block of the house was built c. 1900 by itinerant carpenters, and was added to the existing rear wing. The construction of the main block is consistent with a date of c. 1897-1910. Evidence in the ell is skimpy, however, the first-story floor framing does contain some earlier timber that might signify an existing structure. If so, it was probably a tenant house that was cut off of the original farm to create a second farm. It must have been a small structure, and Hush probably set about to enlarge and improve it immediately.

Geographic Organization: Piedmont
Chronological/Development Period: Industrial/Urban Dominance
Historic Period Themes: Architecture
Resource Types: Rural vernacular

The William Hush House was part of the Ireland Family Farm for much of the nineteenth century. The 1877 atlas does not indicate a dwelling at this site. The Ireland's sold the property to Hush in 1897 for \$1,400, and it probably had few improvements, though apparently did have at least one. According to a former owner, the main block of the house was built c. 1900 by itinerant carpenters, and was added to the existing rear wing. The construction of the main block is consistent with a date of c. 1897-1910. Evidence in the ell is skimpy, however, the first-story floor framing does contain some earlier timber that might signify an existing structure. If so, it was probably a tenant house that was cut off of the original farm to create a second farm. It must have been a small structure, and Hush probably set about to enlarge and improve it immediately.

MARYLAND INVENTORY OF
HISTORIC PROPERTIES

Maryland Historical Trust
State Historic Sites Inventory Form

Survey No. CARR-1451

Magi No.

DOE yes no

1. Name (indicate preferred name)

historic William Hush House

and/or common

2. Location

street & number 6311 Oakland Mills Road not for publication

city, town Eldersburg vicinity of congressional district

state Maryland county Carroll

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input checked="" type="checkbox"/> private residence
			<input type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Harold and Helen Burgard

street & number 6311 Oakland Mills Road telephone no.: 795-2520

city, town Sykesville state and zip code MD 21784

5. Location of Legal Description

courthouse, registry of deeds, etc. Courthouse Annex liber 276

street & number 55 North Court Street folio 23

city, town Westminster state MD

6. Representation in Existing Historical Surveys

title

date federal state county local

pository for survey records

city, town _____ state _____

7. Description

Survey No. CARR-1451

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Summary:

The William Hush House is located at 6311 Oakland Mills Road, on the east side of the road, approximately three miles east of Eldersburg. The house is a three-bay by two-bay, 2½-story structure with a two-bay by one-bay, two-story ell. It has a rubble stone foundation, asbestos-shingle siding, and a pressed-metal shingle roof. The gable roof has a north-south ridge on the main block, and an east-west ridge on the ell. The house faces west toward the road and is a "T" in plan. On the west elevation, the first story has a center door and 2/2 sash. There is a one-story, three-bay porch with a hip roof. It has turned posts. The first story has a center-passage, single-pile plan with a one-room ell. The passage has a straight-run stairway along the south elevation that is enclosed with a half wall. The first story has paneling and drop ceilings throughout much of the rooms. The mantelpieces have been removed. According to the owner, a former owner said that the front of the house was built around 1900 by itinerant carpenters and was an addition to the earlier rear wing.

The William Hush House is located at 6311 Oakland Mills Road, on the east side of the road, approximately three miles east of Eldersburg. The house is a three-bay by two-bay, 2½-story structure with a two-bay by one-bay, two-story ell. It has a rubble stone foundation, asbestos-shingle siding, and a pressed-metal shingle roof. The gable roof has a north-south ridge on the main block, and an east-west ridge on the ell. There is an interior brick chimney on the north end at the ridge that has been rebuilt. The house faces west toward the road and is a "T" in plan. On the west elevation, the first story has a center door with jalousie, a 2/2 sash with blinds in the north bay, and a 1/1 sash with blinds in the south bay. The second story has three 2/2 sash with blinds. There is a central gabled wall dormer with a lancet-shaped 2/2 sash. It has a wood box cornice with returns. There is a one-story, three-bay porch with a hip roof. It has turned posts, German siding on the balustrades, and asphalt shingles. It is set on rubble stone end walls with two center piers. On the north elevation, the foundation has a three-light casement in the west bay. The first and second stories have two 2/2 sash each. The gable end has two four-light casements. The east elevation has a 2/2 sash on both the first and second stories. The north elevation of the ell has a one-light sash in the center of the foundation. The first story has two 1/1 sash. The second story has a 1/1 sash to the east and a 2/2 sash to the west. The east elevation of the ell has new hurricane doors in the foundation. There are paired 1/1 sash on the first story, and paired lying 2/2 sash in the second story. There is a wood soffit with no box cornice or returns on the ell. The south elevation of the ell has an enclosed shed-roof porch on the first story that has asphalt shingles and asbestos shingle siding. The second story has a 2/2 sash to the west and two lying 2/2 sash to the east. On the east elevation of the main block, the

Description (continued)

Section 7 Page 2

first-story south bay is covered by the enclosed porch. The second-story south bay has a 2/2 sash. The south elevation of the main block has a hurricane door in the foundation set to the west, and a three-light sash set to the east. The first story has two 1/1 sash, and the second story has two 2/2 sash. The gable end has two four-light sash.

The cellar under the main block has a circular-sawn summer beam, and joists that are circular sawn on top and bottom and rest on top of the summer beam. Between these joists are 2 x 8 circular-sawn joists that are notched on the bottom to fit over the summer beam. The floor above is circular sawn and is fastened with cut nails.

The first story has a center-passage, single-pile plan with a one-room ell. The passage has a straight-run stairway along the south elevation that is enclosed with a half wall. The first story has paneling and drop ceilings throughout much of the rooms. The mantelpieces have been removed. The ell-room wainscot and stairway have been removed. The second story has a center passage with two rooms on the south and one on the north. Much of the window and door trim used throughout the house is head cut. The second story has several four-panel doors that have sunk fields and ogee panel moulds. The southwest chamber has a floor that is painted and grained to look like oak. The southeast chamber has a similar floor painted a little darker and with a little straighter grain.

The attic construction is consistent throughout the main block and the ell. The rafters are circular sawn 2 x 4's circular sawn supported by knee-wall studs of the same material. The rafters are mitered at the ridge, and the feet are cut at an angle and nailed to the top of the joists. The joists are 2 x 6's that are circular sawn.

The ell cellar is accessible from the exterior of the house only through a beaded-edge, vertical-board door. It has whitewashed rubble stone walls. The east wall has corbelled stone at the top that formerly supported a chimney. There is a circular-sawn summer beam. Some of the joists are mill sawn 3 x 6's that are either earlier or reused, and some are 3½ by 6 inches, have been planed, and must be recent additions. Several other joists are circular sawn and seem to date from the construction period of the main block of the house. According to the owner, a former owner said that the front of the house was built around 1900 by itinerant carpenters and was an addition to the earlier rear wing.

Behind the house is a one-story, two-bay by one-bay garage with asbestos-shingle siding, and a gable roof of inverted V-seam metal with a north-south ridge. There are two roll-up doors on the west elevation. The building is constructed with a 2 x 4 balloon frame of circular-sawn timber that is wire nailed.

8. Significance

Survey No. CARR-1451

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/humanitarian
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> theater
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> transportation
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> other (specify)
		<input type="checkbox"/> invention		

Specific dates c. 1900 **Builder/Architect**

check: Applicable Criteria: A B C D
and/or
Applicable Exception: A B C D E F G

Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

Geographic Organization: Piedmont
 Chronological/Development Period: Industrial/Urban Dominance
 Historic Period Themes: Architecture
 Resource Types: Rural vernacular

The William Hush House was part of the Ireland Family Farm for much of the nineteenth century. The 1877 atlas does not indicate a dwelling at this site. The Ireland's sold the property to Hush in 1897 for \$1,400, and it probably had few improvements, though apparently did have at least one. According to a former owner, the main block of the house was built c. 1900 by itinerant carpenters, and was added to the existing rear wing. The construction of the main block is consistent with a date of c. 1897-1910. Evidence in the ell is skimpy, however, the first-story floor framing does contain some earlier timber that might signify an existing structure. If so, it was probably a tenant house that was cut off of the original farm to create a second farm. It must have been a small structure, and Hush probably set about to enlarge and improve it immediately.

9. Major Bibliographical References

Survey No. CARR-1451

1877, 1917 maps
Land Records

10. Geographical Data

Acreeage of nominated property _____

Quadrangle name Finksburg

Quadrangle scale 1:24000

UTM References do NOT complete UTM references

A	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing

B	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing

C	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

D	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

E	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

F	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

G	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

H	<input type="text"/>	<input type="text"/>	<input type="text"/>
---	----------------------	----------------------	----------------------

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code

state	code	county	code

11. Form Prepared By

name/title Kenneth M. Short, Historic Planner

organization Carroll County Planning

date January 18, 1996

street & number 225 North Center Street

telephone (410) 857-2145

city or town Westminster

state MD



The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

MARYLAND HISTORICAL TRUST
DHCP/DHCD
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2023
614-7400

FREEDOM DISTRICT NO. 5




UNION MILLS AND MYERSVILLE BUSINESS REFERENCES.

- A. K. Shriver & Sons, (H. W. & T. A. Shriver), Manufacturers of Oak-tanned Sole Leather. Union Mills.
- B. F. & T. H. Shriver, Manufacturers of Flour and Dealers in Grain. Packers of Fruits and Vegetables. Union Mills.
- J. N. Mark, Dealer in Dry Goods, Groceries, Boots, Shoes, Hats, Caps, Tobacco and Cigars, Notions, &c., &c. Store at Silver Run.
- John Fesser, Agent for the Sterling and Bay State Cabinet Organs. Silver Run Post-office.
- John Study, Physician and Surgeon. A specialty made of broken limbs and fever sores. Residence and office one and a quarter miles northwest of Silver Run.
- John Wiest, Proprietor of Big Pipe Creek Mills. Manufacturer of Flour, Feed, and Meal. Also, Wholesale and Retail Dealer in the same. Three and a half miles west of Silver Run.
- James E. Dodder, Proprietor of the Old Graves' Mills on Big Pipe Creek. Manufacturer of Flour and Dealer in Grain. Silver Run.
- John Koontz, Manufacturer of Grain Cradles and Repairer of all kinds of Farm Implements. Silver Run.
- Joshua Myers, Blacksmith. Work of all kinds in his line done to order at short notice.
- Josiah Dutser, Raiser and Dealer in Italian Bees. Manufactures and sells the "Langstrath Improved Movable Comb Bee Hive." Residence and farm one and a half miles north of Silver Run.
- Wm. Tagg, Blacksmith. All work done promptly to order.

PINKSBURG BUSINESS REFERENCES.

- Jabez A. Bush, Surveyor, Conveyancer and Scrivener, Patapasco Station.
- J. H. Chew & Co., Dealers in Dry Goods, Groceries, Notions, Books, Shoes, Hats, Caps, Hardware, Teas and Spices of all kinds, and a general line of goods usually kept in a first-class country store.
- Chew & Smelser, Manufacturers of Nova Scotia Plaster. Also, Pure Raw Bone ground very fine. Farmers will do well to call and examine before purchasing.
- Francis Lamotte, Agent for all kinds of Agricultural Implements. Parties wanting anything in this line would do well to call and see him before buying elsewhere. Business headquarters, 70 and 72 North Street, Baltimore.
- Lewis H. Cole, Proprietor of Dairy, and Dealer in Cattle, Hogs, &c.
- F. L. Hering, Proprietor of Saw and Grist Mills.
- Edwin E. Koons, Miller, and Dealer in Flour and Grain, Feed, &c. The best Family Flour in use can be had at his Mill near Patapasco.
- John W. Abbott, Proprietor of Deep Run Mills.
- Samuel Shaner, Manager of Deep Run Mills. Call and examine their fine flour.
- James W. Taylor, Dealer in Dry Goods, Groceries, Notions, Hats, Caps, Boots, Shoes, &c. Everything usually kept in a first-class country store.
- John A. Dushane & Co., Proprietors of Caledonia Paper Mills, and Manufacturers of, and Dealers in, all kinds of Paper. Book and Newspapers a specialty, and made to order at short notice. Office, No. 40 South Charles Street, Baltimore.
- Jarrett N. Shauck, Proprietor of first-class Flouring Mills.
- Wm. Stubbins, Manager of Caledonia Paper Mills.
- William Mengel, Blacksmith. Horseshoeing and Repairing promptly and neatly done. Please extend to him your patronage.
- Gerh Bademacher, Minister in the Lutheran Church.




IS REFERENCES.
 umber of Saddles, Harness, Liberty Road, one mile ce.
 l Surgeon. Office at rest-Freedom.
 gist, Geological Surveyor,
 n Dry Goods, Groceries, Crockery, Patent Medicines, Glass, Drugs, Fancy l other goods usually be sold cheap
 ce.
 e. in
 e. an and Farmer. Sykes-


John M. Berry, Proprietor of Hotel. Sykesville.
 William Davis, Dealer in Dry Goods, Groceries, Notions and General Merchandise. Also, Manufacturer of Flour, Feed, and Meal, and Dealer in Grain. Marriottsville.
 J. T. McComas, Dealer in Dry Goods, Groceries, Boots, Shoes, Hats, Caps, Notions, and all goods usually kept in a country store. Hood's Mills.
 George C. Minor, Manufacturer of Carriages, Buggies, Spring Wagons, Farm Wagons, &c. All kinds of Repairing neatly done to order. Coach Painting a specialty. Eldersburg.
 H. C. Shipley, Physician and Surgeon. Residence and Post-office, Eldersburg.
 Grove J. Shipley, School Teacher. Post-office, Bird Hill.

CARR-1451
 William Hush House
 6311 Oakland Mills Road

Lake, Griffin & Stevenson Atlas 1877



CARR-1451
William Hush House
6311 Oakland Mills Road
Rand McNally map 1917



4365
25'
4364
4362
4361
436000m N.
39°22'31"
76°52'30"

4362

4361

436000m N.

39°22'31"

76°52'30"


(ELLIP. 5662)

ROAD CLASSIFICATION

- Heavy-duty Light-duty
- Medium-duty Unimproved dirt

CARR-1451
William Hush House
6311 Oakland Mills Road

Finksburg quad



STANDARDS
OLORADO 80225

To place on the predicted North American Datum 1983
move the projection lines 7 meters south and
26 meters west as shown by dashed corner ticks

