

CAPSULE SUMMARY SHEET

Survey No.: CH-451 (PACS B16)

Construction Date: 1930

Name: Bridgett Property

Location: 8605 Leonardtown Road, Hughesville, Charles County

Private/Residence/Occupied/Good/Restricted

Description:

The Bridgett Property is a 1½-story, 3-bay, side-gable cottage with Bungalow features on the west side of Leonardtown in Hughesville, Charles County. Constructed in 1930, the cottage has a screened porch on the front elevation, and additions to the north, south and west. The structure has a side-gable roof covered with asphalt shingles, an interior brick chimney, and there is a large shed roof dormer with exposed joists on the front elevation. The cottage is of wood-frame construction with wood siding and it has a concrete block foundation. The cottage has several different window types, including 6/6 and 2/2 double-hung wood, and 1/1 double-hung aluminum replacement windows.

Significance:

Constructed in 1930, the Bridgett Property is an undistinctive example of a common architectural type which has been altered. The side and rear additions have compromised the architectural integrity of the original cottage by changing the form and massing of the original design, and the flat-roof addition with roof railings are architectural elements not found in the original design. There are no detailed, published historic maps of Charles County, Maryland that locate and indicate ownership of structures. The Bridgett Property is located on a 0.06 hectare (0.15 acre) parcel of land on the west side of Leonardtown Road. According to the son of the owner, the residence was constructed in 1930.

Maryland Historical Trust
Maryland Inventory of Historic Properties Form
MD 5 - Hughesville Project

DOE yes no

1. Name: (indicate preferred name)

historic

and/or common Bridgett Property

2. Location:

street & number 8605 Leonardtown Road not for publicationcity, town Hughesville vicinity of congressional districtstate Maryland county Charles

3. Classification:

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> education	<input checked="" type="checkbox"/> private
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> residence
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> religious
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> scientific
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:
			<input type="checkbox"/> transportation	

4. Owner of Property: (give names and mailing addresses of all owners)

name Adrian and Clara Bridgett

street & number P.O. Box 443 telephone no.:city,town Hughesville state and zip code MD 20637-0443

5. Location of Legal Description

Land Records Office of Charles County liber 126street & number Charles Street folio 145city,town La Plata state MD

6. Representation in Existing Historical Surveys

title

date federal state county local

depository for survey records

city,town state

7. Description

Survey No. CH-451 (PACS B16)

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Resource Count: 4

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Bridgett Property is a 1½-story, 3-bay, side-gable cottage with Bungalow features on the west side of Leonardtown Road in Hughesville, Charles County. Constructed in 1930, the cottage has a screened porch on the front elevation, and additions to the north, south and west.

The structure has a side-gable roof covered with asphalt shingles, an interior brick chimney, and there is a large shed roof dormer with exposed joists on the front elevation. The cottage is of wood-frame construction with wood siding and it has a concrete block foundation. The cottage has several different window types, including 6/6 and 2/2 double-hung wood, and 1/1 double-hung aluminum replacement windows.

The east, or front elevation is concealed by the front porch. The porch is screened with a centered screen door. The cottage is accessed by a wood door centered between two 6/6 double-hung windows. Two 1/1, double-hung aluminum replacement windows are located in the shed-roof dormer.

The north elevation has a flat-roof addition on the third bay. The addition has a decorative wood railing around the roof perimeter, a 6/6 double-hung window on the east wall, and a 2/2 double-hung window on the north elevation. The fenestration pattern of the cottage is irregular, with one 6/6 double-hung window on the first story and one 1/1 double-hung window in the gable end.

The rear, or west, elevation has an addition that conceals the first bay of the cottage. The addition is 1-story with a shed-roof, and it has a 4-light wood door and a 6/6 double-hung window. The cottage has minimal fenestration on this elevation, with one 6/6 double-hung window located in the center bay. An enclosed stairwell to the basement, which projects beyond the wall plane of the cottage, is also located in the center bay. The stairwell is accessed by a wood door at grade.

The south elevation of the cottage is partially concealed by a large, gable projecting bay. The bay has a 6/6 double-hung window centered on the south and east elevations. The fenestration pattern of the cottage is irregular, with one 3-light fixed window on the basement level and one 6/6 double-hung window on the first story. The second story has one 1/1 double-hung aluminum replacement window in the gable end.

The interior of the cottage contains a large living room, kitchen, bath, and laundry/coat room on the first story, and bedrooms on the second story.

There are three outbuildings associated with this property. The first outbuilding is a carport with an asphalt shingle, shed-roof. Constructed circa 1990, the carport is of wood-frame construction and is located north of the cottage.

The second outbuilding is a front-gambrel shed with an asphalt shingle roof. Constructed circa 1990, the shed is of wood-frame construction and is located northwest of the cottage and west of the carport.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Bridgett Property

SURVEY NO.: CH-451 (PACS B16)

ADDRESS: 8605 Leonardtown Road, Hughesville, Charles County

7. Description (Continued)

The third outbuilding is a front-gable shed with an asphalt shingle roof. Constructed circa 1980, the shed is of wood-frame construction and is located northwest of the cottage and west of the carport and gambrel shed.

The property is located on the west side of Leonardtown Road, with a residence to the north and commercial property to the south. The site has a few evergreen trees and is generally level to a point past the cottage, where it slopes up to the west. The property's setting is within the crossroads community of Hughesville, along a road that is a major transportation route.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Bridgett Property

SURVEY NO.: CH-451 (PACS B16)

ADDRESS: 8605 Leonardtown Road, Hughesville, Charles County

8. Significance (Continued)

as well as a Friends' school, four (4) general merchandise stores, two (2) saloons, two (2) undertakers, a wheelwright, a blacksmith, a tobacco buyer, and a population of fifty (50). Gannett's 1904 Gazetteer of Maryland defined Hughesville as a "post village...on the Washington, Potomac and Chesapeake Railroad" (Gannett 1904: 43). By 1906 the community was known as "a station of the Southern Maryland Railroad...and a banking town" with two (2) physicians, two (2) general stores, two (2) blacksmiths, a grist and saw mill, a flour mill, an undertaker and livery, a hotel, a hotel and saloon, a grocer and saloon, an insurance salesman, and a population of 150 (Maryland 1906: 667).

The Bridgett Property is a vernacular side-gable cottage. Between 1870 and 1940 the vernacular cottage style was typically built for Americans of modest means. They are characterized by simple ornamentation and mass-produced components, such as door frames, moldings, sash and window units, and porch decoration. The development of post-Civil War machinery capable of producing large amounts of standardized housing elements, such as those found in cottages, contributed greatly to the development of the modern American housing industry. Designs for vernacular cottages were obtained from popular magazines, such as House Beautiful, or carpenter's and builder's journals, such as American Builder. A variety of front-gable, side-gable, cross-gable and hipped roof frame cottages were developed in the early to mid-twentieth century. Front-gable and hipped roof cottages are primarily 1 to 1½-stories tall, 3-bays wide and several rooms deep. Side-gable and cross-gable structures are usually 2 to 2½-stories tall, are typically 2 to 3-bays in width and vary from one to three rooms deep. They usually include a porch covered with a shed roof. Porches are supported by posts often containing machine-produced Victorian ornamentation. Some cottages feature ornamentation drawn from Craftsman style or Colonial Revival architecture (Gottfried and Jennings 1988, viii-xv).

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Bridgett Property

SURVEY NO.: CH-451 (PACS B16)

ADDRESS: 8605 Leonardtown Road, Hughesville, Charles County

8. Significance (Continued)

National Register Evaluation:

Constructed in 1930, the Bridgett Property is not eligible for the National Register of Historic Places. The property is not eligible under Criterion A, as research conducted indicates no association with any historic events or trends significant in the development of national, state or local history. Historic research indicates that the property has no association with persons who have made specific contributions to history, and therefore, it does not meet Criterion B. It is not eligible under Criterion C, as it is an undistinctive example of a common architectural type which has been altered. The side and rear additions have compromised the architectural integrity of the original cottage by changing the form and massing of the original design, and the flat-roof addition with roof railings are architectural elements not found in the original design. Finally, the structure has no known potential to yield important information, and therefore, is not eligible under Criterion D.

MARYLAND HISTORICAL TRUST	
Eligibility recommended _____	Eligibility Not Recommended <u> P </u>
Comments _____	

Reviewer, OPS: <u>[Signature]</u>	Date: <u>5/15/98</u>
Reviewer, NR Program: <u>[Signature]</u>	Date: <u>5/21/98</u>

[Handwritten mark]

9. Major Bibliographical References Survey No. CH-451 (PACS B16)

See Continuation Sheet

10. Geographical Data

Acreage of nominated property _____

Quadrangle name Hughesville, MD

Quadrangle scale 1:24,000

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Caroline Hall/Ryan McKay

organization P.A.C. Spero & Company

date January 1997/revised February 1998

street & number 40 W. Chesapeake Avenue, Suite 412

telephone (410) 296-1635

city or town Baltimore

state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: **Maryland Historical Trust**
DHCP/DHCD
100 Community Place
Crownsville, MD 21032-2023
(410) 514-7600

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Bridgett Property

SURVEY NO.: CH-451 (PACS B16)

ADDRESS: 8605 Leonardtown Road, Hughesville, Charles County

9. Major Bibliographical References (Continued)

- Bland, John R., ed. The Maryland Directory and State Gazetteer. Baltimore: The Baltimore Publishing Company, 1887.
- Brown, Jack D., et al. Charles County, Maryland, A History. La Plata: Charles County Bicentennial Committee, 1976.
- Bridgett. Interview with owner's son by Ryan McKay. January 1997.
- Charles County Department of Assessment and Taxation. 101 Catalpa Drive, La Plata, Maryland.
- Charles County Land Records Office. Charles County Courthouse, Charles Street, La Plata, Maryland.
- Fisher, R.S. Gazetteer of the State of Maryland, Compiled from the Returns of the Seventh Census of the United States, and Other Official Documents. Baltimore: James S. Waters, 1852.
- Gannett, Henry. A Gazetteer of Maryland. Department of the Interior, United States Geological Survey, Bulletin No. 231, Series F, Geography, 39. Washington, D.C.: Government Printing Office, 1904.
- Gottfried, Herbert and Jan Jennings. American Vernacular Design, 1870-1940. Ames, Iowa: Iowa State University Press, 1988.
- Hinkel, John V., ed. See Charles County, Maryland, founded in 1658. Compiled by John V. Hinkel & Associates. La Plata: Charles County Chamber of Commerce, 1959.
- KCI Technologies, Inc. Draft Historic Context for the U.S. 301 South Corridor Transportation Study, Prince George's and Charles Counties, Maryland. Prepared for the Maryland Department of Transportation, State Highway Administration, August 1996.
- Klaphthor, Margaret Brown, and Paul Dennis Brown. The History of Charles County, Maryland. La Plata: Charles County Tercentenary, Inc., 1958.
- Map of a Part of Maryland, Copied from the Geological State Map. 1840. Maryland Historical Trust, Crownsville, Maryland.
- Martenet, Simon J. Martenet's Map of Maryland, Atlas Edition. Baltimore: Simon J. Martenet, 1866.
- Martenet, Simon J. New Topographical Atlas of the State of Maryland. Baltimore: Simon J. Martenet, 1873

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Bridgett Property

SURVEY NO.: CH-451 (PACS B16)

ADDRESS: 8605 Leonardtown Road, Hughesville, Charles County

9. Major Bibliographical References (Continued)

Martenet, Simon J. Martenet's Map of Maryland and District of Columbia, Including a Sketch of Delaware and Parts of Pennsylvania, Virginia and West Virginia. Baltimore: Simon J. Martenet, 1885.

Maryland, Delaware and District of Columbia State Gazetteer and Business Directory 1906-1907. Baltimore: R.L. Polk & Co., 1906.

P.A.C. Spero & Company. Maryland Historic Context, Montgomery County and Prince George's County, Intercounty Connector Project. Volume I. Prepared for the Maryland Department of Transportation, State Highway Administration. Baltimore: P.A.C. Spero & Company, October 1996.

Rivoire, J. Richard. Homeplaces, Traditional Domestic Architecture of Charles County, Maryland. La Plata: Southern Maryland Studies Center, 1990.

State Gazette and Merchants and Farmers Directory for Maryland and the District of Columbia. Baltimore, 1871.

Wearmouth, John M. Charles County's Railroad. Prince George's County Historical Society, Glendale, Maryland.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM


RESOURCE NAME: Bridgett Property

SURVEY NO.: CH-451 (PACS B16)

ADDRESS: 8605 Leonardtown Road, Hughesville, Charles County

10. Geographical Data (Continued)

Resource Sketch Map:



CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Bridgett Property

SURVEY NO.: CH-451 (PACS B16)

ADDRESS: 8605 Leonardtown Road, Hughesville, Charles County

Maryland Comprehensive Historic Preservation Plan Data Sheet

Historic Context:

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization:

Western Shore

Chronological/Developmental Period Theme (s):

Modern Period A.D. 1930-Present

Prehistoric/Historic Period Theme(s):

Architecture

RESOURCE TYPE:

Category (see Section 3 of survey form):

Building

Historic Environment (urban, suburban, village, or rural):

Village

Historic Function(s) and Use(s):

Private Residence

Known Design Source (write none if unknown):

None

Preparer

P.A.C. Spero & Company

January 1997/ revised February 1998



- 1 CH 451
- 2 Bridgett Property
- 3 Charles County, MD
- 4 Eric F Griffiths
- 5 April 1997
- 6 MD SHPO
- 7 East Elevation, View West
- 8 1 of 5



- 1 CH-451
- 2 Bridgett Property
- 3 Charles County, MD
- 4 Eric F Griffiths
- 5 April 1997
- 6 MD SHPO
- 7 North elevation, view South
- 8 2 of 5



- 1 CH-4151
- 2 Bridgett Property
- 3 Charles County, MD
- 4 Eric F Griffiths
- 5 April 1997
- 6 MD SHPO
- 7 West Elevation, View East
- 8 3 of 5



- 1 CH-451
- 2 Bridgett Property
- 3 Charles County, MD
- 4 Eric F. Griffiths
- 5 April 1997
- 6 MD SHPO
- 7 South Elevation, View North
- 8 4 of 5



- 1 CH-451
- 2 Bridgett Property
- 3 Charles County MD
- 4 Eric F Griffiths
- 5 April - 1997
- 6 MD SHPO
- 7 Storage Sheds, View Northwest
- 8 S of S