

**CH-58**  
**Mill Hill Road House**  
**Berry vic.**  
**Private**

**circa 1830**

Known as the "Mill Hill Road House," this modest frame dwelling represents an almost complete reconstruction of the original building that stood on the site. Badly deteriorated in the 1930s, the house was acquired by Alverta Berry and stabilized. Since that time, the dwelling has undergone several renovations. While little of the original building fabric remains, the dwelling retains its typical vernacular Southern Maryland form and interior layout. The only distinguishable original feature is the enclosed dog-leg stair.

The "Mill Hill Road House" stands on a portion of the "Friendship" tract that was owned and occupied by Dominic Mudd during the mid-19th century. In 1862, Mudd devised the 260-acre tract of "Friendship" upon which he was then residing to his children. The Mudd family continued to own the property until 1900 when the remaining 100 acres of it was sold to John D. Jenkins of Prince George's County.

MARYLAND HISTORICAL TRUST  
MD INVENTORY OF HISTORIC PROPERTIES

Inventory No. CH-58

=====

1. Name of Property

=====

historic name Mill Hill Road House

common/other name \_\_\_\_\_

=====

2. Location

=====

street & number 2440 Mill Hill Road not for publication \_\_\_\_\_

city or town Berry vicinity  state Maryland code MD

county Charles code 017 zip code 20603

=====

3. State/Federal Agency Certification

N/A

=====

4. National Park Service Certification

N/A

=====

5. Classification

=====

Ownership of Property (Check all that apply)

- private
- public-local
- public-State
- public-Federal

Category of Property (Check only one box)

- building(s)
- district
- site
- structure
- object

Number of Resources within Property

Contributing      Noncontributing

<u>3</u>	<u>2</u>	buildings
<u>0</u>	<u>0</u>	sites
<u>0</u>	<u>0</u>	structures
<u>0</u>	<u>0</u>	objects
<u>3</u>	<u>2</u>	Total

Is this property listed in the National Register?

Yes  Name of Listing \_\_\_\_\_

No

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. CH-58

=====  
6. Function or Use  
=====

Historic Functions (Enter categories from instructions)

Cat: DOMESTIC Sub: Single dwelling  
AGRICULTURE Processing/storage

Current Functions (Enter categories from instructions)

Cat: DOMESTIC Sub: Single dwelling  
AGRICULTURE Storage

=====  
7. Description  
=====

Architectural Classification (Enter categories from instructions)

Federal (altered)  
\_\_\_\_\_  
\_\_\_\_\_

Materials (Enter categories from instructions)

foundation solid: stone? infilled w/ concrete  
roof side gable: sheet metal  
walls wood frame: weatherboard (replacement)  
other \_\_\_\_\_  
\_\_\_\_\_

Narrative Description (Describe the historic and current condition of the property.)

See Continuation Sheet No. 7-1

=====

8. Statement of Significance

=====

Applicable National Register Criteria (Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing)

- A Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B Property is associated with the lives of persons significant in our past.
- C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D Property has yielded, or is likely to yield information important in prehistory or history.

Criteria Considerations (Mark "X" in all the boxes that apply.)

- A owned by a religious institution or used for religious purposes.
- B removed from its original location.
- C a birthplace or a grave.
- D a cemetery.
- E a reconstructed building, object, or structure.
- F a commemorative property.
- G less than 50 years of age or achieved significance within the past 50 years.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. CH-58

=====  
Areas of Significance (Enter categories from instructions)

ARCHITECTURE

AGRICULTURE

Period of Significance circa 1830

Significant Dates circa 1830

Significant Person (Complete if Criterion B is marked above)

Cultural Affiliation Undefined

Architect/Builder Unknown

Narrative Statement of Significance (Explain the significance of the property.)

See Continuation Sheet No. 8-1

=====

9. Major Bibliographical References

=====

(Cite the books, articles, legal records, and other sources used in preparing this form.)

Brown, Jack D., et al. *Charles County, Maryland, A History*. Charles County Bicentennial Committee, 1976.

Charles County Land Records, Charles County Courthouse, La Plata, Maryland.

Klapthor, Margaret Brown. *The History of Charles County, Maryland*. La Plata, MD: Charles County Tercentenary, Inc., 1958.

=====

10. Geographical Data

=====

Acreage of Property 12.37 acres

**Verbal Boundary Description (Describe the boundaries of the property.)**

The property is designated as Parcel 262 on Map 7, Grid 8 on the Charles County Property Map.

**Boundary Justification (Explain why the boundaries were selected.)**

The Mill Hill Road House has been associated with Parcel 262, Map 7 since its construction circa 1830.

=====

11. Form Prepared By

=====

name/title Kathryn Gettings Smith, Architectural Historian  
 organization Charles County Planning Dept. date November 1998  
 street & number P.O. Box B telephone 301-645-0689  
 city or town La Plata state MD zip code 20646

=====

12. Property Owner

=====

name Alverta B. Berry (contact Diane Rausch, daughter of owner)  
 street & number 3669 Old Washington Rd. telephone 202-358-4510  
 city or town Waldorf state MD zip code 20602

=====

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. CH-58

Section 7 Page 1

Mill Hill Road House  
name of property  
Charles County, Maryland  
county and state

Known as the "Mill Hill Road House," this modest frame dwelling represents an almost complete reconstruction of the original building that stood on the site. Badly deteriorated in the 1930s, the house was acquired by Alverta Berry and stabilized. Since that time, the dwelling has undergone several renovations.<sup>1</sup> While little of the original building fabric remains, the dwelling retains its typical vernacular Southern Maryland form and interior layout. The only distinguishable original feature is the enclosed dog-leg stair.

Located on a rolling 12-acre tract, the house is sited atop a small hill facing north. The house and its immediate surroundings are enclosed by a chainlink fence and only a handful of trees adorn the lot. There are three associated outbuildings, one being a early-to-mid-19th century tobacco barn.

The house displays a common vernacular form for the region. It is 1-1/2-stories in height with a simple single-pile, 2-room plan, and exterior end chimneys. It likely had a full-width front and possibly rear porch. Today, what was once the rear porch has been mostly enclosed to create a utility room.

The building's foundation is not readily visible, but a course of randomly placed stone located at the base of the eastern chimney indicates that it may have once sat on a stone foundation. A recent owner indicated the much of the sill and foundation were replaced or shored-up during the last renovation. The exterior is clad in replacement wood weatherboard, and no original exterior features are evident. Both exterior gable-end chimney stacks have been reconstructed. While the larger of the two chimneys at the eastern gable end was reconstructed in an authentic historic form and incorporates original bricks, the western chimney's design was altered to accommodate the large modern windows that light this

---

<sup>1</sup> The house was minimally surveyed in the 1970s by J. Richard Rivoire who noted that the house was a "One story frame house one room in depth and two in length. Roof ridge runs E and W with chimney at each gable end. Boxed in corner stair on rear center wall of E room. Second floor has narrow center hall sheathed in vertical battens with two rooms containing fireplaces and eave storage. Chimneys fallen and house going fast. Offered once to Society for the Restoration of Port Tobacco but turned down." See Maryland Inventory of Historic Sites Inventory Form for CH-58, "Mill Hill Road House," n.d.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. CH-58

Section 7 Page 2

Mill Hill Road House  
name of property  
Charles County, Maryland  
county and state

=====  
elevation.

The facade arrangement reflects the original hall-parlor plan, featuring a single-leaf off-center entry with a window located directly west of it, and another window set at the eastern end of the facade. Both the 6/6 sash windows and the panel-and-light wood door are replacement materials. A shallow shed-roofed front porch extending across the majority of the facade, is supported on 4" x 4" wood posts and covered with sheet metal roofing. The main side gable roof is also clad with sheet metal and forms a steeply pitched profile.

Two 6/6 wood sash windows open into each of the gable ends, one on the first story and one on the second. The rear elevation is broken by only one window opening that contains a wood 4/4 sash. The only other entrance to the house is located at the west end of the enclosed rear porch. This entry holds a single-leaf panel-and-light wood door.

The house's interior has been significantly altered, although the essential layout appears to remain. The house is divided into two rooms on the first floor now used as a kitchen and living room. The entry opens into the living room with the stair located in the southwest corner of the kitchen. During one of the renovations the original flooring, mantels, and many of the chimney bricks were given to the Barbours who lived at Stagg Hall in Port Tobacco (see CH- ??? ). Today, the interior is finished with modern Colonial Revival style finishes. The original enclosed dog-leg stair features beaded wood paneling, narrow treads and tall risers, and a beaded tongue-and-groove vertical board closet door below the stairs.

The dwelling's second story contains two small bedrooms, similarly re-finished. There was no access to the building's roof structure at the time of the survey.

OUTBUILDINGS:

Of the four related outbuildings, only two can be considered contributing. The oldest of these is a early-to-mid-19th century tobacco barn. The barn is constructed of rough-hewn support posts set in the ground that are mortise-and-tenoned to the sill. The steeply pitched gable roof consists of common rafters butted and nailed at their apex. Many of the barn's original tobacco drying

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. CH-58

Section 7 Page 3

Mill Hill Road House  
name of property  
Charles County, Maryland  
county and state

=====

rods remain in place. Sheds have been added to all four sides, and concrete piers added at the corners. The exterior is clad with vertical boards.

The second contributing outbuilding is a frame corn crib erected in the 1920s. Standing on a wood pier foundation, the building features a front gable roof covered with standing seam metal and slatted walls with weatherboards in the gables.

The remaining two outbuildings are directly related to the house. One, a 1950s garage, features a front gable roof, a hinged double-leaf door, and vinyl siding. The roof is covered with sheet metal. The last outbuilding is a pre-fabricated 1970s-1980s frame shed with an asphalt-shingled gambrel roof.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. CH-58

Section 8 Page 1

Mill Hill Road House  
name of property  
Charles County, Maryland  
county and state

=====

The "Mill Hill Road House" stands on a portion of the "Friendship" tract that was owned and occupied by Dominic Mudd during the mid-19th century. In 1862, Mudd devised the 260-acre tract of "Friendship" upon which he was then residing to his children. The Mudd family continued to own the property until 1900 when the remaining 100 acres of it was sold to John D. Jenkins of Prince George's County.

Five years later, Jenkins sold the same tract to Richard T. Ward of Washington, D.C. The property continued to switch hands going from one absentee owner to another until 1928 when the then owner, George Gibson sold the property to the Hamilton family. The Hamilton's retained ownership until 1972, when they sold 14 acres with the house to Alverta B. Berry. Berry continues to own and rent out the house.

A survey made in the 1970s before the most recent and most major renovation, indicates that the house was constructed circa 1830. (see footnote #1) Little remains today to confirm that date, however.

At one time, the building was offered to the Society for the Restoration of Port Tobacco as a period dwelling, but the society turned it down. The former surveyor noted that the house happens to have the same dimensions and similar form as the old Port Tobacco Times building that once stood in Port Tobacco.

The many alterations made to the house have jeopardized its historical significance. However, the building continues to illustrate a typical vernacular form popular in Southern Maryland during the late 18th and early 19th century.

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. CH-58

Mill Hill Road House  
name of property  
Charles County, Maryland  
county and state

=====

**HISTORIC CONTEXT:**

**Geographic Organization:** Western Shore

**Chronological/Development Period (s):**

Agricultural-Industrial Transition,  
1815-1870

**Prehistoric/Historic Period Theme (s):**

ARCHITECTURE  
AGRICULTURE

**RESOURCE TYPE(S)**

**Category:** Building

**Historic Environment:** Rural

**Historic Function (s):** DOMESTIC/Single dwelling  
AGRICULTURAL/Storage & processing

**Known Design Source:** Unknown

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. CH-58

Mill Hill Road House  
name of property  
Charles County, Maryland  
county and state

=====  
**Chain of Title:**

- August 14, 1862: Dominic Mudd to Julia Ann Mudd, et al.  
to his children: 260 acres, part of "Friendship" on which I now reside  
Charles County Land Records  
Liber GWC 1 Folio 204
- August 15, 1892: Louisa J. McNautz of Washington, DC & Mary Rose Spalding of Charles County to Dominick Mudd  
\$333.34  
211 acres, same land that Julia Ann Mudd formerly owned adjoining the lands of D. Mudd  
Charles County Land Records  
Liber JST 5 Folio 228
- July 2, 1900: Bernard M. & Annie L. Mudd, John E. & Jane E. Mudd, Agnes C. Mudd of Charles County & Julia C. Mudd of Washington, DC (heirs of Dominick Mudd) to John D. Jenkins of Prince George's County  
100 acres, part of "Friendship"  
Charles County Land Records  
Liber BGS 11 Folio 80
- November 6, 1905: John D. Jenkins to Richard T. Ward of Washington, DC  
100 acres situated on Last Nights Branch & the Old Mill Road, subdivision of a tract called "Friendship"  
Charles County Land Records  
Liber FDM 16 Folio 568
- October 16, 1909: Richard T. Ward of Washington, DC to John D. Jenkins of Prince George's County  
called "Friendship"  
Charles County Land Records  
Liber FDM 20 Folio 640

MARYLAND INVENTORY OF HISTORIC PROPERTIES  
CONTINUATION SHEET

Inventory No. CH-58

Mill Hill Road House  
name of property  
Charles County, Maryland  
county and state

=====

June 8, 1911: John D. Jenkins, widower of Prince George's County to George W. Gibson of Washington, DC  
100 acres, Subdivision of a tract known as "Friendship"  
Charles County Land Records  
Liber HCC 23 Folio 435

December 3, 1928: George W. & Grace B. Gibson to Norman L. & James L. Hamilton  
Charles County Land Records  
Liber WMA 49 Folio 429

May 5, 1942: Norman L. & James Hamilton to James L. Hamilton  
55 acres near what was Bolton Post Office called "Friendship" or "Part of Friendship"  
Charles County Land Records  
Liber 76 Folio 425

June 30, 1972: Ralph P. Hamilton, Judith Ann Lloyd & C. Ricardo Hamilton to Alverta B. Berry  
14.16 acres, Parcel "A" of land of James L. Hamilton  
Plat May 10, 1972 Plat Book 18, Folio 146  
Charles County Land Records  
Liber 259 Folio 183

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

STATE:	
COUNTY:	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

1. NAME

COMMON: "MILL HILL ROAD HOUSE"

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER: Mill Hill Road

CITY OR TOWN: Waldorf

STATE Maryland CODE COUNTY: Charles CODE

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP		STATUS	ACCESSIBLE TO THE PUBLIC
District <input type="checkbox"/> Building <input checked="" type="checkbox"/>	Public <input type="checkbox"/>	Public Acquisition: <input type="checkbox"/>	Occupied <input type="checkbox"/>	Yes: <input type="checkbox"/>
Site <input type="checkbox"/> Structure <input type="checkbox"/>	Private <input checked="" type="checkbox"/>	In Process <input type="checkbox"/>	Unoccupied <input checked="" type="checkbox"/>	Restricted <input type="checkbox"/>
Object <input type="checkbox"/>	Both <input type="checkbox"/>	Being Considered <input type="checkbox"/>	Preservation work in progress <input type="checkbox"/>	Unrestricted <input type="checkbox"/>
PRESENT USE (Check One or More as Appropriate)				
Agricultural <input type="checkbox"/>	Government <input type="checkbox"/>	Park <input type="checkbox"/>	Transportation <input type="checkbox"/>	Comments <input type="checkbox"/>
Commercial <input type="checkbox"/>	Industrial <input type="checkbox"/>	Private Residence <input type="checkbox"/>	Other (Specify) <input type="checkbox"/>	
Educational <input type="checkbox"/>	Military <input type="checkbox"/>	Religious <input type="checkbox"/>		
Entertainment <input type="checkbox"/>	Museum <input type="checkbox"/>	Scientific <input type="checkbox"/>		

4. OWNER OF PROPERTY

OWNERS NAME:

STREET AND NUMBER:

CITY OR TOWN: STATE: CODE

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.: Charles County Courthouse

STREET AND NUMBER:

CITY OR TOWN: La Plata STATE Maryland CODE

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:

DATE OF SURVEY: Federal  State  County  Local

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN: STATE: CODE

SEE INSTRUCTIONS

STATE: COUNTY: ENTRY NUMBER DATE FOR NPS USE ONLY

## 7. DESCRIPTION

CONDITION	(Check One)					
	Excellent <input type="checkbox"/>	Good <input type="checkbox"/>	Fair <input type="checkbox"/>	Deteriorated <input checked="" type="checkbox"/>	Ruins <input type="checkbox"/>	Unexposed <input type="checkbox"/>
INTEGRITY	(Check One)			(Check One)		
	Altered <input type="checkbox"/>	Unaltered <input checked="" type="checkbox"/>		Moved <input type="checkbox"/>	Original Site <input checked="" type="checkbox"/>	

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

House situate on the E side of Mill Hill Road.  
 One storey frame house one room in depth and two in length. Roof ridge runs E and W with chimney at each gable end. Boxed in corner stair on rear center wall of E room. Second floor has narrow center hall sheathed in vertical battens with two rooms containing fireplaces and eave storage.

Chimneys fallen and house going fast. Offered once to Society for the Restoration of Fort Tobacco but turned down.

SEE INSTRUCTIONS

## 8. SIGNIFICANCE

N. R. FIELD SHEET

CH-58

## PERIOD (Check One or More as Appropriate)

Pre-Columbian  16th Century  18th Century  20th Century   
 15th Century  17th Century  19th Century  Ca. 1830

## SPECIFIC DATE(S) (If Applicable and Known)

## AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

Aboriginal	Education	<input type="checkbox"/>	Political	<input type="checkbox"/>	Urban Planning	<input type="checkbox"/>
Prehistoric	Engineering	<input type="checkbox"/>	Religion/Phi-		Other (Specify)	<input type="checkbox"/>
Historic	Industry	<input type="checkbox"/>	losophy	<input type="checkbox"/>	_____	
Agriculture	Invention	<input type="checkbox"/>	Science	<input type="checkbox"/>	_____	
Art	Landscape	<input type="checkbox"/>	Sculpture	<input type="checkbox"/>	_____	
Commerce	Architecture	<input type="checkbox"/>	Social/Human-		_____	
Communications	Literature	<input type="checkbox"/>	itarian	<input type="checkbox"/>	_____	
Conservation	Military	<input type="checkbox"/>	Theater	<input type="checkbox"/>	_____	
	Music	<input type="checkbox"/>	Transportation	<input type="checkbox"/>	_____	

## STATEMENT OF SIGNIFICANCE (Include Personages, Dates, Events, Etc.)

Though this house seems in bad shape it is not beyond resotration. From personal notes I found that this house is exactly the same size and shape as the old Port Tobacco Times Building. There is some talk of reconstructing the old Times building and it was suggested that materials from this house be used or at least use it as a pattern but when the house was offered to the Society (when it was still in rather good condition) it was refused.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

N. R. FIELD SHEET

CH-58

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN ONE ACRE		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE

11. FORM PREPARED BY

NAME AND TITLE: J. Richard Rivoire

ORGANIZATION Maryland Historical Trust DATE \_\_\_\_\_

STREET AND NUMBER: \_\_\_\_\_

CITY OR TOWN: Annapolis STATE Maryland CODE \_\_\_\_\_

12. STATE LIAISON OFFICER CERTIFICATION

NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National  State  Local

Name \_\_\_\_\_

Title \_\_\_\_\_

Date \_\_\_\_\_

I hereby certify that this property is included in the National Register.

\_\_\_\_\_  
Chief, Office of Archeology and Historic Preservation

Date \_\_\_\_\_

ATTEST:

\_\_\_\_\_  
Keeper of The National Register

Date \_\_\_\_\_


SEE INSTRUCTIONS

RESOURCE SKETCH MAP

3/99

MILL HILL ROAD HOUSE  
CHARLES COUNTY, MD  
BERRY VIC

CH-58




RESOURCE SKETCH PLAN

3/99


CH-58



MILL HILL ROAD HOUSE  
CHARLES COUNTY, MD  
BERRY VIC.



11/30/98  
KGS



Mill Hill Road House  
Charles County, MD  
CH-58  
PISCATAWAY, MD QUAD



CH-58

MILL HILL ROAD HOUSE  
CHARLES COUNTY, MD

K.G. SMITH

3/99

MARYLAND SHPO

LOOKING SE

1 OF 7



CH-58

MILL HILL ROAD HOUSE  
CHARLES COUNTY, MD

K.G. SMITH

3/99

MARYLAND SHPO

LOOKING NE

2 OF 7



CH-58

MILL HILL ROAD HOUSE  
CHARLES COUNTY, MD

K.G. SMITH

3/99

MARYLAND SHPO  
LOOKING NORTH

3 OF 7



CH-58

MILL HILL ROAD HOUSE

CHARLES COUNTY, MD

K.G. SMITH

3/99

MARYLAND SHPO

LOOKING NW

4 OF 7



CH-58

MILL HILL ROAD HOUSE

CHARLES COUNTY, MD

K.G. SMITH

3/99

MARYLAND SHPO

TOBACCO BARN- LOOKING NE

5 OF 7



CH-58

MILL HILL ROAD HOUSE

CHARLES COUNTY, MD


K.G. SMITH

3/99

MARYLAND SHPD

CORN CRIB - LOOKING SE

6 OF 7



CH-58

MILL HILL ROAD HOUSE  
CHARLES COUNTY, MD  
K.G. SMITH

3/99

MARYLAND SHPO  
GARAGE & SHED - LOOKING SE  
7 OF 7