

Eutah
CH-79
Waldorf vic.
Private

Circa 1850

Constructed around 1850 Eutah is equally significant as an exceptional and well maintained example of Greek Revival architecture in Charles County, and for its association with the notable Confederate Civil War officer Captain William Fendley Dement of the First Maryland Artillery, commonly known as Dement's Battery. Eutah is a 2 ½ story double-parlor, side-passage dwelling with an original 2-story kitchen dependency flanking the north gable end. The dwelling stands on an exquisitely landscaped five acre parcel in the center of Eutah Forest Subdivision comprising much of the associated farms original acreage. The interior features some of Charles County's best example as of Greek Revival inspired woodwork including a prominent stair and original mantels, and a set of pocket doors dividing the double parlors. A two story front gable wing has been recently added to the south gable as well as a single story addition to the north.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. CH-79

1. Name of Property (indicate preferred name)

historic Eutah
 other

2. Location

street and number 3200 Captain Dement Drive not for publication
 city, town Waldorf X vicinity
 county Charles

3. Owner of Property (give names and mailing addresses of all owners)

name Ronald C. Godshalk
 street and number PO Box 298 telephone 301-870-6708
 city, town Pomfret state MD zip code 20675-0298

4. Location of Legal Description

courthouse, registry of deeds, etc. Charles County Courthouse tax map and parcel: 6 p.59
 city, town La Plata, MD liber 2634 folio 229

5. Primary Location of Additional Data

- Contributing Resource in National Register District
- Contributing Resource in Local Historic District
- Determined Eligible for the National Register/Maryland Register
- Determined Ineligible for the National Register/Maryland Register
- Recorded by HABS/HAER
- Historic Structure Report or Research Report
- Other

6. Classification

Category	Ownership	Current Function	Resource Count
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture	Contributing Noncontributing
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	<u>1</u> <u>2</u>
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	buildings
<input type="checkbox"/> site		<input checked="" type="checkbox"/> domestic	sites
<input type="checkbox"/> object		<input type="checkbox"/> education	structures
		<input type="checkbox"/> funerary	objects
		<input type="checkbox"/> government	<u>1</u> <u>2</u> Total
		<input type="checkbox"/> health care	
		<input type="checkbox"/> industry	
		<input type="checkbox"/> landscape	
		<input type="checkbox"/> recreation/culture	
		<input type="checkbox"/> religion	
		<input type="checkbox"/> social	
		<input type="checkbox"/> transportation	
		<input type="checkbox"/> work in progress	
		<input type="checkbox"/> unknown	
		<input type="checkbox"/> vacant/not in use	
		<input type="checkbox"/> other:	
			Number of Contributing Resources previously listed in the Inventory
			<u>1</u>

7. Description

Inventory No. CH-79

Condition

<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated
<input type="checkbox"/> good	<input type="checkbox"/> ruins
<input type="checkbox"/> fair	<input type="checkbox"/> altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

Erected just prior to the Civil War, Eutaw is a 2 1/2 story double-parlor, side-passage dwelling that faces east with an original 2-story kitchen dependency flanking the north gable end. The dwelling stands on an exquisitely landscaped five acre parcel in the center of Eutaw [sic] Forest Subdivision comprising much of the associated farms original acreage. The interior features some of Charles County's best examples of Greek Revival inspired woodwork including a prominent stair and massive newel, original mantels, and a set of pocket doors dividing the double parlor. The main block is three bays in width and is capped with a pair of exterior end chimneys to the north that are laid in American bond with a two course corbelled cap. A two story front gable wing has been recently added to the south gable as well as a single story addition to the north.

The original frame dwelling including the main block and the service wing, rests on a continuous brick foundation. The frame is now clad in fiber-cement siding. The composition shingle roof is pierced by two gabled dormers. The windows are 6/6 wood replacements. The front elevation is symmetrical and three bays in length. The front door is a recent replacement and an earlier shed-roof porch has been rebuilt as the current balustrade porch. Shed-roof porches have been added to the first and second story of the rear elevation and the front elevation of the service wing.

The dwelling has a traditional side passage plan which has been modified as a result of a recent renovations. Exceptional original features include the paneled staircase and massive newel, and original doors. Stair paneling, doors, door molding and mantels share the characteristic long vertical panels often found in Greek Revival features. Alterations to the original floorplan include a partial partition wall erected in the hall to create a foyer and the removal of a doorway into east parlor from the hall. Ceiling medallions and crown molding have been added throughout along with closets and bathrooms on each floor. The kitchen wing includes hand planed paneling in the narrow service stain.

8. Significance

Inventory No. CH-79

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime industry	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input checked="" type="checkbox"/> military	<input type="checkbox"/> other:

Specific dates	Circa 1850	Architect/Builder	Unknown
Construction dates	Circa 1850		

Evaluation for:

National Register Maryland Register not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance reports, complete evaluation on a DOE Form - see manual.)

Although extensively altered during its recent renovation, Eutah is significant equally as an exceptional and well maintained example of Greek Revival architecture in Charles County and for its association with Captain William Fendley Dement, of the First Maryland Artillery, commonly known as Dement's Battery. Richard Rivoire's 1978 inventory conducted for the Maryland Historical Trust summarizes the Dement's major achievements in the First Virginia Artillery. "Dement was instrumental in forming the First Maryland artillery in 1861. Promoted to Captain following the Seven Day battle for Richmond, he soon rose to major, serving under Stonewall Jackson in the valley of Virginia. Considered one of the best artillery officers in the Confederate Army, he participated in the battle of Seven Pines, Second Manassas, Cedar Run, Manchester, the capture of Harper's Ferry, Sharpsburg, Gettysburg, Cold Harbor and Appomattox".

Although no battles were fought on Charles County's soil, the citizens of the county made major contributions to the War, mainly on the side of the Confederates. A large number of the county's young men traveled to Richmond and joined the Confederate armies at the outset of the war. Several individual citizens aided the Confederate cause by ferrying people, supplies, and munitions across the Potomac River to Virginia. In addition, many Charles Countians took part in the transference of messages across the north-south border. Although the Federal government required the furnishing of soldiers from each county, most Charles Countians refused to fight on the side of the Union, sending purchased substitutes in their place. At times, the occupying Union troops had to discipline the rebellious citizens, sending many to Washington, DC for questioning. After the close of the armed conflict, Charles County remained in the spotlight as several citizens were convicted of conspiring to aid John Wilkes Booth in his flight from Washington, DC after the assassination of President Lincoln. Following the assassination, Charles County was once again occupied by several thousand Federal troops who attempted to locate and arrest any local conspirators.

Following the Civil War, Charles County suffered the same fate as most of the southern states. The basis of the economy, slave labor, was gone. Land ceased to be cultivated, credit collapsed and many planters fell deep into debt. In addition, Federal taxes levied by the "carpet-bag" government threatened landowners with the loss of their land. The turmoil of the Reconstruction era continued in Charles County well into the twentieth century. Despite the collapse of the slave-based tobacco economy following the Civil War, Charles County and most of the surrounding counties retained their dependence on tobacco cultivation. While some diversification did occur, the reliance on agriculture, mainly tobacco, remained throughout the 19th century.

When Eutah was erected prior to the Civil War, agriculture and commercial trade flourished. Throughout the 1830s, 1840s, and 1850s, Charles County experienced a period of economic prosperity and associated new construction that was unrivaled until the second half of the 20th century. Eutah preserves some of Charles County's best examples of Greek Revival details, most apparent in the mantels, doors and surrounds of the main block. The Greek Revival style in Charles County was largely interrupted by the Civil War and was thus, never as full-blown locally as in other parts of the South. The small handful of extant examples include Green's Inheritance (CH-61 NR) and Cedar Grove (CH-113 NR).

9. Major Bibliographical References

Inventory No. CH-79

10. Geographical Data

Acreage of surveyed property 5

Acreage of historical setting 355

Quadrangle name Mount Vernon

Quadrangle scale 1:24,000

Verbal boundary description and justification

Eutah is associate with Charles County Property Tax Map 6, Parcel 59, Grid 22. The site currently contains five acres.

11. Form Prepared By

name/title Cathy Hardy/Historic Sites Surveyor

organization Charles County Planning

date 6/6/2002

street and number 200 Baltimore Street

telephone 301-396-5815

city or town La Plata

state MD zip code 20646

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville MD 21032
410-514-7600

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. CH-79

Section 8 Page 1

Eutaw
name of property
Charles County, MD
county and state

Chain of Title:

- 1998 To Ronald Craig Godshalk. Parcel E, "Eutaw[sic] Forest" Subdivision.
2634/229
- 1980 Berry Road Joint Venture to Anthony Wood and Elizabeth Wood
Plat Book 29/82
741/200
- 1978 William E. Padgett and Richard E. Padgett for the estate of Wilbur Padgett (Estate
#4248) to Berry Road Joint Venture. 337.834 acres.
565/259
- 1939 James A. Mitchell, trustee to Wilbur Padgett "Part of Eutaw Forest". 456 acres.
- 1939 Equity Margaret Helena Dement, Mary Agnus Dement, Gertrude Theresa Dement
Will of Mary S. Dement to three daughters Margaret Helena Dement, Mary Agnus
Dement and Gertrude Theresa Dement.

MARYLAND INVENTORY OF HISTORIC PROPERTIES
CONTINUATION SHEET

Inventory No. CH-79

Section 9 Page 1

Eutah
name of property
Charles County, Maryland
county and state

Major Bibliographic References:

Brown, Jack D., et al. Charles County, Maryland, A History.
Charles County Bicentennial Committee, 1976.

Charles County Land Records, Charles County Courthouse, LaPlata, Maryland.


Goldsborough, W.W. The Maryland Line in the Confederate Army.
Board of Governor's of the Association of the Maryland Line. 1900.

Klaphor, Margaret Brown. The History of Charles County, Maryland.
LaPlata, MD: Charles County Tercentenary, Inc., 1958.


Ruffner, Kevin Conley. Maryland's Blue and Gray.
Baton Rouge: Louisiana State University Press. 1997.

EUTAH

FIRST FLOOR PLAN



PREVIOUS DOOR



2ND FLOOR

(NOT DRAWN TO SCALE)

CH-74 _____ Charles County, MD
Name: EUTAH
Location: PDMFRET VIC
Quad: MOUNT VERMILION



CH-79

Utah

Charles Co, MD

C. Hardy

1/2002

MD

SHRO

LOOKING WEST

10F8



CH-79

Eutah

Charles Co., MD

C. Hardy

112002

MD

IN 1998

4028

SHPO



CH-79

Utah

Charles Co, MD

C. Hardy

1/2002

MD

SHPO

DOOR & MANTEL, LOOKING NE

8 of 8



CH-79

Utah

Charles Co, MD

C. Hardy

1/2002

MD

SHPO

DOOR to STAIR, Looking S

70E8



CH-79

Eutah

Charles Co., MD

C. Hardy

1/2002

MD

SHPO

STAIR,
50F8



CH-79

Utah

Charles Co, MD

C Hardy

11/2002

MD

SHPO

STAIR DETAIL

60F8



CH-79

Eutah

Charles Co, MD

C. Hardy

1/2002

MD

SHPO

LOOKING SW

2 of 8



CH-79

Eutah

Charles Co MD

C. Hardy

1/2002

MD

SHPO

LOOKING E, REAR

30F8

CHAS-79
EUTAH (Eutah Forest)
Vicinity of Pomfret
Private

1850's

Originally known as "Eutah Forest," this two part frame house of late-Federal styling was built by Major William Fendlay Dement in the 1850's. Born in Charles County in 1806, Dement was instrumental in forming the First Maryland Confederate Artillery in 1861. Promoted to Captain following the Seven Day Battle for Richmond, he soon rose to Major, serving under Stonewall Jackson in the Valley of Virginia. Considered one of the best artillery officers in the Confederate Army, he participated in the Battle of Seven Pines, Second Manassas, Cedar Run, Manchester, the capture of Harper's Ferry, Sharpsburg, Gettysburg, Cold Harbor and Appomattox. Following the War, Dement returned to Eutah where he farmed until his death in 1907.

Eutah is a very basic Federal house type, two storys with a dormered gable roof and two exterior chimneys at one end. The first floor plan, containing a side hall and adjacent double parlor on the first floor and three bedrooms above, has extremely plain woodwork but is distinguished by a broad and graceful stairway. A two story wing at the east end housed the kitchen and servants quarters. Its end chimney was removed in recent years.

MARYLAND HISTORICAL TRUST

CHAS-79

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY **MDI#0900795404**

1 NAME

HISTORIC

EUTAH (Eutah Forest)

AND/OR COMMON

2 LOCATION

(Bensville Road)

STREET & NUMBER

West side Md. Rte. 228, approx. 3/4 mile north of Bensville

CITY, TOWN

Waldorf

X VICINITY OF

CONGRESSIONAL DISTRICT

First

STATE

Maryland

COUNTY

Charles

3 CLASSIFICATION

CATEGORY

- DISTRICT
- BUILDING(S)
- STRUCTURE
- SITE
- OBJECT

OWNERSHIP

- PUBLIC
- PRIVATE
- BOTH
- PUBLIC ACQUISITION**
- IN PROCESS
- BEING CONSIDERED

STATUS

- OCCUPIED
- UNOCCUPIED
- WORK IN PROGRESS
- ACCESSIBLE**
- YES: RESTRICTED
- YES: UNRESTRICTED
- NO

PRESENT USE

- AGRICULTURE
- MUSEUM
- COMMERCIAL
- PARK
- EDUCATIONAL
- PRIVATE RESIDENCE
- ENTERTAINMENT
- RELIGIOUS
- GOVERNMENT
- SCIENTIFIC
- INDUSTRIAL
- TRANSPORTATION
- MILITARY
- OTHER

4 OWNER OF PROPERTY

NAME

Wilbur Padgett

Telephone #:

STREET & NUMBER

CITY, TOWN

___ VICINITY OF

STATE, zip code

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.

Charles County Courthouse

Liber #: 70

Folio #: 68

STREET & NUMBER

Charles Street (P. O. Box B)

CITY, TOWN

La Plata

STATE

Maryland 20646

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

___ FEDERAL ___ STATE ___ COUNTY ___ LOCAL

DEPOSITORY FOR SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

CONDITION		CHECK ONE	CHECK ONE
<input checked="" type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input checked="" type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Eutah is an extremely plain but well proportioned two part house of Federal styling. The two story main block, typical of this style, is three bays wide at both floor levels of the two side elevations. The entrance doors occupy the first bay from the west end. The main entrance, located on the south side, is unusually wide, having a multi-paned transome over a double leafed paneled door flanked by side lights. This door was once sheltered by a one story porch that was removed when the present exterior sheathing was installed. On both side elevations the two first floor and three second floor windows frame sash of six-over-six panes. On the front and rear slopes of the gable roof are two pedimented dormer windows, also of six-over-six sash. At the west end there is a single centered window on both main floor levels and the attic. At the opposite end stand two exterior chimneys with stepped shoulders and free-standing stacks.

At the east end of the house stands a lower two story wing, two bays wide on both floor levels of the side elevations. A transomed entrance door occupies the first bay from the main block on the south side. All of the seven windows frame six-over-six sash. At the east end of the roof is a single flue interior stove chimney, said to have replaced a large exterior chimney like those of the main block that was removed in this century. The wing is recessed back from the front wall of the main block about half its depth and at one time might have been fronted by a one story porch. The exterior walls of both parts of the house are sheathed with asbestos siding and the roof with composition shingles.

On the interior of the first floor, the main block has a wide hall at the west end. A broad and attractive stair at its north end rises in two flights to the second floor. Adjacent to the hall, on the east side, are double parlors connected by a large doorway. On the second floor there are three bedrooms and an enclosed stair to the attic. Throughout the house the trim is extremely plain, with flat board surrounds and unornamented corner blocks framing the doors and windows. The stair displays the only decorative woodwork in the house.

The east wing originally housed the kitchen and pantry on the first floor and two bedrooms, probably sleeping quarters for domestic servants, on the second floor.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input checked="" type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input checked="" type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

Originally known as "Eutah Forest", this two part frame house of late-Federal styling was built by Major William Fendlay Dement in the 1850's. Born in Charles County in 1806, Dement was instrumental in forming the First Maryland Confederate Artillery in 1861. Promoted to Captain following the Seven Day Battle for Richmond, he soon rose to Major, serving under Stonewall Jackson in the Valley of Virginia. Considered one of the best artillery officers in the Confederate Army, he participated in the Battle of Seven Pines, Second Manassas, Cedar Run, Manchester, the capture of Harper's Ferry, Sharpsburg, Gettysburg, Cold Harbor and Appomattox. Following the War, Dement returned to Eutah where he farmed until his death in 1907.

Eutah is a very basic Federal house type, two storys with a dormered gable roof and two exterior chimneys at one end. The first floor plan, containing a side hall and adjacent double parlor on the first floor and three bedrooms above, has extremely plain woodwork but is distinguished by a broad and graceful stairway. A two story wing at the east end housed the kitchen and servants quarters. Its end chimney was removed in recent years.

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

Eutah is located on a 337.83 acre tract of land indentified as Parcel 11, Maps 6 and 13, Charles County Tax Maps (revised January 1976).

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	COUNTY
STATE	COUNTY

11 FORM PREPARED BY

NAME / TITLE

J. Richard Rivoire, Consultant

ORGANIZATION

Charles County Planning Department

DATE

October 1978

STREET & NUMBER

Charles County Courthouse

TELEPHONE

645-6537

CITY OR TOWN

La Plata

STATE

Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

N. P. FIELD SHEET

CH 79

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM**

(Type all entries - complete applicable sections)

STATE:	
COUNTY:	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

1. NAME

COMMON: EUTAW

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER: BENSVILLE

CITY OR TOWN: WALDORF

STATE: MD. CODE: COUNTY: CHAS. CODE:

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
District <input type="checkbox"/> Building <input checked="" type="checkbox"/>	Public <input type="checkbox"/> Private <input checked="" type="checkbox"/> Both <input type="checkbox"/>	Occupied <input checked="" type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress <input type="checkbox"/>	Yes: Restricted <input type="checkbox"/> Unrestricted <input type="checkbox"/> No: <input checked="" type="checkbox"/>
Site <input type="checkbox"/> Object <input type="checkbox"/>	Public Acquisition: In Process <input type="checkbox"/> Being Considered <input type="checkbox"/>		
PRESENT USE (Check One or More as Appropriate)			
Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment <input type="checkbox"/>	Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum <input type="checkbox"/>	Park <input type="checkbox"/> Private Residence <input checked="" type="checkbox"/> Religious <input type="checkbox"/> Scientific <input type="checkbox"/>	Transportation <input type="checkbox"/> Other (Specify) <input type="checkbox"/> Comments <input type="checkbox"/>

4. OWNER OF PROPERTY

OWNERS NAME: WILBUR L. PADGETT

STREET AND NUMBER: "EUTAW"

CITY OR TOWN: WALDORF STATE: MD. CODE:

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.: Chas. Co. Courthouse

STREET AND NUMBER:

CITY OR TOWN: La Plata STATE: MD. CODE:

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:

DATE OF SURVEY: Federal State County Local

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN: STATE: CODE:

SEE INSTRUCTIONS

STATE: COUNTY: ENTRY NUMBER: DATE: FOR NPS USE ONLY

7. DESCRIPTION

CONDITION	(Check One)					
	Excellent <input type="checkbox"/>	Good <input checked="" type="checkbox"/>	Fair <input type="checkbox"/>	Deteriorated <input type="checkbox"/>	Ruins <input type="checkbox"/>	Unexposed <input type="checkbox"/>
INTEGRITY	(Check One)			(Check One)		
	Altered <input type="checkbox"/>	Unaltered <input checked="" type="checkbox"/>		Moved <input type="checkbox"/>	Original Site <input checked="" type="checkbox"/>	

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

Eufaw is a frame dwelling of two part composition the 2nd, or smaller part possibly later than the main block.

The main block is 2 1/2 storeys three bays in length with the main hall running the width of the W gable. Three windows are on the second floor level with 2 dormers with "A" roofs above. The front door has a 7 light overhead transome with 3 pane side lights, At the E gable of the main block are 2 double flue chimneys with free standing stacks.

The 2nd. part, from the E gable of the main block is 2 storeys and 2 bays in length with the 1st. floor level door (with transome) toward the main block chimney end. Two windows are at the 2nd floor level. On the interior E end wall is a victorian stove chimneys.

The roof plan is "A" frame with the edge running E to W; The facade faces S.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

(This section is currently blank.)

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN ONE ACRE		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE

11. FORM PREPARED BY

NAME AND TITLE: J. R. Rivort

ORGANIZATION _____ DATE _____

STREET AND NUMBER: _____

CITY OR TOWN: _____ STATE _____ CODE _____

12. STATE LIAISON OFFICER CERTIFICATION

NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National State Local

Name _____

Title _____

Date _____

I hereby certify that this property is included in the National Register.

Chief, Office of Archeology and Historic Preservation

Date _____

ATTEST:

Keeper of The National Register

Date _____

SEE INSTRUCTIONS



CHAS-79

EUTAH; View From N.E.

J.R.Rivoire, 1978



CHAS-79

EUTAH; View From S.E.

J.R.Rivoire, 1978