

D-30


George Hart Farmhouse

Bishops Head

c. 1820, c. 1880

While suffering from an advanced state of deterioration, the George Hart farmhouse is the oldest structure to remain standing in the Strait Election District of Dorchester County. The rear two-story, and story-and-a-half sections behind the two-and-a-half story Victorian addition date to the first quarter of the nineteenth century (c. 1820), and the rear wing survives with many intact period finishes. The original two-story, one-room plan house has portions of a fully paneled room accented with an expertly designed and crafted Federal mantel. The two-room plan service wing to the north has beaded floor joists, board walls, and portions of period woodwork including a raised-panel door cupboard. The early nineteenth century frame house was modified around 1880 with the addition of a two-and-a-half story, cross-gabled addition that reoriented the house face the county road instead of Fox Creek.

The early land history of the property in Bishops Head is clouded by vague property descriptions and the lack of probate records predating 1850. During the second quarter of the nineteenth century and prior to the Victorian addition, the early portions of this frame dwelling constituted the residence of merchant George Hart, who operated a general store and post office on the property. When the St. Thomas M. E. Church trustees acquired land for a meeting house near his farm, George Hart served as one of the members in 1839. At the time of the 1860 census he is listed as a successful 68-year old merchant with real estate and personal property valued at \$4500. The post office location in the census was identified as "Hart's Store." He is grouped with his wife Amelia, aged 45, and four children. At some point during the mid 1860s he relocated to property near Lakesville where he resided until his death. The Hart farm and store were acquired by Christopher C. Fallin around 1866, and in 1876, C. C. Fallin petitioned the county Orphan's Court



# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

## 1. Name of Property (indicate preferred name)

historic George Hart Farmhouse

other \_\_\_\_\_

## 2. Location

street and number 1904 Bishops Head Road  not for publication

city, town Bishops Head  vicinity

county Dorchester

## 3. Owner of Property (give names and mailing addresses of all owners)

name Stephen F. Crum and Sharon Reynolds

street and number 7310 Gunpowder Road telephone \_\_\_\_\_

city, town Baltimore state MD zip code 21220

## 4. Location of Legal Description

courthouse, registry of deeds, etc. Dorchester County Clerk of Court liber 202 folio 400

city, town Cambridge tax map 108 tax parcel 173 tax ID number 10-000203

## 5. Primary Location of Additional Data

- Contributing Resource in National Register District  
 Contributing Resource in Local Historic District  
 Determined Eligible for the National Register/Maryland Register  
 Determined Ineligible for the National Register/Maryland Register  
 Recorded by HABS/HAER  
 Historic Structure Report or Research Report at MHT  
 Other: \_\_\_\_\_

## 6. Classification

Category	Ownership	Current Function	Resource Count	
			Contributing	Noncontributing
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture	<input type="checkbox"/> landscape	<input type="checkbox"/> buildings
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	<input type="checkbox"/> recreation/culture	<input type="checkbox"/> sites
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	<input type="checkbox"/> religion	<input type="checkbox"/> structures
<input type="checkbox"/> site		<input type="checkbox"/> domestic	<input type="checkbox"/> social	<input type="checkbox"/> objects
<input type="checkbox"/> object		<input type="checkbox"/> education	<input type="checkbox"/> transportation	<input type="checkbox"/> Total
		<input type="checkbox"/> funerary	<input type="checkbox"/> work in progress	
		<input type="checkbox"/> government	<input type="checkbox"/> unknown	
		<input type="checkbox"/> health care	<input checked="" type="checkbox"/> vacant/not in use	<b>Number of Contributing Resources previously listed in the Inventory</b>
		<input type="checkbox"/> industry	<input type="checkbox"/> other:	_____

Marshall Historical Trust  
Marshall Inventory of  
Historical Properties Form

Form No. 1-1-41

1. Name of Property  
2. Location of Property

3. Owner's Name  
4. Date of Construction

5. Primary Location of Addition  
6. Date of Addition

7. Name of Architect

8. Name of Contractor

Category	Description	Material	Quantity	Remarks
Brick	Common	Red	1000	
Brick	Special	Yellow	500	
Stone	Field	Local	2000	
Stone	Decorative	Granite	100	
Wood	Structural	Oak	500	
Wood	Finish	Pine	1000	
Roofing	Shingles	Asphalt	10000	
Roofing	Flashing	Lead	100	
Paint	Interior	White	1000	
Paint	Exterior	Green	500	
Hardware	Doors	Iron	10	
Hardware	Windows	Iron	20	
Hardware	Stairs	Iron	5	
Hardware	Handrails	Iron	10	
Hardware	Lighting	Iron	10	
Hardware	Decorative	Iron	10	

## 7. Description

Inventory No. D-30

### Condition

excellent     deteriorated  
 good         ruins  
 fair          altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

### DESCRIPTION SUMMARY

The George Hart farmhouse, also known as the Christopher C. Fallin house, is a three-part frame dwelling standing abandoned on the west side of the Wingate-Bishops Head Road in the community of Bishops Head, Dorchester County, Maryland. Dating from three distinct period between c. 1820 and c. 1880, the composite frame dwelling has a south facing two-and-a-half story, cross-gabled, single-pile frame section that fronts a much older early nineteenth century dwelling consisting of two sections built during the late first quarter nineteenth century. Directly behind the Victorian front section is a two-story, one-room plan dwelling that predates by a few years a story-and-a-half service wing. Supported on a combination brick pier and continuous brick foundation, the exterior is clad with a mixture of beaded weatherboard siding fastened with mature cut nails and plain weatherboard siding also fastened with mature cut nails. The various gable roofs are sheathed with either deteriorated asphalt shingles or wood shingles. The house has been abandoned for at least a generation and is falling into an advanced state of disrepair.

### GENERAL DESCRIPTION

The George Hart farmhouse, also known as the Christopher C. Fallin house, stands on the west side of the Wingate-Bishops Head Road in the Strait Election District of Dorchester County, Maryland. The three-part frame house rests on a combination brick pier and continuous brick foundation, and the exterior is clad with a mixture of plain and beaded weatherboard siding. The steeply pitched roofs are clad with a asphalt and/or wood shingles. The house faces south with the gable roof of the main block oriented on an east/west axis. The front section is a c. 1880 addition to an early nineteenth century two-story, one-room plan original house that has a story-and-a-half two-room plan addition built within a decade of initial construction.

The south (main) façade of the c. 1880 house is oriented to an old entrance lane. The three-bay elevation has a center entrance and flanking two-over-two sash windows. The four-panel front door is framed by two-light sidelights and a three-light transom. The second story is marked by three evenly spaced two-over-two sash windows, and the cross gable is pierced by a pointed arch two-over-two sash window. The edges of the roof are finished with an extended eave and open soffits.

The east gable end of the front section is a two-bay façade with pairs of two-over-two sash windows lighting the first and second stories. Small two-over-two sash window light the attic. Piercing the gable is an interior end brick stove chimney.

The west gable end is sheltered on the first story by a deteriorated turned post porch, and the second story is defined by a pair of two-over-two sash windows. Piercing the gable end is a pair of two-over-two attic windows. The edge of the roof has an extended eave with open soffits.

The rear wall of the front section is largely covered by the two-story, one-room plan frame house that

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 7 Page 1

---

dates to the early nineteenth century. Originally built to face west, the two-story structure is three bays across on its south side, and the window openings are fitted with two-over-two sash. The roof of the earlier wing was rebuilt with extended eaves when the Victorian addition was erected. The east wall of the initial two-story house retains one window opening framed by an ovolo molded backband surround with a bullnose sill finished with a cove underneath. HL hinges are attached to the window frame. A rebuilt gable end brick stack rises against the gable end and pierces the extended eave.

Attached to the back of the early nineteenth century two-story house is a story-and-a-half, two-room plan service wing also dating to the early nineteenth century. The west side of the service wing has two door openings flanked by six-over-six sash windows. Surviving on the northernmost opening is a Federal style six-panel door. An exterior brick chimney stack with a corbelled base formerly rose against the north gable end of the service wing, and the former opening is evident in the patched weatherboards.

The interiors of the house have survived relatively unaltered, and the earliest sections of the house are fitted with superior, early nineteenth century finishes. When the Victorian addition was erected around 1880, an open staircase was introduced within the walls of the original house, which required the modification of a fully paneled first floor space. Despite the alteration to the south interior wall, the other three walls retain finely crafted floor-to-ceiling paneling. A combination of vertical and horizontal flat panels finishes the wall surfaces which are further enhanced with early nineteenth-century chair rail, baseboard and door moldings. A finely crafted Federal mantel remains on the north wall, and it features a five-part frieze topped by a crown molded mantel shelf enriched with a dentiled bed molding. Raised panels define the frieze and are alternating with projecting flat-panel frieze blocks underneath the mantel shelf. This room also has a flush board ceiling. Fixed in the south side of the original room is a Victorian staircase featuring a turned newel post with finial, turned balusters and a scroll decorated stringer.

The second floor of the original two-story house has a hall and single chamber, which survives with a period mantel, beaded baseboard and simple chair rail. The mantel has a molded surround and molded mantel shelf. The frieze is enhanced with a decorated board with scroll shaped ends. The enclosed stair to the attic has a reused raised four-panel door. The attic is unfinished and the roof framing was rebuilt during the late nineteenth century.

The story-and-a-half wing is finished on the first floor with horizontal board walls and exposed beaded joists. The center room, formerly a dining room, survives with a built-in raised panel cupboard that is fixed in the southeast corner. The upper section of the cupboard has a pair of raised two-panel doors, and the lower section of the cupboard is enclosed with a pair of single raised-panel doors. The cupboard is framed by an ovolo molded surround. Adjacent to the cupboard is a brick fireplace and

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
**Continuation Sheet**

Number 7 Page 2

---

chimney stack that has been exposed with the removal of sections of lath and plaster. The floor framing in the ceiling above indicates that a large exterior brick stack formerly rose against the two story exterior. When the story-and-a-half wing was erected, the second floor framing was built around the stack. In the first floor there is evidence of the former chimney base. The dining room is separated from the former kitchen by a vertical beaded board wall pierced by a board-and-batten door on its west side.

The former kitchen features horizontal board walls and exposed and beaded ceiling joists. Fixed in the northeast corner is a partially enclosed staircase. The exposed series of steps reveal a former early nineteenth century square newel post and rectangular balusters. The north wall is framed for a large cooking fireplace that was demolished with the rear wall filled in with later weatherboards.

The loft of the service wing is one large space with exposed roof framing. Lapped collar beams are let into the rafter blades and secured with mature cut nails. Two dormers, one each roof slope were introduced during the mid to late nineteenth century. The end wall of the original two-story house has remnants of beaded weatherboards painted a light brown color. The former profile of the corbelled shoulder chimney stack is evident to the side of the rebuilt chimney. There is also a large patch in the loft floor where narrow floor boards contrast with wider ones original to the early nineteenth century house.

History of Properties Form  
Mystic Inventory of  
Marshall Industrial Trust

Page No. 100

Co. Name Street

The first building was constructed in 1880 and was used for the purpose of a warehouse. It was a simple wooden structure with a gabled roof and a central entrance. The building was situated on a corner lot and was the only structure of its kind in the area at that time.

The second building was constructed in 1890 and was used for the purpose of a factory. It was a larger wooden structure with a flat roof and several windows. The building was situated on a lot adjacent to the first building and was the only structure of its kind in the area at that time.

The third building was constructed in 1900 and was used for the purpose of a warehouse. It was a larger wooden structure with a gabled roof and a central entrance. The building was situated on a lot adjacent to the second building and was the only structure of its kind in the area at that time.

# 8. Significance

Inventory No. D-30

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input checked="" type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other: _____

**Specific dates** \_\_\_\_\_ **Architect/Builder** \_\_\_\_\_

**Construction dates** \_\_\_\_\_

Evaluation for:  
 National Register       Maryland Register       not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

## SIGNIFICANCE SUMMARY

While suffering from an advanced state of deterioration, the George Hart farmhouse is the oldest structure to remain standing in the Strait Election District of Dorchester County. The rear two-story and story-and-a-half rear section behind a two-and-a-half story cross-gabled main block dates to the first quarter of the nineteenth century (c. 1820), and it survives with largely intact interiors. The original two-story, one-room plan house has portions of a fully paneled room accented with a finely designed and crafted Federal style mantel. The two-room plan service wing to the north has beaded floor joists, board walls and portions of period woodwork including a raised-panel cupboard. The early nineteenth century frame house was modified around 1880 with the addition of a two-and-a-half story, cross-gabled addition that reoriented the house to face the road instead of nearby Fox Creek.

## HISTORY AND SUPPORT

The early land history of this property in Bishops Head is clouded by vague property descriptions and lack of probate records predating 1850. During the second quarter of the nineteenth century and prior to the Victorian addition, the early portions of this frame dwelling was the residence of merchant George Hart, who operated a general store and post office on the property. When the St. Thomas M.E. Church acquired land for a meeting house near his farm, George Hart served as one of the trustees in 1839.<sup>1</sup> At the time of the 1860 census he is listed as a successful 68-year old merchant with real estate and personal property valued at \$4500.<sup>2</sup> The post office location in the census identified as "Hart's Store." He is grouped with his wife Amelia, aged 45, and four children. At some point during the mid 1860s he relocated to property near Lakesville where he resided until his death. The Hart's Store and farm were acquired by Christopher C. Fallin around 1866, and in 1876, C. C. Fallin petitioned the county Orphan's Court for title to the land that he had purchased ten years earlier for \$5,000.<sup>3</sup> It was likely during Christopher C. Fallin's ownership

<sup>1</sup> Dorchester County Land Record, ER 17/150, 10 January 1839, Dorchester County Courthouse, Ancestry.com.  
<sup>2</sup> Eighth Census of the United States, Population Schedule for Dorchester County, Ancestry.com.  
<sup>3</sup> Dorchester County Land Record, FJH 11/157, 26 June 1876, Dorchester County Courthouse, Cambridge, Maryland.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 8 Page 1

of the farm that the Victorian addition was built with the orientation of the house changed to face the county road. The farm remained in Fallin family ownership until the early twentieth century.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 8 Page 2

---

George Hart Farmhouse  
Bishops Head Road  
Bishops Head, Dorchester County, Maryland

Map 108, Parcel 173

202/400

Barbara A. Stafford

to

10.21.1977

Stephen F. Crum and Sharon Reynolds

PLC 200/662

Jerry L. Cumberland, et al

to

6.2.1977

Barbara A. Stafford

PLC 189/590

Gladys C. Andrews

to

4.26.1975

Jerry L. Cumberland

PLC 138/66

Mary F. Parry, widow

to

5.11.1964

W. Emmett Andrews

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
**Continuation Sheet**

Number 8 Page 3

---

RSM 55/64

Virginia Sallac and Harry Sallac

to

5/1/1945

George Parry and Mary F. Parry, City of Philadelphia

RSM 47/559

Frederick E. Ruark and Ella G. Ruark

to

8.2.1943

Virginia Sallac and Harry Sallac

Mortgage  
JFD 33/613

County Trust Company of Maryland

to

12.30.1933

Frederick E. Ruark and wife

WLR 4/529

Emerson C. Harrington, et al.

to

5.28.1912

Frederick E. Ruark

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
**Continuation Sheet**

Number 8 Page 4

---

Mortgage  
CL 18/376

Emerson C. Harrington

to

7.3.1907

Angie Fallin

1877

Lake, Griffing and Stevenson Atlas

C. C. Fallin

FJH 11/157

Amelia M. Hart, Administratrix of George Hart, deceased

to

6.26.1876

Christopher C. Fallin

168 acres

Administratrix, Amelia M. Hart

Chancery Case No. 66

To the honorable Judges of the Orphan's Court for Dorchester County, The petition of Christopher C. Fallin of Dorchester County humbly shows that sometime about the year 1866 your petitioner purchased of a certain George Heart (sic) of said County, a farm or tract of land with a storehouse thereon, situated on Fox Creek in Strait's Election District; being the farm and premises whereon your petitioner now resides, paying the said Hart the sum of \$5,000

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 8 Page 5

---

- 1870 Census George Hart, "Lakeville"  
George Hart, 77, Farmer, Value of Real Estate, \$3900, P.P. \$750
- 1860 Census George Hart, "Hart's Store" Post Office  
George Hart, 68, Merchant, Value of Real Estate \$2500, P.P. \$2000  
Amelia Hart, 45  
George, 30, Merch., Clerk  
Priscilla, 29  
Maria, 17  
George ?, 14
- 1839 George Hart is cited as one of the trustees of St. Thomas M. E. Church
- ER 16/471 Henry Page  
to
- 4.16.1838 George Hart  
Estate settlement of Robert Hart, Decree of Circuit Court bearing date 12.31.1835; Henry Page was appointed trustee to sell and dispose of to the above named George Hart, part of a tract of land called "Hart's Forest," containing 45 acres and 1/2 acre being a vacancy adjoining "Gootee's Lot" and called Vacancy No. 1 at the price of \$20; And also on the 19<sup>th</sup> day of March 1835 did sell to the said George Hart a tract of land called "Addition to Dove Park," containing eleven acres and "Outlet" containing ten acres...

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
**Continuation Sheet**

Number 8 Page 6

---

ER 13/343

Henry Moore and wife Sally

to

5.30.1833

George Hart

\$55.00 mentions property bordering Fox Creek 14 acres

## 9. Major Bibliographical References

Inventory No. D-30

Dorchester County Land Records, various volumes, Dorchester County Courthouse, Cambridge.

Graham, John L., ed. *The 1877 Atlases and Other Early Maps of the Eastern Shore of Maryland*, Wicomico Bicentennial Committee, 1976.

## 10. Geographical Data

Acreage of surveyed property 1 acre

Acreage of historical setting 168 acres

Quadrangle name Wingate, Maryland Quadrangle Quadrangle scale: 1:24,000

### Verbal boundary description and justification

The metes and bounds of this property are coincidental with the current boundary of the lot.

## 11. Form Prepared by

name/title	Paul B. Touart, Architectural Historian		
organization	Private Consultant	date	10.4.2013
street & number	P. O. Box 5	telephone	410-651-1094
city or town	Westover	state	Maryland 21871

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.


return to: Maryland Historical Trust  
DHCD/DHCP  
100 Community Place  
Crownsville, MD 21032-2023  
410-514-7600

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 1




D-30, George Hart Farmhouse  
Mouth of Honga River and Hooper's  
Straits, U.S. Coast Survey, 1848

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 2




# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 3



# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 4



D-30, George Hart Farmhouse, Bishops Head, Dorchester County, west elevation, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
**Continuation Sheet**

Number 9 Page 5

---



D-30, George Hart Farmhouse, Bishops Head, southwest elevation, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 6



D-30, George Hart Farmhouse, Bishops Head, south elevation, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
**Continuation Sheet**

Number 9 Page 7



D-30, George Hart Farmhouse, Bishops Head, east elevation, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 8



D-30, George Hart Farmhouse, Bishops Head, ovolo backband window surround with HL shutter hinges, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 9



D-30, George Hart Farmhouse, Federal mantel and wall paneling, Bishops Head, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 10



D-30, George Hart Farmhouse, Bishops Head, Federal mantel detail, Paul Baker  
Touart, 10.2-13.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 11



D-30, George Hart Farmhouse, Bishops Head, Federal mantel detail with wall paneling and board ceiling, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 12



D-30, George Hart Farmhouse, Bishops Head, Federal wall paneling,  
Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 13




D-30, George Hart Farmhouse, Bishops Head, six-panel door into dining room, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 14



D-30, George Hart Farmhouse, Bishops Head, Victorian staircase, Paul Baker  
Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 15



D-30, George Hart Farmhouse, Bishops Head, dining room with exposed joist ceiling and raised-panel cupboards and board walls, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 16



D-30, George Hart Farmhouse, Bishops Head, raised-panel cupboard, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
**Continuation Sheet**

Number 9 Page 17




D-30, George Hart Farmhouse, Bishops Head, six-panel kitchen door, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 18



D-30, George Hart Farmhouse, Bishops Head, kitchen with enclosed stair, exposed joist ceiling, and board walls, Paul Baker Touart, 10.2013.

**Maryland Historical Trust  
Maryland Inventory of  
Historic Properties Form**

Inventory No. D-30

Name George Hart Farmhouse  
**Continuation Sheet**

Number 9 Page 19



D-30, George Hart Farmhouse, Bishops Head, vertical board partition and board-and-batten door, Paul Baker Touart, photographer.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 20



D-30, George Hart Farmhouse, Bishops Head, exposed series of steps outside boxed stair, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 21



D-30, George Hart Farmhouse, loft with original weatherboards on north gable end of main house, Paul Baker Touart, 10.2013.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form


Inventory No. D-30

Name George Hart Farmhouse  
Continuation Sheet

Number 9 Page 22



D-30, George Hart Farmhouse, Bishops Head, second floor chamber mantel, Paul Baker Touart, 10.2013.





D-30, George Hart Farmhouse  
Wingate, Md Quadrangle, 1982

'04 1 060 000 FEET '05 5' '06 '07 BLOODWORTH ISLAND) '08  
5760 II NE

SCALE 1:24 000

Survey







D-30

GEORGE HUNT FARMHOUSE

BISHOPS HEAR, DONCASTER CO., MD.

WEST ELEVATION

10, 2013, PAUL B. TOWNT, PHOTO.

NE. / MD. HISTORICAL TRUST

# 1 of 19



D-30

GEORGE HART FREMONTSE

BISITORS HEAD, DORCHESTER C. MD.

SOUTHWEST ELEVATION

10. 2013, PAUL B. TOWANT, PITTS.

NEE/MD. HISTORICAL TRUST

#2 OF 19



D-30

GEORGE HART FARMHOUSE  
BISHOPS HEAD, DORCHESTER CO, MD  
SOUTH ELEVATION

10.2013, PAUL B. TOWART, PHOTOGRAPHER  
NEB./MD. HISTORICAL TRUST

#3 of 19



D-30

GEORGE HART FARMHOUSE

BISHOPS HEAD, DOACHESTER G. MD.

EAST ELEVATION

10.2013, PAUL R. TOWART, PITTSO.

NEB. / MD. HISTORICAL TRUST

#4 OF 19



D-30

GEORGE HART FARMHOUSE  
BISHOPS HEAD, DORCHESTER  
CO., MD.

EAST ELEVATION WINDOW  
WITH OLD MOLDED BACK  
BOARD AND 1 1/2 INCHES

10.2013, PAUL B. TONSET,  
PHOTO.

NEG./MD. HIST. TRUST

# 5 of 19



D-30

George Hart PARMHOUSE  
VISITORS HEAD, DONUTS  
C., MD.

GENERAL MANAGER DETAIL  
10.2013, Paul B. Touart,  
N.E. 1st. Trust

# 6 OF 19



D-50

George Hart Furniture  
Bishops Items, Dorchester  
Co., MD

Federal MASTER DETAIL  
10.2013, Paul B. Touart  
N.W. 1st St. Trust

#7 of 19



40

EROSUN

BY TOYOTOMI

D-30

George Hart Farmhouse  
Bishops Head, Durdentester  
Co., MD.

George Hart and  
Pawling

10.2013, Paul B. Touret,  
Pittsburgh

Not. and Hist. Trust



D-30

GEORGE HART FARMHOUSE  
BRISTOLS ITEM, DOMESTICA  
CO., MD.

GENERAL MANTLE P

MAN POWERING

10.2013, PAUL B. TOUANT,  
PHOTO

W.F.J. MD. HIST. TRUST

#9 OF 19



D-30

GEORGE STANT FARMHOUSE  
BISHOPS HEAD, DORCHESTER  
W., MD.

6-PANEL ROOM & FEDERAL  
WALL PANELING

10.2013, PAUL D. TOUANT,

PHOTOGRAPHER

NEG./MD. HIST. TRUST

#10 OF 19



D-30

George Hart Krautwiese  
Bisittes Head, Donchester  
W. MD.

Victorian ad stain

10. 2013, Paul B. Towant,  
Pilot.

W. MD. Hist. Traps

# 11 of 19



D-30

GEORGE WART PARMITOUSE

BISITORS 1 TENN, DOACITESTON G., MD.

DINING ROOM WITH BUILT-IN CUPBOARD

10, 2013, PAUL B. TOWNAT, PITTSV.

NW. / MD. HISTORICAL TRUST

#12 OF 19



D-30

GEORGE HART FARMHOUSE  
BISHOPS HEAD,  
DORCHESTER C., MD.

DINING ROOM (UPWARD)  
10. 2013, PAUL B. TOWART,  
PHOTO,  
NEB./MD HIST. TRUST

# 13 OF 19



D-30

GEORGE HART PARLITONSE  
BISITORS HEND, DRAUTER

U. M.D.

FEDERAL 6-PANEL BOOK

10. 2012, PAUL B. TONANT,

PITTY.

WEG / M.D. HISE TRUST

#14 of 19



D-30

GEORGE HART FARMHOUSE  
BISHOPS HEAD, DURHAM

KILCUTEN-WITTENABITEN <sup>C. MD.</sup>  
INTERIOR WITH ENCLOSED  
STAIR

10. 2013, PAUL B. TOWANT,

W. 7. / MD. 1st. <sup>PITTY.</sup> TRUST

#15 of 19



D-30

GEORGE HART KEMITOUSE

VISITORS HENR, DONUTESTER, CO. NO.

KITCHEN STAIR

10.2013, PAUL B. TOWERS, PITON.

WASH. MD. HISTORICAL TRUST

#16 OF 19



D-30

GEORGE HART FRAMITENSE  
VISITORS HOME, DUMFRIES  
W, MD.

KITCHEN - WITH TEN VERTICAL  
VERTICAL BOARDS WALL  
AND EXPANDED CEILING  
JOISTS

10. 2013, Panel B. Tourist,  
PITTSBURGH

NEG. / MD. 1st. TRUSS

#17 OF 19



D-30

GEORGE HART FARMHOUSE

BISHOPS HEAD, DORCHESTER CO. MA

LOFT - NORTH END OF 2-STORY  
SECTION

10.2013, PAUL B. TOWART, PITOTV.

NEE. / NO. HISTORICAL TRUSS

#18 OF 19



D-30

GEORGE HART FARMHOUSE  
BISHOPS HEAD, DORCHESTER A. MD  
CHAMBER MANTEL  
10.2013, PAUL B. TOWART, PHOTO.  
W.F.H. / MD HISTORICAL TRUST

#19 OF 19

1000305304

MARYLAND HISTORICAL TRUST WORKSHEET

NOMINATION FORM  
for the  
NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

SEE INSTRUCTIONS

1. NAME				
COMMON: Ogle's House				
AND/OR HISTORIC:				
2. LOCATION				
STREET AND NUMBER: Bishop's Head Road at Fallins Creek (north)				
CITY OR TOWN: Wingate				
STATE: Maryland			COUNTY: Dorchester	
3. CLASSIFICATION				
CATEGORY (Check One)	OWNERSHIP		STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object <input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure 	<input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both	Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered	<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No
PRESENT USE (Check One or More as Appropriate)				
<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input checked="" type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify) _____	<input type="checkbox"/> Comments _____
4. OWNER OF PROPERTY				
OWNER'S NAME: Ogle Z. Jones				
STREET AND NUMBER: 201 N. Lynwood Avenue				
CITY OR TOWN: Baltimore			STATE: Maryland	21200
5. LOCATION OF LEGAL DESCRIPTION				
COURTHOUSE, REGISTRY OF DEEDS, ETC.: Dorchester County Courthouse				
STREET AND NUMBER: High Street				
CITY OR TOWN: Cambridge			STATE: Maryland	21613
Title Reference of Current Deed (Book & Pg. #): 138/143				
6. REPRESENTATION IN EXISTING SURVEYS				
TITLE OF SURVEY:				
DATE OF SURVEY: <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> County <input type="checkbox"/> Local				
DEPOSITORY FOR SURVEY RECORDS:				
STREET AND NUMBER:				
CITY OR TOWN:			STATE:	

7. DESCRIPTION

CONDITION	(Check One)				
	<input type="checkbox"/> Excellent	<input type="checkbox"/> Good	<input checked="" type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins
	(Check One)			(Check One)	
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site	

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

Ogle's House is an interesting combination of three periods, in the vernacular tradition, with a subsequent attempt at grandeur. The front of the house is a three bay long, late nineteenth century dwelling, with 2/2 sash and a gable in the center of the 'A' roof. It now has a piazza made by lengthening the turned posts of the original porch. On the southwest side is the remainder of the porch.

Behind the house and adjacent the porch is a two story, three bay long structure which appears to be earlier due to its tight composition and scale of the second story window. Nevertheless, this section received sash and eaves which match the front.

West of this section is probably the earliest part of the dwelling. Like the Woolford Farmhouse, this has two entrance doors with a single window on each side. On the steeply pitched 'A' roof are two dormers with 4/4 sash.

SEE INSTRUCTIONS

**B. SIGNIFICANCE**

**PERIOD (Check One or More as Appropriate)**

- Pre-Columbian                       16th Century                       18th Century                       20th Century
- 15th Century                       17th Century                       19th Century

**SPECIFIC DATE(S) (If Applicable and Known)**

**AREAS OF SIGNIFICANCE (Check One or More as Appropriate)**

- |  |  |   |  |
|--|--|---|--|
| <ul style="list-style-type: none"> <li>Aboriginal</li> <li><input type="checkbox"/> Prehistoric</li> <li><input type="checkbox"/> Historic</li> <li><input type="checkbox"/> Agriculture</li> <li><input checked="" type="checkbox"/> Architecture</li> <li><input type="checkbox"/> Art</li> <li><input type="checkbox"/> Commerce</li> <li><input type="checkbox"/> Communications</li> <li><input type="checkbox"/> Conservation</li> </ul> | <ul style="list-style-type: none"> <li><input type="checkbox"/> Education</li> <li><input type="checkbox"/> Engineering</li> <li><input type="checkbox"/> Industry</li> <li><input type="checkbox"/> Invention</li> <li><input type="checkbox"/> Landscape Architecture</li> <li><input type="checkbox"/> Literature</li> <li><input type="checkbox"/> Military</li> <li><input type="checkbox"/> Music</li> </ul> | <ul style="list-style-type: none"> <li><input type="checkbox"/> Political</li> <li><input type="checkbox"/> Religion/Philosophy</li> <li><input type="checkbox"/> Science</li> <li><input type="checkbox"/> Sculpture</li> <li><input type="checkbox"/> Social/Humanitarian</li> <li><input type="checkbox"/> Theater</li> <li><input type="checkbox"/> Transportation</li> </ul> | <ul style="list-style-type: none"> <li><input type="checkbox"/> Urban Planning</li> <li><input type="checkbox"/> Other (Specify)</li> <li>_____</li> <li>_____</li> <li>_____</li> <li>_____</li> <li>_____</li> </ul> |
|--|--|---|--|

**STATEMENT OF SIGNIFICANCE**

This house is included in this survey not because of the front portion of the house, but due to the fact that the rear of the building is older and is worthy of some attention to determine its original appearance and owner.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Empty box for Major Bibliographical References.

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreage Justification:

District 10, Tax Map 108, p. 73  
5 acres

SEE INSTRUCTIONS

11. FORM PREPARED BY

NAME AND TITLE: Michael Bourne, Architectural Consultant		
ORGANIZATION Maryland Historical Trust	DATE Nov. 1975	
STREET AND NUMBER: Shaw House, 21 State Circle		
CITY OR TOWN: Annapolis	STATE Maryland	21401

12. State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National  State  Local

\_\_\_\_\_  
Signature

20x1.24

75%

D-30



Ogle House

D-30

M. Bourne Nov 1975