

D-37
Elsing
Woolford vicinity
c. 1725-50, c. 1825
Private

Built on the south shore of Church Creek a short distance west of the historic Trinity Church is a story-and-a-half, part brick, part frame dwelling dating from the eighteenth and nineteenth centuries. The earliest portions of the house are framed by a pair of brick chimneys; the western half was clearly erected during the second quarter of the eighteenth century, while the eastern half, executed in timber frame sheathed with beaded weatherboards, is datable to the first quarter of the nineteenth century. A third section of the story-and-a-half main block was added during the early to mid nineteenth century. Twentieth century modifications include a rear kitchen wing. The house is one of oldest surviving dwellings remaining on the south shore of Church Creek.

While the eighteenth century land ownership of this property is undocumented, the property was for a long time part of the land holdings of John Crawford (1778-1852) and his son William Wallace Crawford (1813-1886). John Crawford is found in the 1850 U.S. Census as a very wealthy Dorchester farmer with \$10,000 in real estate. His son, William Wallace Crawford, inherited the farm from his father, and he is designated as a in the census as a 37-year old merchant and is grouped in the census with his wife Hester. Also in their household was a John Richardson, aged 18, and John and Ally Cornish, negro laborers. Twenty two years later, William W. Crawford is designated on the Lake, Griffing, and Stevenson atlas printed in 1877, and he is included in the atlas patron list as a "farmer," aged 64. The farm bordering the county road and Church Creek was sold by

Frederick Crawford to Julian Woolford in 1912, who transferred it five years later to Joseph W. Bradshaw. Later in the mid twentieth century it was held by Etta B. Bramble and her husband Laird V. Bramble, and after 1955, by the Vestry of Trinity Church, which used it as a rectory. The Vestry of Trinity Church and Dorchester Parish held title to the property until 1964 when it was transferred to Milton A. Noon, Jr.

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-37

1. Name of Property (indicate preferred name)

historic Elsing
other John Crawford House

2. Location

street and number 1654 Taylor's Island Road not for publication
city, town Cambridge vicinity
county Dorchester

3. Owner of Property (give names and mailing addresses of all owner)

name Eleanor N. Triplett
street and number 464 Holly Farms Road telephone
city, town Severna Park state MD zip code 21146

4. Location of Legal Description

courthouse, registry of deeds, etc. Dorchester County Clerk of Court liber MLB 760 folio 343
city, town Cambridge tax map 51 tax parcel 105 tax ID number 9-198296

5. Primary Location of Additional Data

- Contributing Resource in National Register District
- Contributing Resource in Local Historic District
- Determined Eligible for the National Register/Maryland Register
- Determined Ineligible for the National Register/Maryland Register
- Recorded by HABS/HAER
- Historic Structure Report or Research Report at MHT
- Other:

6. Classification

Category	Ownership	Current Function		Resource Count	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture	<input type="checkbox"/> landscape	Contributing	Noncontributing
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	<input type="checkbox"/> recreation/culture	<u>1</u>	<input type="checkbox"/> buildings
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	<input type="checkbox"/> religion	<input type="checkbox"/>	<input type="checkbox"/> sites
<input type="checkbox"/> site		<input checked="" type="checkbox"/> domestic	<input type="checkbox"/> social	<input type="checkbox"/>	<input type="checkbox"/> structures
<input type="checkbox"/> object		<input type="checkbox"/> education	<input type="checkbox"/> transportation	<input type="checkbox"/>	<input type="checkbox"/> objects
		<input type="checkbox"/> funerary	<input type="checkbox"/> work in progress	<u>1</u>	<input type="checkbox"/> Total
		<input type="checkbox"/> government	<input type="checkbox"/> unknown		
		<input type="checkbox"/> health care	<input type="checkbox"/> vacant/not in use		
		<input type="checkbox"/> industry	<input type="checkbox"/> other:		
				Number of Contributing Resources previously listed in the Inventory	

7. Description

Inventory No. D-37

Condition

excellent deteriorated
 good ruins
 fair altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

DESCRIPTION SUMMARY

The property historically known as Elsing is improved by a story-and-a-half part brick, part frame house largely dating from the period between 1725 and 1830. Situated near the head of Church Creek, the property is accessed by land with an address of 1654 Taylor's Island Road in Church Creek Election District, Dorchester County, Maryland. The brick section, although modified during the nineteenth century, appears to date to the second quarter of the eighteenth century, while a north end addition to the brick section was erected during the early nineteenth century. A rear one-and-a-half story kitchen wing was built during the early to mid twentieth century. The house is currently under another wave of restoration and rehabilitation.

GENERAL DESCRIPTION

The story-and-a-half, eighteenth century two-bay brick section is completely stuccoed, and a watertable does define the base of the two-room structure. The front (east) wall of the brick section is pierced by a pair of six-over-six sash windows. The front door as well as two additional six-over-six sash windows define the frame portion of the adjacent frame addition. A final room on the north end of the house was also added during the early nineteenth century. Supported on a low brick foundation, the historic sections are covered by a steeply pitched roof of asphalt shingles. The oldest portions of the house, the eighteenth century section, and the early nineteenth century addition, are framed by large interior end brick chimneys finished with corbelled caps. Defining the roof slope of the entire length of the house are four gable roofed dormers fitted with six-over-six sash windows and diagonal beaded board sides. The base of the roof is finished with a boxed cornice, and a gable roofed entry porch shelters the front door.

The south gable end of the brick section is stuccoed wall surface with a two-course beltcourse stretching across the mid-point of the wall. Two small windows light the upper floor, and the gable end is finished with a plain bargeboard.

The west (rear) wall of the eighteenth century section is fully covered by the mid twentieth century story-and-a-half kitchen wing, which is detailed in a manner similar to the rest of the house with a steeply pitched roof and gable roofed dormers with diagonal board sides. A single flue brick stack rises against the gable end, which is pierced by a single door opening and small attic windows.

The interiors have been opened up in the nineteenth century sections in the process of renovation and restoration, clearly repairing rotten framing members. A straight run staircase finished with early nineteenth century flat panels and a four-panel closet door rises against the gable end of the eighteenth century section. A six-panel door on the west wall of the eighteenth century section opens into the front room which has a corner fireplace framed by an early nineteenth century mantel and early nineteenth century chair rail. A middle raised-panel partition in this room may date to the mid eighteenth century,

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-37

Name Elsing
Continuation Sheet

Number 7 Page 1

and it is the partition wall that separates the front room from the kitchen. The early nineteenth century frame section retains portions of period finishes including vertical beaded board sheathing and a portion of a Federal mantel in the middle room. A layer of exterior beaded weatherboards is exposed in places between the two early nineteenth century sections, thereby indicating that the last section was added slightly later.

8. Significance

Inventory No. D-37

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input checked="" type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other: _____

Specific dates

Architect/Builder

Construction dates

Evaluation for:

National Register

Maryland Register

not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

SIGNIFICANCE SUMMARY

Built on the south shore of Church Creek a short distance west of historic Trinity Church, is a story-and-half, part brick, part frame dwelling dating from the eighteenth and nineteenth centuries. The earlier portions dwelling are framed by a pair of brick chimneys; the western half was clearly erected during the second quarter of the eighteenth century, while the eastern half, executed in timber frame, is datable to the first quarter of the nineteenth century. A third section in the story-and-a-half dwelling was added during the early to mid nineteenth century. Twentieth-century modifications include a rear kitchen wing. The house is one of the oldest surviving dwellings remaining on the southern shore of Church Creek.

HISTORY AND SUPPORT

While the eighteenth century land ownership of this property is still undocumented, the property was for a long time part of the land holdings of John Crawford (1778-1852) and his son William Wallace Crawford (1813-1886). John Crawford is found in the 1850 U.S. Census as a very wealthy Dorchester County farmer with \$10,000 worth of real estate. His son, William Wallace Crawford is designated as a 37-year old merchant and is grouped in the census with his wife Hester. Also in their household was a John Richardson, aged 18, and John and Ally Cornish, negro laborers.¹ Twenty two years later, William W. Crawford is designated at this location on the Lake, Griffing, and Stevenson atlas map printed in 1877, and he is included in the patron list as a "farmer," aged 64. The farm bordering the county road and Church Creek was sold by Frederick Crawford to Julian Woolford in 1912,² who sold it five years later to Joseph W. Bradshaw.³ Later in the mid twentieth century it was held by Etta B. Bramble and her husband Laird V. Bramble, and after 1955 by the Vestry of Trinity Church, which used the house as a

¹ Seventh Census of the United States, 1850, Dorchester County Population Schedule, ancestry.com.

² Dorchester County Land Record, WLR 5/269, 25 November 1912, Dorchester County Courthouse.

³ Dorchester County Land Record, WHM 3/723, 18 September 1917, Dorchester County Courthouse.

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-37

Name Elsing
Continuation Sheet

Number 8 Page 1

home for the rector.⁴ The Vestry of Trinity Church and Dorchester Parish held title to the property until 1964 when it was transferred to Milton A. Noon, Jr.⁵

⁴ Dorchester County Land Record, 96/518, 13 June 1955, Dorchester County Courthouse.

⁵ Dorchester County Land Record, PLC 140/276, 23 October 1964, Dorchester County Courthouse.

Maryland Historical Trust
Maryland Inventory of
Historic Properties Form

Inventory No. D-37

Name Elsing
Continuation Sheet

Number 8 Page 2

Elsing
1654 Taylor's Island Road
Church Creek vicinity, Dorchester County, Maryland

Map 51, Parcel 105

MLB 760/343 Carolyn Noon LeCompte and Eleanor Noon Triplett

to

9.26.2006 Eleanor Noon Triplett

326/371 Carolyn Noon LeCompte, Personal Representative of
Milton A. Noon, Jr.

to

9.28.1995 Carolyn Noon LeCompte and Eleanor Noon Triplett

PLC 140/276 Vestry of Dorchester Parish

to

10.23.1964 Milton A. Noon, Jr. and Lucille B. Noon, City of New Stanton, PA.

\$25,700 all that tract or parcel of land situate lying and being on the North side of the State Road leading from Cambridge to Taylor's Island, near the Village of Woolford, and which according to a Certificate of Survey, dated October 15, 1964, by J. R. McCrone, Jr. Inc.,

19.30 acres

Maryland Historical Trust
Maryland Inventory of
Historic Properties Form

Inventory No. D-37

Name Elsing
Continuation Sheet

Number 8 Page 3

96/518 Bernice Chrysler Garbish, Edgar William Garbish,

to

6.13.1955 Vestry of Trinity Church

15 acres

RSM 42/321 J. Will Bradshaw, widower, et al. (Mary B. Spicer, and L. Leon Spicer, her husband, Whereas by the codicil Number Two of the Last Will and Testament of Joseph W. Bradshaw, RPS 2/399

to

2.10.1941 Etta B. Bramble and Laird V. Bramble

All that tract or parcel of land situate, lying and being in Church Creek Election District, near the village of Woolford, and that part of the home farm of the late William F. Crawford which lies to the north of the county road leading from Church Creek to Woolfords and bounded on the south by the county road aforesaid, on the north by Church Creek, a branch of the Little Choptank River, on the East by the lands of the late Mrs. Sallie B. Dorsey and on the west by the lands of the late D. W. Newbury, being especially the same property which was conveyed to Frederick Crawford by Elizabeth Fooks and others, dated May 23rd 1893 and recorded in CL 17/466

Dorchester County
Will Book
RSM 42/321

Last Will and Testament of Joseph W. Bradshaw

to

Will Bradshaw

Maryland Historical Trust
Maryland Inventory of
Historic Properties Form

Inventory No. D-37

Name Elsing
Continuation Sheet

Number 8 Page 4

WHM 3/723

Julian R. Woolford, widower, Norfolk, Va.

to

9.18.1917

Joseph W. Bradshaw

WLR 5/269

Frederick Crawford

to

11.25.1912

Julian Woolford

CL 17/466

Elizabeth B. Fooks and Stephen J. Fooks, John M. Crawford, and Ida Crawford his wife, all of Baltimore City, Annie M. Graham, and James E. Graham of Caroline County, heirs at law of William W. Crawford

to

5.23.1893

Frederick Crawford

\$1216.26 "home farm of William W. Crawford"

all that tract or parcel of land situate in Church Creek Election District, and near the village of Woolford, Being all that part of the home farm of William W. Crawford, deceased, lying to the north of the county road Leading from Church Creek to Woolford

Maryland Historical Trust
Maryland Inventory of
Historic Properties Form

Inventory No. D-37

Name Elsing
Continuation Sheet

Number 8 Page 5

Dorchester County
Will Book
THH 1/82

Last Will and Testament of John Crawford

To, son William W. Crawford

Written
7.5.1842
Proved
9.6.1852

...my dwelling plantation on which I now reside which I purchased of Roger Jones known by the name of "Jones Range" containing about 100 acres, I do also give and devise unto him my said son William W. Crawford all that tract or parcel of land that I bought of Thomas Jones, "White Marsh" called Delia's Range...5 acres

William Wallace Crawford b. 10.25.1813, d. 2.28.1886

John Crawford (1778-1852)

9. Major Bibliographical References

Inventory No. D-37

Dorchester County Land Records, various volumes, Dorchester County Courthouse

10. Geographical Data

Acreage of surveyed property 2.10 acres

Acreage of historical setting _____

Quadrangle name Church Creek Quadrangle

Quadrangle scale: 1:24,000

Verbal boundary description and justification

The metes and bounds of this property are coincidental with the current boundary of the lot.

11. Form Prepared by

name/title	Paul B. Touart, Architectural Historian		
organization	Chesapeake Country Heritage & Preservation	date	10.15.2012
street & number	Cedar Hill, P. O. Box 5	telephone	410-651-1094
city or town	Westover	state	Maryland 21871

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.


return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville, MD 21032-2023
410-514-7600

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-37

Name Elsing
Continuation Sheet

Number 9 Page 1



SCALE 1:24 000

1 0.5 0 1000 2000
KILOMETERS
0 1000 2000
METERS
0 1 2
MILES
0 1000 2000 3000 4000 5000 6000 7000 8000 9000 10 000
FEET

CONTOUR INTERVAL 1 METER
NATIONAL GEODETIC VERTICAL DATUM OF 1929
CONTROL AND OTHER ELEVATIONS SHOWN TO THE NEAREST 0.1 METER
DEPTH CURVES AND SOUNDINGS IN METERS—DATUM IS MEAN LOW WATER
THE RELATIONSHIP BETWEEN THE TWO DATUMS IS VARIABLE
THE MEAN RANGE OF TIDE IS APPROXIMATELY 0.4 METERS

THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS
FOR SALE BY U. S. GEOLOGICAL SURVEY, RESTON, VIRGINIA 22092
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST




D-37, Elsing
Church Creek Quadrangle

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. D-37

Name Elsing
Continuation Sheet

Number 9 Page 2





D-37

ELSIING

WOOLFORD VIC, DORLITESTER C. MD.

SOUTHWEST ELEVATION

10.2012, PAUL B. TOWANT, PHOTO.

NEB./MD. HISTORICAL TRUST

#1 of 2



D-37

ELKING

WOLFEND VIC, DIRECTESTED C. M. N.

NORTH ELEVATION

10.2012, J. B. TOWNSEND, PITTSB.

OVER J. B. TOWNSEND TRUST

#2 OF 2

MARYLAND HISTORICAL TRUST WORKSHEET

NOMINATION FORM
for the
NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

SEE INSTRUCTIONS

1. NAME

COMMON:
Elsing
AND/OR HISTORIC:
Old House on Church Creek

2. LOCATION

STREET AND NUMBER:
Rt. 16, 1.2 miles west of Rt. 335
CITY OR TOWN:
Woolford
STATE: Maryland COUNTY: Dorchester

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP		STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object <input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure	<input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both	Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered	<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No
PRESENT USE (Check One or More as Appropriate)				
<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input checked="" type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify)	<input type="checkbox"/> Comments

4. OWNER OF PROPERTY

OWNER'S NAME:
Milton A. Noon Jr.
STREET AND NUMBER:
CITY OR TOWN: Woolford STATE: Maryland 21677

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:
Dorchester County Courthouse
STREET AND NUMBER:
High Street
CITY OR TOWN: Cambridge STATE: Maryland 21613
Title Reference of Current Deed (Book & Pg. #): 140/276

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:
DATE OF SURVEY: Federal State County Local
DEPOSITORY FOR SURVEY RECORDS:
STREET AND NUMBER:
CITY OR TOWN: STATE:

7. DESCRIPTION

CONDITION	(Check One)				
	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins
	(Check One)		(Check One)		
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site	

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

Along one of the small coves of Church Creek stands a house called Elsing, formerly known as Old House on Church Creek. It is a six bay long structure composed of one third brick and the other two thirds of frame. Along its steeply pitched roof are four dormers and onto the back of the brick portion a recent addition was constructed.

The earliest portion of the house is the brick west end. It is two bays long and two deep and has been stuccoed to deter the deterioration of the brick. In its gable are two small windows and a belt course at floor level. From the apex of the steep roof rises a tall chimney. Its facade now has two windows but it originally had a door and window like its back wall. There apparently was glazed Flemish bond brickwork on this side, although the stucco now conceals it. Its floor plan now consists of two rooms with diagonal fireplaces and a vertical board partition similar to the second story partitions in Carthegena. When the recent restoration was being undertaken, floor tiles were found beneath the wood framed floor which are similar in size and appearance to Trinity Church floor. These tiles were either the original floors or the hearth(s). In all likelihood, the building was constructed around 1700 as a single room with very large fireplace and was later remodeled, probably when the extensions were constructed.

The wing consists of a stair hall and living room and a kitchen wing which is now a den. From evidence in the attic and the bedroom floor, the den was originally narrower and lower, similar to most kitchen wings in the county. A large brick chimney serves the fireplace in both living room and den. Most of the woodwork throughout the house appears to date from the time the house received its extension. The one exception may be the paneling between the two smaller rooms of the brick part.

SEE INSTRUCTIONS

B. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- Pre-Columbian 16th Century 18th Century 20th Century
- 15th Century 17th Century 19th Century

SPECIFIC DATE(S) (If Applicable and Known)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|---|--|--|--|
| <input type="checkbox"/> Aboriginal
<input type="checkbox"/> Prehistoric
<input type="checkbox"/> Historic
<input type="checkbox"/> Agriculture
<input checked="" type="checkbox"/> Architecture
<input type="checkbox"/> Art
<input type="checkbox"/> Commerce
<input type="checkbox"/> Communications
<input type="checkbox"/> Conservation | <input type="checkbox"/> Education
<input type="checkbox"/> Engineering
<input type="checkbox"/> Industry
<input type="checkbox"/> Invention
<input type="checkbox"/> Landscape
<input type="checkbox"/> Architecture
<input type="checkbox"/> Literature
<input type="checkbox"/> Military
<input type="checkbox"/> Music | <input type="checkbox"/> Political
<input checked="" type="checkbox"/> Religion/Phi.
losophy
<input type="checkbox"/> Science
<input type="checkbox"/> Sculpture
<input type="checkbox"/> Social/Human-
itarian
<input type="checkbox"/> Theater
<input type="checkbox"/> Transportation | <input type="checkbox"/> Urban Planning
<input type="checkbox"/> Other (Specify)
<hr/> <hr/> <hr/> <hr/> <hr/> <hr/> |
|---|--|--|--|

STATEMENT OF SIGNIFICANCE

The house is a very handsome and well maintained structure. It is at least as early as the second quarter of the 18th century with the wing being added around 1800. Possibly the brick section dates back into the 17th century in which case it is the earliest house thus far located in Dorchester County. Because of the scarcity of early dwellings in Dorset, this house is one of the most important surviving dwellings.

Elsing was patented to James Busick in 1671. James Busick mentioned in his will of 1749 that the property on which Trinity Church was built was indeed theirs for as long as it is used for religious purposes.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Forman, H. C., Early Manor and Plantation Houses of Maryland, 1934, p. 170.

Laskowski Papers, 1955, p. 213.

Maryland, A Guide to the Old Line State, Oxford University Press, New York, 1941.

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreeage Justification:

District 9, Map 51, p. 105

SEE INSTRUCTIONS

11. FORM PREPARED BY

NAME AND TITLE: Michael Bourne, Architectural Consultant		
ORGANIZATION Maryland Historical Trust	DATE Nov, 1975	
STREET AND NUMBER: Shaw House, 21 State Circle		
CITY OR TOWN: Annapolis	STATE Maryland	21401

12. State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National State Local

Signature

2 SHOTS: Fig 2.3 @ 140% 10X1.59 (D-37) @ 50%

D37



D-37 Elsing

Milbourne Nov 1975