

F-3-112

Braddock Survey District
Frederick vicinity
Private

Ca. 1810-ca. 1915

The village of Braddock was established on the National Road turnpike as "Fair View" about 1810 with the construction of a tollhouse and a tavern, both now used as residences, and grew slowly through the 19th century, acquiring other transportation corridor structures such as blacksmith shops, stables, and other residences, as well as a schoolhouse in 1841 and a Lutheran and German Reformed church in 1859. The town reached its peak of growth about 1880-1885 with the building of the two largest houses, the John H. Williams House at 5519 and the Daniel Gibbons House at 5606 Old National Pike. Also about this period, the name was changed to Braddock and a post office was established in the tollhouse. The survey district includes about 15 acres on both sides of the old turnpike route. It is significant in community planning as a good example of a turnpike town with two of the key structures related to the transportation corridor intact in the tollhouse and the tavern. It is moderately significant for the architecture of its vernacular buildings, most of which have been altered by artificial siding and additions, and the two high style houses, the Queen Anne style Gibbons House and the Colonial Revival Williams House, which are good examples of the late 19th and early 20th century historical revivals. Under the name "Fair View", the village was mentioned by Oliver Wendell Holmes, Sr. in "My Hunt after 'The Captain'" (1862) in which his phrase regarding Frederick's "clustered spires" seen from Fair View may have been the inspiration of John G. Whittier's opening lines in the poem "Barbara Fritchie".

F-3-112
Braddock Survey District
Frederick
Frederick County

HISTORIC CONTEXT:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont
(Harford, Baltimore, Carroll, Frederick, Howard, Montgomery
Counties, and Baltimore City)

Chronological/Development Period:
Rural Agrarian Intensification, A.D. 1680-1815
Agricultural-Industrial Transition, A.D. 1815-1870
Industrial/Urban Dominance, A.D. 1870-1930

Prehistoric/Historic Period Themes
Architecture, Landscape Architecture and Community Planning
Economic (Commercial & Industrial)
Social/Educational/Cultural
Transportation

Resource Types:

Category: District

Historic Environment: Suburban

Historic Function and Use:
Domestic/single dwelling/residence
Domestic/single dwelling/mansion
Domestic/secondary structure/smokehouse
Domestic/hotel
Agriculture/subsistence/animal facility/barn
Education/school/schoolhouse
Religion/religious structure/church

Known Design Source: None

Maryland Historical Trust State Historic Sites Inventory Form

Magi No.

DOE yes no

1. Name (indicate preferred name)

historic Braddock Survey District; Fair View

and/or common

2. Location

street & number 5519-5707 Old National Pike not for publicationcity, town Frederick vicinity of congressional district 6th

state Maryland county Frederick

3. Classification

Category	Ownership	Status	Present Use	
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	<input checked="" type="checkbox"/> other: social

4. Owner of Property (give names and mailing addresses of all owners)

name See Section 7

street & number telephone no.:

city, town state and zip code

5. Location of Legal Description

courthouse, registry of deeds, etc. Frederick County Courthouse liber

street & number 100 W. Patrick Street folio

city, town Frederick state Md. 21701

6. Representation in Existing Historical Surveys

title

date federal state county local

depository for survey records

city, town state

7. Description

Survey No. F-3-112

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

CONTRIBUTING RESOURCE COUNT: 33

The Braddock Survey District encompasses approximately 15 acres on the north and south sides of Old National Pike (U.S. 40A) immediately west of Blentlinger Road, the center of the village of Braddock (sometimes called Old Braddock, and originally named Fair View) which developed on the National Road turnpike from about 1806 to the first quarter of the 20th century just west of Frederick (City), Frederick County, Maryland. The survey district adjoins a section of the current Frederick (City) boundary at Blentlinger Road. The district is currently principally residential, with one working farmstead and one residence with associated horse barns and pastures within the survey district boundary, which includes 12 residences and one stone grange hall, a former church building. One of the residences was originally built as a school, one was a toll house on the National Road turnpike, and one was originally a hotel or tavern. The buildings are fully occupied except the grange hall, which is used intermittently for grange and community meetings, and the general condition of the buildings is good.

The survey district is linear in form, consisting of buildings closely built along the early 19th century National Road turnpike route running east-west across Frederick County. The houses are more evenly spaced on the south side of the road than on the north, and the two easternmost buildings, 5630 and 5707 Old National Pike, are somewhat isolated from the rest of the district by open fields and woode areas. Surrounding the district are suburban mid-20th century developments along the Old National Pike to the west, farmland on the south, with access roads to the farmstead clusters running off the main road bracketing the survey district boundary. On the north is a small area of farmland wedged between the two highway routes, U.S. 40 and U.S. 40A (Old National Pike), part of the property of 5526 and 5620 Old National Pike.

The building materials evident in the Braddock Survey District include stone, brick, log, and frame, with standing seam metal, modern composition, and slate roofs. Most exteriors have been altered with artificial siding and additions. Front and rear wing porches are common. Two-story heights are the most common, although the former schoolhouse, built as one story, has been altered with the addition of a half story as well as other additions and the two largest dwellings, at 5519 and 5606 Old National Pike, have 2-1/2 stories. Braddock's buildings are principally vernacular in style, although the dwelling at 5606 is in the Queen Anne style of the late 19th and early 20th century and the house at 5519 is a large Colonial Revival mansion built possibly beginning in the 1880's with later additions about 1912-1915. Most of the dwellings have associated outbuildings including small domestic structures such as former summer kitchens and smokehouses, and several have garages built from about 1920 into the 1980's. At least three barns are included, ranging in date from about 1850 to about 1915. The working farm at 5620 Old National Pike also has several other agricultural outbuildings including a silo and frame sheds for equipment and animal shelters.

(Continued on separate sheet)

8. Significance

Survey No. F-3-112

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input checked="" type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input checked="" type="checkbox"/> education	<input type="checkbox"/> military	<input checked="" type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input checked="" type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates C. 1810 - C. 1915 **Builder/Architect**

check: Applicable Criteria: A B C D
and/or
Applicable Exception: A B C D E F G

Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

The Braddock Survey District is significant for its early and mid-19th century character as an early settlement on the National Road turnpike, laid out through the area just west of Frederick during the period about 1806 - 1810. The linearity of its form, with buildings closely sited on both sides of the road, backed by farmland, and intersected by a secondary road (now Blentlinger Road) are similar to that of most of the other towns and villages along the route of the National Road through Frederick County. The principal structures which mark it as a turnpike town are the former tavern at 5707 Old National Pike and the former tollhouse at 5617 Old National Pike, both of which are now residences. The tavern had several outbuildings related to the transportation corridor which are no longer standing, including a stable and a blacksmith shop. The tavern and tollhouse were probably built in the first decade of the 19th century, shortly after the National Road was built through the central part of Frederick County. Braddock was originally named Fair View. Growth was slow through the rest of the 19th century, reaching a peak about 1880 when the post office of Braddock was established. At that point the principal structures in the village were the Lutheran and German Reformed Church (now the Braddock Grange No. 365) of 1859, the schoolhouse of about 1841 (converted to a residence in about 1928), and the tollhouse which continued as a combined transportation structure, residence, and post office. Two of the largest and most architecturally elaborate houses were built about this period, the John H. Williams House at 5519 Old National Pike and the Daniel Gibbons House at 5606. These were the last major constructions in the survey district until 1908, when a second church was built by the Lutheran congregation. This church was moved to another location outside the district in 1974.

In addition to the town planning and transportation significance of Braddock, the architecture of the buildings is indicative of the period 1810 to about 1912. The majority of the buildings are in the vernacular style, with stone, log, brick, and frame materials. Most have been altered, principally in exterior coverings and rear additions. The two most architecturally sophisticated buildings are the Queen Anne style Daniel Gibbons House, a good representative of the style in the context of Frederick County, and the John H. Williams House, a good example of the Colonial Revival style. In comparison with other turnpike towns, such as Middletown, Libertytown, Jefferson, and Woodsboro, Braddock is much smaller in size and thus does not have the variety of structures found elsewhere. Considerable alteration

(Continued on separate sheet)

9. Major Bibliographical References

Survey No. F-3-112

Bond, Isaac. Map of Frederick County, 1858.

Hooper, Anne B. Braddock Heights: A Glance Backwards. Privately published, 1974, p. 67.

Land Records of Frederick County

(Continued on separate sheet)

10. Geographical Data

Acreeage of nominated property 15

Quadrangle name Frederick, Md.

Quadrangle scale 1:24000

UTM References do NOT complete UTM references

A	<input type="checkbox"/>								
	Zone	Easting	Northing						

B	<input type="checkbox"/>								
	Zone	Easting	Northing						

C	<input type="checkbox"/>								
---	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------

D	<input type="checkbox"/>								
---	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------

E	<input type="checkbox"/>								
---	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------

F	<input type="checkbox"/>								
---	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------

G	<input type="checkbox"/>								
---	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------

H	<input type="checkbox"/>								
---	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------	--------------------------

Verbal boundary description and justification

Approx imately 15 acres as shown enclosed by dark line on attached quad map section.

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
state	code	county	code

11. Form Prepared By

name/title Janet L. Davis, Historic Sites Surveyor

organization Frederick County Planning & Zoning Dept. date January 1993

street & number 12 E. Church Street telephone 696-2958

city or town Frederick state Maryland 21701

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

MARYLAND HISTORICAL TRUST
DHCP/DHCL
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2023
514-7400

7.1 Description

Following are brief descriptions of the buildings in the district:

5526 Old National Pike, Helen Smith House: The 1-1/2 story house has the general appearance of a log house with german siding, but is in fact of frame construction, placing it in date about 1870-1875. Title research indicates that a structure probably existed on the site as early as 1821 when the property was owned by John and Barbara Fritchie. Barbara Fritchie later achieved fame as the alleged heroine of Frederick's invasion by Confederate forces in 1862, immortalized in John G. Whittier's poem "The Ballad of Barbara Fritchie". Miss Helen Smith, the owner since 1940, believes that the earlier structure was replaced by the present building, which closely resembles vernacular log houses of the early and mid-19th century. The south elevation has three bays with a center entrance framed by a mid-20th century Georgian style pedimented surround. The windows are 6/6 with paneled shutters on the first story and the windows at the half-story level are paired 2/2. The east and west elevations have two bays each, with louvred shutters. The composition roof has interior end chimneys. A two-story rear wing extends from the northwest corner. The wing has a two-level open porch and an exterior stone and brick chimney on the north elevation. The interior of the house is notable for the floral painted walls and wood trim, the work of Miss Smith, who has been a noted artist in the Mid-Atlantic region since the mid-1920's. The former summer kitchen located east of the house is currently used by Miss Smith as a studio. The rectangular frame building has german siding and a composition gable roof. An interior brick chimney is located on the north elevation. A modern bay window is in the east gable end and 6/6 windows are on the south and west elevations. A vertical board door is also in the west elevation. A small frame garage is located north of the house. It has vertical board siding with a tongue-and-groove swing door. The gable roof is corrugated metal. Owner: Miss Helen Smith, 5526 Old National Pike, Frederick, MD 21701.

5519 Old National Pike, "Highland Lodge": This is a large frame Colonial Revival mansion with associated outbuildings built about 1881 with probable additions made about 1912-1915 which is set back from the south side of the road at the end of a circular driveway flanked at its entrance by stone pillars, an iron gate, and a stone fence. The main house is a 2-1/2 story structure with five bays on the north elevation. The center bay projects and has a cross gable at the roofline. The exterior is covered with german siding and a one-story veranda extends across the north elevation. The window and door openings have segmental arches and 2/2 sash flanked by louvred shutters. The gable roof appears to be slate and has five dormers on the north elevation. Interior chimneys rise above each side of the center gable junction. The porch has fluted columns with composition capitals, a dentil molding, and a Chippendale style railing on its flat roof. The entrance has a fanlight and sidelights. A one-story polygonal bay is located on the west elevation and a two-story, flat-roofed addition adjoins the main section on the east. A two-story rear wing extends from the south elevation. The outbuildings include a one-story log building with a modern porch and three bays on the west elevation. The building is located northeast of the dwelling

7.2 Description (Continued)

and was apparently built in the early or mid-19th century. It has been considerably restored and may have been moved to the present site from another part of the property or from another farm. East of the house are a frame carriage house now used as a garage, with a hipped standing seam metal roof with a central cupola. Three lift-type modern doors are in the north elevation. The exterior has german siding. East of the garage is a stable with german siding, sliding tongue-and-groove doors, and a cross-gabled composition roof. Both of these buildings appear to date from about 1912. South of the house are a frame privy with vertical siding and a shed corrugated roof, and a square plan frame smokehouse with german siding and a composition hipped roof. These also appear to be of the early 20th century period. South of the garage and stable are a circa 1912 barn with tongue-and-groove siding and sliding doors on the west elevation and a corn crib on the north elevation. The roof is corrugated metal. A non-contributing modern shed is located between the stable and the barn. A two-story tenant house, possibly with some log structure, is located at some distance south of the main dwelling and outbuildings. This structure may have been built about 1840-1860 and may be one of the original farmhouses on the land which became the present property, which was a consolidation of purchases by John H. Williams in 1881 from two farms adjoining Braddock. It has asbestos shingle siding and additions on the east and west gable ends. The roof is standing seam metal and the sash is 1/1. A one-story porch extends across the north elevation. John H. Williams was a prominent banker, the president of the Frederick County National Bank from 1867 until his death in 1894. The house was his summer residence and was one of two late 19th century estates cited in Braddock in the 1887 compilation of the post offices of Frederick County by Charles W. Miller. The name "Highland Lodge" was apparently given to the property under the ownership of Casper E. Cline, a prosperous furniture merchant in Frederick, who also probably made several additions to the outbuildings and to the main building in about 1912-1915.

Braddock Grange No. 365 (German Reformed & Evangelical Lutheran Church): The stone one-story building originally built in 1859 according to land records and a dated stone in the structure was used by the German Reformed and Evangelical Lutheran congregations in the Braddock vicinity with pastors provided by the Frederick churches of each denomination. In 1908, the Evangelical Lutheran Church sold its interest to the Braddock Reformed Church and built their own building just west of 5707 Old National Pike. It was moved in 1974 to North Clifton Road (see F-3-107). In 1920, the Braddock Reformed Church was merged with Frederick's congregation and the building was sold to the Braddock Grange No. 365. It has remained in occasional use by the Grange and community groups from 1920 to the present. The building is a rectangular structure with random field stone walls and a projecting foyer on the south elevation. The south elevation and the foyer are plastered and scored, while the other elevations reveal the stonework. The foyer has Gothic arched windows in its sides and a shingled gable above the double 6-panel doors with a fanlight. The east and west elevations have three bays with round-arched windows. The sash is 2/2 with colored glass and tracery in the upper frames. The arches are brick. The roof is covered with corrugated metal and the cornice is boxed. A plastered

7.3 Description (Continued)

exterior chimney is located on the north elevation and a second door is located in the north bay on the east elevation. A dated brownstone block inscribed "1859" is located at the southeast corner.

5605 Old National Pike: This is a two-story log or frame dwelling with a center cross gable in the north elevation. The three-bay elevation is crossed by a one-story porch with Tuscan columns. The exterior is covered with vinyl siding and the roof is standing seam metal. The windows are 2/2 with replacement shutters. Interior end chimneys are located on the east and west gable ends. A two-story rear wing extends to the south; it has both 6/6 and 2/2 sash and a side entrance on the west elevation. A non-contributing concrete block garage is located southwest of the house. Based on its general architectural form and details and land records, the date of construction is estimated at about 1840-1865, although the deeds indicate that a structure may have existed on the site since about 1825. This structure may be concealed within the current exterior details.

5606 Old National Pike, Daniel Gibbons House: The 2-1/2 story frame Queen Anne style house was possibly built about 1885-1890 by Daniel Gibbons, according to land records. The german sided house has a generally square plan with a cross gable roof covered with composition material. The gables are faced with patterned shingles and a Palladian-inspired window is located in the south gable on the principal elevation. The eaves are extended with exposed rafters. The south elevation has a wide veranda with fluted columns and a plain railing. The windows are paired 1/1 flanking a center entrance with a plain transom and sidelights. A two-story vinyl covered rear addition has been built on the north elevation. A polygonal bay window is located on the east elevation. A small frame garage with german siding and a composition roof is located northwest of the house. It has folding doors on the south elevation.

5607 Old National Pike: The two-story dwelling may have been built about 1840-1860, based on its architectural details and land records. It has vinyl siding, but may be a log structure. The gable roof is covered with standing seam metal and an interior end chimney is located on the east elevation. The north elevation has three bays with a center entrance with a 4-panel door. A one-story porch on this facade has turned columns and brackets. The sash is 2/2 with louvred shutters. A two-story rear wing extends from the south elevation, with some modern alterations in the windows and an exterior brick chimney. A square plan brick smokehouse is located just south of the rear wing. It has a composition hipped roof over wood shingles and a vertical board door in the east elevation.

5609 Old National Pike: This dwelling appears to have been greatly altered during both the late 19th century and the mid and late 20th century. It is a two-story brick house with a mansard roof covered with composition material. Clear bay definitions have been obscured by a two-story porch on the north elevation with an enclosed second story level covered with T-111 siding and modern aluminum 1/1 sash. Below the enclosure, the north elevation appears to be stone covered with plaster. Dormers are in the north and south slopes of

7.4 Description (Continued)

the mansard. The cornice visible below the mansard is corbeled brick. A one-story porch on the rear elevation is enclosed with screens. An interior chimney is located on the east elevation. A two-story frame garage with tongue-and-groove siding may have been built in the early 20th century as a stable or barn. It has a german sided shed addition on the west elevation and a corrugated metal roof.

5613 Old National Pike, Fair View School House: The former school was converted to a residence about 1928 when the school was consolidated with Frederick city schools. Built about 1840 according to land records, the school house was originally a one-story brick structure with a stone section adjoining it on the south elevation, with a gable facade facing north toward the turnpike. It is set back about 100 feet from the road. The building has been considerably altered over the years from 1928 to the present, with relocated doors and windows and additions on the east and west elevations. The exterior is painted white and a corbeled brick cornice is visible on the east and west elevations. A half-story was added to the building after 1928 and windows and door openings in the north elevation are functionally placed incorporating this change. A one-story porch is attached to the east elevation. Two interior chimneys rise on the west elevation. The one-story stone section may be the oldest section, built possibly in 1840, with the brick section added in the 1850's, as the brickwork and proportions are similar to other County schools of that period. A frame garage with a standing seam metal roof and german siding is located south of the school; it was probably built in the 1930's.

5620 Old National Pike: The two-story log or frame dwelling is located on the north side of the road and has several frame, metal, and other types of agricultural outbuildings arranged around the northern side of the house. The house has asbestos shingle siding and a one-story porch with turned columns, brackets, and a scroll-sawn railing on the south elevation. The three-bay elevation has 2/2 windows with louvred shutters. The roof is standing seam metal. A two-story rear wing on the north has an enclosed two-story porch on the east elevation and a modern bay window on the west side. The agricultural outbuildings include a brick smokehouse, a frame bank barn, and several frame, concrete block, and metal sheds. The house may date from about 1840-1850 based on its architectural details, although land records suggest that a structure may have existed as early as 1830. A blacksmith shop, no longer extant, is shown on the 1858 and 1873 maps located east of the house. This is the only active farm in the survey district, although horses are kept at 5519 Old National Pike.

5617 Old National Pike, former toll house: The two-story dwelling is identified on the 1858 and 1873 maps and by Mrs. Grace Summers Stone, a native of Braddock, as the former toll house on the National Road. This may indicate that the earliest part of the building may date from about 1810, although land records are unclear on its early history. It is possibly log under the current pressboard siding and has been much altered over many years. Brick faces the foundation on the main section and the roof is covered with composition. The main entrance has been relocated to the west elevation and is sheltered by an

7.5 Description (Continued)

entry porch. The north elevation has 6/6 sash and louvred shutters. Interior end chimneys are located on the east and west elevations. A two-story rear wing extends to the south and has replacement shutters. A frame garage with german siding and a standing seam metal roof is located south of the house. It had modern paired 1/1 windows and shutters on the north elevation, but the stone foundation indicates that it may be a late 19th century structure in its original form. In the 1880's, a post office was established in Braddock and the gatekeeper on the toll road, Daniel Grumbine, was designated as the postmaster.

5627 Old National Pike: The two-story, two-section house has been greatly altered, but may have at least one log section on the west. This part has asbestos shingle siding and two bays with 6/6 sash on the second story. The eastern section's facade is slightly recessed with a one-story porch with brackets and dentil moldings. It also has asbestos shingle siding, but with 2/2 sash. The roof of both sections is standing seam metal. An interior chimney is located on the west elevation and a modern exterior chimney is on the east elevation. A frame and concrete block outbuilding with a corrugated roof is located southeast of the house. Its much-altered exterior does not give much evidence of its original character, although it probably was originally a barn, possibly built in the mid to late 19th century. The house may date from about 1840-1850, based on its vernacular form and details.

5630 Old National Pike, Hoffman House: This two-story log or frame dwelling was probably built about 1840-1845. It does not appear on the 1858 map, but Charlotte Hoffman, the resident indicated on the 1873 map, and her husband William purchased the property in 1842. It has five bays on the south elevation where the german siding has a vertical member separating the eastern two bays, indicating the probable expansion of an original three-bay house. The entrance is in the center bay of the western section. A one-story porch extends across both sections and has a plain balustrade and chamfered columns. The stone foundation is exposed on the south elevation and the porch is reached by a wide staircase in the center of the facade. The roof is composition and has interior end chimneys. A two-story rear wing extending from the northwest corner has an additional entrance and an entry porch on the west elevation. A frame garage is located near the edge of the road and has tongue-and-groove siding, a standing seam metal roof, and a sliding door on the south. A frame shed, possibly a chicken house, is located west of the house. It has a standing seam metal roof and a cantilevered shed roof on the east elevation. The two outbuildings appear to date from the 1920's.

5707 Old National Pike, former hotel/tavern: The two-story brick dwelling was probably built about 1810-1815 as a tavern or hotel on the National Road. Land records indicate that Jacob Smith willed his brick residence with 20.5 acres to his two sons Emmanuel and Jacob Smith in 1816. By 1841, the house was occupied by Emmanuel Smith and was sold to Daniel Baugher. Baugher died in 1848 and his will does not specifically mention the house. The records from 1841 are obscure, but the 1858 and 1873 maps indicate that Joseph Flemming and his wife occupied the property and Mrs. Susannah Flemming retained a life estate until

7.6 Description (Continued)

about 1890 when it was sold to William H. Summers as the result of an equity sale. Mrs. Grace Summers Stone, who grew up in the house, relates that local tradition had always identified the house as a tavern, although no documentation other than the historical maps has been found to verify its use. The house has a painted brick exterior with flemish bond on the north elevation, which is at present only about 6 feet from the edge of the road. Mrs. Stone remembers a one-story porch extending across the north elevation and the east elevation, which has been removed. The east, west and south elevations are 5:1 American bond. The north elevation has five bays with gauged brick arches and a center entrance. The door surround is particularly elaborate, with a bolection frieze, crossettes, a molded cornice, a traceried transom, and an eight-panel door. The windows are 9/9 with wood sills and once had shutters, now removed. The east elevation of the main section has two bays and an additional door near the northeast corner. The cornice is corbeled and molded brick. The roof is wood shingles and has interior end chimneys at the gable ends. The two-story rear wing extends from the southwest corner and has a two-story integral porch on the east side. The porch has beaded posts and railing, possibly indicating that they were rebuilt in the early 20th century. A vertical board door leads into the basement level on the south end of the wing. The interior was not accessible for this survey; however, Mrs. Stone described the interior as having a center hall flanked by two rooms on each side. The western room had built-in cupboards and shelves between the fireplace and the interior partition wall, through which a door led to a small rear room. She had heard it described as a "ballroom", perhaps a misunderstanding of the word "barroom", indicating that this was the tavern's main drinking room. She also recalls that the stairs rose to the fully floored attic space at the same width from the first floor. These features are also found in other taverns of about the same period surveyed in the Middletown Valley to west of Braddock. Anne B. Hooper's Braddock Heights: A Glance Backward (1974), which gives a brief description of some of Braddock's buildings, states that the house was Getzendanner's Tavern. However, Searight's 1894 history of The Old Pike described Getzendanner's as a stone building. No other references to Getzendanner in association with this property have been located, although further research remains to be done. A frame bank barn is the only outbuilding remaining on the property, which, according to Mrs. Stone, also included a stable on the north side of the road, a smokehouse, and other secondary structures. The historical maps show a blacksmith shop west of the house, although it no longer exists. The barn has a shed addition on the west, possibly a wagon shed originally, which now has a lift-type garage door. The barn appears to have been built about 1900, with vertical board siding, a sliding tongue-and-groove door on the north elevation and a corrugated metal roof. The forebay on the south elevation shelters the stall level which has a horizontal flush board enclosing wall.

8.1 Significance

has taken place over many years, as formerly combined residence/commercial, transportation, or agricultural buildings were converted to primarily residential uses. The church was converted to a social hall for the Grange. The integrity level is therefore moderate in comparison with the less-altered and more varied survey districts in the other turnpike towns.

In 1862, Oliver Wendell Holmes Sr. wrote in "My Hunt after 'The Captain'" of the impressive outlook from Fair View:

"In approaching Frederick, the singular beauty of its clustered spires struck me very much, so that I was not surprised to find 'Fair View' laid down about this point on a railroad map. I wish some wandering photographer would take a picture of the place, a stereoscopic one, if possible, to show how gracefully, how charmingly, its group of steeples nestles among the Maryland hills. The town had a poetical look from a distance, as if seers and dreamers might dwell there."

Various writers from at least the early 20th century to the present have theorized that Holmes's use of the phrase "clustered spires" was the inspiration for John G. Whittier's opening lines in "Barbara Fritchie", which was published shortly after Holmes's account initially appeared in the Atlantic Monthly in December 1862.

9.1 Bibliography (Continued)


Miller, Charles W. Post Offices of Frederick County for the Year of 1887.
Typescript in Frederick County Department of Planning & Zoning.

Seawright, Thomas B. The Old Pike: A History of the National Road. Privately
published, Uniontown, PA., 1894, 195.

The Works of Oliver Wendell Holmes, Vol. 8. "My Hunt after 'The Captain'".
Boston: Houghton Mifflin & Co., 1892, p. 47.

Titus, C.O. Atlas of Frederick County, 1873.

Williams, T.J.C., & Folger McKinsey. History of Frederick County, 1910.
Reprinted Baltimore: Regional Publishing Co., 1979, pp.



F-3-112
 Braddock Survey District
 Frederick County

Janet Davis
 December 9, 1992
 Not to Scale

Braddock S.D.

F-3-112

Liber/Folio	Grantee	Grantor	Lot Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
5707 O.N.P. 712/169 7 Oct 64	John D. & Irene D. White	Richard C. & John A. Summers, execs of LW & T of Grace R. B. Summers	mentions brick dwelling & 6' strip between house & road 2.60a. 1963 set post shows spring house down hill to side of barn	#20,000	Grace Summers will in TME 2/178 Also see Equity 20,385
374/385 3 June 30	George W. S. Summers	John W. S. Summers et ux	20 1/2 a.		
WIP 11/251 18 Apr 1890	Wm. H. Summers	Chas. W. Ross & Jacob Rohrbach Trustees in Equity 5670	20 1/2 a., improvements, Row except 6 a. of rye growing, prop. of Zimmerman, tenant of Mrs. Susannah Fleming, dec.	\$2801	Will of Daniel B Baughen GME 3/25 209 Jan 1848 life tenant
H 5 13/254 30 Apr 1841	Daniel Baughen	Emmanuel & Margaret Smith	1 of 3 parcels, same devised to Jacob & Emmanuel Smith leg Jacob Smith's LW & T, dated 1 June 1816		TG 4/445, P of R. 5 Feb 1876 David Schaeffer to Joseph & Susannah Fleming
Will Record H 5 2/98 1 Jun 1816	Emmanuel & Jacob Smith, sons of Jacob	Jacob Smith	Part of "Suldeea Manor" "Salisbury Plains Helped" mentions brick building held, possessed, & occupied by Emmanuel Smith		
WR 23/439 3 May 1802	Henry Dent	Doctor Thomas Bartlett	Will mentions brick bdy. which I now occupy with 20 1/2 a.		
5630 O.N.P. 472/28 20 Apr 48	Clarence C. & Mabel E. Couell	Grace E. Rice, unm.			
WIP 6/293 472/27 20 Apr 48	Grace E. Rice	Clarence C. & Mabel E. Couell			
WIP 6/243 26 May 1888					

Liber/Folio	Grantee	Grantor	Loc Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
5630 O.N.P. 472/28	Cozell & wife	Grace E. Rice			
472/27 20 Apr 48	Grace E. Rice	Clarence & Mabel E. Cozell			
	(Mabel E. Hoffman Cozell obtained upon death of mother Edna Hoffman Edna Hoffman received upon death of her husband Leonard B. Hoffman aka Glenmore B. Hoffman)			Leonard B. Hoffman	Hoffman aka
Will Record SDT 2/326	Glenmore B. & Roger L. Hoffman	Amanda C. Reckards			
STH 280/325 16 Sept 07	Glenmore Leonard B. & Edith L. Hoffman	Amanda C. Reckards			
31 Aug 07	Amanda C. Reckards	Emily J. Colletty & Shaddicus M. Baker, trustees in Equity 7913			
WIP 6/293 26 May 1888	Perry A. Reckards	Amanda M.E. Zimmerman (Wife of Charlotte Hoffman) & husb. Edward G.		\$151	
H S 23/28 8 Apr 1844	Charlotte Hoffmann	William E. Hoffman exec 1/2 a.	"Neighbors Agreement"	\$200	
H S 18/40 16 Jul 1842	Man. C. Hoff- man	Melly Pearl	1/2 a. "Neighbors agreement"	\$175	
J S 20/219 12 Jun 1824	Andrew Drull	John L. Levy	"Neighbors Agreement"	\$1230	

Liber/Folio	Grantee	Grantor	Lot Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
56270NP. 953/501 27 Dec 74	C. Leo & Marguerite K. Krantzy	Braddock Lutheran Church	2271 sq. ft. parcel		
STH 289/304 22 Jun 07	Evangelical Luth. Church of Braddock	Anna J. & Simeon L. Bast - no earlier refs -		#5	
5617 O.N.P. 1504/779 5 Aug 88	Jed J. Merser	Dorothy E. Lucas, widow	2 parcels: 1 = 130, 187.25 sq. ft. 2 = 1, 815 sq. ft.	#225,000	
720/238 20 Feb 65	Harry L. & Dorothy E. Lucas	Charles G., Jr. & Evelyn E. Mallon			
673/312 4 Sept 62	Charles G. & Evelyn E. Mallon	Charles H. C. Wright et ux			
645/391 7 Nov 60	Charles H. C. Wright et ux	Kennard G. & Frances H. Porter			
491/99 20 Feb 51	Kennard G. & Frances H. Porter	Carlton A., Jr. & Evelyn A. Marvel			
466/126 16 Oct 47	Carlton A. Marvel, Jr.	Hugh H. Melomick et ux			
426/92 30 Nov 40	Hugh H. Melomick et ux	Charles E. & Anna D. Meitzler	4a.		
378/391 11 May 31	Charles E. & Anna D. Meitzler	John F. & Lona B. Sponseller			

Liber/Folio	Grantee	Grantor	See Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
5617 O.N.P. (Cont.)					
362/3 19 Mar 27	John R. & Laura B. Sporseller	Myra B. Zeiler widow			
346/586 5 Mar 24	J. Dean Zeiler & Myra B. Zeiler	C. Willard Met- calfe & Adela L. Metcalfe			
329/37 1 Oct 19	C. Willard Metcalfe et ux	Marshall L. & Margaret L. Grove			
316/418 8 Apr 16	Marshall L. Grove et ux	Simson L. & Annie J. Bast	plotting distances mention new divisional line, indicating possible date after which has ^{this deed} to provide lot for house to be built		
HWB 304/235 1 Apr 13	Simson L. & Annie J. Bast	J. Allen Erumhine & Rose Hagan, et al			
5613 O.N.P. 1308/821 7 Nov 85	(School) James A. & Melony B. Casell	Philip W. Metyger	part of "Neighbor's Agreement"	\$82,000	
1081/490 3 May 79	Philip W. Metyger	Ruth E. ^{Fischer} & Dennis V. Riley		\$55,900	
1039/231 14 Dec 77	Ruth E. Fischer & Dennis V. Riley, et al	Ruth E. Fischer & Dennis V. Riley			
831/101 26 Aug 70	Ruth E. Fischer & Michael F. Riley	Richard C. & Mary Edith Meaders			
768/191 7 June 67	Richard C. Meaders et ux	James D. Conroy Jr. et al			

Bradlock S.D. P. 5

F-3-112

Liber/Folio	Grantee	Grantor	Loc. Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
56(30-N.P. (cont.))					
533/87 18 Jun 54	James G. Courcy Gr. et al	James G. Courcy Sr. widower	reserving life estate		
434/254 26 May 42	James G. & Anna E. Courcy	Davis B. & Stanton L. Haine, his wife			
414/371 19 Nov 38	Davis B. & Stanton L. Haine	Irving A. & Dorothy M. Abb	"Fairview School Property", part of		
370/220 5 Apr 29	Irving A. Abb et al	Clarence M. Phlegger, et al	part of lot ^{former} for school school		
368/481 18 Dec 28	Clarence M. Phlegger & Walter S. Reeder	Board of Education & Albert S. Cook, State Supl. of Schools	part of former school lot		
4514/12 6 Aug 1840	Joseph Stup, Henry Leightert trustees	John A. & Elizabeth Schaeffer (or Shafer)	"part of Neighbor's Agreement 87 sq. perches	\$100	in trust that they shall erect or cause to be built a school- house for school Dist. 16 to be called "Fairview Schoolhouse"
5620 O.N.P.					
400/607					
14 Aug 75					
482/93 9 Dec 49	J. Wilson Clemson & Ruth E. Clemson	Fannie Phlegger, widow	P. 1: 1/2 A. 399/283 P. 2: same ref, no area total given P. 3: 12 ft strip from board of ed.		
481/583 10 Nov 49	Fannie Phlegger	Charles Jackson, widower	life estate		

Liber/Folio	Grantee	Grantor	Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
5620 O.N.P. (cont) 399/283 8 Jun 26	Jannie Phlegge wife of Clarence M. Phlegge	Flora V. & Charles Jackson	2 parcels reserving life estates to grantors		
342/215 24 Feb 23	Flora V. & Charles Jackson	George E. & Elizabeth L. Stine	2 parcels 1: 338/240 2: 338/592		
2) 338/592 5 June 22	George E. Stine et ux	C. Willard Metcalf et ux	60 ft. wide strip east of land of Metcalf		
1) 338/248 30 Mar 22	George E. Stine et ux	Jesse L. & Mary A. C. Haines			
316/406 23 Sept 15	Jesse L. Haines et ux	J. Henrietta Grove			
DHH 17/474 1 Aug 03	J. Henrietta Grove	Charles W. Groce	1/2 A.	\$900	
DHH 17/204 22 Apr 03	Charles W. Groce	J. Henrietta Groce widow of Elias Grove	1/2 A.	\$900	
DHH 13/548 19 Apr 02	J. Henrietta Grove	Daniel Gibbon	1/2 A.	\$900	
AF 5/218 26 Apr 1882	Daniel Gibbon	Minnie L. & Louise A. Wickham	1/2 A.	\$325	
AF 2/735 21 Feb 1881	Minnie L. Wickham	Mary Wickham	1/2 A.	\$112	

Liber/Folio	Grantee	Grantor	Loc. Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
5620 O.N.P. (cont.)	Louisa Wickham (Lewis)	Daniel Getzendamer et ux + David E. Muller et ux	1/2 A. (deed from Getzendamer to Miller never recorded)	#400	
WBT 7/475 7 Nov 1848	Daniel Getz- endamer	Susan Ridgely	1/2 A.	\$300	
WBT 3/574 9 Feb 1847	Susan Ridgely	Christian Warner et ux	1/2 A.	\$600	
JS 48/402 1st Apr 1835	Christian Warner et ux	Jacob Shotts et ux	1/2 A.	#350	
JS 31/500 27 May 1829	Jacob Shotts	Peter Sulzger (Sulzer) - no earlier refs -	1/2 A.	\$35	
5607 O.N.P. 1543/157 14 Feb 89	John W. + Christine L. Cooper	Kenneth Todd Bauer	0.31 A. 0.31 A.		
1195/843 12 Apr 83	Kenneth Todd Bauer	Curtis A. + Deloras A. Bauer	0.31 A.	\$51,400	
1117/417 17 Jun 80	Curtis A. + Deloras A. Bauer	Stateria Keyser Wagner	0.31 A.		
808/251 9 Jul 69	Stateria Keyser Wagner, undiv	Richard H. + Shirley E. Summers	0.31 A.		
766/113 15 May 67	Richard H. Summers et ux	J. Edward + Agnes S. Tobey	0.31 A.		

Bra dock S. D. p. 7

F-3-112

Liber/Folio	Grantee	Grantor	L. Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
5607 O.N.P. (Cont)					
570/263 17 Sept 56	J. Edward Tobay et ux	Blanche E. Cramer	1a, except 0.69a. sold to J. Wilson Olmson 56 8/383, 11 Aug 56		
418/564 24 Apr 39	Blanche E. Cramer	Grayson H. Mayer, exec. of LW & T. of Wm. S. Kinty	see also AF 3/10, 2 Mar 1881 except .	\$1450	
5TH 282/280 25 Mar 08	William Kinty et ux	Milton E. Akers et ux	1a.		
DHH 13/305 17 Mar 02	Milton E. Akers et ux	Mary E. Bruckey (Wash. D.C.)	1a.	\$875	
DHH 5/655 28 Mar 1900	Mary E. Bruckey	LW & T of Anne C. Bruckey & other heirs of Ann C. Bruckey			
JLJ 1/335 2 Apr 1892	Ann C. Bruckey	Josiah & Rebecca D. Schildknicht	part of "Neighbors Agreement" 2a.	\$725	
WIP 1/55 1 Jan 1885	Josiah Schild knicht	C. V. D. Levy, Trustee in Equity 5126		\$760	
AF 3/10 2 Mar 1881	Mary E. Reil	Margaret Kaufmann	"house and lot" "Neighbors Agreement"	\$450	
JWLC 2/102 26 Jul 1864	Margaret Kaufmann	John Culler & Maria Culler	1a.	\$450	
J S 37/320 13 May 1831	Harry Frazier	Peter Siltzer	1a.	\$100	
			end of toll; house prob. dates 1830-1840		

Bradlock S.D. p. 8

F-3-112

Liber/Folio	Grantee	Grantor	Lot Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
5606 O.N.P. 1032/1006 17 Oct 77	Wm H. House II & Kathleen B. House	Hugh James Lee & Carol Jane Lee	8/11 A.		
916/199 21 Jun 73	Hugh J. Lee et ux	Allan M. & Katherine S. Creed	8/11 A. mentions Bradlock Ref Church as ref. point in description (Grange)		
599/418 23 May 58	Allan M. Creed et al	Roland E. & Janet M. Beldon	8/11 A.		
487/260 19 Aug 50	Roland E. Beldon et ux	Wm E. & Dorothy S. Trail	8/11 A.		
402/397 15 Jul 36	Wm. E. Trail et ux	Clarence A. & Katherine E. Bussard			
EG 4322/511 17 Oct 17	Clarence A. Bussard	H. K. DeLauter trustee in Equity 9634, Frank H. Grove et ux	322/204	\$3450	
314/321 13 Nov 15	Frank H. & Ella E. Grove	Marshall L. Grove et ux	1/2 A.		
STH 286/60 2 Dec 08	Marshall L. Grove	Singleton J. Stull et ux	Part of "Neighbors Agree- ment" known as "Reach Grove" 12 1/2 A.	\$2950	
STH 284/419 22 Nov 07	Singleton Stull et ux	Susan S. Harrison et ux	"		
DHH 11/569 11 Sept 01	Susan S. Harrison	D. Gibbon	"	\$2350	

Braddock S. D. p. 9

F-3-112

Lot Size, Description,
Other Information,
Original Tracts

Liber/Folio

Grantee

Grantor

Cost

Miscellaneous

5606 O.N.P. (cont.) AF 9/148 5 Apr 1884	D. Gibbons	John C. Hagan & Noah Coburn Execs. of LW+T of John Hagan	11 @.	\$1680	
CM 3/75 17 Feb 1869	John Hagan	Michael P. Hagan			
5605 O.N.P. 75 2/141 28 Jul 66	James S. & June C. May	Calvin R. & Mary B. Miller			
506/37 25 Aug 52	Calvin R. & Mary B. Miller	Clinton E. Smith, Jr. et al	O-6690.		
388/340 29 Aug 33	Clinton E. Smith et al	Clarence A. Bussard et ux			
388/340 29 Aug 33	Clarence A. Bussard et ux	Clinton E. Smith et ux			
372/83 31 Aug 29	Clinton E. Smith et ux	Edward M. Dodd			
366/83 8 Mar 28	Edward M. Dodd	George S. Crawford et ux & F+M Bank			
362/126 2 Apr 27	George S. & Lula Crawford	Ella E. Howe widow			
344/97 30 Apr 23	Frank H. & Ella E. Howe	Ezra Hoffman widower et al			

F-3-112

Braddock S.D. p. 10

Lot Size, Description,
Other Information,
Original Tracts

Liber/Folio	Grantee	Grantor	Cost	Miscellaneous
5605 O.N.P. (cont.) HWB 304/187 29 Mar 13	Oda V. Hoffman w/plot of Egra	Mary Smith w/m.		
JLJ 1/498 2 Apr 1892	Mary Smith	Edward S. & Sallie E. Tucker	\$750	
AF 9/27 20 Mar 1884	Edward S. Tucker	Wm. E. Mercer et ux	\$550	
AF 7/741 1 Mar 1884	Wm. E. Mercer	Mary H. Coleyger	\$500	
AF 4/292 5 Nov 1881	Mary M. Hunter	Henry M. Nix dorft		
AF 4/137 24 Apr 1880	Henry M. Nixdorff	George H. Rauling et ux	\$750	
CM 3/363 5 Apr 1869 2	George H. Rauling	Charles E. Feaga	\$650	
CM 1/84 14 Dec 1867	Charles E. Feaga	Stephen J. Webster exec. of LW & T of John S. Webster	\$400	
JS 33/49 27 May 1829	John S. Webster	Peter Sulger	\$13	
JS 23/221 1 Sept 1825	John S. Webster	Peter Sulger	\$40	

Braddock S. D. P. 11


F-3-112

Lot Size, Description,
Other Information,
Original Tracts

Liber/Folio	Grantee	Grantor	Lot Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
Grange (Braddock Ref. Church) 929/532 4 Dec 73	Braddock Grange 365, Inc.	Braddock Grange 365	1/2 A.		
333/259 2 Oct 20	Braddock Grange 365	G. Elmer Stone et al		\$500	
333/161 4 Aug 20	G. Elmer Stone et al	Evangelical Reformed Church			
STH 282/321 14 Jan 08	Ev. Luth. Church Braddock Ref. Church	Ev. Luth. Church			
CM 7/341 7 Feb 1871	Ev. Luth. Ch. & Ev. Ref. Ch.	Daniel Getzendanner et al	Church described as having been erected on lot for use of German Ref. & Ev. Luth. congr.		
CM 2/512 25 May 1859	Daniel Getzen danner et al	Michael P. Hagom et ux	1/2 A.	\$80	
5519 O. N. P. 1085/288 8 Jun 79	Erma R. Little widow	Erma R. Little widow	P. 1: 6A. 302/184 P. 2: 4.9A. 316/339		
466/120 23 Oct 47	Erma R. & Ralph J. Little	Mary B. Kline widow			
421/561 2 Jan 40	Ralph L. & Mary B. Kline	John C. Dyley assignee & FBIC in Equity 14047, Roscoe Admire		\$9350	
402/554 30 Jul 36	Roscoe Admire	Casper E. Cline et ux			

Lot Size, Description,
Other Information,
Original Tracts


Liber/Folio	Grantee	Grantor	Lot Size, Description, Other Information, Original Tracts	Cost	Miscellaneous
5519 O.N. 302/184 26 Sept 12	P. (cont.) Casper E. Cline	Gertrude B. Hoopes, widow	6 A. P. 1		JLJ 16/242
Will Record WBC 2/371 will date 16 Dec 10	Gertrude Hoopes	Samuel M. Hoopes			
STH 269/175 14 Jan 05	Samuel M. Hoopes	Edward G. Smith, assignee in Equity 784 B.	6 A. Paupel P. Frank Paupel Franklin B. Smith	# 3500	
JLJ 16/242 18 May 1897	P. Frank Paupel	Margaret B. & Charles J. Ramsburg	Plat w/ deed shows 6 A. w/ pine trees n. of rect. house & dark square (log house?) e of house	# 4,000	
JLJ 7/11 1 May 1894	Margaret B. & Charles J. Ramsburg	John H. Williams	31 A. of "Neighbors Agreement" 2 adj. parcels	# 7,750	
AF 3/9 8 21 Feb 1881	John H. Williams	Benjamin Keyser			
AF 4/11 8 10 May 1881	John H. Williams	John Young of C. St. W.			
5526 O.N. 423/415 25 Apr 40	Helen L. Smith	Millard S. & Amanda E. Kefauver			
366/386 27 Mar 28	Millard S. Kefauver et ux	George S. Crawford et ux			
JLJ 1/389 9 Apr 1892	M. S. Kefauver	R. S. Barrick, exec. of John Young of C.		# 1700	




FREDERICK

DIST. No. 2


Scale 1/4 Inches to the Mile



F-3-112
Braddock Survey District
Frederick County
C.O. Titus, Atlas of Frederick
County, 1873
Fair View until c. 1880



F-3-112
 Braddock Survey District
 Frederick County
 Isaac Bond, Map of Frederick
 County, 1858
 Fair View until c. 1880



FORT DETRICK

Shookstown

Braddock

INTERCHANGE

Clifton

Flier

Radio Towers

Memorial Park Cem

Driver Theater

F-3-112
Braddock Survey District
Frederick County
USGS Frederick, Md.
1:24000



F-2-12

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

5707 Old National Pike, Boomer tavern, northeast
elevation

1/24



F. - 112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg loc.: Md. SWPO, Crownsville, Md.

5707 Old National Pike, doorway detail,
north elevation

2/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

5707 Old National Pike, southeast corner
view

3/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

5707 Old National Pike, barn, north elevation

4/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Braddock Grange #365 (German Reformed
& Evangelical Lutheran Church), south elevation

5/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Helen Smith House, 5526 Old National Pike,
south elevation

6/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Helen Smith House, 5526 Old National Pike,
east elevation and summer kitchen/studio

7/24



F-3-112

Broddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Daniel Gibbons House, 5606 Old National Pike,
Southwest corner view

8/24



F-3-112

Broddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

5605-5609 (Right to Left) Old National Pike,
view from northwest

9/24



F-3-112

Broddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

5607 - 5609 (Right to Left) Old National Pike,
view from northwest

10/24



F-3-112

Broddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

5607 Old National Pike, south elevation
and outbuildings

11/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Fair View Schoolhouse, 5613 Old National Pike,
west elevation

12/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Fair View Schoolhouse, 5613 Old National Pike,
northeast corner view

13/24



F.3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

5620 Old National Pike, south elevation

14/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

Decembet 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

5617 Old National Pike, former tollhouse,
view from north west

15/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md

5E27 Old National Pike, view from northeast

16/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md

Hoffman House, 5630 Old National Pike,
southwest corner view

17/24



F.3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Highland Lodge, 5519 Old National Pike,
north elevation

18/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md SHPO, Crownsville, Md

Highland Lodge, 5519 Old National Pike,
southwest corner view

19/24



F-3-112

Broddock Survey District
Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Highland Lodge, 5519 Old National Pike,
log outbuilding, west elevation

20/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.
Highland Lodge, 5519 Old National Pike,
Garage and stable, north elevation

21/24



F-3-112

Broddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Highland Lodge, 5519 Old National Pike,
Smokehouse, west elevation

22/24



F-3-112

Broddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md

Highland Lodge, 5519 Old National Pike,

barr, west elevation

23/24



F-3-112

Braddock Survey District

Frederick County

Photo: Janet Davis

December 1992

Neg. loc.: Md. SHPO, Crownsville, Md.

Highland Lodge 5519 Old National Pike,
tenant house, north elevation

24/24