

Frederick Church of Christ  
F-3-265  
1305 North Market Street  
Frederick, MD  
1947-1948  
Private access

### **Capsule Summary**

The Frederick Church of Christ is located on a 0.83099-acre parcel at 1305 North Market Street in Frederick. The property is located just outside the northern boundary of the National Register-listed Frederick Historic District (Maryland Inventory of Historic Properties [MIHP] No. F-3-039). The building comprises a main block and a rear addition. Both sections are one story in height with a raised basement and are constructed of concrete block with brick facing. The main block exhibits elements of the Gothic Revival architectural style, including an irregular plan, a steeply pitched roof, a castellated tower, pointed-arch grouped windows, pointed-arch designs contained in rectangular stained-glass windows, and tracery ornamentation in the front door lights.

The church was built on an undeveloped parcel located within the Maple Park subdivision, a planned development platted in 1922. The Frederick Seventh-day Adventist Church constructed the main block in 1947-1948 following their purchase of the property in 1947. The pastor, Elder David G. Fleagle, was a former builder, and he directed the church's construction with assistance from members of the congregation and community. The Frederick Church of Christ constructed the church's rear addition ca. 1970 following their purchase of the property in 1969.

The Frederick Church of Christ possesses significance in the area of architecture. The main block is an example of post-World War II Gothic Revival design, illustrating the lingering use of that nationwide style in mid-twentieth-century ecclesiastical architecture in Frederick. The main block retains most of its original design elements and materials.

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. F-3-265

## 1. Name of Property (indicate preferred name)

historic Frederick Seventh-day Adventist Church  
 other Frederick Church of Christ (preferred)

## 2. Location

street and number 1305 North Market Street \_\_\_ not for publication  
 city, town Frederick \_\_\_ vicinity  
 county Frederick

## 3. Owner of Property (give names and mailing addresses of all owners)

name Frederick Church of Christ  
 street and number 1305 North Market Street telephone 301-662-5789  
 city, town Frederick state MD zip code 21701

## 4. Location of Legal Description

courthouse, registry of deeds, etc. Frederick County Courthouse liber 00817 folio 00519  
 city, town Frederick tax map 0409 tax parcel 0628C tax ID number 02-044838

## 5. Primary Location of Additional Data

- Contributing Resource in National Register District
- Contributing Resource in Local Historic District
- Determined Eligible for the National Register/Maryland Register
- Determined Ineligible for the National Register/Maryland Register
- Recorded by HABS/HAER
- Historic Structure Report or Research Report at MHT
- Other: \_\_\_\_\_

## 6. Classification

Category	Ownership	Current Function	Resource Count
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture	Contributing
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	Noncontributing
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	<u>1</u> buildings
<input type="checkbox"/> site		<input type="checkbox"/> domestic	_____ sites
<input type="checkbox"/> object		<input type="checkbox"/> education	_____ structures
		<input type="checkbox"/> funerary	_____ objects
		<input type="checkbox"/> government	<u>1</u> Total
		<input type="checkbox"/> health care	
		<input type="checkbox"/> industry	
		<input type="checkbox"/> landscape	
		<input type="checkbox"/> recreation/culture	
		<input checked="" type="checkbox"/> religion	
		<input type="checkbox"/> social	
		<input type="checkbox"/> transportation	
		<input type="checkbox"/> work in progress	
		<input type="checkbox"/> unknown	
		<input type="checkbox"/> vacant/not in use	
		<input type="checkbox"/> other:	
			<b>Number of Contributing Resources previously listed in the Inventory</b>
			<u>0</u>

---

## 7. Description

Inventory No. F-3-265

---

### Condition

excellent       deteriorated  
 good             ruins  
 fair               altered

---

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

### Introduction

The Frederick Church of Christ occupies a 0.83099-acre parcel at 1305 North Market Street in Frederick. The property is located just outside the northern boundary of the National Register-listed Frederick Historic District (expanded); the assigned Maryland Inventory of Historic Properties (MIHP) number for the district is F-3-039 (National Register of Historic Places 1988). The Frederick Church of Christ stands on the west side of the street and faces east. A concrete sidewalk leads to the front entrance of the church. Landscaping consists of front and side lawns, well-tended planting beds, and small shrubs and deciduous trees. The Frederick Church of Christ converted a former lawn at the rear of the addition to a gravel parking lot for the church (Jim Denison personal communication May 3, 2013; Reed 2012).

The building, which is in excellent condition, comprises a main block and a rear addition. Both sections are one story in height with a raised basement and are constructed of concrete block with brick facing (Frederick Seventh-day Adventist Church 2012:8). The main block exhibits elements of the Gothic Revival architectural style. The Frederick Seventh-day Adventist Church constructed the main block in 1947-1948 following their purchase of the property in 1947 (Frederick County Land Records (FCLR) ECW 460:331; *Frederick Seventh-day Adventist Church* 2012:7). The pastor, Elder David G. Fleagle, was a former builder, and he directed the church's construction with assistance from members of the congregation and community (Frederick Seventh-day Adventist Church 2012:7; *The Frederick Post* October 4, 1948). The Frederick Church of Christ constructed the rear addition ca. 1970 following their purchase of the property in 1969 (FCLR ECW 817:519).

### Exterior

#### *Main Block*

The one-story-with-raised-basement, brick-faced main block rests on a concrete foundation with an irregular footprint. The main block comprises a front-gable nave section (on the north) and a side-gable section (on the south). Both sections occupy rectangular footprints. The combined sections create a modified T-shape, as shown in the attached sketch of the upper-level floor plan. The intersecting, steeply pitched gable roofs of the sections are sheathed in asphalt shingles. The main block includes an off-center, flat-roofed, castellated tower; the tower occupies a square footprint along the east (front) elevation at the junction of the two sections of the main block. The tower rises to the height of the roof ridges and accommodates the building's main entrance. The brick facing on the concrete walls of the main block is laid in 8:1 common bond; every ninth row is a course of Flemish bond. A water table constructed of vertically laid brick stretchers ornaments all elevations of the main block. Stained-glass windows original to the building pierce the upper levels of each elevation; the windows have brick sills and metal-frame protective plexiglass. The lower levels of each elevation feature painted, metal-frame, eight-over-eight-light, double-hung windows with brick sills; these windows appear to be original to the building.

The one-bay tower provides the focal point of the front elevation of the main block. Concrete steps enclosed by brick sides with metal railings lead to the building's main entrance. The wood door features two blue stained-glass, rounded-arch lights over two rectangular wood panels. The door is accented by sidelights; each sidelight contains one blue stained-glass, rounded-arch light over one rectangular wood panel. The blue stained-glass door lights feature metal tracery. The door was renovated by the Frederick Church of Christ during the early 1970s after they purchased the church in 1969 (Jim Denison personal communication May 3, 2013). The door is topped by a pointed-arch, stained-glass window installed by the Frederick Church of Christ during the renovation. The window features the words "CHURCH OF CHRIST" and is accented by a row of brick headers along its edges. Two decorative metal lamps flank the front door. A rectangular stained-glass window pierces the south wall of the tower. The front and south elevations of the

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. F-3-265

### Frederick Church of Christ Continuation Sheet

Number 7 Page 1

---

tower feature a round opening in the top portions of the walls; the opening is encircled by brick headers and is enclosed with modern prefabricated material.

The east (front) elevation of the front-gable nave section of the main block (north of the tower) contains two bays. A stained-glass trio window arrangement occupies the upper level. The arrangement consists of two pointed-arch units with a round unit between and above them. The name "CHURCH OF CHRIST" appears in white letters south of the window arrangement. On the lower level of this portion of the elevation, one eight-over-eight-light window occupies the northernmost bay; the southernmost bay is blind. A brick-and-glass sign box advertising the church has been installed in the planting bed in front of these windows. The four-bay north elevation of the nave section contains four symmetrically located rectangular stained-glass windows on the upper level and three eight-over-eight-light windows on the lower level. The westernmost bay is blind on the lower level. The west (rear) elevation of the nave section features an off-center, exterior brick chimney flanked by one bay on the north and three bays on the south. The two outermost bays of the upper level contain rectangular metal-frame, single-light windows, and the two central bays are blind. Each lower-level bay features an eight-over-eight-light window. A metal vent is located in the gable, just beneath the roof ridge. The two-bay south elevation of the nave section includes two openings on the upper level that consist of a metal pedestrian door in the west bay and a rectangular stained-glass window in the east bay.

*The east (front elevation) of the side-gable section of the main block (south of the tower) contains one bay that features a rectangular stained-glass window on the upper level and an eight-over-eight-light window on the lower level. The south elevation (gable end) of the side-gable section features a stained-glass trio window arrangement on the upper level; the arrangement is similar to the window grouping on the front elevation of the nave section. The lower level of the elevation contains an eight-over-eight-light window in the west bay and a one-light metal pedestrian door in the east bay. A metal vent is located in the gable, just beneath the roof ridge. The west (rear) elevation of the side-gable section has three bays. Rectangular stained-glass windows occupy the upper levels of the two southernmost bays; eight-over-eight-light windows are located on the lower levels of these bays. The northernmost bay contains a nine-light pedestrian door on the lower level. Concrete steps with a metal railing provide access to the door.*

#### *Addition*

A two-level, covered corridor connects the rear elevation of the main block to the building's addition. Both levels of the corridor have concrete floors and metal railings. Metal posts support the shallow-gable roof sheathed in asphalt. A metal staircase on the south side provides access to the upper corridor.

The one-story-with-raised-basement, brick-faced rear addition rests on a concrete foundation and occupies a rectangular footprint. The addition terminates in a gable roof sheathed in asphalt shingles. The brick facing on the concrete block walls is laid in a running-bond pattern.

The east elevation (gable end) of the addition connects to the main block of the building via the corridor. A two-level elevator shaft with metal pedestrian doors, each of which has one small light, is located along this elevation on the south side of the corridor. An off-center, exterior brick chimney rises along the elevation on the north side of the addition.

The south and north elevations of the addition each contain four symmetrical bays. On the south elevation, metal-frame, one-over-one-light, double-hung windows occupy the upper and lower levels of each bay. On the north elevation, identical windows occupy the westernmost three bays. The lower level of the easternmost bay contains a metal pedestrian door accessed by concrete steps with a metal railing; the upper level of this bay is blind.

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. F-3-265

Frederick Church of Christ  
**Continuation Sheet**

Number 7 Page 2

---

The west elevation (gable end) of the addition has three bays. On the upper level, a central metal pedestrian door is flanked by metal-frame, one-over-one-light, double-hung windows. The door is accessed by a metal staircase with a metal railing; metal posts support a shed porch roof. A similar door is located in the central bay on the lower level; this door is accessed via concrete steps with metal railings.

### **Interior**

#### *Main Block*

The upper-level floor plan is illustrated in the attached sketch. The front entrance of the building leads to an upper-level vestibule that occupies the tower and features a decorative metal ceiling lamp that is original to the building. The vestibule has vinyl flooring. The Frederick Church of Christ completed interior renovations to the main block during the early 1970s following their purchase of the building in 1969 (Jim Denison personal communication May 3, 2013; Reed 2012). A narrow stairway previously occupied the southwest corner of the vestibule. The stairway was removed during the renovations. Paired wood-panel doors on the north wall of the vestibule lead to the nave. A door opening on the west wall of the vestibule provides access to the nave's annex.

The nave is illuminated primarily by the stained-glass trio window arrangement on the east wall and the rectangular stained-glass windows along the north wall. Each rectangular stained-glass window contains a design enclosed by a pointed-arch border. Decorative metal ceiling lamps that are original to the building provide additional light. The stage area occupies the west end of the nave and consists of a stepped platform partially within an alcove that is original to the building (Reed 2012; Frederick Seventh-day Adventist Church 2012:7). A podium stands on the platform. The Frederick Church of Christ enlarged the stage area and added stone ornamentation along the west wall of the alcove. A baptistry is located on the north side of the stage area. The nave has minimal ornamentation. The floor is carpeted.

The annex is located on the south side of the nave in the side-gable section of the main block. A "welcome room," which formerly served as the minister's office, and a stairwell are located off the south side of the annex. The "welcome room" occupies the southwest corner of the side-gable section. The Frederick Church of Christ constructed a stairwell east of the "welcome room" as part of the 1970s renovations. The side entrance on the lower level of the south elevation (gable end) of the side-gable section was added during these renovations.

The lower level of the main block contains three offices, a nursery, and a mechanical room. Concrete-block walls are visible in the mechanical room. The Frederick Church of Christ converted one large room into the offices and nursery and replaced the former floor carpeting.

#### *Addition*

The majority of the lower level of the rear addition is occupied by a large fellowship hall that has a carpeted floor, metal support poles, and fluorescent ceiling lights. A kitchen, a small fellowship room, and a storage room are located along the north wall (east to west). The upper level of the addition features classrooms. The classrooms and central hallway are decorated with wall murals.

## 8. Significance

Inventory No. F-3-265

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other: _____

**Specific dates** 1947-1948 **Architect/Builder** Elder David G. Fleagle

**Construction dates** 1947-1948, ca. 1970

Evaluation for:

National Register  Maryland Register  not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

### Statement of Significance

The Frederick Church of Christ possesses significance in the area of architecture. The main block is an example of post-World War II *Gothic Revival* design, illustrating the lingering use of that nationwide style in mid-twentieth-century ecclesiastical architecture in Frederick. Gothic Revival traits exhibited by the Frederick Church of Christ include the irregular plan, the steeply pitched roof, the castellated tower, the pointed-arch grouped windows, the pointed-arch designs contained in the rectangular stained-glass windows, and the tracery ornamentation in the front door lights. The main block retains most of its original design elements and materials.

### Architectural Context: Gothic Revival Ecclesiastical Architecture

The Gothic Revival architectural style for church buildings became well established in the United States during the mid-nineteenth century (Rifkind 1980:137). Invoking the English medieval parish church, Gothic Revival ecclesiastical design was popularized by architects Richard Upjohn and James Renwick. Especially preferred by Episcopalian and Catholic parishes, the Gothic Revival church reflected “a new intensity of religious attitude and a revived orthodoxy in religious practice” (Rifkind 1980:137).

The Gothic Revival church plan typically consists of a rectangular nave with projecting additions such as towers, vestibules, baptisteries, and various service rooms, resulting in an irregular footprint. Gothic Revival church buildings are of masonry or frame construction and exhibit characteristics such as steeply pitched roofs, pointed-arch window openings (either single or grouped), stepped buttresses, and recessed openings (Rifkind 1980:138). Gothic windows often feature tracery ornamentation (Bucher 1996).

During the twentieth century, the Gothic Revival style remained popular for ecclesiastical architecture throughout the United States. Selective historical details were used in a manner that was compatible with modern needs (Rifkind 1980:158). Gothic Revival ornamentation was used in a manner that expressed “a quiet, rather than a blatant, originality” (Rifkind 1980:158). The style’s popularity for ecclesiastical construction declined after the 1920s. At that time, other styles such as Georgian, Colonial, or Romanesque were preferred (Rifkind 1980:158).

### Property History

The Frederick Church of Christ was constructed as the Frederick Seventh-day Adventist Church in 1947-1948 on an undeveloped parcel located within the Maple Park subdivision. Platted in 1922, the Maple Park subdivision was a planned development that reflected the broader pattern of residential development in the City of Frederick during the early twentieth century. The church property is located in the 1300 block along North Market Street, just outside the northern boundary of the National Register-listed Frederick Historic District (expanded) (National Register of Historic Places 1988). The National Register of Historic Places

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. F-3-265

Frederick Church of Christ  
Continuation Sheet

Number 8 Page 1

---

Nomination Form for the expansion of the historic district identifies two residential building types constructed within the city during the district's period of significance: "the vernacular attached building and the free-standing, more stylistic residence" (National Register of Historic Places 1988:7/2). The vernacular detached building was characterized as having two to three stories, two to three bays, and a shallow set back. The free-standing, more stylistic residence was characterized by its "scale, proportions and setting," which included a greater set-back and increased building size (National Register of Historic Places 1988:7/3). Free-standing residences became the norm after 1890 and appeared "in areas south, west, and north of the established [city] grid pattern," including the Maple Park subdivision (National Register of Historic Places 1988:7/3).

The Maple Park subdivision extended west from North Market Street to North Bentz Street, with interior lots fronting 12<sup>th</sup> and 13<sup>th</sup> Streets, the two streets immediately south of the present-day church property. Lots within the subdivision were subject to restrictions regarding building placement, use, and occupancy. The lots fronting 12<sup>th</sup> and 13<sup>th</sup> Streets had a minimum set-back of 25 feet, with larger, 88-foot set-backs on the lots fronting North Market Street. Stables could not be erected on the front portion of any lot. For a term of 25 years, no lots could be used for business purposes (FCLR Plat Book STH:139).

The Chesapeake Conference Association of Seventh-day Adventists purchased Lots 10 and 11 of the Maple Park subdivision in February 1947 as the site of their new church building (FCLR ECW 460:331). Construction of the building was organized by Elder David Fleagle and completed largely through the efforts of the congregation and volunteers from the community. Construction of the church foundation began in March (Frederick Seventh-day Adventist Church 2012:7). In August, *The Frederick News* reported that construction had begun on the roof "with their leaders from both Virginia and Maryland assisting Elder David Fleagle" (*The Frederick News* August 2, 1947). The church building was completed in 1948, and the first service was held on October 2 of that year (Frederick Seventh-day Adventist Church 2012:7). *The Frederick Post* reported on the church dedication ceremony:

More than 400 persons attended dedication ceremonies for the church, which was largely built by the laymen themselves, directed by the local pastor, Elder David Fleagle.

"Our little group of 42 persons could never have built this church, estimated by contractors as a \$50,000 structure, by themselves." Mr. Fleagle told the group. "Almost everybody in town had a hand in it. Electricians and other skilled workmen donated their services, businessmen gave money and materials. We feel that this is in a special way the community's church." [*The Frederick Post* October 4, 1948]

A church school was operated in the basement of the church building from 1951 until 1963, when construction was completed at the Frederick SDA Church School on Shookstown Road (Frederick Seventh-day Adventist Church 2012:9). The congregation of the Frederick Seventh-day Adventist Church grew rapidly during the 1960s. Much of this growth resulted from expansion at nearby Fort Detrick, as "U.S. Army servicemen who were part of the White Coat Operation at Fort Detrick and their families joined the growing congregation" (Frederick Seventh-day Adventist Church 2012:9). As the congregation outgrew the church building, the decision was made to temporarily relocate to the Shookstown Road School gymnasium until a new building could be constructed. The congregation held their final service at the North Market Street church building on December 27, 1969 (Frederick Seventh-day Adventist Church 2012:7, 9).

On December 31, 1969, the Frederick Church of Christ purchased the North Market Street church property (FCLR ECW 817:519). During the early 1970s, the Frederick Church of Christ constructed the rear addition and undertook renovations to the main church building. Alterations included renovation of the front door and replacement of the stained glass over it, relocation of the interior stairway to the church basement, reconfiguration of the basement rooms, and replacement of the basement floor carpeting. Interior renovations to the nave included enlargement of the stage area and the addition of stone ornamentation to the alcove. The Frederick Church of Christ also converted the rear lawn to a gravel parking lot (Jim Denison personal communication May 3, 2013).

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. F-3-265

Frederick Church of Christ  
Continuation Sheet

Number 8 Page 2

The chain of title for the Frederick Church of Christ summarizes its history of property ownership:

Liber/Folio	Date	Grantor/Grantee
ECW 817/519	12/31/1969	Chesapeake Conference Association of Seventh-day Adventists to Frederick Church of Christ; designated as Lot Nos. 10 and 11 on plat of "Maple Park" dated 10/21/1922 (FCLR Plat Book STH:139), excepting parcel previously conveyed (FCLR ECW 469:99); no restrictions on use or occupancy
ECW 460/331	2/5/1947	Robert L. Grove and Elizabeth F. Grove (his wife) to Chesapeake Conference Association of Seventh-day Adventists; Lots 10 and 11 of a Sub-division or Development known as "Maple Park"; subject to existing restrictions
ECW 442/334	6/9/1944	Clifford A. Bayard, <i>et al.</i> to Robert L. Grove and Elizabeth F. Grove (his wife); Lots 10 and 11 of a Sub-division or Development known as "Maple Park"; subject to existing restrictions
RLL 1/390 (Wills)	7/12/1941	Stephen A. Bayard (Last Will and Testament) to Clifford A. Bayard, <i>et al.</i> ; Lots 10 and 11 of a Sub-division or Development known as "Maple Park"; subject to existing restrictions
EGH 354/331	8/27/1925	Dora C. Fowler to Stephen A. Bayard and Sarah R. Bayard (his wife); Lots 10 and 11 of a Sub-division or Development known as "Maple Park"; subject to existing restrictions
EGH 340/568	12/15/1922	William C. Neidig to Dora C. Fowler; Lots 10, 11, 50, 51, 59, and 60 of a Sub-division or Development known as "Maple Park"; subject to seven restrictions on occupancy and use
WIP 4/231	4/12/1887	George Lawrence Cramer and Mary O. Cramer to William C. Neidig; sum of \$10,250.00; part of "Taskers Chance" also known as "Holly Park" containing 21 acres of land; sale included 1/4 of wheat crop "now growing" and the "hanging lamps attached to and now in the dwelling house"; grantor reserved right of entry to harvest wheat crop; no restrictions on occupancy or use

---

## 9. Major Bibliographical References

---

Inventory No. F-3-265

See continuation sheet.

---

## 10. Geographical Data

---

Acreage of surveyed property 0.83099  
Acreage of historical setting 0.83099  
Quadrangle name Frederick, MD

Quadrangle scale: 1:24,000

---

### Verbal boundary description and justification

The property boundaries are those of the 0.83099-acre parcel owned by the Frederick Church of Christ (Map 0409, Parcel 0628C).

---

## 11. Form Prepared by

---

name/title	Kathryn Dixon, Historic Preservation Specialist; Jennifer Evans, Historian		
organization	R. Christopher Goodwin & Associates, Inc.	date	May 2013
street & number	241 East Fourth Street	telephone	301-694-0428
city or town	Frederick	state	MD

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust  
Maryland Department of Planning  
100 Community Place  
Crownsville, MD 21032-2023  
410-514-7600

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. F-3-265

Frederick Church of Christ  
**Continuation Sheet**

Number 9 Page 1

---

### References Cited

Bucher, Ward (editor)

1996 *Dictionary of Building Preservation*. John Wiley & Sons, Inc., New York.

Denison, Jim

2013 Personal communication with pastor of Frederick Church of Christ on May 3.

Frederick County Land Records (FCLR)

various dates Deeds, Plats, and Equity Cases on file at the Frederick County Courthouse, Frederick, Maryland.

Frederick County Wills (FCW)

various dates Wills and Administrative Accounts on file at the Frederick County Courthouse, Frederick, Maryland.

*The Frederick News* [Frederick, Maryland]

various dates Electronic scans of original documents, <http://www.ancestry.com>, accessed May 9, 2013.

*The Frederick Post* [Frederick, Maryland]

various dates Electronic scans of original documents, <http://www.ancestry.com>, accessed May 9, 2013.

Frederick Seventh-day Adventist Church

2012 *Our Frederick Adventist Heritage*. Booklet prepared by Frederick Seventh-day Adventist Church, 6437 Jefferson Pike, Frederick, Maryland.

National Register of Historic Places

1988 Frederick Historic District (expanded), Frederick, Frederick County, Maryland, National Register #88000713.

Reed, Alberta

2012 Letter from Chairman, 100<sup>th</sup> Anniversary Celebration, Frederick Seventh-day Adventist Church, to Rev. Jim Denison, Pastor, Frederick Church of Christ. October 10.

Rifkind, Carole

1980 *A Field Guide to American Architecture*. Penguin Group, New York.

---

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. F-3-265

Frederick Church of Christ  
**Continuation Sheet**

Number Photo Log Page 1

---

### Photo Log


The following information is the same for each photograph:

1. MIHP # F-3-265
2. Frederick Church of Christ
3. Frederick County, MD
4. Kathryn Dixon, R. Christopher Goodwin & Associates, Inc. (RCG&A)
5. May 3, 2013
6. MD SHPO
7. Photo paper and ink: HP Vivera ink 97 Tri-Color cartridge, 101 Blue Photo cartridge, and 102 Gray Photo cartridge on HP Premium Photo Paper (high gloss)
8. Verbatim Ultralife Gold Archival Grade CD-R, Phthalocyanine Dye

F-3-0265_2013-05-03_01.tif	Context, view northwest from North Market Street
F-3-0265_2013-05-03_02.tif	Main block, east (front) elevation
F-3-0265_2013-05-03_03.tif	Main block, northeast corner
F-3-0265_2013-05-03_04.tif	Main block and addition, southeast corner
F-3-0265_2013-05-03_05.tif	Main block, tower, east (front) elevation, door detail
F-3-0265_2013-05-03_06.tif	Main block, side-gable section, east (front) elevation, window detail
F-3-0265_2013-05-03_07.tif	Main block, nave section, north elevation
F-3-0265_2013-05-03_08.tif	Main block, nave section, west (rear) elevation
F-3-0265_2013-05-03_09.tif	Main block, nave section, south elevation; connecting corridor, south elevation
F-3-0265_2013-05-03_10.tif	Main block, side-gable section and tower, southeast corner
F-3-0265_2013-05-03_11.tif	Main block, side-gable section, southwest corner
F-3-0265_2013-05-03_12.tif	Connecting corridor, north elevation
F-3-0265_2013-05-03_13.tif	Addition, southeast corner
F-3-0265_2013-05-03_14.tif	Addition, northwest corner
F-3-0265_2013-05-03_15.tif	Main block, nave interior, upper level, view west
F-3-0265_2013-05-03_16.tif	Main block, nave interior, upper level, view east

F-3-265  
Frederick Church of Christ  
Frederick  
Frederick County, MD  
May 2013  
Drawn by Kathryn G. Dixon

MAIN BLOCK: UPPER LEVEL  
Room Arrangement Only - Not to Scale







MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RCG+A

May 3, 2013

MD SHPO

Context, view northwest from North Market  
street

1/16



CHURCH  
OF  
CHRIST

WEDNESDAY 8:00 P.M.  
SUNDAY 10:00 A.M.  
SUNDAY 5:00 P.M.  
BAPTIST CHURCH OF CHRIST  
1000 N. 10th St. - Grand Rapids, Mich.

MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon RCG+A, Inc.

May 3, 2013

MD SHPO

Main block, east (front) elevation

2/16



MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RCGTA

May 3, 2013

MD SHPO

Main block, northeast corner

3/16



URCH  
RIST

MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RCB+A

May 3, 2013

MD SHPO

Main block and addition, southeast  
corner

4/16



CHURCH OF  
CHRIST

MHP# F-3-265

Frederick Church of Christ  
Frederick County, MD  
Kathryn Dixon, RC&TA  
May 3, 2013  
MD SH PO

Main block, tower, east  
(front) elevation, door  
detail

5/16



MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RCG+A

May 3, 2013

MD SHPO

Main block, side-gable section, east (front)  
elevation, window detail

6/16



MHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RCG+A

May 3, 2013

MD SHPO

Main block, nave section, north elevation

7/16



MHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RC&A

May 3, 2013

MD SHPO

Main block, nave section, west (rear)  
elevation

8/16



MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RCG+A

May 3, 2013

MD SHPO

Main block, nave section, south elevation;  
connecting corridor, south elevation

9/16



MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RCB+A

May 3, 2013

MD SHPO

Main block, side-gable section and tower,  
Southeast corner

10/16



MIHP # F-3-265

Frederick Church of Christ  
Frederick County, MD

Kathryn Dixon, RCB+A

May 3, 2013

MD SHPO

Main block, side-gable section, southwest  
corner

11/16



MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RCG+A

May 3, 2013

MD SHPO

Connecting corridor, north elevation

12/16



MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RCG+A

May 3, 2013

MD SHPO

Addition, southeast corner

13/16



MIHP # F-3-265

Frederick Church of Christ  
Frederick County, MD

Kathryn Dixon, RCG+A

May 3, 2013

MD SHPO

Addition, northwest corner

14/16



A HEAVY  
FORTRESS  
IS OUR GOD  
BULWARK  
NEVER FAILS

*Hosanna!*

MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RCG+A

May 3, 2013

MD SHPO

Main block, have interior, upper level,  
view west

15/16



MIHP # F-3-265

Frederick Church of Christ

Frederick County, MD

Kathryn Dixon, RC&A

May 3, 2013

MD SHPO

main block, nave interior, upper level,  
view east

16/16