

**MARYLAND HISTORICAL TRUST
DETERMINATION OF ELIGIBILITY FORM**

NR Eligible: yes
no

Property Name: Olin Wilhelm House Inventory Number: G-I-A-148
 Address: 988 Lancaster Hill Road Historic district: yes no
 City: Avilton Zip Code: 21539 County: Garrett
 USGS Quadrangle(s): Avilton
 Property Owner: Ada E. Layton Tax Account ID Number: 001933
 Tax Map Parcel Number(s): 0019 Tax Map Number: 0029
 Project: Fourmile Ridge Wind Energy Project Agency: USACE
 Agency Prepared By: GAI Consultants, Inc.
 Preparer's Name: Mike Kenneally Date Prepared: 12/3/2013
 Documentation is presented in: MIHP form
 Preparer's Eligibility Recommendation: Eligibility recommended Eligibility not recommended
 Criteria: A B C D Considerations: A B C D E F G
Complete if the property is a contributing or non-contributing resource to a NR district/property:
 Name of the District/Property: _____
 Inventory Number: _____ Eligible: yes Listed: yes
 Site visit by MHT Staff yes no Name: _____ Date: _____

Description of Property and Justification: *(Please attach map and photo)*

Physical Description

The Olin Wilhelm House is located in a hilly area on the south side of Lancaster Road at the intersection of Avilton-Lonaconing Road in Garrett County. The resource consists of a circa 1902 dwelling and five circa 1940 outbuildings, including a shed, coal shed, springhouse, vehicle shed, and equipment shed.

Dwelling (Circa 1902)

The dwelling is a circa 1902 two-story, four-bay, wood-frame vernacular house constructed upon a concrete block foundation, clad in replacement weatherboard siding, and capped with a corrugated metal side gable roof. The weatherboard siding is unpainted and has recently been added to the dwelling. A central interior concrete block chimney pierces the roof at the ridgeline. It appears that this chimney replaces an original. The façade (east elevation) and north elevation features a wrap-around porch covered with a corrugated metal shed roof with exposed rafter tails. The porch rests on a concrete block foundation and is supported by square posts. According to photographs taken during the previous 1982 survey, a one-story gable roof addition was once appended to the north elevation, but it has recently been removed (MIHP G-I-A-148). Fenestration consists of paired and single one-over-one double-hung replacement vinyl sash windows, and the original wood window surrounds have been removed. The house stands in

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended Eligibility not recommended
 Criteria: A B C D Considerations: A B C D E F G

MHT Comments:

Jonathan Sager
 Reviewer, Office of Preservation Services

1/3/14

Date

NA
 Reviewer, National Register Program

Date

fair condition.

Coal Shed (Circa 1940)

A one-story wood-frame coal shed is located to the south of the dwelling. The coal shed is clad on the south and west elevations in vertical plank siding and a panel of corrugated metal, but it is otherwise open. The shed is capped with a corrugated metal shed roof with exposed rafter tails. An open shed roof shelter is appended to the west elevation. The interior of the shed also features a coal furnace. The siding and corrugated metal roof appear to have recently been added.

Shed (Circa 1940)

A one-story wood-frame shed is located to the southwest of the dwelling. The shed is clad in vertical wood boards and capped with a shed roof covered with corrugated metal and featuring exposed rafter tails. The façade also features a plywood door. This structure appears to have been recently re-sided and the corrugated metal roof appears to be new.

Springhouse (Circa 1940)

A one-story concrete block springhouse is located to the west of the dwelling. The springhouse is clad in vertical wood boards in the gables, and capped with a front gable roof covered with corrugated metal. Fenestration consists of a metal sliding sash window on the façade. A small shed roof concrete block structure also sits on the south side of the springhouse.

Equipment/Vehicle Sheds #1 and #2 (Circa 1940)

Two one-story wood-frame equipment/vehicle sheds are located to the northeast of the dwelling on the east side of a dirt lane. Both sheds were constructed circa 1940, clad in vertical wood boards, and capped with a front gable roof covered with corrugated metal. Equipment/Vehicle Shed #1 features exposed rafter tails, and the west elevation features a large sliding bay door. Equipment/Vehicle Shed #2, located to the south of Equipment/Vehicle Shed #1, features shed roof additions appended to the north and south elevations, and the west elevation features a central sliding bay door with entry doors in each of the shed roof additions.

History and Significance:

The first Europeans began to arrive in the area around Avilton, Maryland in the mid-eighteenth century. There is little record of those who settled in the area first, as they did not file patents or commission surveys, but built cabins and cleared small portions of land. However, after the Revolutionary War development in the area greatly expanded. The forests that covered the mountains were slowly but surely cleared. Pine forests largely made up the land between Savage and Negro Mountains, with a few other varieties like spruce and hemlock intermixed (Brown 1896:54). These large wood-covered miles attracted many hunters to the area, including Meshach Browning, who wrote a book about the many years he spent living as a pioneer in the area around Avilton and directly west. Hunters like Browning who populated the area used the National Road, which was constructed through the area in the early nineteenth century, to get their hides and meats back to eastern markets (Browning 1942:195). While the hunters settled early, it was not long before additional lots were readied for settlement. Many of the earliest lots in the area were surveyed for veterans of the Revolutionary War. Some of these lots went to men like Thomas Johnson, who eventually became Governor of Maryland. There were also land speculators who made their mark on the area, including men like Brooke Beall and William Deakins (Rowland 2009:39).

The earliest land records of the area typically consist of people with large tracts of land selling those tracts to other speculators. But, starting in the mid-1800s that began to change, as smaller portions of land were sold off, and more and more farms were raised in the valleys between the mountains. As land was freshly cleared, many farmers from east of the Appalachians began to plant tobacco. However, they learned quickly that the soil was made too poor by tobacco farming in this area (Brown 1896:300).

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended

Eligibility not recommended

Criteria: A B C D Considerations: A B C D E F G

MHT Comments:

Reviewer, Office of Preservation Services

Date

Reviewer, National Register Program

Date

The settlement that would later become Avilton was originally known as "The McKenzie Settlement" for the many numbers of Scottish immigrants, particularly McKenzies, who settled there. The early farmers of this area grew primarily wheat, rye, oats and potatoes. A partial listing of the founding families of this area was included in Garrett County: A History of Maryland's Tableland and includes: Garlitz, Blocher, Wilhelm, Broadwater, Miller, Crowe and Merrill among others. By 1885, the area was known as Avilton, and a post office was opened under that name (Schlosnagle 1978:65).

In the second half of the nineteenth century, railroads made their way through Garrett County, connecting the area like never before. As the railroads arrived, the many pine forests that surrounded area farms were looked at with a new sense of their value. While they had been used as a source of building materials for years, the forests were now logged and the timber was shipped to larger markets on the railroad. On Savage Mountain, it was the Juniata Lumber Company that took advantage of the fine timber of the area (Brown 1896:264,275). Increasingly, the agricultural area was dotted throughout by people who worked in the industry. As Jacob Brown described the area "she grew from a county of crude backwoods settlements and small self-sufficient farms to a county of coal towns, timber towns, resort towns, trade towns, and increasingly fertile fields and meadows." (Brown 1896:304) While the area was still largely rural, times were slowly changing.

By the first half of the twentieth century, more and more people were working both on their farms and in various industries. By the 1940 Census, many household heads were listed as working in mining or timbering, while it is also indicated that many continued to pursue agriculture (Ancestry.com). While they produced goods for local markets, the demands of an increasingly connected society drew more and more residents off their farms. The effects of the great depression were also seen in the 1940 Census of the area, with many people listed as road builders or general laborers who were employed in emergency government work (Ancestry.com). After World War II, some farms began to not be used for agriculture. This has led to the decline of some of the properties, and the destruction of others. Many families, descendants of the original settlers at McKenzie Settlement, continue to use the fields around Avilton to raise cows and some grains, continuing some of the traditions that were started so many years ago.

The Olin Wilhelm House is located near Lonaconing, an agricultural community in eastern Garrett County. The area around the property is largely forest and agricultural fields, and has been for many years. The property consists of a circa-1902 wood-frame dwelling, and several circa-1940 outbuildings.

The earliest recovered deed transfer of the property dates from September 21, 1887, when the Lochiel Lumber, Mining, Manufacturing, and Improvement Company sold 269.25 acres of the "Lochiel" tract to John Wilhelm (Garrett County Deed Book 13:184). Just over one year later, on November 10, 1888, John Wilhelm sold 115 acres of his "Lochiel" property to his son John Olin Wilhelm (Garrett County Deed Book 14:195).

John Olin Wilhelm was born April 24, 1863, to John and Racheal Jenkins Wilhelm in Allegany/Garrett County (United States Census Bureau 1870; Find A Grave 2000c). According to the 1880 United States Census, John Olin worked as a laborer, while his father worked as a carpenter (United States Census Bureau 1880). John Olin married Mary C. Garlitz in about 1885, and a few years later purchased the 115-acre "Lochiel" tract in Garrett County (Garrett County Deed Book 14:195). After Mary Garlitz Wilhelm died in 1892, John Olin married her younger sister Ada Elizabeth Garlitz. John O. Wilhelm worked as a farmer for approximately 44 years and raised seventeen children, five with Mary C. Wilhelm and twelve with Ada E. Wilhelm, on the 115-acre property (United States Census Bureau 1900; 1910; 1920; 1930). After John O. Wilhelm's death in 1932, Ada Wilhelm continued to live and farm the property until her own death in 1947 (United States Census Bureau 1940; Find a Grave 2000a; 2000c).

After the deaths of John O. and Ada E. Wilhelm, ownership of the property passed to their heirs, including Metta Seiforth, Minnie Russell, Leonard Wilhelm, Mary Broadwater, Asa Wilhelm, Thomas Wilhelm, Elizabeth Wilhelm, and their respective spouses. The Wilhelm heirs conveyed the 115-acre property to John O. and Ada E. Wilhelm's son Thomas R. Wilhelm and his wife Hilda

MARYLAND HISTORICAL TRUST REVIEW													
Eligibility recommended							Eligibility not recommended						
Criteria:	A	B	C	D	Considerations:	A	B	C	D	E	F	G	
MHT Comments:													
_____ Reviewer, Office of Preservation Services							_____ Date						
_____ Reviewer, National Register Program							_____ Date						

on March 8, 1975 (Garrett County Deed Book 368:229). In 1940, Thomas Wilhelm lived with his mother and younger siblings Floyd and Elizabeth Wilhelm on the family farm, and it is likely that Thomas continued to operate the farm after his mother's death (United States Census Bureau 1940). Thomas R. Wilhelm died in 1992, and Hilda Wilhelm died in 1998 (Find a Grave 2000b; 2000d). Ada E. Layton, Thomas and Hilda's daughter, purchased the property from their estate on June 22, 1999 (Garrett County Deed Book 776:738).

NRHP Evaluation

No information could be located that connects the Olin Wilhelm Farm to significant events or themes in local, state, or national history. As such, this resource is recommended not eligible for NRHP listing under Criterion A. The extant resources on the property are associated with farmer John Olin Wilhelm who owned the farmstead from 1888 until his death in 1932, and likely constructed the circa-1902 dwelling, and his son Thomas R. Olin, who likely operated the farm from circa 1940 until his death in 1992, and likely constructed most of the extant outbuildings. Local historical and genealogical sources provide no further information relating to John Olin Wilhelm, Thomas R. Wilhelm, or any other individuals associated with the property, and there is no evidence that any individuals associated with the property were significant in local, state, or national history. Therefore, this resource is recommended not eligible for NRHP listing under Criterion B. The Olin Wilhelm House stands as a common and unexceptional example of early twentieth-century vernacular architecture in western Maryland. In addition, the house is heavily altered, and the application of modern wood siding, vinyl replacement windows, modern chimney stack, and removal of original window surrounds has diminished the dwelling's historic character and integrity. The house no longer maintains integrity of design, materials, workmanship, and feeling. The extant barn, sheds, and springhouse also represent common and altered examples of agricultural buildings in western Maryland. As such, the Olin Wilhelm Farm is recommended not eligible for NRHP listing under Criterion C. Eligibility under Criterion D cannot be determined as this resource has not undergone archaeological testing.

References

Allegany County Land Records.
Various years Recorder of Deeds. Retrieved from <http://www.mdlandrec.net>.

Brown, Jacob
1896 Brown's Miscellaneous Writings Upon a Great Variety of Subjects. J. J. Miller: Cumberland, MD.

Browning, Meshach
1942 44 Years of the Life of a Hunter. Winston Printing Company: Winston-Salem, NC.

Find a Grave
2000a "Ada E. Wilhelm." Find a Grave. Electronic document, <http://www.findagrave.com/cgi-bin/fg.cgi?page=gr&Grid=5073745>, accessed 1 December 2013.
2000b "Hilda Wilhelm." Find a Grave. Electronic document, <http://www.findagrave.com/cgi-bin/fg.cgi?page=gr&Grid=5073776>., accessed 1 December 2013.
2000c "John Olin Wilhelm." Find a Grave. Electronic document, <http://www.findagrave.com/cgi-bin/fg.cgi?page=gr&Grid=5073741>, accessed 1 December 2013.
2000d "Thomas Richard Wilhelm." Find a Grave. Electronic document, <http://www.findagrave.com/cgi-bin/fg.cgi?page=gr&Grid=5073787>, accessed 1 December 2013.

Garrett County GenWeb

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended _____ Eligibility not recommended _____
Criteria: A B C D Considerations: A B C D E F G

MHT Comments:

Reviewer, Office of Preservation Services

Date

Reviewer, National Register Program

Date

2013 "Garrett County Marriages." Garrett County Maryland Genealogy. Electronic document, <http://www.rootsweb.ancestry.com/~mdgarret/marriages/marws.html>, accessed 1 December 2013.

Garrett County Land Records
Various years Recorder of Deeds. Retrieved from <http://www.mdlandrec.net>.

H., W. A.
1935 Map of Military Lots, Tracts, Escheats, &c. in Garrett County, MD and Allegany County, MD.
West of Cumberland: Prepared Under Act of 1874 Chapter 322 &c.

Rowland, Tim
2009 Maryland's Appalachian Highlands. History Press: Charleston, SC.

Schlosnagle, Stephen and the Garrett County Bicentennial Committee
1978 Garrett County: A History of Maryland's Tableland. McClain Printing Company: Parsons, WV.

United States Census Bureau
1870 1870 United States Federal Census. Available at Ancestry.com.
1880 1880 United States Federal Census. Available at Ancestry.com.
1900 1900 United States Federal Census. Available at Ancestry.com.
1910 1910 United States Federal Census. Available at Ancestry.com.
1920 1920 United States Federal Census. Available at Ancestry.com.
1930 1930 United States Federal Census. Available at Ancestry.com.
1940 1940 United States Federal Census. Available at Ancestry.com.

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended _____ Eligibility not recommended _____

Criteria: A B C D Considerations: A B C D E F G

MHT Comments:

Reviewer, Office of Preservation Services

Date

Reviewer, National Register Program

Date




SOURCE: MICROSOFT CORPORATION, 2013.

gai consultants

G-I-A-148
Resource Sketch Map

Olin Wilhelm House
988 Lancaster Hill Road
Avilton, Garrett County



gai consultants

SOURCE: USGS 7.5 MINUTE AVILTON
QUADRANGLE MAP (1947, PHOTOREVISED
1981).

G-I-A-148

Olin Wilhelm House
988 Lancaster Hill Road
Avilton, Garrett County

G-I-A-148
Olin Wilhelm House
GAI Consultants, Inc.
Previously Recorded Resources within Indirect APE – Fourmile Wind Energy Project
Garrett County, Maryland
Epson Premium Glossy Paper/Epson UltraChrome pigmented inks

G-I-A-0148_2013-08-22_01 – Main dwelling, north façade, facing south

G-I-A-0148_2013-08-22_02 – Main dwelling, north and west facades, facing southeast

G-I-A-0148_2013-08-22_03 – Coal shed, facing southeast

G-I-A-0148_2013-08-22_04 – Shed, facing west

G-I-A-0148_2013-08-22_05 – Springhouse, facing northwest

G-I-A-0148_2013-08-22_06 – Main dwelling, south and west facades, facing northeast

G-I-A-0148_2013-08-22_07 – Main dwelling, south façade, facing north

G-I-A-0148_2013-08-22_08 – Main dwelling, south and east façades, facing northwest

G-I-A-0148_2013-08-22_09 – Vehicle shed, facing east

G-I-A-0148_2013-08-22_10 – Equipment shed, facing northeast



G-1-A-148
Olin Wilhelm House
Garrett County, Maryland

Liz Williams

8-22-13

MD SHPO

Main dwelling, North facade, facing South

1/10



G-1-A-148

Olin Wilhelm House

Garrett County, Maryland

Liz Williams

8-22-13

MD SHPO

Main dwelling, north and west facades, facing Southeast

2/10



G-1-A-148
Olin Wilhelm House
Garrett County, Maryland
Liz Williams
8-22-13
MD SHPO
Coal shed, facing Southeast
3/10



G-1-A-148
Olin Wilhelm House
Garrett County, Maryland
Liz Williams
8-22-13
MO SHPO
Shed, facing west
4/10



G-1-A-148
Olin Wilhelm House
Garrett County, Maryland
Liz Williams
8-22-13
MD SHPO
Springhouse, facing northwest
5/10



G-1-A-148

Olin Wilhelm House
Garrett County, Maryland

Liz Williams

8-22-13

MD SHPO

Main dwelling, south and west facades, facing northeast

6/10



G-1-A-148

Olin Wilhelm House

Garrett County, Maryland

Liz Williams

8-22-13

MD SHPO

Main dwelling, south facade, facing north

7/10



G-1-A-148
Olin Wilhelm House
Garrett County, Maryland

Liz Williams

8-22-13

MD SHPO

Main dwelling, south and east facades, facing northwest

8/10



G-1-A-14B
Olin Wilhelm House
Garrett County, Maryland
Liz Williams

8-22-13

MD SHPD

Vehicle shed, facing east

9/10



G-1-A-148

Olin Wilhelm House

Garrett County, Maryland

Liz Williams

8-22-13

MD SHPO

Equipment Shed, facing northeast

10/10

G-I-A-148

Olin Wilhelm House
Avilton
Private

c.1902

The Olin Wilhelm house is a four bay by two bay, two story frame structure with a gable roof. A single story gable roof addition is located to the rear of the northeast elevation. The house is covered with hemlock weatherboard with cornerboards. The roof is covered with tar paper. The house was built by farmer Olin Wilhelm approximately 80 years ago.

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

AND/OR COMMON

Olin Wilhelm House

2 LOCATION

STREET & NUMBER

Lancaster Hill Rd. , at intersection with Avilton-Lonaconing Rd.

CITY, TOWN

Avilton

VICINITY OF

CONGRESSIONAL DISTRICT

6th

STATE

Maryland

COUNTY

Garrett

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE	
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL	<input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL	<input checked="" type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT	<input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> GOVERNMENT	<input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL	<input type="checkbox"/> TRANSPORTATION
		<input checked="" type="checkbox"/> NO	<input type="checkbox"/> MILITARY	<input type="checkbox"/> OTHER

4 OWNER OF PROPERTY

NAME

Telephone #:

STREET & NUMBER

CITY, TOWN

VICINITY OF

STATE, zip code

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC.

Garrett County Courthouse

Liber #:

Folio #:

STREET & NUMBER

Third and Alder Streets

CITY, TOWN

Oakland

STATE
Maryland 21550

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

None

DATE

FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

G-I-A-148

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input checked="" type="checkbox"/> UNALTERED	<input type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

This frame house is situated on a hilly, semi-wooded area on Lancaster Hill Road near the intersection with Avilton-Lonaconing Road and faces southeast. It is a four bay by two bay, two story structure with a gable roof. A single story gable roof addition is located to the rear of the northeast elevation. A wooden porch with wooden posts, balustrades and bracketing runs the length of the facade and the northeast elevation of the main block. Entrances are located on the facade, the southwest elevation of the main block and on the southwest elevation of the addition.

The house has a central brick chimney on the main block and an exterior brick end chimney on the northeast elevation of the addition. Six over six windows light the house. The window heads are pedimented and ornamented. Six pane windows appear in the gables. The house is covered with hemlock weatherboard with cornerboards. The roof is covered with tarpaper.

A frame barn, springhouse and coal shed are included on the property.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION	
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE	
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE	
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER	
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION	
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)	
		<input type="checkbox"/> INVENTION			

SPECIFIC DATES	1902	BUILDER/ARCHITECT	Olin Wilhelm
----------------	------	-------------------	--------------

STATEMENT OF SIGNIFICANCE

This house is an example of a common western Maryland type. Houses of this general configuration, a rectangular main block, were constructed in Garrett County from the late nineteenth through the early twentieth centuries. The house was built by farmer, Olin Wilhelm approximately 80 years ago.

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE COUNTY

STATE COUNTY

11 FORM PREPARED BY

NAME / TITLE

Valerie Cesna, Historic Sites Surveyor

ORGANIZATION

Maryland Historical Trust/ Bureau of Mines

DATE

May 1982

STREET & NUMBER

Shaw House, 21 State Circle

TELEPHONE

(301) 269-2438

CITY OR TOWN

Annapolis

STATE

Maryland 21401

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438



Avilton, MD-PA
 USGS 7.5 Minute Series
 Scale 1:24,000
 1947; photorevised 1974

Site #: G-I-A-148
 Olin Wilhelm House
 Lancaster Hill Road
 at intersection with
 Avilton-Lonaconing Rd.



G-I-A-148

Olin Wilhelm House

Garrett Co., MD

Valerie Cesna 6/18/81

Facade: SE & NE elevs.



G-I-A-148

Olin Wilhelm House

Garrett Co., MD

Valerie Cesna 6/18/81

Rear: NW & SW elevs.