


Addendum

G-IV-A-059
Mountain Lake Park
Historic District
Garrett County

Preparer: Richard A. Geidel
Date prepared: October 28, 1998

Based on information from a survey of the Mountain Lake Park Historic District in January 1997 by KCI Technologies, Inc., the district remains eligible for listing in the National Register of Historic Places. Although some changes have occurred within the district, these changes have not fundamentally altered the historical and architectural significance of the district as a whole. The boundaries of the district as mapped and described in the National Register Nomination Form completed in 1983 remain valid.

A copy of a figure showing the boundaries of the Mountain Lake Park Historic District accompanies this Addendum.



US 219 in Oakland, Garrett County, MD March, 1998



Figure 13
 Sections of the Oakland, MD-WVA (USGS, 1974) and Deer Park, MD (USGS 1981) 7.5' Quadrangle maps showing the location of historic resources previously documented by the MHT within or adjacent to the southern half of the APE (Resources within Oakland shown on Figure 15)

Form HCRS 100-100

received

date entered

National Register of Historic Places Inventory—Nomination Form

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic Mountain Lake Park

and or common Mountain Lake Park Historic District (preferred)

2. Location

street & number Multiple Streets N/A not for publication

city, town Mountain Lake Park N/A vicinity of congressional district Seventh

state Maryland code 24 county Garrett code 023

3. Classification

Category	Ownership	Status	Present Use
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture
<input type="checkbox"/> building(s)	<input type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial
<input type="checkbox"/> structure	<input checked="" type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input checked="" type="checkbox"/> private residence
			<input type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property

name Multiple public and private owners

street & number

city, town _____ vicinity of _____ state _____

5. Location of Legal Description

courthouse, registry of deeds, etc. Garrett County Courthouse

street & number

city, town Oakland state Maryland

6. Representation in Existing Surveys

title Maryland Historical Trust
Historic Sites Inventory has this property been determined eligible? yes no

date 1983 federal state county local

depository for survey records Maryland Historical Trust, 21 State Circle

city, town Annapolis state Maryland 21401

7. Description

G-IV-A-059

Condition		Check one	Check one
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

SUMMARY DESCRIPTION

The Mountain Lake Park Historic District is a group of 212 buildings lying within the town of Mountain Lake Park, a residential community built beginning in the 1880's as a summer resort and important as a center of the Chautauqua movement in Maryland. The town is situated on a high plateau in the section of Garrett County known as "the Glades", three miles east of Oakland in western Maryland. The street plan of Mountain Lake Park was designed by H. E. Faul, the creator of Druid Hill Park in Baltimore, and consists of a grid of streets through which run several curving drives. These were designed primarily as scenic carriage drives, particularly Mountain Lake Drive which follows the outline of the artificial lake created in the early 1880's on the eastern edge of town. The only major change to this plan occurred in the mid-twentieth century when Maryland Route 135 was run through the center of town in an east-west direction, thereby dividing Mountain Lake Park into approximately equal halves. The district is roughly bounded by the tracks of the Baltimore and Ohio Railroad on the south, Youghiogeny Drive to the east, Oakland Avenue to the north and "D Street" to the west. The area of Mountain Lake Park outside of the historic district contains both modern houses and extensively altered nineteenth century ones. The district still includes many of the houses built by summer residents of Mountain Lake Park in the late nineteenth and early twentieth centuries. The majority of these houses are frame and were built in various interpretations of the "Country Gothic" or Rural Queen Anne styles. Many are still painted in the original bright colors and are in generally good or fair condition. Several of the houses were sited to take advantage of a particular view or natural feature, and most stand on large wooded lots. Also within the district are several of the educational and recreational buildings constructed by the Mountain Lake Park Association, the Methodist-led group which owned and managed the town for many years after its founding in 1881. Notable buildings within the district include those associated with the Mountain Chautauqua program: the tabernacle, a ticket office, and the tennis clubhouse. There are also several outstanding and well maintained Queen Anne style summer residences built at the turn of the century, along with a number of boarding houses dating from the period when Mountain Lake Park was a popular summer resort on the route of the B & O Railroad.

GENERAL DESCRIPTION

Among the largest and best preserved residences, is the frame Queen Anne style house on the west side of "G" Street close to the B & O railroad tracks. It is a rambling two and one half story house with a wide one story porch which wraps around the south and east facades. Its irregular appearance is accentuated by a two story polygonal bay on both the south and north facades and the one story square tower with a bell cast roof which sits on the north east corner of the roof. The combination of different textures is a hallmark of the Queen Anne style; on this house there is fish scale shingling covering the northeast tower as well as on a band running between the first and second floors and there is

United States Department of the Interior
National Park Service

G-IV-A-059

For NPS use only

National Register of Historic Places Inventory—Nomination Form

received

date entered

Continuation sheet	Mountain Lake Park Historic District Garrett County, Maryland	Item number	7	Page	1
--------------------	--	-------------	---	------	---

GENERAL DESCRIPTION (Continued)

half timbering in a checker-board pattern on the north and south gables. Also notable is the wooden balustrade and gallery of the porch which are in a similar geometric design.

On a similar scale is the two and one half story house built on an "L" shaped plan at the northeast corner of "I" and Cedar Streets. The house is notable for the tall diamond headed windows with matching shutters on the second story, the wrap-around porch with jigsaw brackets, and the three story tower with a cross gabled roof set between the two arms of the house.

Both this house and the Vandiver cottage at the corner of Youghiogheny Drive and M Street are known locally as examples of "Missionary Gothic" because of the tall lancet windows and the fact that both were built for Methodist clergymen. The latter house is a large two and one half story frame house with steeply pitched gable roofs, "picket fence" gables, one story wrap around porch and a three story tower on the southwest corner. The tower is topped with a steeply pitched roof with flaring eaves and the recessed dormers have trapezoidal gables, also with flaring eaves. An almost exact replica of the house stands on "I" Street in the southern half of town.

Another example of the rural Gothic style is the house at the southeast corner of Oak and "G" Streets. The two and one half story house is built with board and batten and has steeply pitched roofs, irregularly placed dormers and chimneys, and a one story roof supported by crucked posts. It is one of several board and batten houses in Mountain Lake Park, another being at the southeast corner of "G" and Spruce Streets. It is notable for the way in which the vertical boards are carried up two full stories, uninterrupted by either a porch or protruding bay.

A notable example of a house built in the Colonial Revival style is the residence on the east side of "G" Street between Cedar and Oak Streets. It is a two and one half story frame house painted yellow with a symmetrical facade, shingle covered gables, and a wrap-around porch supported by plain Doric columns. A center gable roof extends over the second story and is supported by a row of Doric columns, forming a small porch on the second story. The elaborately stained glass front door is also an outstanding original feature. The circular one story wing with conical roof is a recent addition.

Of the smaller houses in Mountain Lake Park, the Baldwin Cottage on "N" Street is one of the most distinctive. The porch is this house's most outstanding feature and is covered with jig-sawn decorations in a vaguely Gothic motif. A small porch with a hooded gable roof extends from the center of the second story and a triangular hood extends over the first story entrance.

United States Department of the Interior
National Park Service

C-107-A-059

For NPS Use Only

National Register of Historic Places Inventory—Nomination Form

received

date entered

Continuation sheet Mountain Lake Park Historic District
Garrett County, Maryland Item number 7 Page 2

GENERAL DESCRIPTION (Continued)

The Chautauqua Cottage at "H" and Oakland Streets was originally built as an annex to the now demolished Chatauqua Hotel and is therefore indicative of the appearance of the larger building. Plainer than the Baldwin Cottage, it is distinguished nonetheless by the three sided porch with brackets, scrolled woodwork between the posts, and jigsaw balustrade, as well as the diamond headed windows on the second story.

The Carr Cottage on Allegheny Drive is a similarly charming cottage. Very asymmetrical in its composition and roofline, the two story house has a one story porch with whimsical scrolled brackets, a projecting bay on the east facade and an incongruous French Second Empire style window on the east side of the south facade.

Of the nearly thirty hotels and boarding houses which once stood in Mountain Lake Park until 1911, only the Hotels Washington and Braethorn are still standing. The former, on Philadelphia Avenue, is a two and one half story frame house with a mansard roof and four bay wide bracketed porch with folding shutters. Actually a boarding house, the building had no lobby, but meals were served in a large dining room.

Considerably larger is the Hotel Braethorn on Oakland Avenue, a two story "T" shaped building with a high mansard roof covered with shingles and dormer windows on all four sides. A one story veranda wraps around two of the sides and is pedimented at the southwest corner over the entrance.

The Mountain Lake Park Association, which founded the town as a center of Methodist educational and cultural activity, erected a number of buildings in the town. These were used during the summer performances of the Mountain Chautauqua, held annually between 1882 and 1941. Unfortunately, the Tabernacle building on Spruce Street is the only major building connected with the Chautauqua programs still standing. Built in 1882, it has been expanded several times, most recently in the 1950's, and is still used by Methodist camp meetings. The original part is an imposing two story, seven bay wide building with a double gable roof. A three bay wide pedimented and bracketed porch frames the front entrance and there is a belfry atop the center dormer on the same facade.

Nearby is the little one story ovoid ticket office built in 1900, the same year that the magnificent circular Bashford amphitheatre was built. Other buildings formerly owned by the Park Association are the El Lobo's Restaurant, once operated as a refreshment stand, and the tennis club house, now used for the town council office. The tennis club house was at one time connected to a bowling alley, but the latter was disengaged from the club house and moved to the far northern part of town.

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input checked="" type="checkbox"/> community planning	<input checked="" type="checkbox"/> landscape architecture	<input checked="" type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input checked="" type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input checked="" type="checkbox"/> other (specify) recreation

Specific dates 1881 - c. 1920 Builder Architect H. E. Faul, landscape architect

Statement of Significance (in one paragraph) Applicable Criteria: A and C

SIGNIFICANCE SUMMARY

The Mountain Lake Park Historic District is significant for its association with the development of resort communities in late 19th century America, and for its cohesive collection of well-preserved buildings representing various types of resort architecture of the period. Among the resort communities which developed late in the 19th century in the mountains of Western Maryland in response to the B & O Railroad's extension of service to the area, Mountain Lake Park is unique. It was established in 1881 by a group of Methodist ministers; the religious and educational programs which the community offered, and the code of conduct which it maintained, provided vacationers with an alternative to the sinful and frivolous entertainments available in other nearby resorts which were founded as secular, speculative ventures. Among the cultural programs offered in Mountain Lake Park was the "Mountain Chautauqua," which blended religious revivalism with cultural and educational activities; in its heyday between the 1880's and World War I, this program attracted thousands to the community for symphonies, operas, plays, and nationally-prominent speakers including President Taft, Samuel Gompers, William Jennings Bryan and Billy Sunday. The popularity of Mountain Lake Park during these years spurred the construction of numerous cottages, hotels, and boarding houses, as well as public buildings; the present Historic District retains many of these buildings in excellent condition, and achieves significance for its outstanding collection of late 19th and early 20th century resort architecture. The District also retains much of its original wooded setting and street plan, designed by landscape architect H. E. Faul.

HISTORY AND SUPPORT

Mountain Lake Park, the site of an annual summer Chautauqua for nearly sixty years, was at one time one of the most important centers of religious, cultural and educational activity in the state. Indeed, its purpose for coming into existence as well as the prominent personalities with which it was associated, make the story of Mountain Lake Park important to the cultural history of America.¹ It also remains the best preserved of the once numerous resort communities which grew up along the route of the Baltimore and Ohio Railroad in southern Garrett County.²

The initial impetus for the establishment of Mountain Lake Park was undoubtedly the success of the nearby resort communities owned and operated by the B & O Railroad in Oakland and Deer Park.³ With these two in mind, a group of five Methodist ministers from Wheeling, West Virginia formed the Mountain Lake Park Association in 1881 to purchase eight hundred acres three miles east of Oakland for the site of a resort community.⁴ Unlike most of the other founders of speculative resorts in the area, however, these ministers sought

United States Department of the Interior
National Park Service

G-3N-A-059

For NPS use only

National Register of Historic Places
Inventory—Nomination Form

received

date entered

Mountain Lake Park Historic District
Continuation sheet Garrett County, Maryland Item number 8 Page 3

HISTORY AND SUPPORT (Continued)

"an ideal location for a religious and educational summer resort founded upon Christian principles."⁵ Soon after, Mountain Lake Park, "based on mountain air and idealism", was incorporated and placed under the management of the board of directors composed of prominent Maryland Methodists.⁶ The board promulgated a code of conduct for the community which adhered closely to current Methodist doctrine and included laws forbidding the use or sale of alcohol, gambling, dancing, or card playing by Mountain Lake Park residents.⁷ When the B & O established a railroad stop in the town that same year the Park Association even stipulated that there was to be no Sunday service.⁸ In short, Mountain Lake Park was a sober religious community and, in the words of the Park Association, "not a place for expensive dressing and meaningless idling... (nor) a place given to social frivolities which enervate and rob a vacation of its real purpose."⁹

To this end, the Association in 1882 instituted the "Mountain Chautauqua," its version of the nationally famous Chautauqua program. This program, begun in 1874 in Chautauqua, New York offered a mixture of religious revivalism, with cultural and educational activities. During its heyday, between the 1880's and World War I, the Mountain Chautauqua attracted thousands to Mountain Lake Park for a month of symphonies, operas, plays and nationally prominent speakers. Among those who spoke there were Presidents William Howard Taft, Samuel Gompers, William Jennings Bryan and Billy Sunday.

The phenomenal success of these programs, (the B & O ran as many as thirteen special trains to Mountain Lake Park during the summer months)¹⁰ stimulated a flurry of building activity by the Park Association. The original tabernacle, built in 1882, was expanded twelve years later to accommodate two thousand seats. By 1900, there were buildings to house a Hall of Philosophy, as well as schools of Oratory and Photography in addition to ticket officer, restaurants and refreshment stands. In that year the Bashford amphitheatre, a magnificent frame circular building, measuring 176 feet in diameter and built without center posts, was dedicated." (It was torn down in 1946.)

The Association also expended much time and money on the design of the surrounding town. H. E. Faul, the creator of Druid Hill Park in Baltimore, was employed to lay out the curving drives which wound among the numerous small hills in the town. The centerpiece of his design was the Mountain Lake itself, measuring forty acres and enlarged numerous times, created by the damming of several natural springs and streams. On the perimeter of the lake were several bathhouses, a boathouse and a scattering of rustic piers and bridges. The association also built a tennis club and bowling alley; both were connected to the railroad station and post office by boardwalks. Also on the lake was an ice house, built by the B & O to store ice cut from the lake for use on the railroad's dining cars.¹²

United States Department of the Interior
National Park Service

For NPS use only

National Register of Historic Places Inventory—Nomination Form

received

date entered

Mountain Lake Park Historic District

Continuation sheet Garrett County, Maryland Item number 7 and 8

Page 5

FOOTNOTES

- ¹Burns, Michael U., "Mountain Lake Park Woman Saves Memories of a Resort Without 'Sin'". Baltimore Sun. December 27, 1981, p. B1.
- ²"Mountain Lake Park Association", Tableland Trails, Vol. II, no. 2, Summer 1956, p. 106.
- ³Schlosnagle, Stephen, et. al., Garrett County - A History of Maryland's Tableland (Parsons, West Virginia: McLain Printers) 1976, pps.278-280.
- ⁴Hardesty, Leona "Mountain Lake Park in its 'Heyday'". Glades Star, vol. 4, no. 2, (Sept. 1969) p. 621.
- ⁵Love, Mary I., "The Mountain Chautauqua - Mountain Lake Park 1881-1941", Glades Star vol. 5, no. 20 (March 1982) p. 386.
- ⁶Ibid. p. 385.
- ⁷Ibid. p. 388.
- ⁸Schosnagle, p. 291.
- ⁹Hardesty, p. 630.
- ¹⁰Stacy, Cindy, "Mountain Lake Park - An Era Gone By," Cumberland Sunday Times (Sept. 27, 1981) p. E-1.
- ¹¹Love, p. 390.
- ¹²Ibid. p. 392.
- ¹³Ibid. p. 392.
- ¹⁴Burns, p. B-1.
- ¹⁵Ibid. p. B-1.

United States Department of the Interior
National Park Service

For NPS use only

National Register of Historic Places Inventory—Nomination Form

received

date entered

Continuation sheet Mountain Lake Park Historic District
Garrett County, Maryland Item number 9 and 10 Page 6

MAJOR BIBLIOGRAPHICAL REFERENCES

Burns, Michael U., "Mountain Lake Park Woman Saves Memories of a Resort Without 'Sin'". Baltimore Sun, December 27, 1981.

Hardesty, Leona "Mountain Lake Park in its 'Heyday'". Glades Star, vol. 4, no. 2, September 1969.

Love, Mary I., "The Mountain Chautauqua - Mountain Lake Park 1881-1941," Glades Star vol. 5, no. 20, March 1982.

"Mountain Lake Park Association", Tableland Trails, Vol. II, no. 2, Summer 1956.

Schlosnagle, Stephen, et. al., Garrett County - A History of Maryland's Tableland, Parsons, West Virginia: McLain Pringers, 1976.

Stacy, Cindy, "Mountain Lake Park - An Era Gone By," Cumberland Sunday Times, September 27, 1981.

BOUNDARY JUSTIFICATION

The area within the Mountain Lake Park Historic District contains the majority of those buildings which are of architectural and/or historic significance in Mountain Lake Park. This area has most nearly retained its late nineteenth/early twentieth century appearance. In contrast, the section of Mountain Lake Park north of the boundary is made up of generally deteriorated frame houses, vacant lots and modern houses. Although Maryland Route 135 is a modern thoroughfare, it does not seriously impair the visual integrity of the district, nor does it serve to divide the district to any great degree. A concentration of vacant lots, deteriorated frame houses, and modern residences distinguishes the areas to the east and west of the district boundary. The southern boundary of the district is defined by Alleghany Drive; beyond this line are open fields and the tracks of the Baltimore and Ohio Railroad.

United States Department of the Interior
National Park Service

G-IV-A-059

For NPS Use only

National Register of Historic Places Inventory—Nomination Form

received

date entered

Continuation sheet	Mountain Lake Park Historic District Garrett County, Maryland	Item number	8	Page	4
--------------------	--	-------------	---	------	---

HISTORY AND SUPPORT (Continued)

In addition to the numerous and often highly ornate cottages built by summer time residents, Mountain Lake Park held a number of large hotels and boarding houses. Among these were the Columbian, Chautauqua, Dennett, Allegany House, Briar Bend, Queenwood, Mountain Lake Park, Thoburn Hall and Braethorn Hotels, all of which advertised "either their proximity to the amphitheatre or the beautiful walk to it."¹³ All except the Braethorn have burned or been torn down, but during their heyday were the center of social life for their residents, many of whom returned to the same hotel year after year. Along with the owners of private homes in the Park, hotel owners were forbidden to sell or have alcoholic beverages on the premises or to permit other "vices." The Loch Lynn Hotel, built in 1894 in nearby Loch Lynn Heights was not subject to these regulations and therefore attracted a number of Mountain Lake Park visitors who heeded the local saying, "if you want to sin, go to Loch Lynn."

A number of factors contributed to the end of these halcyon days in Mountain Lake Park's history. Foremost of these was the advent of automobile travel, which caused a radical change in the vacationing habits of many Americans. The B & O discontinued the operation of its hotels at Deer Park and Oakland in the 1910's and the number of visitors to the other Garrett County resorts, including Mountain Lake Park, declined. The Chautauqua programs at Mountain Lake Park, plagued by financial mismanagement and the departure of many of its leaders, lost much of its former vitality during the 1920's and '30's.¹⁵ By 1941, when the last program of the Mountain Chautauqua was staged, Mountain Lake Park had become a primarily residential community, with many of its older houses either torn down or converted to year round use. The town government, which gained control of the streets and parks from the Park Association also relaxed or did away with the earlier regulations, most of which had fallen victim to changing standards of morality by the 1930's. The few summer time activities which still take place in Mountain Lake Park, an annual tennis tournament and a week long summer religious camp-meeting, are only vestiges of the numerous events which once made this a cultural center in Maryland.

SEE CONTINUATION SHEET NO. 6

10. Geographical Data

Acreage of nominated property approx. 110 acres

Quadrangle name Oakland, Maryland - West Virginia

Quadrangle scale 1:24,000

UMT References

A	<u>1</u> <u>8</u>	<u>6</u> <u>3</u> <u>9</u> <u>7</u> <u>2</u> <u>0</u>	<u>4</u> <u>3</u> <u>6</u> <u>2</u> <u>2</u> <u>2</u> <u>0</u>
	Zone	Easting	Northing

B	<u>1</u> <u>8</u>	<u>6</u> <u>3</u> <u>9</u> <u>9</u> <u>2</u> <u>0</u>	<u>4</u> <u>3</u> <u>6</u> <u>2</u> <u>0</u> <u>2</u> <u>0</u>
	Zone	Easting	Northing

C	<u>1</u> <u>8</u>	<u>6</u> <u>3</u> <u>9</u> <u>4</u> <u>7</u> <u>0</u>	<u>4</u> <u>3</u> <u>6</u> <u>1</u> <u>4</u> <u>8</u> <u>0</u>
---	-------------------	---	--

D	<u>1</u> <u>8</u>	<u>6</u> <u>3</u> <u>9</u> <u>0</u> <u>7</u> <u>0</u>	<u>4</u> <u>3</u> <u>6</u> <u>1</u> <u>3</u> <u>7</u> <u>0</u>
---	-------------------	---	--

E	<u>1</u> <u>8</u>	<u>6</u> <u>3</u> <u>8</u> <u>9</u> <u>6</u> <u>0</u>	<u>4</u> <u>3</u> <u>6</u> <u>2</u> <u>1</u> <u>4</u> <u>0</u>
---	-------------------	---	--

F	<u> </u>	<u> </u> <u> </u> <u> </u> <u> </u>	<u> </u> <u> </u> <u> </u> <u> </u>
---	-----------	---	---

G	<u> </u>	<u> </u> <u> </u> <u> </u> <u> </u>	<u> </u> <u> </u> <u> </u> <u> </u>
---	-----------	---	---

H	<u> </u>	<u> </u> <u> </u> <u> </u> <u> </u>	<u> </u> <u> </u> <u> </u> <u> </u>
---	-----------	---	---

Verbal boundary description and justification Boundaries are delineated on the attached map; for Boundary Justification see Continuation Sheet #6

List all states and counties for properties overlapping state or county boundaries

state	N/A	code	county	code
-------	-----	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Geoffrey B. Henry

organization Maryland Historical Trust date April 15, 1983

street & number 21 State Circle telephone 301-269-2438

city or town Annapolis state Maryland 21401

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the Heritage Conservation and Recreation Service.

State Historic Preservation Officer signature [Signature] 7-7-83

title STATE HISTORIC PRESERVATION OFFICER date

For HCRS use only I hereby certify that this property is included in the National Register

Keeper of the National Register date

Attest: Chief of Registration date

CONTRIBUTING RESOURCE
MARYLAND HISTORICAL TRUST
INTERNAL NR-ELIGIBILITY REVIEW FORM

Property Name: 404 E Street Survey Number: GA-IV-A-059

Property Address: 404 E Street, Mountain Lake Park

Project: Home Rehab Agency: DHCD

Site visit by MHT Staff: no yes Name _____ Date _____

District Name: Mountain Lake Park Historic District Survey Number: GA-

Listed Eligible _____ Comment _____

Criteria: A B C D Considerations: A B C D E F G None

The resource contributes/ does not contribute to the historic significance of this historic district in:

Location Design Setting Materials

Workmanship Feeling Association

Justification for decision: (Use continuation sheet if necessary and attach map)

The house at 404 E Street is located within the boundaries of the National Register Mountain Lake Park Historic District, but no longer is a contributing resource to the former resort community. The two-story, three-bay frame dwelling has been extensively altered, leaving few of the original materials and details intact, compromising its architectural integrity.

Documentation on the property is presented in: Review and Compliance Files

Prepared by: Eileen Hagan / CDA

Jo Ellen Freese 11/13/95
Reviewer, Office of Preservation Services Date

NR program concurrence: yes no not applicable
Orlando Pimentel 2-12-96 rev'd 2/8/96
Reviewer, NR program Date

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA - HISTORIC CONTEXT

I. Geographic Region:

- Eastern Shore (all Eastern Shore counties, and Cecil)
- Western Shore (Anne Arundel, Calvert, Charles, Prince George's and St. Mary's)
- Piedmont (Baltimore City, Baltimore, Carroll, Frederick, Harford, Howard, Montgomery)
- Western Maryland (Allegany, Garrett and Washington)

II. Chronological/Developmental Periods:

- Paleo-Indian 10000-7500 B.C.
- Early Archaic 7500-6000 B.C.
- Middle Archaic 6000-4000 B.C.
- Late Archaic 4000-2000 B.C.
- Early Woodland 2000-500 B.C.
- Middle Woodland 500 B.C. - A.D. 900
- Late Woodland/Archaic A.D. 900-1600
- Contact and Settlement A.D. 1570-1750
- Rural Agrarian Intensification A.D. 1680-1815
- Agricultural-Industrial Transition A.D. 1815-1870
- Industrial/Urban Dominance A.D. 1870-1930
- Modern Period A.D. 1930-Present
- Unknown Period (prehistoric historic)

III. Prehistoric Period Themes:

- Subsistence
- Settlement
- Political
- Demographic
- Religion
- Technology
- Environmental Adaption

IV. Historic Period Themes:

- Agriculture
- Architecture, Landscape Architecture, and Community Planning
- Economic (Commercial and Industrial)
- Government/Law
- Military
- Religion
- Social/Educational/Cultural
- Transportation

V. Resource Type:


Category: Building

Historic Environment: Suburban

Historic Function(s) and Use(s): Domestic/Single Dwelling

Known Design Source: _____

G-III-A-059



IRST AVE
3015
3013
3011
3009
3007

ST. NAYLOR
1182
1177

1070
1068
1066
1064
1062
1060
1058
1056
1071
1069
1067
1065
1063
1061
1059
1057

OAKLAND
P.76
P.119
P.77
WILLIAM E. WOTING
459/380 P.21 O.71 A.
ROBERT M. FLINN
289/77
1534
P.36
ROBERT GIBBY
508-DIV.

1447
1445
1443
P.93
1442
1441
1439
1437
1435
1433
1448
1446
1444
P.19
1442
1441
1439
1437
1435
1433
1430

DRIVE
4034
4033
4032
4031
4030
4029
4028
4027
4026
4025
4024
4023
4022

4013
4012
4011
4010
4009
4008
4007
4006
3997
4000
4001
4002
4003
4004
4005

DEER PARK
3010
3008
3006
3004
3002
3000
2998
2996
2994
2992
2990
2988
2986
2984
2982
2980
2978
2976
2974
2972
2970
2968
2966
2964
2962
2960
2958
2956
2954
2952
2950
2948
2946
2944
2942
2940
2938
2936
2934
2932
2930
2928
2926
2924
2922
2920
2918
2916
2914
2912
2910
2908
2906
2904
2902
2900
2898
2896
2894
2892
2890
2888
2886
2884
2882
2880
2878
2876
2874
2872
2870
2868
2866
2864
2862
2860
2858
2856
2854
2852
2850
2848
2846
2844
2842
2840
2838
2836
2834
2832
2830
2828
2826
2824
2822
2820
2818
2816
2814
2812
2810
2808
2806
2804
2802
2800
2798
2796
2794
2792
2790
2788
2786
2784
2782
2780
2778
2776
2774
2772
2770
2768
2766
2764
2762
2760
2758
2756
2754
2752
2750
2748
2746
2744
2742
2740
2738
2736
2734
2732
2730
2728
2726
2724
2722
2720
2718
2716
2714
2712
2710
2708
2706
2704
2702
2700
2698
2696
2694
2692
2690
2688
2686
2684
2682
2680
2678
2676
2674
2672
2670
2668
2666
2664
2662
2660
2658
2656
2654
2652
2650
2648
2646
2644
2642
2640
2638
2636
2634
2632
2630
2628
2626
2624
2622
2620
2618
2616
2614
2612
2610
2608
2606
2604
2602
2600
2598
2596
2594
2592
2590
2588
2586
2584
2582
2580
2578
2576
2574
2572
2570
2568
2566
2564
2562
2560
2558
2556
2554
2552
2550
2548
2546
2544
2542
2540
2538
2536
2534
2532
2530
2528
2526
2524
2522
2520
2518
2516
2514
2512
2510
2508
2506
2504
2502
2500
2498
2496
2494
2492
2490
2488
2486
2484
2482
2480
2478
2476
2474
2472
2470
2468
2466
2464
2462
2460
2458
2456
2454
2452
2450
2448
2446
2444
2442
2440
2438
2436
2434
2432
2430
2428
2426
2424
2422
2420
2418
2416
2414
2412
2410
2408
2406
2404
2402
2400
2398
2396
2394
2392
2390
2388
2386
2384
2382
2380
2378
2376
2374
2372
2370
2368
2366
2364
2362
2360
2358
2356
2354
2352
2350
2348
2346
2344
2342
2340
2338
2336
2334
2332
2330
2328
2326
2324
2322
2320
2318
2316
2314
2312
2310
2308
2306
2304
2302
2300
2298
2296
2294
2292
2290
2288
2286
2284
2282
2280
2278
2276
2274
2272
2270
2268
2266
2264
2262
2260
2258
2256
2254
2252
2250
2248
2246
2244
2242
2240
2238
2236
2234
2232
2230
2228
2226
2224
2222
2220
2218
2216
2214
2212
2210
2208
2206
2204
2202
2200
2198
2196
2194
2192
2190
2188
2186
2184
2182
2180
2178
2176
2174
2172
2170
2168
2166
2164
2162
2160
2158
2156
2154
2152
2150
2148
2146
2144
2142
2140
2138
2136
2134
2132
2130
2128
2126
2124
2122
2120
2118
2116
2114
2112
2110
2108
2106
2104
2102
2100
2098
2096
2094
2092
2090
2088
2086
2084
2082
2080
2078
2076
2074
2072
2070
2068
2066
2064
2062
2060
2058
2056
2054
2052
2050
2048
2046
2044
2042
2040
2038
2036
2034
2032
2030
2028
2026
2024
2022
2020
2018
2016
2014
2012
2010
2008
2006
2004
2002
2000
1998
1996
1994
1992
1990
1988
1986
1984
1982
1980
1978
1976
1974
1972
1970
1968
1966
1964
1962
1960
1958
1956
1954
1952
1950
1948
1946
1944
1942
1940
1938
1936
1934
1932
1930
1928
1926
1924
1922
1920
1918
1916
1914
1912
1910
1908
1906
1904
1902
1900
1898
1896
1894
1892
1890
1888
1886
1884
1882
1880
1878
1876
1874
1872
1870
1868
1866
1864
1862
1860
1858
1856
1854
1852
1850
1848
1846
1844
1842
1840
1838
1836
1834
1832
1830
1828
1826
1824
1822
1820
1818
1816
1814
1812
1810
1808
1806
1804
1802
1800
1798
1796
1794
1792
1790
1788
1786
1784
1782
1780
1778
1776
1774
1772
1770
1768
1766
1764
1762
1760
1758
1756
1754
1752
1750
1748
1746
1744
1742
1740
1738
1736
1734
1732
1730
1728
1726
1724
1722
1720
1718
1716
1714
1712
1710
1708
1706
1704
1702
1700
1698
1696
1694
1692
1690
1688
1686
1684
1682
1680
1678
1676
1674
1672
1670
1668
1666
1664
1662
1660
1658
1656
1654
1652
1650
1648
1646
1644
1642
1640
1638
1636
1634
1632
1630
1628
1626
1624
1622
1620
1618
1616
1614
1612
1610
1608
1606
1604
1602
1600
1598
1596
1594
1592
1590
1588
1586
1584
1582
1580
1578
1576
1574
1572
1570
1568
1566
1564
1562
1560
1558
1556
1554
1552
1550
1548
1546
1544
1542
1540
1538
1536
1534
1532
1530
1528
1526
1524
1522
1520
1518
1516
1514
1512
1510
1508
1506
1504
1502
1500
1498
1496
1494
1492
1490
1488
1486
1484
1482
1480
1478
1476
1474
1472
1470
1468
1466
1464
1462
1460
1458
1456
1454
1452
1450
1448
1446
1444
1442
1440
1438
1436
1434
1432
1430
1428
1426
1424
1422
1420
1418
1416
1414
1412
1410
1408
1406
1404
1402
1400
1398
1396
1394
1392
1390
1388
1386
1384
1382
1380
1378
1376
1374
1372
1370
1368
1366
1364
1362
1360
1358
1356
1354
1352
1350
1348
1346
1344
1342
1340
1338
1336
1334
1332
1330
1328
1326
1324
1322
1320
1318
1316
1314
1312
1310
1308
1306
1304
1302
1300
1298
1296
1294
1292
1290
1288
1286
1284
1282
1280
1278
1276
1274
1272
1270
1268
1266
1264
1262
1260
1258
1256
1254
1252
1250
1248
1246
1244
1242
1240
1238
1236
1234
1232
1230
1228
1226
1224
1222
1220
1218
1216
1214
1212
1210
1208
1206
1204
1202
1200
1198
1196
1194
1192
1190
1188
1186
1184
1182
1180
1178
1176
1174
1172
1170
1168
1166
1164
1162
1160
1158
1156
1154
1152
1150
1148
1146
1144
1142
1140
1138
1136
1134
1132
1130
1128
1126
1124
1122
1120
1118
1116
1114
1112
1110
1108
1106
1104
1102
1100
1098
1096
1094
1092
1090
1088
1086
1084
1082
1080
1078
1076
1074
1072
1070
1068
1066
1064
1062
1060
1058
1056
1054
1052
1050
1048
1046
1044
1042
1040
1038
1036
1034
1032
1030
1028
1026
1024
1022
1020
1018
1016
1014
1012
1010
1008
1006
1004
1002
1000
998
996
994
992
990
988
986
984
982
980
978
976
974
972
970
968
966
964
962
960
958
956
954
952
950
948
946
944
942
940
938
936
934
932
930
928
926
924
922
920
918
916
914
912
910
908
906
904
902
900
898
896
894
892
890
888
886
884
882
880
878
876
874
872
870
868
866
864
862
860
858
856
854
852
850
848
846
844
842
840
838
836
834
832
830
828
826
824
822
820
818
816
814
812
810
808
806
804
802
800
798
796
794
792
790
788
786
784
782
780
778
776
774
772
770
768
766
764
762
760
758
756
754
752
750
748
746
744
742
740
738
736
734
732
730
728
726
724
722
720
718
716
714
712
710
708
706
704
702
700
698
696
694
692
690
688
686
684
682
680
678
676
674
672
670
668
666
664
662
660
658
656
654
652
650
648
646
644
642
640
638
636
634
632
630
628
626
624
622
620
618
616
614
612
610
608
606
604
602
600
598
596
594
592
590
588
586
584
582
580
578
576
574
572
570
568
566
564
562
560
558
556
554
552
550
548
546
544
542
540
538
536
534
532
530
528
526
524
522
520
518
516
514
512
510
508
506
504
502
500
498
496
494
492
490
488
486
484
482
480
478
476
474
472
470
468
466
464
462
460
458
456
454
452
450
448
446
444
442
440
438
436
434
432
430
428
426
424
422
420
418
416
414
412
410
408
406
404
402
400
398
396
394
392
390
388
386
384
382
380
378
376
374
372
370
368
366
364
362
360
358
356
354
352
350
348
346
344
342
340
338
336
334
332
330
328
326
324
322
320
318
316
314
312
310
308
306
304
302
300
298
296
294
292
290
288
286
284
282
280
278
276
274
272
270
268
266
264
262
260
258
256
254
252
250
248
246
244
242
240
238
236
234
232
230
228
226
224
222
220
218
216
214
212
210
208
206
204
202
200
198
196
194
192
190
188
186
184
182
180
178
176
174
172
170
168
166
164
162
160
158
156
154
152
150
148
146
144
142
140
138
136
134
132
130
128
126
124
122
120
118
116
114
112
110
108
106
104
102
100
98
96
94
92
90
88
86
84
82
80
78
76
74
72
70
68
66
64
62
60
58
56
54
52
50
48
46
44
42
40
38
36
34
32
30
28
26
24
22
20
18
16
14
12
10
8
6
4
2

MT. LAKE PARK HOLINESS
CAMPMEETING ASSOC INC
213/431
56A
P.13

CARL DELSIGNORE
374/608
6.99A.
P.17

ROBALIND R.
BEAVER
354/500
2.99A.
P.15

HAMER L. DENNE
175/508
11.49A
P.2



404 E Street
Mountain Lake Park
Garrett County, MD

G-IV-A-059

**INDIVIDUAL PROPERTY/DISTRICT
MARYLAND HISTORICAL TRUST
INTERNAL NR-ELIGIBILITY REVIEW FORM**

Property/District Name: 915 H Street, Mountain Lake Park Survey Number: G-IV-A-059

Project: Rehabilitation of 915 H Street Agency: HOME/CDA

Site visit by MHT Staff: X no ___ yes Name _____ Date _____

Eligibility recommended _____ Eligibility **not** recommended X

Criteria: ___A ___B XC ___D Considerations: ___A ___B ___C ___D ___E ___F ___G ___None

Justification for decision: (Use continuation sheet if necessary and attach map)

Based on the available information, the house at 915 H Street, Mountain Lake Park does not meet the National Register Criteria for individual listing. The property is located just north of the historic district boundary, presumably in area that lacks the concentration of historic properties found in the district. The two story, gable-end house is similar to other modest turn-of-the century residences found in the historic district and would most likely be considered to be eligible as a contributing resource, if it were within the boundaries. However, as an individual resource, it lacks sufficient architectural distinction to merit consideration under Criterion C. In addition, it has no known association with any significant event or person, as required for consideration under Criteria A and B.

Documentation on the property/district is presented in: Project File

Prepared by: _____

Elizabeth Hannold
Reviewer, Office of Preservation Services

August 23, 1995
Date

NR program concurrence: yes ___ no ___ not applicable

Quanda Redant
Reviewer, NR program

8-23-95
Date

Handwritten initials

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA - HISTORIC CONTEXT

I. Geographic Region:

- Eastern Shore (all Eastern Shore counties, and Cecil)
- Western Shore (Anne Arundel, Calvert, Charles, Prince George's and St. Mary's)
- Piedmont (Baltimore City, Baltimore, Carroll, Frederick, Harford, Howard, Montgomery)
- Western Maryland (Allegany, Garrett and Washington)

II. Chronological/Developmental Periods:

- Paleo-Indian 10000-7500 B.C.
- Early Archaic 7500-6000 B.C.
- Middle Archaic 6000-4000 B.C.
- Late Archaic 4000-2000 B.C.
- Early Woodland 2000-500 B.C.
- Middle Woodland 500 B.C. - A.D. 900
- Late Woodland/Archaic A.D. 900-1600
- Contact and Settlement A.D. 1570-1750
- Rural Agrarian Intensification A.D. 1680-1815
- Agricultural-Industrial Transition A.D. 1815-1870
- Industrial/Urban Dominance A.D. 1870-1930
- Modern Period A.D. 1930-Present
- Unknown Period (prehistoric historic)

III. Prehistoric Period Themes:

- Subsistence
- Settlement
- Political
- Demographic
- Religion
- Technology
- Environmental Adaption

IV. Historic Period Themes:

- Agriculture
- Architecture, Landscape Architecture, and Community Planning
- Economic (Commercial and Industrial)
- Government/Law
- Military
- Religion
- Social/Educational/Cultural
- Transportation

V. Resource Type:

Category: Building

Historic Environment: Village

Historic Function(s) and Use(s): Domestic - Single Dwelling

Known Design Source: na

950 2382

CONTRIBUTING RESOURCE
MARYLAND HISTORICAL TRUST
INTERNAL NR-ELIGIBILITY REVIEW FORM

Property Name: 915 H Street Survey Number: G-III-A-059

Property Address: 915 H Street, Mountain Lake Park

Project: Rehabilitation of 915 H Street Agency: HOME/CDA

Site visit by MHT Staff: no yes Name _____ Date _____

District Name: Mountain Lake Park Survey Number: G-IV-A-059

Listed Eligible _____ Comment _____

Criteria: A B C D Considerations: A B C D E F G None

The resource contributes/ does not contribute to the historic significance of this historic district in:

- Location Design Setting Materials
- Workmanship Feeling Association

Justification for decision: (Use continuation sheet if necessary and attach map)

Based on the available information, the house at 915 H Street, Mountain Lake Park is eligible for the National Register as a contributing resource in the Mountain Lake Park Historic District. The two story, gable-end house is similar to other modest turn-of-the century residences found in the historic district. Although known for its more elaborate Victorian summer residences, simple cottages such as this one are found throughout the district and function as "background buildings." The front porch (though the current one is an obvious replacement) and open, bracketed eaves lend the house the appearance of a summer cottage.

Documentation on the property is presented in: Project file

Prepared by: _____

Elizabeth Hannold September 28, 1995
Reviewer, Office of Preservation Services Date

NR program concurrence: yes no not applicable
Orlando Pizarro Sept. 28 1995.
Reviewer, NR program Date

[Handwritten initials]

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA - HISTORIC CONTEXT

I. Geographic Region:

- Eastern Shore (all Eastern Shore counties, and Cecil)
- Western Shore (Anne Arundel, Calvert, Charles, Prince George's and St. Mary's)
- Piedmont (Baltimore City, Baltimore, Carroll, Frederick, Harford, Howard, Montgomery)
- Western Maryland (Allegany, Garrett and Washington)

II. Chronological/Developmental Periods:

- Paleo-Indian 10000-7500 B.C.
- Early Archaic 7500-6000 B.C.
- Middle Archaic 6000-4000 B.C.
- Late Archaic 4000-2000 B.C.
- Early Woodland 2000-500 B.C.
- Middle Woodland 500 B.C. - A.D. 900
- Late Woodland/Archaic A.D. 900-1600
- Contact and Settlement A.D. 1570-1750
- Rural Agrarian Intensification A.D. 1680-1815
- Agricultural-Industrial Transition A.D. 1815-1870
- Industrial/Urban Dominance A.D. 1870-1930
- Modern Period A.D. 1930-Present
- Unknown Period (prehistoric historic)

III. Prehistoric Period Themes:

- Subsistence
- Settlement
- Political
- Demographic
- Religion
- Technology
- Environmental Adaption

IV. Historic Period Themes:

- Agriculture
- Architecture, Landscape Architecture, and Community Planning
- Economic (Commercial and Industrial)
- Government/Law
- Military
- Religion
- Social/Educational/Cultural
- Transportation

V. Resource Type:

Category: Building

Historic Environment: Village

Historic Function(s) and Use(s): Domestic -Single Dwelling

Known Design Source: na



Garrett Co.
905 H West

Morton Lake Park

6-11-4-05^o

Side



G-IV-1 059

Garrett Co.

905 H Street

Mountain Lake Park

FRONT



G-IV-4-059

Yarrett Co.

905 4 Street

Mountain Lake Park

Side




G-IV-A-059
Y
Summit Co.

105 W. 5th St.

Mountain Lake Park

REAR

MARYLAND HISTORICAL



TRUST

William Donald Schaefer
Governor

Jacqueline H. Rogers
Secretary, DHCD

CONTRIBUTING RESOURCE
MARYLAND HISTORICAL TRUST
INTERNAL NR-ELIGIBILITY REVIEW FORM

Property Name: 414 1st Street, Mountain Lake Park Survey Number: _____

Property Address: 414 1st Street

Project: Remove + Replace Rear Addition Agency: MHRP

Site visit by MHT Staff: no yes Name _____ Date _____

District Name: Mountain Lake Park Survey Number: G-11-A-059

Listed Eligible _____ Comment _____

Criteria: A B C D Considerations: A B C D E F G None

The resource contributes/_____ does not contribute to the historic significance of this historic district in:

Location Design Setting Materials

Workmanship Feeling Association

Justification for decision: (Use continuation sheet if necessary and attach map)

414 1st Street, a late 19th c., 2 story frame house. Contributes to the Mountain Lake Park Historic District. It is representative of the more modest Queen Anne Victorian houses found in the district. It is distinguished by the use of varied siding - shingles + clapboard, and decorative diamond-shaped windows.

Mt. Lake Park was founded in the 1880s as summer resort and was a center of the Chataqua movement in Maryland. It contains 145 buildings, most residential, including many fine examples of Queen Anne + Carpenter Gothic.

Documentation on the property is presented in: Project File

Prepared by: _____

Elizabeth Hannott

Reviewer, Office of Preservation Services

8/2/91

Date

NR program concurrence: yes no not applicable

R. Anderson

Reviewer, NR program

8/2/91

Date

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA - HISTORIC CONTEXT

I. Geographic Region:

- Eastern Shore (all Eastern Shore counties, and Cecil)
- Western Shore (Anne Arundel, Calvert, Charles, Prince George's and St. Mary's)
- Piedmont (Baltimore City, Baltimore, Carroll, Frederick, Harford, Howard, Montgomery)
- Western Maryland (Alleghany, Garrett and Washington)

II. Chronological/Developmental Periods:

- Paleo-Indian 10000-7500 B.C.
- Early Archaic 7500-6000 B.C.
- Middle Archaic 6000-4000 B.C.
- Late Archaic 4000-2000 B.C.
- Early Woodland 2000-500 B.C.
- Middle Woodland 500 B.C.- A.D. 900
- Late Woodland/Archaic A.D. 900-1600
- Contact and Settlement A.D. 1570-1750
- Rural Agrarian Intensification A.D. 1680-1815
- Agricultural-Industrial Transition A.D. 1815-1870
- Industrial/Urban Dominance A.D. 1870-1930
- Modern Period A.D. 1930-Present
- Unknown Period (prehistoric historic)

III. Prehistoric Period Themes:

- Subsistence
- Settlement
- Political
- Demographic
- Religion
- Technology
- Environmental Adaption

IV. Historic Period Themes:

- Agriculture
- Architecture, Landscape Architecture, and Community Planning
- Economic (Commercial and Industrial)
- Government/Law
- Military
- Religion
- Social/Educational/Cultural
- Transportation

V. Resource Type:

Category: Building

Historic Environment: Settlement Village

Historic Function(s) and Use(s): Domestic - Single

Dwelling

Known Design Source: _____

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA - HISTORIC CONTEXT

I. Geographic Region:

- Eastern Shore (all Eastern Shore counties, and Cecil)
- Western Shore (Anne Arundel, Calvert, Charles, Prince George's and St. Mary's)
- Piedmont (Baltimore City, Baltimore, Carroll, Frederick, Harford, Howard, Montgomery)
- Western Maryland (Allegany, Garrett and Washington)

II. Chronological/Developmental Periods:

- Paleo-Indian 10000-7500 B.C.
- Early Archaic 7500-6000 B.C.
- Middle Archaic 6000-4000 B.C.
- Late Archaic 4000-2000 B.C.
- Early Woodland 2000-500 B.C.
- Middle Woodland 500 B.C. - A.D. 900
- Late Woodland/Archaic A.D. 900-1600
- Contact and Settlement A.D. 1570-1750
- Rural Agrarian Intensification A.D. 1680-1815
- Agricultural-Industrial Transition A.D. 1815-1870
- Industrial/Urban Dominance A.D. 1870-1930
- Modern Period A.D. 1930-Present
- Unknown Period (prehistoric historic)

III. Prehistoric Period Themes:

- Subsistence
- Settlement
- Political
- Demographic
- Religion
- Technology
- Environmental Adaption

IV. Historic Period Themes:

- Agriculture
- Architecture, Landscape Architecture, and Community Planning
- Economic (Commercial and Industrial)
- Government/Law
- Military
- Religion
- Social/Educational/Cultural
- Transportation

V. Resource Type:

Category: Building

Historic Environment: Village

Historic Function(s) and Use(s): Domestic Dwelling

Known Design Source: unknown

**CONTRIBUTING RESOURCE
MARYLAND HISTORICAL TRUST
INTERNAL NR-ELIGIBILITY REVIEW FORM**

Property Name: 515 L Street Survey Number: G-IVA-059

Property Address: 515 L St., Mountain Lake Park

Project: CDBG Agency: GCCAC

Site visit by MHT Staff: no yes Name _____ Date _____

District Name: MT. LAKE PARK HISTORIC DISTRICT Survey Number: G-IVA-059

Listed Eligible _____ Comment _____

Criteria: A B C D Considerations: A B C D E F G None

The resource contributes/ does not contribute to the historic significance of this historic district in:

Location Design Setting Materials

Workmanship Feeling Association

Justification for decision: (Use continuation sheet if necessary and attach map)

The dwelling at 515 L Street is located within the Mt. Lake Park Historic District, but is considered a non-contributing resource. The one-story dwelling is not fifty years old and does not contribute to the architectural or historical significance of the historic district.

Documentation on the property is presented in: Project Review and Compliance

Prepared by: Aurelia Marple

Kim Williams Reviewer, Office of Preservation Services April 3, 1996 Date

NR program concurrence: yes no not applicable

Aurelia Marple Reviewer, NR program April 10, 1996 Date

1764

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA - HISTORIC CONTEXT

I. Geographic Region:

- Eastern Shore (all Eastern Shore counties, and Cecil)
- Western Shore (Anne Arundel, Calvert, Charles, Prince George's and St. Mary's)
- Piedmont (Baltimore City, Baltimore, Carroll, Frederick, Harford, Howard, Montgomery)
- Western Maryland (Allegany, Garrett and Washington)

II. Chronological/Developmental Periods:

- Paleo-Indian 10000-7500 B.C.
- Early Archaic 7500-6000 B.C.
- Middle Archaic 6000-4000 B.C.
- Late Archaic 4000-2000 B.C.
- Early Woodland 2000-500 B.C.
- Middle Woodland 500 B.C. - A.D. 900
- Late Woodland/Archaic A.D. 900-1600
- Contact and Settlement A.D. 1570-1750
- Rural Agrarian Intensification A.D. 1680-1815
- Agricultural-Industrial Transition A.D. 1815-1870
- Industrial/Urban Dominance A.D. 1870-1930
- Modern Period A.D. 1930-Present
- Unknown Period (prehistoric historic)

III. Prehistoric Period Themes:

- Subsistence
- Settlement
- Political
- Demographic
- Religion
- Technology
- Environmental Adaption

IV. Historic Period Themes:

- Agriculture
- Architecture, Landscape Architecture, and Community Planning
- Economic (Commercial and Industrial)
- Government/Law
- Military
- Religion
- Social/Educational/Cultural
- Transportation


V. Resource Type:

Category: Building

Historic Environment: Village

Historic Function(s) and Use(s): Domestic/Single dwelling

Known Design Source: _____




G-II-A-059



515 L Street G-IV-A-059
Mountain Lake Park



515 L Street G-IV-A-059
Mountain Lake Park



G-IV-A-059

MOUNTAIN
LAKE PARK
HISTORIC
DISTRICT

GARRETT CO., MD.

A: 18-639720-
4362220

B: 18-639920-
4362020

C: 18-639470-
4361480

D: 18-639070-
4361370

E: 18-638960-
4362140

4360000 N.
320 000 FEET
(W. VA.)

5' GORTNER 1.5 MI.
SILVER LAKE 12 MI.

1:63000 E 2 030 000 FEET (W. VA.)

INTERIOR - GEOLOGICAL SURVEY,
RESTON, VIRGINIA - 1975

39°22'30"
79°22'30"



G-IV-A-059



G-IV-A-059



G-IV-A-059

Mountain Lake Park Survey District

FIGURE 120



G-IV-A-059

Mountain Lake Park Survey District

Photos pulled 6/1985
for Coal Basin Final Report
(Fig 121).



G-IV-A-059



G-IV-A-059

MOUNTAIN LAKE PARK HISTORIC DISTRICT

(HOTEL BRAETHORN)

FIGURE 124