

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

HA-153
25

EASEMENT

FOR NPS USE ONLY

RECEIVED **JUL 3 1978**

DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

SEE INSTRUCTIONS IN *HOW TO COMPLETE NATIONAL REGISTER FORMS*
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC

Norris-Stirling house

AND/OR COMMON

Mount Pleasant

2 LOCATION

STREET & NUMBER SE side of Ring Factory Road, NE of its junction with
Hollingsworth Road, 4 miles SW of Bel Air

NOT FOR PUBLICATION

CITY, TOWN

CONGRESSIONAL DISTRICT

Bel Air

VICINITY OF

First

STATE

CODE

COUNTY

CODE

Maryland

024

Harford

025

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> MUSEUM
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> COMMERCIAL
<input type="checkbox"/> SITE	<input type="checkbox"/> PUBLIC ACQUISITION	<input type="checkbox"/> ACCESSIBLE	<input type="checkbox"/> EDUCATIONAL
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES: RESTRICTED	<input checked="" type="checkbox"/> PRIVATE RESIDENCE
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> ENTERTAINMENT
		<input checked="" type="checkbox"/> NO	<input type="checkbox"/> GOVERNMENT
			<input type="checkbox"/> INDUSTRIAL
			<input type="checkbox"/> MILITARY
			<input type="checkbox"/> PARK
			<input type="checkbox"/> RELIGIOUS
			<input type="checkbox"/> SCIENTIFIC
			<input type="checkbox"/> TRANSPORTATION
			<input type="checkbox"/> OTHER:

4 OWNER OF PROPERTY

NAME

Mrs. Campbell Lloyd Stirling

STREET & NUMBER

2211 North Charles Street

CITY, TOWN

STATE

Baltimore,

VICINITY OF

Maryland 21218

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC.

Harford County Courthouse

STREET & NUMBER

CITY, TOWN

STATE

Bel Air,

Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Norris-Stirling house, presently known as Mount Pleasant, is located approximately four miles southwest of Bel Air on the southeast side of Ring Factory Road, northeast of its junction with Hollingsworth Road. The house is comprised of an early nineteenth century stone section and two later frame additions. Outbuildings include a frame barn and corn-crib, a stone springhouse and a garage.

The original section of the house is three bays by one room deep. It is constructed of uncoursed fieldstone with a slate roof. Its front and rear elevations both consist of an entrance in the north bay with two nine-over-six windows in the south bays of the first floor. Over the plainly trimmed, recessed door is a four-light transom. Flanking the entrance, reveals carved with three panels echo the pattern of the six-paneled door. A reconstructed hood, contemporary in design to the house, protects the entrance. On the second floor, three six-over-six sash windows are aligned with the door and two first floor windows. All of these windows have narrow, white painted trim and green shutters with stationary louvers. The gabled dormer window was probably added after the first addition was constructed to admit light to the south attic room. Two casement windows, in the peak of the north elevation, illuminate the other small attic room and stairway. The windows in the house all have very wide sills due to the thickness of the walls, and many window panes retain the original glass.

The floor plan consists of a stair hall and one room on both the first and second stories. Much attention was given to the design and execution of the open string stair with halfpace landings. Opposite these two landings, the well is terminated in a quarter circle which lends simple elegance to the lines of the stair. The balusters, square at the bottom and round above, are delicately proportioned, as are brackets along the string course. The division of a second story rear window by a stair landing is functional as it illuminates two flights of the stair and retains the symmetry of the exterior elevation.

There is an interior end chimney of brick at the east end of the stone portion. The first floor wooden mantel is carved with plain pilasters, topped by a frieze with torus molding and a simple mantel shelf. The mantel on the second floor is also classically inspired but is more simple in its execution.

Six-paneled doors throughout the original section are identical to the one of the front entrance. They have brass box locks which were present when Mrs. Stirling's mother, Mrs. Louis Muller, purchased the house in 1936. One of the attic doors has a wooden box lock. The original walnut floors remain throughout this section.

The first addition may be entered from the older part by a door cut

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

FOR NPS USE ONLY	
RECEIVED	JUL 3 1978
DATE ENTERED	

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

Norris-Stirling house
Harford County,

CONTINUATION SHEET Maryland ITEM NUMBER 7 PAGE 1

DESCRIPTION (continued)

through the south end of the chimney wall of the first and second stc
This section was in extreme disrepair when Mrs. Muller became the owr
As many of the walnut floorboards as possible were left on the first
The replacements are well matched. The fireplace in the single first
story room is wide and has an old iron crane in place at the back of
hearth. As the upstairs was beyond restoration, it was reconstructed
include a bath and two bedrooms. A winding stair which led to the
second story was replaced by a straight stair located behind the same
which hid the original stair. The door to the stair is hung on iron
strap hinges as is the closet next to it. The second floor doorway v
cut through a closet in which some of the wooden clothes pegs remain.

A double-tiered porch was added to the front of the first addition in
1936. The first floor of the porch is paved with slate slabs origina
from the streets of Delta, Pennsylvania. The upstairs porch is screen
The front and back doors with panes on the first floor were also in-
stalled at that time.

A lean-to which forms the most southern section replaces a smaller,
earlier addition. This 1936 addition contains a kitchen, 2 baths, ma
room and kitchen porch. Both this addition and the earlier one have
slate roofs.

The large bank barn is constructed of roughly sawn timber and covered
by a gable roof with cedar shingles. The foundation is of stone.
Nearby is a frame corncrib. A stone springhouse is located in the wo
area in front of the house. In addition to the springhouse, there is
spring in the original cellar. The frame, three-car garage was built
in 1936 and conforms to the lines of the barn.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

Norris-Stirling house
Harford County

CONTINUATION SHEET

Maryland

ITEM NUMBER

7

PAGE 2

ENVIRONMENT OF MOUNT PLEASANT

Built on a high elevation in the rolling hills of Harford County, Mount Pleasant commands a view of spacious lawns and unspoiled woodlands. A number of the original trees and shrubs remain on the property, and others have been planted to enhance the landscape-box, magnolias, holly, azaleas, some evergreens, etc.

Whereas there are no formal gardens, there are thousands of spring bulbs and a wealth of native fern, myrtle, pachysandra, and dogwood. Violets carpet some areas in the spring, lilies-of-the-valley bloom in profusion and lilac waft their fragrance. Handsome stone walls of local fieldstone, restored or built by Mr. Stirling, are an unusual feature.

The large wooded areas abound in wild life, and are rich in laurel, wild azaleas, great masses of fern, wild flowers of many varieties. Any everywhere -- the music of birds.

Two streams water the property, and the half-mile wooded frontage along Ring Factory Road extends northerly to within about 400 feet of Winter's Run, a broad rock-bound creek in a picturesque valley. Truly a nature preserve.

The natural spring in the old stone springhouse is the source of an abundant supply of fine water, brought to the main house by an electric pump in the springhouse.

The large pastures are fenced for livestock.

ARCHEOLOGICAL NOTE: According to Mr. Stirling, an old resident of the neighborhood told him years ago that as a boy he remembered an Indian village nearby, and that he used to play with the Indian children. He said there were probably Indian mounds in our woods. Indian relics have been found there in the past.

Sept. 6, 1977

Amy A. Stirling
(Mrs. Campbell Lloyd Stirling)

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input checked="" type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input checked="" type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES Circa 1803

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

Situated in the midst of a wooded tract of about 50 acres, the Norris-Stirling house is an early 19th century farmhouse with a later 19th century addition and small 20th century addition.

The original section of the house is a small, stone structure typical in style of early 19th century stone architecture in Harford County. The quality of craftsmanship on the interior is unusually fine and well preserved for a house of this type in this area.

Outbuildings, including the stone springhouse, frame barn, and corn house, are evidence of the agricultural activity which supported at least three generations of the Norris family. The property consists of pasture, in addition to its wooded areas, enhancing the farm setting of the complex.

Aquilla Norris purchased this land, part of a tract known as Clegates Forest, from John Beale Bordley in 1784 (JLG F/132). The 73½ acres were conveyed by Aquilla to his son Rhesa in 1803 (HD U/423). The house is thought to have been built within several years of this date. In 1843 Rhesa and his wife Susannah deeded 26½ acres to their son Silas N., "in consideration of love and affection for their son" (HD 29/89). After the death of Silas, his trustee, Frank C. Norris, sold the property to Archibald H. Wann (WSF 95/145). The land passed to Benjamin F. Wann, and in 1936 he sold it to Amelia V. Muller, who listed Amelia Prescott Stirling and Campbell Lloyd Stirling as tenants in common (SWC 241/447). The house was restored by Baltimore architect, Laurence Ewald, shortly thereafter.

In 1976 Mr. and Mrs. Campbell Lloyd Stirling granted an easement on the house and surrounding acres to the Maryland Historical Trust. This document states that the property constitutes a "significant historical and cultural resource."

9 MAJOR BIBLIOGRAPHICAL REFERENCES

HA-153

Land Records of Harford County.
Research provided by Mrs. Stirling, copy in the files of the Maryland Historical Trust.

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 50 acres (approximately)

QUADRANGLE NAME Edgewood

QUADRANGLE SCALE 1:24000

UTM REFERENCES

A 1,8 | 3,8,3 | 2,6,0 | 4,3,7,2 | 2,8,0

B 1,8 | 3,8,3 | 6,0,0 | 4,3,7,1 | 9,2,0

ZONE EASTING NORTHING

ZONE EASTING NORTHING

C 1,8 | 3,8,2 | 8,9,0 | 4,3,7,1 | 5,6,0

D 1,8 | 3,8,2 | 6,8,0 | 4,3,7,1 | 5,8,0

E | | | |

F | | | |

G | | | |

H | | | |

VERBAL BOUNDARY DESCRIPTION

See enclosed plat map and boundary description.

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	CODE	COUNTY	CODE
STATE	CODE	COUNTY	CODE

11 FORM PREPARED BY

NAME / TITLE

Cheryl Dees, Summer Intern

ORGANIZATION

Maryland Historical Trust

DATE

August 1977

STREET & NUMBER

21 State Circle

TELEPHONE

(301) 269-2438

CITY OR TOWN

Annapolis

STATE

Maryland 21401

12 STATE HISTORIC PRESERVATION OFFICER CERTIFICATION

THE EVALUATED SIGNIFICANCE OF THIS PROPERTY WITHIN THE STATE IS:

NATIONAL STATE LOCAL X

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

STATE HISTORIC PRESERVATION OFFICER SIGNATURE

[Signature]

3-15-79

TITLE

STATE HISTORIC PRESERVATION OFFICER

DATE

FDR NPS USE ONLY

I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER


DATE

KEEPER OF THE NATIONAL REGISTER

ATTEST:

DATE

CHEF OF REGISTRATION



MOUNT PLEASANT
 BFL AIR (near)
 HARFORD COUNTY

EASEMENT EXHIBIT NO. B, page 18 of 39

FIRST FLOOR PLAN

SCALE: 1/8"=1'-0"
 PREPARED: 10/76

MARYLAND HISTORICAL TRUST

JAC



MOUNT PLEASANT

PROPERTY DESCRIPTION

This Deed of Easement applies to the lands and buildings of the grantor situated in the Third Election District of Harford County, Maryland. Said lands are more particularly described as follows:

Beginning at a stone on the south side of Ring Factory Road, approximately 1007 feet southwest from where the entrance drive, into the property of the grantor, meets Ring Factory Road and following the center line of Ring Factory Road in a northeasterly direction the following courses:

1. North 40 degrees 37 minutes east, 780.0 feet coming over an iron pipe;
2. North 64 degrees 39 minutes east, 407.9 feet;
3. North 50 degrees 00 minutes east, 79.55 feet;
4. North 33 degrees 12 minutes east, 130.79 feet, crossing over the branch stream;
5. North 35 degrees 09 minutes east, 106.9 feet;
6. North 19 degrees 33 minutes east, 122.6 feet, again crossing over the branch stream;
7. North 51 degrees 39 minutes east, 176.11 feet;
8. North 60 degrees 41 minutes east, 246.9 feet;
9. North 44 degrees 59 minutes, east 90.29 feet;
10. North 14 degrees 18 minutes, east 57.05 feet;
11. North 63 degrees 20 minutes east, 255.55 feet;
12. North 50 degrees 0 minutes, east 175.8 feet;
13. North 65 degrees 51 minutes, east 111.95 feet;

Thence leaving the centerline of said Ring Factory Road in a southeasterly direction the following courses:

14. South 54 degrees 04 minutes 665.5 feet, to a stone;
15. South 37 degrees 28 minutes 500.0 feet, to a stone marking the eastern most corner of the herein described property;
16. Thence running south 67 degrees 20 minutes west, 2231.2 feet to a stone marked "NH";
17. Thence running north 77 degrees 30 minutes west, 458.8 feet to a stone and the place of beginning.

MOUNT PLEASANT - PROPERTY DESCRIPTION (continued)

The entire parcel containing 50 acres more or less and being made up of smaller parcels described in one or more of the following deeds, agreements and/or easements:

1. Benjamin F. Wann, Bertha R. Wann, his wife, Bessie E. Wann Archer, Theodore S. Archer, her husband and Evelyn Wann; To Amelia V. Muller, Amelia Prescott Stirling and Campbell Lloyd Stirling, dated July 10, 1936 and recorded in Liber 241 Folio 447 of Harford County, Maryland.
2. William C. Bavington to Amelia V. Muller, Amelia Prescott Stirling and Campbell Lloyd Stirling, dated July 10, 1936 and recorded in Liber 241, Folio 450 of Harford County, Maryland.
3. Sarah M. Davis and Walter F. Davis, her husband to John P. Bailey and Lillian C. Bailey, his wife, dated October 6, 1942 and recorded in Liber 275, Folio 152 of Harford County, Maryland.
4. John P. Bailey and Lillian C. Bailey, his wife, to Campbell L. Stirling, et. al., dated May 3, 1943 and recorded in Liber GCB 278, Folio 47 of Harford County, Maryland.
5. Erle P. Barlow and Ruth H. Barlow, his wife, to Amy A. Stirling, et. al., dated November 18, 1946 and recorded in Liber GCB 301, Folio 119 of Harford County, Maryland.
6. Campbell L. Stirling and Amy A. Stirling, his wife to Harford County, Maryland, dated November 7, 1974 and recorded in Liber 962, Folio 138 of Harford County, Maryland.

*no corrected by. HA 153
Mrs. Stirling*

Description

MT. PLEASANT

The Norris-Stirling house, presently known as Mount Pleasant, is located approximately four miles southwest of Bel Air on the southeast side of Ring Factory Road, northeast of its ~~intersection~~ ^{junction} with ~~state road 152~~ ^{Hollingsworth Road.} The house is comprised of an early nineteenth century stone section and two later frame additions. Outbuildings include a frame barn and corncrib, a stone springhouse and a garage.

The original section of the house is three bays by one room deep. It is constructed of uncoursed fieldstone with a slate roof. Its front and rear elevations both consist of an entrance in the north bay with two nine-over-six windows in the south bays of the first floor. Over the plainly trimmed, recessed door is a four-light transom. Flanking the entrance, reveals carved with three panels echo the pattern of the six-paneled door. A reconstructed hood, contemporary in design to the house, protects the entrance. On the second floor, three six-over-six sash windows are aligned with the door and two first floor windows. All of these windows have narrow, white painted trim and green shutters with stationary louvers. The gabled dormer window was probably added after the first addition was constructed to admit light to the south attic room. Two casement windows, in the peak of the north elevation, illuminate the other small attic room and stairway. *The windows in the house all have very wide sills due to the thickness of the walls and many window panes retain the original glass.*

The floor plan consists of a stair hall and one room on both the first and second stories. Much attention was given to the design and execution of the open string stair with halfpace landings. Opposite these two landings, the well is terminated in a quarter circle which lends simple elegance to the lines of the stair. The ~~square~~ ^{square at the bottom and round above,} balusters, are delicately proportioned as are brackets along the string course.

*square at the bottom and round above,
A*

The division of a second story rear window by a stair landing is functional as it illuminates two flights of the stair and retains the symmetry of the exterior elevation.

There is an interior end chimney of brick at the east end of the stone portion. The first floor wooden mantel is carved with plain pilasters, topped by a frieze with torus molding and a simple mantel shelf. The mantel on the second floor is also classically inspired but is more simple in its execution.

Six-paneled doors throughout the original section are identical to the one of the front entrance. They have brass box locks which were present when ~~the~~ ^{Mrs. Mother, Mrs. Louis Muller,} Stirlings purchased the house in 1936. One of the attic doors has a wooden box lock. *The original walnut floors remain throughout this section.*

The first addition may be entered from the older part by a door cut through the south end of the chimney wall of the first and second stories. This section was in extreme disrepair when ~~the Stirlings~~ ^{Mrs. Muller} ~~mother~~ became the owner~~s~~. ~~Mrs. Louis Muller~~ As many of the walnut floorboards as possible were left on the first level. The replacements are well matched. The fireplace in the single first story room is wide and has an old iron crane in place at the back of the hearth. As the upstairs was beyond restoration, it was reconstructed to include a bath and two bedrooms. A winding stair which led to the second story was replaced by a straight stair located behind the same door which hid the original stair. The door to the stair is hung on iron strap hinges as is the closet next to it. The second floor doorway was cut through a closet in which some of the wooden clothes pegs remain.

A double-tiered porch was added to the front of the first addition in 1936. *The first floor of the porch is paved with slate slabs from the streets of Delta, Pennsylvania. The upstairs porch is screened.* The front and back doors with panes on the first floor were also installed at that time.

HA-153

A lean-to which forms the most southern section replaces a ~~similar~~ ^{smaller,} earlier addition. This 1936 addition contains a kitchen, bath, ~~and~~ maid's room ^{and kitchen porch.} Both this addition and the earlier ^{one have slate roofs.}

The large bank barn is constructed of roughly sawn timber and covered by a gable roof with cedar shingles. The foundation is of stone. Nearby is a frame corncrib. A stone springhouse is located in the wooded area in front of the house. ^{In addition to the spring here, there is} ~~This well and the one in~~ the original cellar. ~~may be of interest to archaeologists.~~ ^{frames, three-} The garage ^{car} was built in 1936, and conforms to the lines of the barn.

Significance Statement, for the Norris-Stirling house (Ha-153)

45.55-

Situated in the midst of a ~~26 1/2~~ acre wooded tract, the Norris-Stirling house retains the atmosphere of an early 19th century farmhouse while functioning today as a summer residence. The original section of the house is a small, stone structure typical in style of early 19th century stone architecture in Harford County. A frame addition to the south, remodeled and added onto, makes the stone structure habitable for present use without damaging the integrity of the site.

The quality of craftsmanship on the interior of this dwelling is unusually fine and well preserved for a house of this type. Achieving elegance through simplicity, the woodwork in both the original rooms is in a vernacular tradition. The carpentry of the stair is a delicate, country craftsman's interpretation of the Federal style.

Outbuildings, such as the stone springhouse, the frame barn and the corn house, are evidence of the agricultural activity which supported at least three generations of the Norris family. Aquilla Norris purchased this land, part of a tract known as Clegates Forest, from John Beale Bordley in 1784, (JLG F/132). The 73 1/2 acres were conveyed by Aquilla to his son Rhesa in 1803, (HD U/423). The house is thought to have been built within several years of this date. In 1843 Rhesa and his wife Susannah deeded 26 1/2 acres to their son Silas N., "in consideration of love and affection for their son," (HD 29/89). After the death of Silas, his trustees, Frank C. and ~~Elizabeth~~ Norris, sold the property to Archibald H. Wann, (WSF 95/145). The land passed ~~to the Wann family~~ to Benjamin F. Wann, ~~who~~ ^{and} ^{he} in 1936 ^{he} sold it to Amelia Muller, ^{V.} ^{who listed} Amelia Prescott Stirling and Campbell Lloyd Stirling ^{as tenants in common} (SWC 241/447). The house was restored by Baltimore architect Laurence Ewald shortly thereafter.

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC Norris - Stirling house, ~~Mount Pleasant~~

AND/OR COMMON Mount Pleasant

2 LOCATION

STREET & NUMBER SE side of Ring Factory Road, NE of its junction with Hollingsworth Road, 4 miles SW of Bel Air

CITY, TOWN Bel Air VICINITY OF X CONGRESSIONAL DISTRICT FIRST

STATE Maryland COUNTY Harford

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> MUSEUM
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> COMMERCIAL
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> EDUCATIONAL
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES RESTRICTED	<input checked="" type="checkbox"/> PRIVATE RESIDENCE
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES UNRESTRICTED	<input type="checkbox"/> ENTERTAINMENT
		<input checked="" type="checkbox"/> NO	<input type="checkbox"/> GOVERNMENT
			<input type="checkbox"/> INDUSTRIAL
			<input type="checkbox"/> MILITARY
			<input type="checkbox"/> OTHER

4 OWNER OF PROPERTY

NAME Mrs. Campbell Lloyd Stirling Telephone #:

STREET & NUMBER 2211 North Charles Street

CITY, TOWN Baltimore VICINITY OF _____ STATE Maryland zip code 21218

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC. Harford County Courthouse Liber #: 241

STREET & NUMBER _____ Folio #: 447

CITY, TOWN Bel Air STATE Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE _____

DATE _____

_____ FEDERAL _____ STATE _____ COUNTY _____ LOCAL

DEPOSITORY FOR SURVEY RECORDS _____

CITY, TOWN _____ STATE _____

HA-153

7 DESCRIPTION

CONDITION

EXCELLENT
 GOOD
 FAIR

DETERIORATED
 RUINS
 UNEXPOSED

CHECK ONE

UNALTERED
 ALTERED

CHECK ONE

ORIGINAL SITE
 MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

NR-153

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Land Records of Harford County,
~~Probate Records of Harford County~~
 Research provided by Mrs. Stirling, copy in the
 files of the Maryland Historical Trust.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	COUNTY

11 FORM PREPARED BY

NAME / TITLE	Cheryl Dees, Summer Intern		
ORGANIZATION	Maryland Historical Trust	DATE	August 1977
STREET & NUMBER	21 State Circle	TELEPHONE	(301) 269-2438
CITY OR TOWN	Annapolis	STATE	Maryland 21401

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
 The Shaw House, 21 State Circle
 Annapolis, Maryland 21401
 (301) 267-1438

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

DATE:	
COUNTY:	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

1. NAME

COMMON: Stirling - Morris house

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER: Lane goes east from Ring Factory Road about 0.2 mi north

CITY OR TOWN: Wilna of Hollingsworth Road near

STATE: Maryland CODE: COUNTY: Harford CODE:

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
District <input type="checkbox"/> Building <input type="checkbox"/>	Public <input type="checkbox"/> Private Acquisition:	Occupied <input type="checkbox"/>	Yes: <input type="checkbox"/>
Site <input type="checkbox"/> Structure <input type="checkbox"/>	Private <input type="checkbox"/> In Process <input type="checkbox"/>	Unoccupied <input type="checkbox"/>	Restricted <input type="checkbox"/>
Object <input type="checkbox"/>	Both <input type="checkbox"/> Being Considered <input type="checkbox"/>	Preservation work in progress <input type="checkbox"/>	Unrestricted <input type="checkbox"/>
PRESENT USE (Check One or More as Appropriate)			
Agricultural <input type="checkbox"/>	Government <input type="checkbox"/> Park <input type="checkbox"/>	Transportation <input type="checkbox"/>	Comments <input type="checkbox"/>
Commercial <input type="checkbox"/>	Industrial <input type="checkbox"/> Private Residence <input type="checkbox"/>	Other (Specify) <input type="checkbox"/>	
Educational <input type="checkbox"/>	Military <input type="checkbox"/> Religious <input type="checkbox"/>		
Entertainment <input type="checkbox"/>	Museum <input type="checkbox"/> Scientific <input type="checkbox"/>		

4. OWNER OF PROPERTY

OWNERS NAME: Campbell L. Stirling

STREET AND NUMBER: 2211 N. Charles Street

CITY OR TOWN: Baltimore STATE: Maryland CODE:

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.: Clerk of the Circuit Court

STREET AND NUMBER: Harford County Courthouse 410 S Main ST

CITY OR TOWN: Bel Air 21014 STATE: Md CODE:

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:

DATE OF SURVEY: Federal State County Local

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN: STATE: CODE:

STATE: Md

COUNTY: Harford

FOR NPS USE ONLY

ENTRY NUMBER

DATE

SEE INSTRUCTIONS

18 Dec. BW 3 C19

7. DESCRIPTION

CONDITION	(Check One)					
	Excellent <input type="checkbox"/>	Good <input checked="" type="checkbox"/>	Fair <input type="checkbox"/>	Deteriorated <input type="checkbox"/>	Ruins <input type="checkbox"/>	Unexposed <input type="checkbox"/>
INTEGRITY	(Check One)			(Check One)		
	Altered <input type="checkbox"/>	Unaltered <input checked="" type="checkbox"/>	Moved <input type="checkbox"/>	Original Site <input checked="" type="checkbox"/>		

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

Stone and frame house, ^{facing south} the stone part at west end is 2 1/2 stories, frame 2 stories with a 2-story porch facing south. The ridge line runs east-west. Stone section three bays by two, Frame three bays by two.

Three Chimneys are at the ends of the stone sections and in the center of the frame part of the house, suggesting that it may be built at two times.

~~The house was closed, but the barn was in use in December, suggesting an owner who lives here part time.~~

There is a springhouse below the house, and a carriage-house; ~~many~~ chicken-house; food house row of outhouses above the house.

The owner reports that the staircase, locks doorways are good old work, the floors walnut planks, the original crane is in the fireplace, the beams hand hewn.

SEE INSTRUCTIONS

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

Pre-Columbian <input type="checkbox"/>	16th Century <input type="checkbox"/>	18th Century <input type="checkbox"/>	20th Century <input type="checkbox"/>
15th Century <input type="checkbox"/>	17th Century <input type="checkbox"/>	19th Century <input checked="" type="checkbox"/>	<i>conformate!</i>

SPECIFIC DATE(S) (If Applicable and Known)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

Aboriginal	Education <input type="checkbox"/>	Political <input type="checkbox"/>	Urban Planning <input type="checkbox"/>
Prehistoric <input type="checkbox"/>	Engineering <input type="checkbox"/>	Religion/Philosophy <input type="checkbox"/>	Other (Specify) <input type="checkbox"/>
Historic <input type="checkbox"/>	Industry <input type="checkbox"/>	Science <input type="checkbox"/>	<u>Architecture</u>
Agriculture <input type="checkbox"/>	Invention <input type="checkbox"/>	Sculpture <input type="checkbox"/>	_____
Art <input type="checkbox"/>	Landscape <input type="checkbox"/>	Social/Humanitarian <input checked="" type="checkbox"/>	_____
Commerce <input type="checkbox"/>	Architecture <input type="checkbox"/>	Theater <input type="checkbox"/>	_____
Communications <input type="checkbox"/>	Literature <input type="checkbox"/>	Transportation <input type="checkbox"/>	_____
Conservation <input type="checkbox"/>	Military <input type="checkbox"/>		
	Music <input type="checkbox"/>		

STATEMENT OF SIGNIFICANCE (Include Personages, Dates, Events, Etc.)

Once a farmhouse, this is now a summer & weekend country refuge for people who work in Baltimore, who cherish the fine workmanship and the pleasant site.

The stone section, the oldest, was built by the Norrie family in 1804, the frame part added not long afterwards, with a ~~was~~ kitchen fireplace that may have replaced an outside kitchen.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN ONE ACRE		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	0 ' "	0 ' "		0 ' "	0 ' "	
NE	0 ' "	0 ' "				
SE	0 ' "	0 ' "				
SW	0 ' "	0 ' "				

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE

11. FORM PREPARED BY

NAME AND TITLE: Jean S. Powell

ORGANIZATION: Maryland Historic Trust DATE: Dec 69

STREET AND NUMBER: 50 State Circle

CITY OR TOWN: Annapolis STATE: Maryland CODE: _____

12. STATE LIAISON OFFICER CERTIFICATION

NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National State Local

Name _____

Title _____

Date _____

I hereby certify that this property is included in the National Register.

Chief, Office of Archeology and Historic Preservation

Date _____

ATTEST:

Keeper of The National Register

Date _____

SEE INSTRUCTIONS




HA-153




HA-153




HA-153



HA-153



HA-153



HA-153



HA-153

11/11/11 - 11/11/11



HA-153



HA-153



HA-153



HA-153



HA-153



HA-153



HA-153



HA-153



HA 153



HA-153



HA-153