

MARYLAND HISTORICAL TRUST  
DETERMINATION OF ELIGIBILITY FORM

NR Eligible: yes \_\_\_  
no

Property Name: Otsego Street Survey District Inventory Number: HA-2048  
Address: 700 and 800 Blocks of Otsego Street City: Havre de Grace, MD Zip Code: 21078  
County: Harford USGS Topographic Map: Havre De Grace  
Owner: Multiple owners Is the property being evaluated a district?  yes  
Tax Parcel Number: Multiple Tax Map Number: 601 Tax Account ID Number: Multiple  
Project: MD 7A (Otsego Street): US 40 to Union Street Agency: FHWA/SHA  
Site visit by MHT staff:  no \_\_\_ yes \_\_\_ Name: \_\_\_ Date: \_\_\_  
Is the property is located within a historic district? \_\_\_ yes  no

If the property is within a district District Inventory Number: \_\_\_  
NR-listed district \_\_\_ yes Eligible district \_\_\_ yes Name of District: \_\_\_  
Preparer's Recommendation: Contributing resource \_\_\_ yes \_\_\_ no Non-contributing but eligible in another context \_\_\_ yes

If the property is not within a district (or the property is a district) Preparer's Recommendation: Eligible  yes \_\_\_ no

Criteria: \_\_\_ A \_\_\_ B  C \_\_\_ D Considerations: \_\_\_ A \_\_\_ B \_\_\_ C \_\_\_ D \_\_\_ E \_\_\_ F \_\_\_ G \_\_\_ None

Documentation on the property/district is presented in:  
Project Review and Compliance Files

Description of Property and Eligibility Determination: (Use continuation sheet if necessary and attach map and photo)

The Otsego Street Survey District consists of houses on the north and south sides of the street between Legion and Adams Street, generally the 700 and 800 blocks of Otsego. The houses date from the late nineteenth and early twentieth centuries, based on research conducted using the 1885, 1899, 1904 and 1910 Sanborn Insurance Company maps for Havre de Grace. Although the streets had been planned and laid out, house construction occurred slowly. The area closest to the river and the bay between Union and Stokes filled in first. This part of Otsego Street is included in the Havre de Grace Historic District and is not part of the current Survey District. One building that is an example of the houses in the area is the Kitzmiller Apartment Building (HA-1096). By 1899, eight houses on the south side of Otsego between Adams and Juniata had been built. There were also several houses at the rear of these properties along an unnamed alley. Between 1904 and 1907, the area west of Juniata became built up, including the Taylor-Griffith House at 823-825 Otsego (HA-828) and the Kennedy-Johnson House at 840-842 Otsego (HA-829).

The Otsego Street Survey District represents the continued prosperity of Havre de Grace's middle class at the beginning of the 20th century which allowed them to buy single family or semi-detached dwellings which marked their permanent achievement in the middle class. Alterations have occurred over the years, as many have been clad in either asbestos shingle or aluminum siding. These alterations however, do not lessen the integrity of the district. The district's period of significance dates from

**MARYLAND HISTORICAL TRUST REVIEW**

Eligibility recommended \_\_\_ Eligibility not recommended

Criteria: \_\_\_ A \_\_\_ B \_\_\_ C \_\_\_ D Considerations: \_\_\_ A \_\_\_ B \_\_\_ C \_\_\_ D \_\_\_ E \_\_\_ F \_\_\_ G \_\_\_ None

MHT Comments

[Signature] Reviewer, Office of Preservation Services Date 10/7/03

[Signature] Reviewer, NR Program Date 10/14/03

NR-ELIGIBILITY REVIEW FORM

Otsego Street Survey District

Inventory Number: HA-2048

Page 2

1899 to 1925, which includes the dates of the earliest house constructions (the Kennedy-Johnson House) through the end of World War I and the economic and transportation changes that occurred as the federal government took over the Aberdeen peninsula to use as the Aberdeen Proving Ground. The loss of the lower portion of Harford County permanently changed the economic climate in Havre de Grace, as it did in Aberdeen and Bel Air.

There area approximately sixteen houses included in the district. They are similar in architectural style, setback, building height, and use common architectural motifs for decoration, such as decorative scroll work for porch brackets.

The Otsego Street Survey District is eligible for inclusion in the National Register of Historic Places under Criterion C (Architecture). The buildings are similar to other buildings included in the Havre de Grace Historic District, but represent a slightly later period of significance for the City. Research did not indicate signifiante for these buildings under Criteria A or B, and Criterion D was not included in this study.

Prepared by: Anne E. Bruder, SHA Arch. Hist.

Date Prepared: 08/13/2003

**MARYLAND HISTORICAL TRUST REVIEW**

Eligibility recommended \_\_\_\_\_ Eligibility not recommended \_\_\_\_\_

Criteria: \_\_\_ A \_\_\_ B \_\_\_ C \_\_\_ D Considerations: \_\_\_ A \_\_\_ B \_\_\_ C \_\_\_ D \_\_\_ E \_\_\_ F \_\_\_ G \_\_\_ None

MHT Comments

Reviewer, Office of Preservation Services

Date

Reviewer, NR Program

Date

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No. HA-2048

### 1. Name of Property (indicate preferred name)

historic Otsego Street Survey District

other

### 2. Location

street and number 700 and 800 Blocks of Otsego Street not for publication

city, town Havre de Grace, MD vicinity

county Harford

### 3. Owner of Property (give names and mailing addresses of all owners)

name Multiple Owners

street and number telephone

city, town state zip code

### 4. Location of Legal Description

courthouse, registry of deeds, etc. Harford County Circuit Court tax map and parcel: See Sec. 7

city, town Bel Air, MD liber folio

### 5. Primary Location of Additional Data

- Contributing Resource in National Register District
- Contributing Resource in Local Historic District
- Determined Eligible for the National Register/Maryland Register
- Determined Ineligible for the National Register/Maryland Register
- Recorded by HABS/HAER
- Historic Structure Report or Research Report at MHT
- Other: \_\_\_\_\_

### 6. Classification

Category	Ownership	Current Function	Resource Count		
			Contributing	Noncontributing	
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture			
<input type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	16	5	buildings
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense			sites
<input type="checkbox"/> site		<input checked="" type="checkbox"/> domestic			structures
<input type="checkbox"/> object		<input type="checkbox"/> education			objects
		<input type="checkbox"/> funerary			Total
		<input type="checkbox"/> government			
		<input type="checkbox"/> health care			
		<input type="checkbox"/> industry			
		<input type="checkbox"/> landscape			
		<input type="checkbox"/> recreation/culture			
		<input type="checkbox"/> religion			
		<input type="checkbox"/> social			
		<input type="checkbox"/> transportation			
		<input type="checkbox"/> work in progress			
		<input type="checkbox"/> unknown			
		<input type="checkbox"/> vacant/not in use			
		<input type="checkbox"/> other:			
			Number of Contributing Resources previously listed in the Inventory		
					2

## 7. Description

Inventory No. HA-2048

### Condition

<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

The Otsego Street Survey District consists of houses on the north and south sides of the street between Legion and Adams Streets, in the 700 and 800 blocks of Otsego. The houses date from the late nineteenth and early twentieth centuries, based on research conducted using the 1885, 1894, 1899, 1904, 1910 and 1921 Sanborn Insurance Company maps for Havre de Grace. Although the streets had been planned and laid out, house construction occurred slowly. The area closest to the river and the bay between Union and Stokes filled in first. This part of Otsego Street is included in the Havre de Grace Historic District (HA-1617) and is not part of the current Survey District. One building that is an example of the houses in the area is the Kitzmiller Apartment Building (HA-1096). By 1899, eight houses on the south side of Otsego between Adams and Juniata had been built. There were also several houses at the rear of these properties along an unnamed alley. Between 1904 and 1907, the area west of Juniata became built up, including the Taylor-Griffith House at 823-825 Otsego (HA-828) and the Kennedy-Johnson House at 840-842 Otsego (HA-829).

Sixteen houses included in the district. They are similar in architectural style, setback, building height, and use common architectural motifs for decoration (scroll work for porch brackets) or cladding (asbestos shingles or aluminum siding). The houses are generally 2-1/2 story side gable houses, and some could be called I-houses. They are 2, 3 or 4 bays wide with shed roof front porches and dormer gables in the attic story. There are few fireplace chimneys, but many houses have central chimneys which indicates an oil furnace or wood stoves which are typical of houses of this period. The houses have been altered through the years but taken together form an identifiable early 20th century residential district. The period of significance dates from 1899 to 1925.

#### SOUTH SIDE OF OTSEGO STREET (east of Juniata):

Minor House, 716 Otsego -- Parcel 573, Map 601, is 2-1/2 stories tall, clad in asbestos shingles, side gable roof of composite shingles, a front gable dormer, and a shed roof porch. The building is 3 bays wide. The Minor House is a contributing resource to the survey district.

O'Brien House, 720 Otsego -- Parcel 572, Map 601, building is 2 stories tall, with an interior end chimney, 3 bays wide. Its exterior cladding is aluminum siding, and the roof is side gable with composite shingles. The O'Brien House is a contributing resource to the survey district.

Shutts House, 726 Otsego -- Parcel 571, Map 601 was built in 1945 and is non-contributing to the Survey District.

Wright House, 730 Otsego -- Parcel 569, Map 601, is a two story stucco building with a formstone façade. It has a side gable roof of composite shingles and is 3 bays wide. There is an interior chimney at the north end of the building and it has a front gable porch roof over the main center entry. The Wright House is a contributing resource to the survey district.

Clifford House, 734 Otsego -- Parcel 567, Map 601, is a two story, 3 bay wide dwelling with a metal awning over the center entrance. The side gable roof is of

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory N HA-2048

Name Otsego Street Survey District  
Continuation Sheet

Number 7 Page 1

composite shingle, while the main walls are clad in aluminum siding. The house has a central chimney. The Clifford House is a contributing resource to the survey district.

Rabold House, 736 Otsego Street, Parcel 566, Map 601. This is a two story, two bay building with a hipped roof porch that has been enclosed. The windows are replacements, and the exterior is clad in aluminum siding. The building has a shed roof with a shallow slope. The Rabold House is a contributing resource to the survey district.

Moseley House, 738 Otsego Street, Parcel 565, Map 601. This is a 3 story, two bay house with a basement. It is clad in green and white aluminum siding and has 1 over 1 replacement windows. The Moseley House is a contributing resource to the survey district.

St. James AME Church House, 742 Otsego Street, Parcel 564, Map 601. This is a 3 story, 2 bay wide building with a front gable roof clad in composite shingles, a shed roof and one over one windows on a parged foundation. A side entrance facing Juniata Street has a gable porch roof, and there is one 2-story shed roof addition. Note: this building was previously inventoried on 2/11/2003 on a DOE short form and determined not eligible for inclusion in the National Register. It is not individually eligible, but is similar in style and age to the other houses on this block, thus making it a contributing resource to the survey district. Its construction date, based on the evidence in the Sanborn Maps, dates to 1910, rather than 1930 as previously stated.

#### SOUTH SIDE OF OTSEGO (west of Juniata):

The Hoffman, Petrick and Evans Houses, 820, 822 and 834 Otsego Street, Map 601, Parcels 555, 554 and 553, are noncontributing resources to the Otsego Street Survey District. Although the Evans House was constructed in 1920 (it appears on the 1921 Sanborn map), these three houses on the south side of Otsego Street are one-story, two or three bay buildings that are much smaller and unlike the other houses in the neighborhood. For this reason, they are considered noncontributing.

Kennedy-Johnson House, 840-842 Otsego Street, Map 601, Parcels 374-375. A contributing resource to the survey district. See individual MIHP and DOE forms for HA-828. The building is a 2-1/2 story 6-bay double house with a side gable roof which dates from 1900. Although now owned by a single family, the house remains two individual dwellings.

#### NORTH SIDE OF OTSEGO STREET (west of Juniata):

Savino Building, 801 Otsego, Map 601, Parcel 380, was constructed in 1965 and is not a contributing resource to the Otsego Street Survey District.

Perkins House, 805 Otsego, Map 601, Parcel 379 was previously surveyed using a DOE short form in February 2003. It was determined not eligible individually for inclusion in the National Register. However, the house, which is 2-1/2 stories tall, and 4 bays wide with one over one replacement windows and vinyl siding. The shed

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory N HA-2048

Name Otsego Street Survey District

Continuation Sheet

Number 7 Page 2

---

roof porch has been enclosed and there is a second shed roof one story addition in the rear. Although not individually eligible, the building is similar in style, age and alterations to other buildings within the survey district. It is therefore recommended as a contributing resource to the survey district.

Dunlap House, 813 Otsego, Map 601, Parcel 378 is a 2-story, 2-bay wide dwelling with a side gable roof, and shed-roof front porch and two additions on the north side of the house -- a two story, two bay, front gable structure appended to the original house, as well as a one-story shed roof enclosed room attached to the two story portion of the house. The Dunlap House is clad in aluminum siding and has replacement one over one windows. Dunlap House is a contributing resource to the survey district.

Angelucci House, 819 Otsego Street, Map 601, Parcel 376, is a contributing resource to the survey district. It is a 3 story building with two bays on the front façade. There is a large gable dormer on the front roof and the building sits on a parged, raised basement. There are two additions at the rear of the building, a two-bay gable roof, two story addition and a one story, one bay addition. The Angelucci House is clad in vinyl siding, has both decorative wood brackets and metal porch supports on the front porch, and the windows have been replaced.

Taylor-Griffith Double House, 823-825 Otsego Street, Map 601, Parcel 374-375, has been individually surveyed and a DOE form completed for it. The Taylor-Griffith Double House is not individually eligible for inclusion in the National Register, but is a contributing resource to the Otsego Street Survey District. See form for HA-829 for additional information.

Daub House, 827 Otsego Street, Map 601, Parcel 373, was constructed between 1899 and 1921 according to the Sanborn Insurance Company maps. However, due to unsympathetic alterations, it is not a contributing resource to the Otsego Street Survey District. It is similar in style to the Angelucci House, but all of its windows have been replaced and moved. The front shed-roof porch has been completely enclosed and two gable dormers have been added to the main roof.

Powell House, 833 Otsego Street, is a two bay, 2-1/2 story Gothic Revival Style House that the tax records date as 1930, but it appears to be an earlier building, probably built around the same time as the Kennedy-Johnson House in 1900. The house has a contemporary addition, which is also 2 bays and 2-1/2 stories tall. It has been stepped back by one bay from the main pile's front façade so that the impact of the addition will be less on streetscape. The entire building is clad in vinyl siding. Although altered, it continues to contribute to the Otsego Street Survey District, since it is similar in style, size and treatment to other houses on the street.

Wright House, 843 Otsego Street, Map 601, Parcel 370, is a 2-1/2 story 3 bay house with two rear additions. The building is clad in aluminum siding and has replacement windows. It sits on a raised foundation, and like many other houses in the neighborhood has a center chimney indicating the presence of some sort of central heating system, whether a flue for wood stoves or a furnace. The porch has been redone, and is more ornate than others on Otsego Street. There is a raised basement,

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory N HA-2048

Name Otsego Street Survey District

Continuation Sheet

Number 7 Page 3

---

and two shed roof additions. Powell House contributes to the Otsego Street Survey District.

Adams-Jackson Double House, 847-849 Otsego Street, Map 601, Parcels 369 and 368, is a four bay, 3 story house with a large wrap around front porch. The entrance to both houses is on the side of each dwelling. The building is clad in asbestos shingle, the roof has composite shingles, and the porch is supported with decorative posts. The tax records indicate that the house was constructed in 1910, but several houses are shown on the north side of Otsego Street in Fowler's Bird's Eye View of Havre de Grace which dates to 1907. The house is unusual and does not seem to be associated with any historical style. If it were a single family dwelling, it would have been an L-shaped 3-5 bay building. But because it was constructed as a duplex, the plan appears to be one room facing the street, the entry, the ell and several more windows/bays. The rear of each house forms a large rectangle, and in plan the houses form a T-shape. The Jackson-Adams House is a contributing element to the Otsego Street Survey District.

Jobes House, 855 Otsego Street, Map 601, Parcel 367, is a 2-story, 2 bay house with a side gable roof with one front gable dormer. It resembles several other houses on the block, and it dates to at least 1910, despite the tax record's date of 1920. Because it appears on the Sanborn Insurance Company map, the 1910 date is more likely to be accurate. The building has a raised foundation, replacement windows and a two story, one bay rear addition, which is newer than the one covered by the asbestos shingle. It is painted grey to differentiate the age. According to the sign at front, the property belongs to Charles Jobes, a noted decoy carver. He uses the addition as his studio and business office. The Jobes House is a contributing resource to the Otsego Street Survey District.

## 8. Significance

Inventory No. HA-2048

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	philosophy
<input type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	other.
<b>Specific dates</b>	1899-1925	<b>Architect</b>	None known	
<b>Construction dates</b>	1899-1925	<b>Builder</b>	None known	

Evaluation for:

National Register

Maryland Register

not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance reports, complete evaluation on a DOE Form - see manual.)

The Otsego Street Survey District is comprised of 16 houses which stand close to the Havre de Grace Historic District. The houses were excluded from the National Register district due to in-fill buildings and lack of continuity, unsympathetic alterations or a twentieth century construction date, since the historic district's period of significance is during the 19th century. However, the Otsego Street Survey District's buildings provide sufficient continuity and integrity of feeling, association, setting, and design to demonstrate a cohesive unit of buildings representing the continued prosperity of Havre de Grace's rising middle class in the early part of the 20th century.

Havre de Grace is well known for its role from the late 18th through the 19th centuries as a commercial port in the upper Chesapeake Bay. However, following the Civil War, the canning industry in Harford County developed as an important industry. The confluence of the Susquehanna River, the Bay, the Baltimore & Ohio (B&O), the Philadelphia, Wilmington & Baltimore (PWB), and the Pennsylvania Railroads within Havre de Grace made the development and transportation of goods and services its primary focus. Canning of fruits, vegetables and seafood were the primary resources. At the same time, recreational hunting, fishing and horse racing brought many visitors to the City. As these industries grew, so too did many industries necessary to support those engaged in the food support industries.

One example of the growth of the rising middle class in Havre de Grace is the subdivision of property west of Adams Street along Otsego Street.

Although the 1980 NRHP nomination for Havre de Grace mentions the early 20th century history, the town's 19th century history is the main focus. As the 19th century ended, Havre de Grace was the largest town in Harford County, and part of a string of boomtowns along the Chesapeake Bay, including Perryville and Aberdeen. The city had prospered through the construction of the canal and the two railroad companies, B&O and PW&B. Each railroad laid tracks through the city, and built passenger and freight stations. This occurred quite slowly starting in the 1880s. The PW&B owned right-of-way that entered the city near Juniata south of Warren Street. This area appears to have been built up, so that the tracks were (and remain so today) elevated on a high berm. The berm is large enough to allow a through pedestrian passageway near Stokes Street, and cars pass under it on other streets. In Fowler's 1907 Bird's Eye View of Havre de Grace, the PW&B station is a prominent landmark in the cityscape, as is the

# Maryland Historical Trust

## Maryland Inventory of Historic Properties Form

Inventory No HA-2048

Name Otsego Street Survey District

Continuation Sheet

Number 8 Page 2

berm which stretches across the northwest part of the city. The berm appears to have been built in the 1890s, following the joint agreement for use between the PW&B and the Pennsylvania Railroad. The agreement gave PW&B a cash infusion which allowed it to build a passenger station and raise the railroad tracks above street level. All of the water resources, the Susquehanna River and the Chesapeake Bay, as well as the highways, brought goods from local farmers and fishermen, which were either shipped directly to northern cities such as New York, or were canned and then shipped to markets around the world. The railroad allowed farmers to ship their goods further without the necessity of making special trips to the city.

All of this activity required the support of other commercial activities, which in turn, attracted more citizens to live in Havre de Grace. By 1900, the northwest corner of Havre de Grace beyond the PW&B tracks was made available for residential development. The land was not formally platted by a real estate developer, but was laid out by the city in lots of varying sizes. This allowed people who were part of Havre de Grace's rising middle class to purchase a lot and build a house. While none seem to be specifically a Sears, Roebuck or Montgomery Ward type house, it is possible that some are from one of the catalog companies. More likely however, is that the houses were designed and built by local builders, since the styles are similar to others found within Havre de Grace and the nearby countryside. One form that is found consistently is the double house - there are 3 in the Otsego Street Survey District, and other examples abound in Havre de Grace. The buildings are designed to look like one house, but have separate entrances, and are mirror images of one another. The Kennedy-Johnson Double House is on the south side of Otsego Street, across the street from both the Jackson-Adams House and the Taylor-Griffith House.

The people who lived on Otsego Street in 1910 held a variety of jobs that in turn provided them with the means to live in the houses. According to the 1910 U.S. Census for Harford County, the Otsego Street residents worked as a stone quarry engineer, railroad watchman, telegraph operator, boardinghouse keeper, dressmaker, harness maker, music teacher, electric company machinist and railroad carpenter. While not well-off, the residents were comfortable. Today, the district has several decoy carvers, and other residents are employed and successful in their pursuits.

While the Otsego Street Survey District houses represent several different styles, most are typical of early 20th century. They are not specifically Arts & Crafts, nor do they represent many of the revival styles that were popular at the time. Most are 2 or 3 bays, reflecting the homeowners' practical needs for a house, but also the desire for a substantial dwelling. Many of the lots are narrow and deep. As a result the houses have side gable roofs and long additions at the rear of the buildings. Some lots were clearly made in order to support a double house, but some residents built smaller houses, which provided for a larger yard.

See attached DOE form for NRHP evaluation

# Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. HA-2048

Name Otsego Street Survey District

Continuation Sheet

Number 8 Page 1

---

## HISTORIC CONTEXT

### MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization:

Chronological/Developmental Period(s): 1899-1925

Historic Period Theme(s): Commerce, transportation, rise of middle class

Resource Type: Building

Category:

Historic Environment Urban

Historic Function(s) and Use(s): Single family dwellings

Known Design Source: None known

---

## 9. Major Bibliographical References

---

Inventory No. HA-2048

See Continuation Sheet.

---

## 10. Geographical Data

---

Acreage of surveyed property 5  
Acreage of historical setting 5  
Quadrangle name Havre de Grace Quadrangle scale 1:24,000

---

### Verbal boundary description and justification

The Otsego Street Survey District boundaries are confined to the tax parcels shown on Harford County Tax Map 601 (attached) and listed with the contributing properties under Section 7 of this form.

---

## 11. Form Prepared By

---

name/title	Anne E. Bruder, Architectural Historian		
organization	Maryland State Highway Administration	date	08/13/2003
street and number	707 North Calvert Street	telephone	410-545-855
city or town	Baltimore	state MD	zipcode 21202

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust  
DHCD/DHCP  
100 Community Place  
Crownsville MD 21032  
410-514-7600

9. Major Bibliographical References

*Annual Report of the Philadelphia, Baltimore & Wilmington Railroad Company, 11<sup>th</sup> Annual Report of the Board of Directors to the Stockholders, Presented and Adopted at the Annual Meeting of the Stockholders 9<sup>th</sup> of March 1914.* [n.d.]

Fowler, Thaddeus M., *Bird's Eye View of Havre de Grace*, Morrisville, PA: Fowler & Kelly, 1907

Brugger, Robert, *Maryland – A Middle Temperment – 1634-1980*, Baltimore: Johns Hopkins University Press, 1988

Hagan, David and Joan, *Upper Chesapeake Bay Decoys and Their Makers*, West Chester, PA: Schiffer Publishing, Ltd., 1990

*Havre de Grace, An Informal History*, ed. Peter A. Jay, Havre de Grace, MD: The Susquehanna Publishing Company, 1986

Low, Paula, Nield, Wayne L II and Shultz, Darlene, *Havre de Grace, Maryland National Register of Historic Places Nomination Form*, Washington, DC: National Park Service, 1981

Sanborn Fire Insurance Company, *Havre de Grace, Maryland*, maps for 1884, 1894, 1899, 1904, 1910 and 1921.

United States of America, Decennial Census, 1910

Weeks, Christopher, *An Architectural History of Harford County, Maryland*, Baltimore: Johns Hopkins University Press, 1996

Wright, C. Milton, *Our Harford Heritage, A History of Harford County, Maryland*, privately published, 1967

# Harford County Tax Map 601

840-2048  
HA-2048

Taylor-Griffith Double House  
823-825 Otsego Street  
HA-829


Kitzmiller Apartments  
667 Otsego Street  
HA-1096


Kennedy-Johnson Double House  
840-842 Otsego Street  
HA-828

Otsego Street Survey District  
HA-2048

Havre de Grace Historic District

SCALE 1:4800





HAVRE DE GRACE

Garrett Island

Perryville

Good Shepherd Sch

Taylor-Griffith House, HA-829

Havre de Grace Historic District

HA-1617 Perry Point

Kennedy-Johnson House, HA-828

Otsego Street Survey District

HA-2048

Kitmiller Apartments, HA-1096

HAVRE DE GRACE

Concord Pt Lighthouse

Park Island

8702-VH

166

Osborne

40



SPE  
LIM  
2

HA-2048

BEKINS, JUNILIA & ANGELOCCI

HOUSES (805-813-819)

OTSEGO ST. SENECA DISTRICT

HARFORD CO. MD

A BROWNE

ART <No. 4A>005  
160 6917 -1 N-1-2-46 (042)0

INDSNAP

JUNE 2003

LOOKING WEST ON OTSEGO ST  
NORTH SIDE

1/7



HA-2045.

POWELL - DAUB - TAYLOR - GERMAIN

HOUSES, 823-825-827-833

OTSEGO ST. SURVEY DISTRICT

WAGFORD CO. MD.

H. BRUBAKER

ART (No. 1A)025  
160 6917 -1 N-1+4-A6 (042)©

JUNE 2003

INDIANO.

LOOKING EAST ON OTSEGO ST.  
(NORTH SIDE)

2/7



NA-2048

WRIGHT, JOHNSON & JACKSON HOUSES  
(843, 847 & 849) OTSEGO ST. SWAY  
DISTRICT

NARFORD CO. MD

JUNE 2003

ART (No. 0A)001  
160 6917 -1 N-1-5 05 (042)©

A. BRUNDER  
MD SAPO

LOOKING WEST END OTSEGO (NORTH SIDE)

3/7



HA 2048

HOFFMAN, PETRICK & EVANS HOUSES  
(820, 822 & 834) OTSEGO STREET  
SWANSEA DISTRICT - NON CONTRIB.  
RESOURCES

HARTFORD CO, MD.

ART 985 6917 <No. 5A>030  
N N N N-92 <042>©

ARBRIDGE

JUNE 2003

WINDSPO

LOOKING EAST ON OTSEGO ST. (SOUTH  
SIDE)

4/7



HA-2048

OSCEGO STREET SURVEY DISTRICT  
KENNEDY-JONNISON HOUSE (HA-828)

WARFORD Co MD

JUNE 2003

A. PARUDER

ART <No. 4A>029  
985 6917 N N N+1-A9 (042)0

INDSNBC

LOOKING START AT KENNEDY-JONNISON  
HOUSE.

8/7



NA-2040

ST. JAMES AVE & WOODLEE HOUSES  
(142 R 73E) OTSEGO ST. SWEDEN  
DISTRICT

HARFORD CO. MD

JUNE 2003

ART <No. 7A>008  
160 6917 -1 N-1-3-64 (042)©

ARBUZZER  
MD SAPO.

LOOKING WEST ON OTSEGO ST (SOUTH  
SIDE).

6/7



HA-2048

OTSEGO ST. SURVEY DISTRICT

MINOR, OFFICER, SHUTS & WEIGHT HOUSE

716, 720, 726 & 730

HARFORD CO. MD

JUNE, 2003

ART <No. 6A>007  
160 6917 -1 N-1-3-93 (042)©

ARRIVED

MD SNPOI

LOOKING EAST ON OTSEGO (SOUTH SIDE)

V7