

United States Department of the Interior
Heritage Conservation and Recreation Service

National Register of Historic Places
Inventory—Nomination Form

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

For HCRS use only

received

date entered

1. Name

historic Chestnut Ridge, Christian Hoopman House

and or common Chestnut Ridge (preferred)

2. Location

street & number 3850 West Chapel Road n/a not for publication

city, town Aberdeen n/a vicinity of congressional district First

state Maryland code 24 county Harford County code 025

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture <input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial <input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational <input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment <input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government <input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial <input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military <input type="checkbox"/> other:

4. Owner of Property

name Dr. and Mrs, Richard A. Mones

street & number 3850 West Chapel Road

city, town Aberdeen n/a vicinity of state Maryland 21001

5. Location of Legal Description

courthouse, registry of deeds, etc. Harford County Courthouse

street & number 40 South Main Street

city, town Bel Air, Maryland state

6. Representation in Existing Surveys

title 1. Maryland Historical Trust Historic Sites Inventory
2. Historic American Bldg. Survey has this property been determined eligible? yes no

date 1. 1983
2. 1936 2. federal 1. state county local

depository for survey records 1. Maryland Historical Trust, 21 State Circle, Annapolis, MD 21401
2. Department of the Interior, Washington, D. C.

city, town 1. Annapolis Maryland
2. Washington state D. C.

7. Description

HA-664

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

DESCRIPTION SUMMARY

Chestnut Ridge is a c. 1810 two-story brick dwelling with an earlier frame wing located near Aberdeen in Harford County, Maryland. The house is three bays wide and one room deep, with a center-hall plan. The principal (south) facade is laid in Flemish bond, and features a central entrance with a six-panel door surmounted by a 4-light transom and flanked on either side by a 6/9 sash window in a flat-arched opening. A one-story porch spans this facade; with turned columns and scrollwork brackets, this porch represents an addition made in the third quarter of the 19th century. The second story is lighted by three evenly-spaced 6/9 windows. The gable ends are laid in common bond; the east wall has a basement entrance and two 4-light attic windows. A three-course corbeled cornice defines the roofline. The west end shows evidence of alteration to its fenestration, and is currently pierced by a 6/9 window on both stories, offset to the left, and french doors on the right. Both gables have an interior chimney. A 1½-story frame wing extends from the northwest corner; this section, two bays wide by one bay deep with a central chimney, predates the brick section. The house retains considerable integrity and is noteworthy for its vernacular Federal woodwork which remains substantially intact, and for the Greek Revival trim in the east parlor which reflects an early renovation. The house is currently undergoing restoration. Also on the property is a stone springhouse which is being restored. The site of an 18th-century mill, and a marker from the original survey of the tract, also survive on the property.

GENERAL DESCRIPTION

Chestnut Ridge, located on the east side of West Chapel Road, about ½ mile southeast of Aldion Road (Rt. 156), comprises about two acres of landscaped grounds, with five acres of woodland to the east. Bounding the visible acreage is Swan Creek on the south; West Chapel Road on the west; a hedgerow separating this property from Winsted, a National Register site on the north, and a stone wall on the east that runs perpendicular to the hedgerow then turns 90 degrees in an east-west direction back to the woods. Two large Norway spruce trees shade the brick facade year round and a variety of other shrubs, including azaleas, rhododendron, ornamental fruit trees and a large Eastern hemlock offer an attractive view of the landscape. A number of small boxwoods line both sides of a brick path that branches midway to lead to the front and side entrances to the house.

This Federal period house, c. 1800-1810, consists of two sections: a brick section and a frame section. The brick section lies in an east-west direction with the front facing south; the frame section lies in a north-south direction and joins the brick portion at the northwest corner. The brick facade contains a screened porch running almost the full width of the house, with the porch lying just below the second story windows. Turned posts with curvilinear spandrels date the porch c. 1850-60.

United States Department of the Interior
National Park Service

HA-664

For NPS use only

National Register of Historic Places
Inventory—Nomination Form

received

date entered

Continuation sheet Chestnut Ridge Harford County, Maryland Item number 7 Page 1

GENERAL DESCRIPTION

The brick section is 3 bays wide and 1 room deep; 2 stories high with an attic and basement. The front facade is laid in Flemish bond, while the sides and back are common (American) bond. There is a stepped, 3-brick cornice surrounding the brick portion, with two end chimneys. The windows are six over nine with a flat arch above. On the west side is a doorway measuring 3'7½" x 7'6½", thought to be original, but now has 2 french-doors occupying it. The doorway also has a flat arch above it, as do two windows on that side which are directly above each other at the first and second levels. The principal entrance to the brick section is through a 6-panel wooden door with a 4-light transom. The interior is laid out with a center hall floor plan, with a room to the east and west of the hall. A 3-flight stairway has 2 landings with six over six windows at the top of each landing. A small landing is present where the stairs lead to the attic. The handrail is supported by plain, rectangular ballusters, turned newels, and the railing forms an acute angle where it turns to go to the attic stairs. Most of the chair-rail is original in the upstairs, the south wall of the west room of the brick section and the southern room of the frame section. No chair-rail is present in the kitchen. The chair-rail has a ½" bead at the bottom and a bullnose molding at the top of a flat board 3 3/4" high. Window frames throughout both sections have a ½" bead on the inner surface and applied moldings on the outer surface. The moldings in the frame section are slightly smaller in scale. Baseboard is found throughout both sections measuring 6" high with a ½" bead at the top and shoe-molding at the base.

The east room in the brick section has bullseye moldings with fluted frames around the north and south windows and the interior of the door frame. Most of the doors throughout the house have 6-panels, with the exception of batten doors in the room above the kitchen.

The frame section is 1½ stories with a gabled roof and central chimney. It is two rooms in line extending north from the northwest corner of the brick section. Each of the upper rooms has a dormer on the east and west sides, with six lights on the east; nine lights on the west. Windows on the first level are six over six. Walls are plastered throughout the house, with the exception of the west wall of the kitchen where a doorway, not original, was closed.

Fireplaces are found in all but the room above the kitchen, however the fireplace in the upstairs west bedroom in the brick section has been plastered over at some earlier time. All but two fireplaces have wooden mantels with a shelf, while the kitchen fireplace and second level room in the southern section frame portion have only the shelf and plaster surround.

United States Department of the Interior
National Park Service

HA-664

For NPS use only

received

date entered

**National Register of Historic Places
Inventory—Nomination Form**

Continuation sheet Chestnut Ridge Item number 7 and 10 Page 2
Harford County, Maryland

GENERAL DESCRIPTION (Continued)

Floors are random width pine floors, with the exception of the south room, first level frame portion which has 2" wide oak boards. The floor in the west room of the first level brick section has unusual plugged, pine floor boards, somewhat uniform in width measuring average 5-6" and containing plugs about 1½" diameter, in addition to the natural knotholes sporadically positioned in the floorboards. There are as many as four plugs in some boards with no obvious pattern. The room above the kitchen has unusually wide boards, ranging from 7-12" in areas.

Rafters in the attic are visible, with the original roof supports having numbered members in Roman numerals and are jointed in mortise and tenon style. The roof is asphalt shingle.

Spring-House Outbuilding

An original, fieldstone spring-house with an original, stone-lined well lies about 30 feet east of the frame section of the house. The spring-house measures approximately 6 feet 4 inches high by 9 feet 9 inches long, although it is not exactly square. The interior reveals the original trough running along the north and east walls. The building has no roof at present.

Garage

Also on the property is a 1½ story, gambrell-roofed stone garage dating from ca. 1950, which does not contribute to the significance of the resource.

BOUNDARY JUSTIFICATION

The nominated property, approximately two acres, encompasses the resource within its immediate landscaped setting. Boundaries are defined by Swan Creek on the south, West Chapel Road on the west; a hedgerow and stone wall on the north, and a tree line on the east. The boundaries exclude approximately five acres of undeveloped woodland to the east and north, which does not contribute to the significance of the resource.

8. Significance

HA-664

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input checked="" type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates 1800-1810 **Builder/Architect** Christian Hoopman

Statement of Significance (in one paragraph)

SIGNIFICANCE SUMMARY

Applicable Criteria: A, C

Chestnut Ridge derives significance from several sources. It represents a type of architecture which is now rare in Harford County: probably fewer than a dozen brick Federal-style houses survive in the county, and of these Chestnut Ridge is a particularly fine example, unusual for its Flemish bond facade with scored joints and for the quantity of original decorative trim that it retains. Other houses of this type in Harford County have generally been heavily restored; Chestnut Ridge has escaped this fate, and current restoration plans emphasize sensitivity and restraint. The 18th century frame portion of the house is also rare in the area. The house derives additional significance from its historical association with the Hoopman family, who were among the earliest and most influential settlers of the Aberdeen area.

HISTORY AND SUPPORT

Christian Hoopman, a brick-molder and artisan, built Chestnut Ridge, as well as building other fine brick structures in the Harford County community. With few existing examples of such architecture today, Chestnut Ridge represents a building that contains many original features of the period, with some alterations being done to maintain the internal and external integrity of the house.

The Chestnut Ridge tract was bought by Christian Hoopman in 1797. Christian and his brother Peter Hoopman, a brick molder and millwright, respectively, both made the bricks for the house and ran a mill on the property, with the contour of the land showing evidence of the millrace.

According to an account written by Jacob P. Walker, grandson of Christian Hoopman, the Hoopman brothers acquired large tracts of land in increments of 500 acres and that by the late 1790's had holdings extending from Swan Creek below Post Road to Hopewell Church and included the land on which the Church stands, as well as the land on which this house stands.

Christian Hoopman is attributed to donating the land and building Wesleyan Chapel, located near the bottom of West Chapel Road on Paradise Road (Rt. 462). He also has been credited with building a larger brick house, now known as Winsted, presently listed as a National Register site, neighboring this property.

The frame part of this house, located on West Chapel Road near a bend in Swan Creek, matches measurements given in the 1798 Federal Tax List. The 1814 tax assessment is incomplete for the Fifth Election District, but it is thought that the brick section was built about 1800-1810.

THE HARFORD MEMORIAL
GARDEN, INC.
560/4, 473 275 E
973/280
82 67A.
P. 124

F 325

JAMES A. TAYLOR
1012/433
21 249A
P. 128

GRACIE H. HOPKINS
ETAL
1117/415
93 61A
P. 133

USA
267/229
7.54A
P. 129

GEORGE E.
DAIL
1048/26
14 48A.
P. 130

NATIONAL REGISTER
BOUNDARY

CHESTNUT RIDGE (HA-664)

HARFORD COUNTY, MARYLAND


OCTOBER 1983

SCALE: 1" = 600'


SAMUEL T. JONES
1004/517
244.74A
P. 155


ANDREW C. NORLOCK
485/380
47.49A.
P. 157

SCALE: 1" = 600'



Assessment C





(second level)

"Chestnut Ridge" HA 664



HA-664
CHESTNUT
RIDGE
HARFORD COUNTY
MARYLAND
18-398510-
4379310

9. Major Bibliographical References

HA-664

Federal Direct Tax of 1798
Maryland Tax List, 1814

Historical research by Dr. Joseph Sternberg, former owner. (Copy in MHT files, Annapolis).
Walker, Jacob P. "History of Wesleyan Chapel." 1926. (Copy in Md. Hist. Trust files).

10. Geographical Data

Acree of nominated property approximately 2 acres

Quadrangle name Aberdeen, Maryland

Quadrangle scale 1:24,000

UMT References

A

1	8	3	9	8	5	1	0	4	3	7	9	3	1	0
Zone		Easting				Northing								

B

Zone		Easting				Northing								

C

Zone		Easting				Northing								

D

Zone		Easting				Northing								

E

Zone		Easting				Northing								

F

Zone		Easting				Northing								

G

Zone		Easting				Northing								

H

Zone		Easting				Northing								

Verbal boundary description and justification

Boundaries are indicated on the attached map; for boundary justification, see Continuation Sheet #2.

List all states and counties for properties overlapping state or county boundaries

state n/a code county code

state code county code

11. Form Prepared By

name/title 1. Pamela Mones, owner
2. Michael Trostel, A.I.A. (historical architect)

organization date July 1983

street & number 1. 3850 West Chapel Road
2. 1307 Bolton Street telephone

city or town 1. Aberdeen Maryland 21001
2. Baltimore state Maryland 21217

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the Heritage Conservation and Recreation Service.

State Historic Preservation Officer signature *J. Mitt* 10-27-83

title STATE HISTORIC PRESERVATION OFFICER date

For HCRS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

Attest:

date

Chief of Registration

Title Search
HA-664

Clarence A. and Mary RF Tinsman
3844 West Chapel Road
Aberdeen, MD 21001

	761	302	11/9/1967	Grantor: Wendell S. Muncie and Rachel Cary, wife Grantee: Clarence A. Tinsman and Mary, wife Acreage: 64 acres (1 rood) 34 perches
GRG	370	567	3/25/1952	Grantor: Wendell S. Muncie and Rachel Cary, wife Grantee: Joseph Sternberg and Edith Jacobs, wife
GRG	370	572	3/25/1952	Grantor: Joseph Sternberg and Edith Jacobs, wife Grantee: Wendell S. Muncie and Rachel Cary, wife
GCB	292	46	11/13/1945	Grantor: William B. Vinson and Margueritte, wife Grantee: Rachel C. Muncie Acreage: 12½ acres
DGW	201	120	8/31/1926	Grantor: William B. Vinson and Margueritte, wife Grantee: Samuel L. Fyle and Mary E., wife Acreage: "Brookside Farm"
DGW	198	400	3/29/1926	Grantor: Johanne E. Armstrong and Andrew T, her husband Grantee: Samuel L. Fyle Acreage: 12½ acres "Brookside Farm"
DGW	181	447	5/3/1923	Grantor: Catherine E. Whyte, John Whyte, husband Grantee: Johanne E. Armstrong Acreage: "Brookside Farm"
JAR	160	492	11/7/1918	Grantor: Sarah W.N. Leonard, husband Grantee: Catherine E. Whyte, John Whyte, husband
JAR	139	415	4/14/1913	Grantor: Mary E. Donahue Grantee: Sarah W.N. Leonard, husband Acreage: "Chestnut Ridge", "Woods Meadow Enlarged", "Eagons Lot"
WG	10	75	6/3/1858	Grantor: William Rienick and Sarah W., wife Grantee: James L. Donahoo Acreage: "Chestnut Ridge", "Wood Meadow Enlarged", "Eagon's Lot"

ALJ	5	69	10/26/1854	Grantor: John and Elizabeth Robinson, wife Grantee: Sarah Wills Rienick Acreage: "Chestnut Ridge", "Wood Meadow Enlarged", "Eagon's Lot"
HDG	35	421	8/3/1849	Grantor: Hiram McCullough and Sarah Jone, wife Grantee: Elizabeth Robinson and John husband, Purchased at a sale made by William Bond, Trustee. The property was sold to Justus Fox.
HDG	7	87	6/3/1845	Equity: Bartol and others, complainant William Bond, trustee and Jacob Hoopman, defendent
HD	19	373	2/15/1837	Grantor: Christian Hoopman, et al Grantee: Jacob Hoopman
JLG	N	590	11/6/1797	Grantor: William Wood Grantee: Christian Hoopman Acreage: "Chestnut Ridge", "Wood Meadow Enlarged", "Eagon's Lot"
JLG	K	113	9/8/1788	Grantor: Issac Wood Grantee: William Wood Acreage: "Meadows Enlarge"
JLG	K	182	9/8/1788	Grantor: Issac Wood Grantee: William Wood Acreage: Chestnut Ridge containing 90 acres
JLG	K	103	9/8/1788	Grantor: Issac Wood Grantee: William Wood Acreage: "Chestnut Ridge"

Title Search
HA-664

Mr. and Mrs. Clifford F. Shaw
3850 West Chapel Road
Aberdeen, MD 21001

1006	881	8/16/76	Grantor: Robert Karl Dietz and George William Brown, Jr. Grantee: Clifford F. and Alice B. Shaw Acreage: 7.205 acres
HDC	875	874 6/30/71	Grantor: The Maryland Title Guarantee Company Grantee: Robert Karl Dietz and George William Brown, Jr.
HDC	871	614 5/7/71	Grantor: Joseph Sternberg, et al Grantee: Maryland Title Guarantee Company
GRG	370	567 3/25/52	Grantor: Wendel L. Muncie Grantee: Joseph Sternberg
GRG	764	280 12/2/67	Grantor: Wendel L. Muncie Grantee: Joseph Sternberg
GRG	370	572 3/25/1952	Grantor: Joseph Sternberg and Edith Jacobs, wife Grantee: Wendell S. Muncie and Rachel Cary, wife
GCB	292	46 11/13/1945	Grantor: William B. Vinson and Margueritte, wife Grantee: Rachel C. Muncie Acreage: 12½ acres
DGW	201	120 8/31/1926	Grantor: William B. Vinson and Marguertitte, wife Grantee: Samuel L. Fyle and Mary E., wife Acreage: "Brookside Farm"
DGW	198	400 3/29/1926	Grantor: Johanne E. Armstrong and Andrew T, her husband Grantee: Samuel L. Fyle Acreage: 12½ acres "Brookside Farm"
DGW	181	447 5/3/1923	Grantor: Catherine E. Whyte, John Whyte, husband Grantee: Johanne E. Arsmstrong Acreage: "Brookside Farm"
JAR	160	492 11/7/1918	Grantor: Sarah W.N. Leonard, husband Grantee: Catherine E. Whyte, husband

JAR	139	415	4/14/1913	Grantor: Mary E. Donahue Grantee: Sarah W.N. Leonard, husband Acreage: "Chestnut Ridge", "Woods Meadow Enlarged", "Eagons Lot"
WF	10	75	6/3/1858	Grantor: William Rienick and Sarah W., wife Grantee: James L. Donahoo Acreage: "Chestnut Ridge", "Wood Meadow Enlarged" "Eagon's Lot"
ALJ	5	69	10/26/1854	Grantor: John and Elizabeth Robinson, wife Grantee: Sarah Whills Rienick Acreage: "Chestnut Ridge", "Wood Meadow Enlarged" "Eagon's Lot"
HDG	35	421	8/3/1849	Grantor: Hiram McCullough and Sarah Jone, wife Grantee: Elizabeth Robinson and John, husband, Purchased at a sale made by William Bond, Trustee. The property was sold to Justus Fox.
HDG	7	87	6/3/1845	Equity: Bartol and others, complainant William Bond, trustee and Jacob Hoopman, defendent
HD	19	373	2/15/1837	Grantor: Christian Hoopman, et al Grantee: Jacob Hoopman
JLG	N	590	11/6/1797	Grantor: William Wood Grantee: Christian Hoopman Acreage: "Chestnut Ridge", "Wood Meadow Enlarged", "Eagon's Lot"
JLG	K	113	9/8/1788	Grantor: Issac Wood Grantee: William Wood Acreage: "Chestnut Ridge" containing 90 acres
JLG	K	103	9/8/1788	Grantor: Issac Wood Grantee: William Wood Acreage: "Chestnut Ridge"

**United States Department of the Interior
Heritage Conservation and Recreation Service
National Register of Historic Places
Inventory—Nomination Form**

For HCRS use only

received

date entered

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic Chestnut Ridge, Christian Hoopman House

and/or common Chestnut Ridge (preferred)

2. Location

street & number 3850 West Chapel Road n/a not for publication

city, town Aberdeen n/a vicinity of congressional district First

state Maryland code 24 county Harford County code 025

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture <input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial <input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational <input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment <input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government <input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial <input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military <input type="checkbox"/> other:

4. Owner of Property

name Dr. and Mrs. Richard A. Mones

street & number 3850 West Chapel Road

city, town Aberdeen n/a vicinity of state Maryland 21001

5. Location of Legal Description

courthouse, registry of deeds, etc. Harford County Courthouse

street & number 40 South Main Street

city, town Bel Air, Maryland state

6. Representation in Existing Surveys

title 1. Maryland Historical Trust Historic Sites Inventory
2. Historic American Bldg. Survey has this property been determined eligible? yes no

date 1. 1983
2. 1936 federal state county local

depository for survey records 1. Maryland Historical Trust, 21 State Circle, Annapolis, MD 21401
2. Department of the Interior, Washington, D. C.

city, town 1. Annapolis Maryland
2. Washington state D. C.

7. Description

HA-664

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

DESCRIPTION SUMMARY

Chestnut Ridge is a c. 1810 two-story brick dwelling with an earlier frame wing located near Aberdeen in Harford County, Maryland. The house is three bays wide and one room deep, with a center-hall plan. The principal (south) facade is laid in Flemish bond, and features a central entrance with a six-panel door surmounted by a 4-light transom and flanked on either side by a 6/9 sash window in a flat-arched opening. A one-story porch spans this facade; with turned columns and scrollwork brackets, this porch represents an addition made in the third quarter of the 19th century. The second story is lighted by three evenly-spaced 6/9 windows. The gable ends are laid in common bond; the east wall has a basement entrance and two 4-light attic windows. A three-course corbeled cornice defines the roofline. The west end shows evidence of alteration to its fenestration, and is currently pierced by a 6/9 window on both stories, offset to the left, and french doors on the right. Both gables have an interior chimney. A 1½-story frame wing extends from the northwest corner; this section, two bays wide by one bay deep with a central chimney, predates the brick section. The house retains considerable integrity and is noteworthy for its vernacular Federal woodwork which remains substantially intact, and for the Greek Revival trim in the east parlor which reflects an early renovation. The house is currently undergoing restoration. Also on the property is a stone springhouse which is being restored. The site of an 18th-century mill, and a marker from the original survey of the tract, also survive on the property.

GENERAL DESCRIPTION

Chestnut Ridge, located on the east side of West Chapel Road, about ½ mile southeast of Aldion Road (Rt. 156), consists of 7+ acres of land, 5 of which are wooded; the rest comprising the land surrounding the house. Bounding the visible acreage is Swan Creek on the south; West Chapel Road on the west; a hedgerow separating this property from Winsted, a National Register site on the north, and a stone wall on the east that runs perpendicular to the hedgerow then turns 90 degrees in an east-west direction back to the woods. Two large Norway spruce trees shade the brick facade year round and a variety of other shrubs, including azaleas, rhododendron, ornamental fruit trees and a large Eastern hemlock offer an attractive view of the landscape. A number of small boxwoods line both sides of a brick path that branches midway to lead to the front and side entrances to the house.

This Federal period house, c. 1800-1810, consists of two sections: a brick section and a frame section. The brick section lies in an east-west direction with the front facing south; the frame section lies in a north-south direction and joins the brick portion at the northwest corner. The brick facade contains a screened porch running almost the full width of the house, with the porch lying just below the second story windows. Turned posts with curvilinear spandrels date the porch c. 1850-60.

United States Department of the Interior
National Park Service

HA-664

For NPS use only

received

date entered

National Register of Historic Places
Inventory—Nomination Form

Continuation sheet Chestnut Ridge
Harford County, Maryland Item number 7 Page 1

GENERAL DESCRIPTION

The brick section is 3 bays wide and 1 room deep; 2 stories high with an attic and basement. The front facade is laid in Flemish bond, while the sides and back are common (American) bond. There is a stepped, 3-brick cornice surrounding the brick portion, with two end chimneys. The windows are six over nine with a flat arch above. On the west side is a doorway measuring 3'7½" x 7'6½", thought to be original, but now has 2 french-doors occupying it. The doorway also has a flat arch above it, as do two windows on that side which are directly above each other at the first and second levels. The principal entrance to the brick section is through a 6-panel wooden door with a 4-light transom. The interior is laid out with a center hall floor plan, with a room to the east and west of the hall. A 3-flight stairway has 2 landings with six over six windows at the top of each landing. A small landing is present where the stairs lead to the attic. The handrail is supported by plain, rectangular ballusters, turned newels, and the railing forming an acute angle where it turns to go to the attic stairs. Most of the chair-rail is original in the upstairs, the south wall of the west room of the brick section and the southern room of the frame section. No chair-rail is present in the kitchen. The chair-rail has a ½" bead at the bottom and a bullnose molding at the top of a flat board 3 3/4" high. Window frames throughout both sections have a ½" bead on the inner surface and applied moldings on the outer surface. The moldings in the frame section are slightly smaller in scale. Baseboard is found throughout both sections measuring 6" high with a ½" bead at the top and shoe-molding at the base.

The east room in the brick section has bullseye moldings with fluted frames around the north and south windows and the interior of the door frame. Most of the doors throughout the house have 6-panels, with the exception of batten doors in the room above the kitchen.

The frame section is 1½ stories with a gabled roof and central chimney. It is two rooms in line extending north from the northwest corner of the brick section. Each of the upper rooms has a dormer on the east and west sides, with six lights on the east; nine lights on the west. Windows on the first level are six over six. Walls are plastered throughout the house, with the exception of the west wall of the kitchen where a doorway, not original, was closed.

Fireplaces are found in all but the room above the kitchen, however the fireplace in the upstairs west bedroom in the brick section has been plastered over at some earlier time. All but two fireplaces have wooden mantels with a shelf, while the kitchen fireplace and second level room in the southern section frame portion have only the shelf and plaster surround.

**United States Department of the Interior
National Park Service**

HA-664

For NPS use only

**National Register of Historic Places
Inventory—Nomination Form**

received

date entered

Continuation sheet Chestnut Ridge Harford County, Maryland Item number 7 Page 2

GENERAL DESCRIPTION (Continued)

Floors are random width pine floors, with the exception of the south room, first level frame portion which has 2" wide oak boards. The floor in the west room of the first level brick section has unusual plugged, pine floor boards, somewhat uniform in width measuring average 5-6" and containing plugs about 1 1/4" diameter, in addition to the natural knotholes sporadically positioned in the floorboards. There are as many as four plugs in some boards with no obvious pattern. The room above the kitchen has unusually wide boards, ranging from 7-12" in areas.

Rafters in the attic are visible, with the original roof supports having numbered members in Roman numerals and are jointed in mortise and tenon style. The roof is asphalt shingle.

Spring-House Outbuilding

An original, fieldstone spring-house with an original, stone-line well lies about 30 feet east of the frame section of the house. The spring-house measures approximately 6 feet 4 inches high by 9 feet 9 inches long, although it is not exactly square. The interior reveals the original trough running along the north and east walls. The building has no roof at present.

8. Significance

HA-664

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input checked="" type="checkbox"/> exploration settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates 1800-1810 **Builder/Architect** Christian Hoopman

Statement of Significance (in one paragraph)

SIGNIFICANCE SUMMARY

Applicable Criteria: A, C

Chestnut Ridge derives significance from several sources. It represents a type of architecture which is now rare in Harford County: probably fewer than a dozen brick Federal-style houses survive in the county, and of these Chestnut Ridge is a particularly fine example, unusual for its Flemish bond facade with scored joints and for the quantity of original decorative trim that it retains. Other houses of this type in Harford County, have generally been heavily restored; Chestnut Ridge has escaped this fate, and current restoration plans emphasize sensitivity and restraint. The 18th century frame portion of the house is also rare in the area. The house derives additional significance from its historical association with the Hoopman family, who were among the earliest and most influential settlers of the Aberdeen area.

HISTORY AND SUPPORT

Christian Hoopman, a brick-molder and artisan, built Chestnut Ridge, as well as building other fine brick structures in the Harford County community. With few existing examples of such architecture today, Chestnut Ridge represents a building that contains many original features of the period, with some alterations being done to maintain the internal and external integrity of the house.

The Chestnut Ridge tract was bought by Christian Hoopman in 1797. Christian and his brother Peter Hoopman, a brick molder and millwright, respectively, both made the bricks for the house and ran a mill on the property, with the contour of the land showing evidence of the millrace.

According to an account written by Jacob P. Walker, grandson of Christian Hoopman, the Hoopman brothers acquired large tracts of land in increments of 500 acres and that by the late 1790's had holdings extending from Swan Creek below Post Road to Hopewell Church and included the land on which the Church stands, as well as the land on which this house stands.

Christian Hoopman is attributed to donating the land and building Wesleyan Chapel, located near the bottom of West Chapel Road on Paradise Road (Rt. 462). He also has been credited with building a larger brick house, now known as Winsted, presently listed as a National Register site, neighboring this property.

The frame part of this house, located on West Chapel Road near a bend in Swan Creek, matches measurements given in the 1798 Federal Tax List. The 1814 tax assessment is incomplete for the Fifth Election District, but it is thought that the brick section was built about 1800-1810.

INVENTORY NO. 6664

ELECTION DISTRICT 5

N side	3	S
→	1	H
	5	S
	1	H
	5	S
	1	H
	5	S
	1	H

DATE: 3/23

TAX MAP NO. _____

REMODELING: Drastic, moderate, minor

PARCEL NO. _____

NAME OF PROPERTY: _____

LOCATION OF PROPERTY: South

DIRECTION DWELLING FACES: _____

NAME OF OWNER: Mr + Mrs Clifford Shaw - Eagle's Nest

ADDRESS: 3850 West Chapel Road
Aberdeen 21001 836-2496

STORIES: 1[] 2[] 3[] 4[] 5[] 6[] BAYS:

WINGS, ADDITIONS:

1 1/2 stories sec 1
2 stories sec 2 3 x 2
 ↓ modern dormer to match 2 1/2 stories

WALL CONSTRUCTION:

- Sec 1 ✓ [x] FRAME: Bevel, clapboard, weatherboard, wood shingles, board & batten(type?)
- Sec 2 ✓ [x] BRICK: Bond type- common, English, Flemish Sketch variants.
- [] STONE: Bond type- rubble, ashlar (random or regular), quoins-plain, rusticated
- [] LOG

WALL FEATURES: BELT COURSE, PILASTERS, OTHERS _____

FOUNDATIONS: HIGH, LOW, BRICK, STONE _____

WATER TABLE: NONE, PLAIN, BEVELED, MOULDED BRICK _____

→ WINDOWS, TRIM, SHUTTERS: ^{lowered} 1/1[] 2/2[] 6/6[] 9/6[] 9/9[] other[]
 pegged[] nailed[] wide[] narrow[]
 original[] replaced[] 6/9 in sec 2

ENTRANCE, DOORS: LOCATION: center bay
 HARDWARE: original[] replaced[]
 FAN LIGHT, TRANSOM, SIDE LIGHTS, PLAIN

CORNICE, BARGE, EAVES:
 original[] replaced[]


x ROOF: GABLE FRONT, GABLE FLANK, HIP, MANSARD, FLAT, DORMERS
 MATERIAL: wood shingles, slate, tin, asphalt original[] replaced[]

Sec 2 PORCHES: SHAPE OF ROOF - shed[x] hip[] gable[] 3 bays victorian (scrolled brackets)
Screened in turned columns

x CHIMNEYS: NUMBER 2 BRICK[x] STONE[] CORBELED[x] original[] replaced[]
 LOCATION: each inside end modern dormer center of

x ARCHES: flat brick arches Sec II w/ masonry doors Sec 2 - 3 sets of 6 ft case
ment windows
Hip dormer - cedar shakes

COMMENTS:



MARYLAND HISTORICAL TRUST

1306644204
HA-664

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC Chestnut Ridge Tract
AND/OR COMMON Royal Exchange

2 LOCATION

STREET & NUMBER 3850 West Chapel Road
CITY, TOWN Aberdeen VICINITY OF CONGRESSIONAL DISTRICT first
STATE Maryland COUNTY Harford County

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL <input checked="" type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input checked="" type="checkbox"/> YES- RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES- UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER

4 OWNER OF PROPERTY

NAME Mr. and Mrs. Clifford F. Shaw Telephone #: 836-2496
STREET & NUMBER The Eagle's Nest, Jarrettsville Pike
CITY, TOWN Phoenix VICINITY OF STATE, zip code MD 21131

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC. Harford County Courthouse
STREET & NUMBER 40 South Main Street
CITY, TOWN Bel Air STATE Maryland

Liber #: 1006
Folio #: 381

6 REPRESENTATION IN EXISTING SURVEYS

TITLE
DATE
DEPOSITORY FOR SURVEY RECORDS
CITY, TOWN STATE
FEDERAL STATE COUNTY LOCAL

A-664

7 DESCRIPTION

CONDITION		CHECK ONE	CHECK ONE
<input checked="" type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED	slightly	

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

This house consists of two sections and is located at a bend in West Chapel Road north east of Swan Creek. The house faces south.

The main part of this house is brick, three bays by two. It is built onto low stone foundations and has a lighted cellar. A modern dormer on the south side of the asphalt, gable flank roof makes this section two and one half stories high. A corbeled brick chimney is located at each inside end. These are flanked by small windows. Brick bond type on the south facade is flemish while the remaining walls are of common bond. Many headers on the west facade are glazed. Flat brick arches are above all windows and doors in this section. Windows on the first elevation are six lights over nine. Windows have louvered shutters. The principal entrance is at the center bay of the south facade. Its door is quite wide and has 6 moulded wood panels. It has an iron and brass box lock. A four light transom is overhead.

A double hung door is on the south bay of the west facade. Each door has ten small panes of glass and an iron lock. A four light transom is over head and the door has louvered shutters.

On the east facade a cellar entrance is located on the south bay. This short door-approximately five feet high is of vertical beaded board.

A one tier porch runs the length of the south facade. This has a shed roof and turned columns with scroll brackets. It is screened in.

Inside, this section has a center through hall floor plan. The stairway, in the north east corner of the hall, is closed. It has square balusters and a turned newel. Floors appear to be replaced and are of pine. Beaded chair rails are in all rooms. Door have fluted trim with corner blocks. Fireplaces in the house are brick lined. The fireplace in the west room has plain pilasters and a simple mantle shelf.

In the attic, the pegged beams are scored with roman numerals. Attic windows are also pegged.

In the cellar, a brick fireplace support is at one end while a stone fireplace support is at the other.

Section two is one and one half stories high and is constructed of frame built onto low stone foundations. This section is on the north west of the brick section. It has a gable flank, asphalt covered roof with a dormer on both the east and west sides. The west dormer is gable front with a nine light casement window. The east dormer has a shed roof and a six light casement window. A wide, corbeled brick chimney is located near the center of the roof. Windows in this section are six lights over six. A door is located on the east facade. This entrance is sheltered by a two bay enclosed porch. There is also a door opposite this one on the west facade.

CONTINUE ON SEPARATE SHEET IF NECESSARY

HA-664

8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input checked="" type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES

BUILDER/ARCHITECT

Christian Hoopman

STATEMENT OF SIGNIFICANCE

The frame part of this house, located on West Chapel Road near a bend in Swan Creek, matches measurements given in the 1798 Federal Tax List. This one and one half story structure is of simple construction and it is difficult to ascertain its age. It is believed to have been several decades old in 1798. The pegged and beaded boards bear some indication of its age.

Christian Hoopman had purchased the land and house in 1797 and it is thought that the brick Federal/Georgian vernacular section was built soon after 1798. The 1814 tax assessment is very incomplete for the Fifth Election District but it is thought that the brick section was built prior to 1814.

In 1858, this house was inhabited by the Rienick family while the brick house next door was occupied by Mrs. Hoopman. Both houses remained under single ownership until 1952 when Wendell and Rachel Muncie sold this property.

Christian Hoopman's greatest contribution to this small community was the founding and construction of the Wesleyan Chapel. His beautifully constructed dwellings are among the monuments of this community.

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Preston, Walter W; History of Harford County, Press of the Sun Book Office, Baltimore, 1901. 1783 Maryland Tax t
 Wright, C. Milton; Our Harford Heritage, French Bray Press, Baltimore, 1967. 1798 Federal Tax List
 History of Wesleyan Chapel by Jacob P. Walker October 10, 1926. 1814 Maryland Tax List
 Historical Background by Joseph Sternberg.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 7.205 acres

VERBAL BOUNDARY DESCRIPTION

This property is bounded on the north by the property of Dr. and Mrs. Clarence Tinsman, and on the south and west by West Chapel Road.

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	COUNTY
STATE	COUNTY

11 FORM PREPARED BY

NAME / TITLE

Susan M. Deeney, Field Historian

March 1977

ORGANIZATION

Historic District Commission

DATE

838-6000 ext. 207

STREET & NUMBER

45 South Main Street

TELEPHONE

CITY OR TOWN

Bel Air

STATE

Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.


The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

Inside, this section consists of two main rooms on each elevation. On the first floor chair rails are present and the floor is replaced. The simple wall cornice in the south room is probably added. The fireplace in this room has a moulded architrave. A built in closet with double hung, moulded panel doors is to the west of the fireplace on the north wall. The north rooms has been altered several times. At present, the old kitchen fireplace has been uncovered. Originally, I am told, this fireplace has a stone hearth. Beaded boards from the attic floor of the brick section have been used as a wall in this kitchen room. It encases the fireplace. On the north wall of this room an enclosed stairway has added in the more recent past. This leads to the second elevation.


The upstairs rooms are very simple. The random plank pine flooring is still intact. An interesting corner brace is visible in the south west corner of the south room where the frame section joins the brick.

A porch on the east facade has been altered. A portion of this porch has been closed to accomodate a down stairs bath so that what was once a through hall in the brick section now leads to a bathroom instead. Another section of the porch on the north end has been enclosed for use as a laundry room. The center remains a screened in porch.



"Royal Exchange of Chestnut Ridge"
HA - 664

HA-664



HA-664
Chestnut Ridge

1

Earlton

Webster


Wesleyan
Chapel

Reservoirs

Burns
Corner

Oak

OHIO
HIGHWAY



HA-664

HA-664

002

Oakington St.

OHIO HIGHWAY 27

Webster

Earlton

Wesleyan Ch.

Chapel

Burn's Corner

Reservoirs & Tanks

ROAD

ROAD

ROAD

ROAD

BEARDS HILL

SWING

ROAD

ROAD

Gus Run

CHAPEL

ROAD

ROAD

ROAD

ROAD

ROAD

ROAD

434

400

305

380

356

400

400

300

260

300

200

300

300

300

200

331

362

287

317

261

51

100

100

200

200

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100

100


100

100

100

HA-664







Royal Exchange of Chestnut Ridge
HA-664
Aberdeen/Aldino Area, MD
Susan M. Deeney
Southwest
March, 1977



Royal Exchange of Chestnut Ridge
HA-664
Aberdeen/Aldino Area, MD
Susan M. Deeney
West
March, 1977