

HO-1080

9263 Cartersville Road
Private

Description:

The house at 9263 Cartersville Road is located on the southeast corner of the intersection with Thomas Road and faces north toward Cartersville Road, in Guilford, in southeastern Howard County, Maryland. It is set close to the road on a small lot. It is a one-story, three-bay by two-bay frame Cape Cod with a parged foundation, aluminum siding, and a gable roof with asphalt shingles and an east-west ridge. There is a brick chimney in the center of the building. The north elevation has a door in the center that has six panels, with the top two glazed. To either side is a one-over-one sash. There is a one-bay, shed-roofed porch in the center with a wood deck and modern posts and balustrades. The interior is divided into five rooms, with a living room in the northwest corner, kitchen in the southwest corner, and a bedroom and bathroom in the southeast corner. The doorway between the northwest and southwest rooms has a triangular top, and never had a door.

Significance:

Cartersville Road is part of the historically African-American community of Guilford. The Maryland Department of Assessments records indicate that this house was built in 1948, and there is no good reason to dispute the date. The Cape Cod became a very popular national housing type, especially after the Second World War, when there was a strong need to provide cheap housing quickly for returning veterans. This example is on the smaller end of the housing type and is very simply finished inside, which undoubtedly reflects the limited opportunities still available to African-Americans at a time when racism and segregation were still rampant; yet it also reflects the growing trend of home ownership among working class blacks and whites after the war. The house was owned by the Carter family. The house is scheduled to be demolished in 2012 and replaced with a new house.

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. HO-1080

1. Name of Property (indicate preferred name)

historic

other

2. Location

street and number 9263 Cartersville Road __ not for publication

city, town Guilford X vicinity

county Howard

3. Owner of Property (give names and mailing addresses of all owners)

name Viola & Wesley Kelly

street and number 9263 Cartersville Road telephone

city, town Columbia state MD zip code 21046

4. Location of Legal Description

courthouse, registry of deeds, etc. Howard County Courthouse liber 348 folio 216

city, town Ellicott City tax map 42 tax parcel 261 tax ID number

5. Primary Location of Additional Data

- Contributing Resource in National Register District
- Contributing Resource in Local Historic District
- Determined Eligible for the National Register/Maryland Register
- Determined Ineligible for the National Register/Maryland Register
- Recorded by HABS/HAER
- Historic Structure Report or Research Report at MHT
- Other: _____

6. Classification

Category	Ownership	Current Function	Resource Count	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input type="checkbox"/> agriculture	Contributing	Noncontributing
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	1	1
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> defense	0	0
<input type="checkbox"/> site		<input type="checkbox"/> domestic	0	0
<input type="checkbox"/> object		<input type="checkbox"/> education	0	0
		<input type="checkbox"/> funerary	1	1
		<input type="checkbox"/> government		
		<input type="checkbox"/> health care		
		<input type="checkbox"/> industry		
		<input type="checkbox"/> landscape		
		<input type="checkbox"/> recreation/culture		
		<input type="checkbox"/> religion		
		<input type="checkbox"/> social		
		<input type="checkbox"/> transportation		
		<input type="checkbox"/> work in progress		
		<input type="checkbox"/> unknown		
		<input checked="" type="checkbox"/> vacant/not in use		
		<input type="checkbox"/> other:		
			Number of Contributing Resources previously listed in the Inventory	
			0	

7. Description

Inventory No. HO-1080

Condition

excellent deteriorated
 good ruins
 fair altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

The house at 9263 Cartersville Road is located on the southeast corner of the intersection with Thomas Road and faces north toward Cartersville Road, in Guilford, in southeastern Howard County, Maryland. It is set close to the road on a small lot and also has a modern shed behind it.

It is a one-story, three-bay by two-bay frame Cape Cod with a parged foundation, aluminum siding, and a gable roof with asphalt shingles and an east-west ridge. There is a brick chimney in the center of the building.

The north elevation has a door in the center that has six panels, with the top two glazed. To either side is a one-over-one sash. There is a one-bay, shed-roofed porch in the center with a wood deck and modern posts and balustrades.

The west elevation has an exterior oil tank set on rock-faced concrete blocks. The first story has two one-over-one sash and the gable end has a vent. The east elevation has a one-over-one sash in the north bay and a vent in the gable end.

The south elevation has a one-over-one sash in each end bay, with a door set west of center that has nine lights over a crossbuck. There is a two-bay shed-roofed porch with a concrete deck, wood posts, and metal railings.

The interior is divided into five rooms, with a living room in the northwest corner, kitchen in the southwest corner, and a bedroom and bathroom in the southeast corner. The doorway between the northwest and southwest rooms has a triangular top, and never had a door.

8. Significance

Inventory No. HO-1080

Period	Areas of Significance	Check and justify below		
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy
<input type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/ recreation	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> law	<input type="checkbox"/> science
	<input type="checkbox"/> communications	<input type="checkbox"/> exploration/ settlement	<input type="checkbox"/> literature	<input type="checkbox"/> social history
	<input type="checkbox"/> community planning		<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation
	<input type="checkbox"/> conservation		<input type="checkbox"/> military	<input type="checkbox"/> other: _____

Specific dates	N/A	Architect/Builder	N/A
Construction dates	c. 1930-1960		

Evaluation for:

National Register Maryland Register not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

Cartersville Road is part of the historically African-American community of Guilford. The Maryland Department of Assessments records indicate that this house was built in 1948, and there is no good reason to dispute the date. The Cape Cod became a very popular national housing type, especially after the Second World War, when there was a strong need to provide cheap housing quickly for returning veterans. This example is on the smaller end of the housing type and is very simply finished inside, which undoubtedly reflects the limited opportunities still available to African-Americans at a time when racism and segregation were still rampant; yet it also reflects the growing trend of home ownership among working class blacks and whites after the war. The house was owned by the Carter family.

The house is scheduled to be demolished in 2012 and replaced with a new house.

9. Major Bibliographical References

Inventory No. HO-1080

10. Geographical Data

Acreage of surveyed property .36 A
Acreage of historical setting .36A
Quadrangle name Savage

Quadrangle scale: 1:24000

Verbal boundary description and justification

The boundaries consist of the outlines of the property, tax map 42, parcel 261, which encompasses all of the historic buildings and features on the site.


11. Form Prepared by

name/title	Ken Short		
organization	Howard County Department of Planning & Zoning	date	March 2012
street & number	3430 Courthouse Drive	telephone	410-313-4335
city or town	Ellicott City	state	MD

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville, MD 21032-2023
410-514-7600



HO-1080

9263 Cartersville Road
Savage quad

HO-1080

9263 Cartersville Road
Howard County, Maryland
Ken Short, photographer

Photo Log

Nikon D-70 camera
HP Premium Plus paper
HP Gray Photo print cartridge

HO-1080_2012-01-17_01
North & west elevations

HO-1080_2012-01-17_02
South & east elevations



PUBLIC NOTICE

File Number: 2008-0001
Subdivision Name: [illegible]
Number of Lots/Units: [illegible]

HO-1080

9263 Cartersville Road
Howard County, Maryland

Ken Short

2012-01-17

MD SHPO

North + west elevations

1 of 2



HO-1080

9263 Cartersville Road
Howard County, Maryland

Ken Short

2012-01-17

MD SHPO

South + east elevations

2 of 2