

Ho-218
The Mansion House
Savage
Private

circa 1878

Built between the years 1859 and 1878 by the Baldwin family, the Mansion House was used as a summer home for the owner and President of the Savage Manufacturing Company. It was also known as the "Company House" or the "Proprietor's House," and was maintained and kept in a state of good repair by the Company who managed all the mill houses in the Savage Mill village.

It is a five bay wide, four bay deep, two story high, tent roofed, frame house set on a stone foundation with a three bay long, one bay deep, two story high, gabled roof (running north-south) frame structure springing from its north wall, creating an "L" plan.

The main body of the house is crowned by a flat roofed, square, windowed, frame cupola, with three sets of three scrolled brackets decorating its cornice on the south elevation which are each underlined by a row of dentils. A one story high, hipped roof, open porch runs along the east and south elevations of the building supported by twelve slender, round, fluted columns.

1 NAME

HISTORIC

The Mansion House

AND/OR COMMON

The Baldwin House

2 LOCATION

STREET & NUMBER

9110 Washington Street

CITY, TOWN

Savage

— VICINITY OF

CONGRESSIONAL DISTRICT

6th District

STATE

Maryland 20863

COUNTY

Howard

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input checked="" type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL <input checked="" type="checkbox"/> PRIVATE RESIDENCES
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input checked="" type="checkbox"/> YES, RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES, UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER:

4 OWNER OF PROPERTY

NAME

Mr. & Mrs. Borough Storch

Telephone #: 792-0393

STREET & NUMBER

8930 Baltimore St.

Maryland 20863

CITY, TOWN

STATE, zip code

Savage

— VICINITY OF

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE.
REGISTRY OF DEEDS, ETC.

Hall of Records

Tax Map 47 p.453

Liber #: 212

Folio #: 154

STREET & NUMBER

Howard County Court House

CITY, TOWN

Ellicott City

STATE

Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE National Register of Historic Places

Nomination form for Savage Mill Historic District

DATE

September 1973

FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR
SURVEY RECORDS

Office of Archeology and Historic
Preservation NPS

CITY, TOWN

Washington

STATE

D.C.

7 DESCRIPTION

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The mansion house sits on a gently sloping hill on the north-west corner of Commercial and Washington Streets facing south.

It is a five bay wide, four bay deep, two story high, tent roofed frame structure set on a stone foundation. It is crowned by a flat roofed, square frame cupola, with three sets of three scrolled brackets decorating its cornice on the south elevation. A three bay long, one bay deep, two story high, gabled roof (running north-south) frame structure springs from its north wall creating a "L" plan. An open wooden staircase runs up the east wall of this north wing.

The south elevation holds the central double paneled, rectangular entrance door which is surmounted by a four light transom and flanked by four vertical side lights. Five granite block steps flanked by brick knevel posts lead to a wide open, one story high, shed roofed porch which runs along the east, and south elevations of the building.

Fenestration is vertically aligned and proportionally scaled. Windows are all rectangular and double-hung, holding six-over-six lights. Those on the first floor have been altered. Originally they were each french doors which led out to the open porch, which is now supported by some twelve round, fluted, wooden columns.

The west elevation holds a gabled roof portico supported by two square wooden columns and two pilasters supported by two brick columns and two brick pilasters. The rectangular entrance door covered by the portico is surmounted by a three light transom. The west wall of the house lies flush with the west wall of the north wing and is punctuated by five first floor windows and seven second floor windows. A brick chimney lies in the west side of the main body of the house.

The square cupola has pilasters applied to each side of each wall. Three sets of three brackets hold the cornice on the south elevation. These brackets are underlined by a row of dentils.

Each wall of the square cupola holds a rectangular, double-hung window with six-over-six lights.

The interior once held a central hall with single room on the east and west sides. The north wing served as a service and bedroom wing. Today the building has been cut up into apartments of various sizes. Its facade, however, still maintains its original integrity and holds a commanding position in Savage.

CONTINUE ON SEPARATE SHEET IF NECESSARY

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input checked="" type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION		
<input type="checkbox"/> 1400-1499	<input checked="" type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE		
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN		
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER		
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION		
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input checked="" type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)		
		<input type="checkbox"/> INVENTION				

SPECIFIC DATES *circa 1878*

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

The Mansion House is significant historically as the Company House or the Proprietor's House of the Savage Manufacturing Company. It was occupied by the owner and president of the mill. (A manager's house was also constructed at the end of Baltimore Street to be occupied by the General Manager and Vice-President of the Mill.) The Mansion House was built by the Baldwin family, who owned the mill, as a summer house. It was maintained and kept in a state of good repair by the Savage Mill, as were all the mill houses in the village constructed sometime after 1859 and before 1878.

Architecturally the mansion house has a bit of the feeling of the Greek-inspired house with its porch columns, applied pilasters on the corners of the cupola and horizontal four light transom above the central entrance door. All the first floor windows were at one time french doors which led out to the open porch running along the east and south elevations.

In the fields of community planning and industry it is an interesting example of how industry accomodated its management within its village plan, furnishing a summer home which was no doubt often used to entertain visiting dignitaries.

Located in close proximity to the plant, the owner could, it he chose to, walk to the mill easily during his stays here.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Interview with Mr. William Reeley, Vice President and Manager of the Savage Manufacturing Company, 1947.
Howard County Land Records
Filbey, Vera. Savage, Maryland. Savage, 1965.
Savage Historic District Nomination Form for the National Register.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

Please see attachment 1, Tax Map 47, p.453.

VERBAL BOUNDARY DESCRIPTION

Please see Howard County Land Records Liber 212, Folio 154.

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	Maryland	COUNTY	Howard
STATE		COUNTY	

11 FORM PREPARED BY

NAME / TITLE

Cleora Barnes Thompson, Archivist

ORGANIZATION

Office of Planning & Zoning-Comprehensive Planning Section 465-5000 x257

DATE

STREET & NUMBER

3450 Court House Drive

TELEPHONE

CITY OR TOWN

Ellicott City

STATE

Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

SAVAGE PARK

HO-42
District Boundary

COMMERCIAL

FOUNDRY

STREET

BALTIMO

★
220

221

223

224

FAIR

222

★ ★ ★ ★ ★
225

214

★
BALDWIN
COMMON

WILLIAMS

ST.

522

STREET

SAVAGE

219

218

215

216

STREET

★
WASHINGTON

STREET

★
217

★
213

RACE

ROAD


BLVD.

SAVAGE

Scale, 1"=200'

Historic Monument
BOLLMAN TRUSS BRIDGE
HO 81

RAILROAD




BY:
C. 1820 to 1870
1879 to 1940
1941 to

Historic District Boundaries

SAVAGE HISTORIC DISTRICT
SAVAGE, MARYLAND


Attachment 3.
Ho-218.
The Mansion House
Savage Historic District Map



J.R. Rivoire; 5/74. Not drawn to scale.

Savage Mill District Gets National Designation

Attachment 1
Ho-218
The Mansion
House
Tax Map 47



R.J. HUTCHISON, JR., ET AL.
497/577
264.73A.
P.141

BD. OF CO.
COMM. OF HO. CO.
501/704
43.68A.
P.92

LAUREL HARRISS RACING ASSOC INC
305/102
69494
P.422

TRAVENOL
LAB, INC
634/749
11.50A
P.145

ALFRED H. SMITH
305/422
36.16A.
P.144

BESURE
CORP.
522/655
5.66A.
P.619

STEVEN N. STORCH
19.99A.
P.882

RIVER ISLAND
APARTMENTS
A-26/9

CARRIATION ST
SEC. 2
CEM.


BYRD O.
SFENCE
149/11
244
P.112

S.H.A.
227/14
25.90A
P.113

HOLDING, INC.
403/723
P.503

EPITY
FINANCIAL
CORP.
411/572
1.94A
P.59


48



Attachment 4.
 Ho-218
 The Mansion House
 Hopkin's Atlas of 1878.

SAVAGE FACTORY


Scale 300 feet per Inch



Savage Factory Business Notices.

- CONSTABLE.
- WM. CLARK.
- MANUFACTURERS.
- PAUL KEIPER.
- J. W. VANDERGRIFT.
- PHYSICIAN.
- THOMAS C. WORTHINGTON.
- TINSMITH.
- WM. FERGUSON.
- WEAVERS.
- RALPH LEE.

SAVAGE QUADRANGLE
USGS 7.5 minute map
scale: 1: 24,000
1957



Attachment 2
Ho-218
The Mansion House


U.S. Geological Survey Map
Savage Quadrangle

HO-218
 Savage-Irving House (Mansion House, Baldwin House)
 9110 Washington Street, Savage
 Savage Quadrangle 1957, Photorevised 1966 and 1974



Map 47, Parcel 79

National Web Map Service 6" Orthophoto Map, c. 2010





H0-218
THE MANSION HOUSE
(SOUTHEAST)

CHEORA THOMPSON
NOV. 1978

HO.218 14021855
4

STATE:	
COUNTY:	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM**

(Type all entries - complete applicable sections)

MD. HISTORICAL TRUST
BOX 1704
ANNAPOLIS, MD. 21404

1. NAME

COMMON: Savage - Irving House

AND/OR HISTORIC: "The Mansion House"

2. LOCATION

STREET AND NUMBER: North West corner of Washinton & Commercial

CITY OR TOWN: Savage

STATE: Md CODE: COUNTY: HOWARD CODE:

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
District <input type="checkbox"/> Building <input checked="" type="checkbox"/>	Public <input type="checkbox"/>	Public Acquisition: <input type="checkbox"/> Occupied <input checked="" type="checkbox"/>	Yes: <input checked="" type="checkbox"/> Restricted <input type="checkbox"/>
Site <input type="checkbox"/> Structure <input checked="" type="checkbox"/>	Private <input checked="" type="checkbox"/>	In Process <input type="checkbox"/>	Unoccupied <input type="checkbox"/>
Object <input type="checkbox"/>	Both <input type="checkbox"/>	Being Considered <input type="checkbox"/>	Preservation work in progress <input type="checkbox"/>
No: <input type="checkbox"/>			

PRESENT USE (Check One or More as Appropriate)

Agricultural <input type="checkbox"/>	Government <input type="checkbox"/>	Park <input type="checkbox"/>	Transportation <input type="checkbox"/>	Comments <input type="checkbox"/>
Commercial <input type="checkbox"/>	Industrial <input type="checkbox"/>	Private Residence <input checked="" type="checkbox"/>	Other (Specify) <input type="checkbox"/>	_____
Educational <input type="checkbox"/>	Military <input type="checkbox"/>	Religious <input type="checkbox"/>	_____	_____
Entertainment <input type="checkbox"/>	Museum <input type="checkbox"/>	Scientific <input type="checkbox"/>	_____	_____

4. OWNER OF PROPERTY

OWNERS NAME: Borough Storch

STREET AND NUMBER: Baltimore Street

CITY OR TOWN: ~~Baltimore~~ Savage STATE: Md CODE:

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.: CLERK OF THE CIRCUIT COURT

STREET AND NUMBER: HARFORD COUNTY COURthouse 40 S. MAIN ST.

CITY OR TOWN: BEL AIR STATE: MARYLAND CODE:

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: _____

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY: _____

DATE OF SURVEY: _____ Federal State County Local

DEPOSITORY FOR SURVEY RECORDS: _____

STREET AND NUMBER: _____

CITY OR TOWN: _____ STATE: _____ CODE: _____

SEE INSTRUCTIONS
47
453

STATE:
COUNTY:
ENTRY NUMBER
DATE
FOR NPS USE ONLY

7. DESCRIPTION

CONDITION	(Check One)					
	Excellent <input checked="" type="checkbox"/>	Good <input type="checkbox"/>	Fair <input type="checkbox"/>	Deteriorated <input type="checkbox"/>	Ruins <input type="checkbox"/>	Unexposed <input type="checkbox"/>
INTEGRITY	(Check One)			(Check One)		
	Altered <input type="checkbox"/>	Unaltered <input checked="" type="checkbox"/>		Moved <input type="checkbox"/>	Original Site <input checked="" type="checkbox"/>	

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

This severely symmetrical ^{clapboard} frame house, 2 stories under a hip roof topped by an enclosed "windows walk" or turret, is oblong, 5 bays by 4. A one-story porch shelters the east and south sides. Windows have 6 lights over 6 (even in the turret,) and are without shutters.

SEE INSTRUCTIONS

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- Pre-Columbian 16th Century 18th Century 20th Century
 15th Century 17th Century 19th Century

SPECIFIC DATE(S) (If Applicable and Known)

1856

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|---|---------------------------------------|---|--|
| Aboriginal | Education | Political | Urban Planning |
| Prehistoric <input type="checkbox"/> | Engineering <input type="checkbox"/> | Religion/Phi- | Other (Specify) <input type="checkbox"/> |
| Historic <input type="checkbox"/> | Industry <input type="checkbox"/> | losophy <input type="checkbox"/> | _____ |
| Agriculture <input type="checkbox"/> | Invention <input type="checkbox"/> | Science <input type="checkbox"/> | _____ |
| Art <input type="checkbox"/> | Landscape | Sculpture <input type="checkbox"/> | _____ |
| Commerce <input type="checkbox"/> | Architecture <input type="checkbox"/> | Social/Human- | _____ |
| Communications <input type="checkbox"/> | Literature <input type="checkbox"/> | itarian <input checked="" type="checkbox"/> | _____ |
| Conservation <input type="checkbox"/> | Military <input type="checkbox"/> | Theater <input type="checkbox"/> | _____ |
| | Music <input type="checkbox"/> | Transportation <input type="checkbox"/> | _____ |

STATEMENT OF SIGNIFICANCE (Include Personages, Dates, Events, Etc.)

The mill owner's house of William Henry Baldwin, once well planned and maintained, now altered to contain for a six apartments.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Interview with Mrs Matthews, Librarian, Sawafe 11/6 11/72

3781

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN ONE ACRE		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	0 . "	0 . "		0 . "	0 . "	
NE	0 . "	0 . "		0 . "	0 . "	
SE	0 . "	0 . "		0 . "	0 . "	
SW	0 . "	0 . "		0 . "	0 . "	

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE

11. FORM PREPARED BY

NAME AND TITLE: **JEAN S. EWING**

ORGANIZATION: **MARYLAND HISTORICAL TRUST** DATE: _____

STREET AND NUMBER: **50 STATE CIRCLE**

CITY OR TOWN: **ANNAPOLIS** STATE: **MARYLAND** CODE: _____

12. STATE LIAISON OFFICER CERTIFICATION

NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National State Local

Name _____

Title _____

Date _____

I hereby certify that this property is included in the National Register.

Chief, Office of Archeology and Historic Preservation

Date _____

ATTEST:

Keeper of The National Register

Date _____

SEE INSTRUCTIONS



H 218

Savage - living house

888 11/72