

(NOTE - PART OF NR  
SAVAGE HISTORIC DISTRICT)

HO-220  
The Holte-Grafton House  
Savage  
Private

circa 1895

The Holte-Grafton house faces east on the west side of Fair Street, at the end of Baltimore Street. It is a five bay wide, one room deep, three story high, slate mansard roofed, "T" shaped, German siding, frame house, resting on a stone foundation, featuring three tall, wide, corbeled brick chimneys, a central projecting bay on the east facade, a two story high, bay window on the south elevation, and some thirteen, gabled roof, third floor, dormer windows on the north, south and east elevations, holding roman arched, double-hung windows with two-over-two lights. A notable cornice runs around the entire perimeter of the house, decorated with a row of brackets, on the north, south and east elevations.

A one story high, flat roofed, open porch, following the outline of the building's east facade is held by eight square posts and two pilasters, whose cornice is decorated with a row of brackets, similar to those along the main roof line.

Six wide, brick steps, flanked by an iron railing, lead to the landing and the two-two light, rectangular double entrance door, surmounted by a two light transom.

Another shed roofed, one story high, open porch runs along the north wall of the dining room - kitchen wing, which forms the base of the building's "T" plan. It is held by three square posts and two flat pilasters and covers the first floor rectangular kitchen entrance, located in the west bay, whose transom has been blocked.

A one bay wide, one room deep, two story high, low pitched, gable roof (running east-west) frame addition, extends west from the north side of the west wall of the original kitchen,

The building is notable architecturally, as an example of the French Empire Style, and historically, as the home of the manager of the old nineteenth century Savage Mill.

MARYLAND HISTORICAL TRUST

HO-220  
Dist. 1

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

MAGI # 1402305604

**1 NAME**

HISTORIC

House of the Manager of the Savage Mill

AND/OR COMMON

The Holte-Grafton House

**2 LOCATION**

STREET & NUMBER

8502 Fair Street

CITY, TOWN

Savage

\_\_\_ VICINITY OF

CONGRESSIONAL DISTRICT

6th

STATE

Maryland

COUNTY

Howard

**3 CLASSIFICATION**

CATEGORY	OWNERSHIP	STATUS	PRESENT USE	
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL	<input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL	<input checked="" type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	<b>PUBLIC ACQUISITION</b>	<b>ACCESSIBLE</b>	<input type="checkbox"/> ENTERTAINMENT	<input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input checked="" type="checkbox"/> YES - RESTRICTED	<input type="checkbox"/> GOVERNMENT	<input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES - UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL	<input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY	<input type="checkbox"/> OTHER

**4 OWNER OF PROPERTY**

NAME

Mr. and Mrs. Hartley O. Holte

Telephone #: 301-498-5492

STREET & NUMBER

8502 Fair Street

CITY, TOWN

Savage

\_\_\_ VICINITY OF

STATE, zip code

Maryland

**5 LOCATION OF LEGAL DESCRIPTION**

COURTHOUSE,  
REGISTRY OF DEEDS, ETC

Hall of Records

Tax Map 47  
p. 397

Liber #: 551

Folio #: 004

STREET & NUMBER

Howard County Court House

CITY, TOWN

Ellicott City

STATE

Maryland

**6 REPRESENTATION IN EXISTING SURVEYS**

TITLE

Howard County Historic Sites Inventory

DATE

1978-1979

\_\_\_ FEDERAL  STATE \_\_\_ COUNTY \_\_\_ LOCAL

DEPOSITORY FOR  
SURVEY RECORDS

Maryland Historical Trust

CITY, TOWN

21 State Circle, Annapolis

STATE

Maryland

# 7 DESCRIPTION

HO-220  
Dist. 6

CONDITION		CHECK ONE	CHECK ONE
<input checked="" type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		DATE _____

## DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Holte-Grafton house faces east on the west side of Fair Street, at the end of Baltimore Street, in Savage, Maryland. It is a five bay wide, one room deep, (the north side measuring 15' X 17') three story high, mansard roofed, "T" shaped, German siding, frame house, resting on a stone foundation, featuring three tall, wide, corbeled, brick chimneys, a central projecting bay on the east facade, a two story high bay window on the south elevation and some thirteen gabled roof, third floor dormer windows on the north, south and east elevations, holding roman arched, double-hung windows with two-over-two lights. A notable cornice runs around the entire perimeter of the house, decorated with a row of brackets, on the north, south and east elevations.

A one story high, flat roofed, open porch, following the outline of the building's east facade is held by eight square posts and two pilasters, whose cornice is decorated with a row of brackets similar to those along the main roof line. Six, wide, brick steps, flanked by an iron railing, lead to the landing and the two-two light, rectangular, double entrance door, surmounted by a two light transom.

Another shed roofed, one story high, open porch runs along the north wall of the dining room - kitchen wing, which forms the base of the building's "T" plan. It is held by three square posts and two flat pilasters and covers the rectangular, kitchen entrance, located in the west bay, whose transom has been blocked. Another four light, rectangular entrance is centered into the north wall of the summer kitchen which is a one bay wide, one room deep, two story high, low pitched, gable roof (running east-west) frame addition, extending from the north side of the west wall of the original kitchen. Its west wall holds a central square brick chimney. Two additional entrances have been blocked in. One leads into the west wall of the central hall of the front section of the house, while the other is located at right angles to it, and enters the dining room on its north wall.

At this corner one of two interesting outlines in the building's profile occurs. The central bay of the second and third floor, which is the central bay of the main section's west wall, the head of the staircase, projects westward (perhaps originally a two story high oriele window), resting on the shed roof of the kitchen porch, previously described. Its cornice matches and continues the main cornice of the building and is original to the building.

The second interesting projection is that of the dining room's bay window, located on the south elevation, previously mentioned.

Fenestration for the building is proportionally scaled and vertically aligned. Windows are rectangular and double-hung, holding two-over-two lights, underlined by projecting wooden sills. Only the original kitchen's two south west corner windows have been diminished in size to accommodate a modern kitchen.

The building is noteworthy for its fine proportions, tempered with variety and interest. For example, the north wall of the front section of the house, off the building's central hall, holds two first, second and third floor windows, while the first, second and third floors of the south wall of this front section holds only one first, second and third floor window. You would expect these two walls to be identically treated, for the east

CONTINUE ON SEPARATE SHEET IF NECESSARY

facade of the building is perfectly symmetrical, featuring a central projecting bay flanked by two first, second and third floor windows or that one window might be placed in the building's north wall and two in the south wall for greater protection from the weather. A probably explanation may have been the architect or contractor's desire to provide greater balance on this north elevation. The base of the "T" forming the dining room-kitchen area, divided by a wide cement fireplace is also off center, as well as its north and south walls. The north wall holds two second and third floor windows, vertically aligned to the first floor kitchen entrance and dining room window, while the south elevation features the two story high, dining room, bay window and shortened kitchen window, vertically aligned to a second and third floor window.

The building is reminiscent of MacAlpine, Ho-400, located on MacAlpine Road, also built on the French Empire design, which is represented by the mansard roof and its third floor gabled roof dormer windows, which hold roman arched, double-hung windows with two-over-two lights. The house features a central hall floor plan for the front section of the house and a kitchen-dining room west wing, which creates the "T" plan for the house.

The interior has cross paneled doors (many of which retain handsome copper door knobs) random width floors and a central staircase which rises from the first to the third floor, with carved spindles and original knewel post. A kitchen staircase has been eliminated to provide space for a first floor bath. Another staircase led from the north east corner of the two story high, west addition, to its second floor, totally separated second floor room.

# 8 SIGNIFICANCE

HO-220  
DIST 6

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION		
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE		
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN		
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER		
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION		
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input checked="" type="checkbox"/> OTHER (SPECIFY) Local history		
		<input type="checkbox"/> INVENTION				

SPECIFIC DATES Circa 1895

BUILDER/ARCHITECT

## STATEMENT OF SIGNIFICANCE

The Holte-Grafton house is significant to Howard County, the State of Maryland and the nation. Architecturally, it is an example of the French Empire style, and historically, it is the home of the manager of the Savage Mill whose early nineteenth century mill town is on the National Register of historic places. The building is most significant to Howard County for its architectural style and for the fact that it was constructed by Mr. Frank Shipley who also constructed Fairview, Senator Gorman's home, HO-153, which consists of some thirty-two rooms. Whether Mr. Shipley also designed the Holte-Grafton house is not certain. He is known, however, to have designed the old frame houses, which line the eastern end of Baltimore Street, the present entrance into Savage from Route I. They are modest, but well scaled, two story high, three bay wide homes with central intersecting bays over central entrances. The east facade of the Holte-Grafton house is symmetrical, acting as a focal point at the termination of the west end of Baltimore Street at Fair Street. The central projecting bay rises to the mansard roof's third floor while the first floor porch, which follows the building's outline, creates a graceful horizontal element, as well as a continuity to the east facade, by repeating its stylistic detail on its own cornice, (a row of brackets) of the cornice of the slate mansard roof.

Two tall, wide, corbeled brick chimneys rise from either side of the central hall. Within the house, up through the third floor fire places, they are not totally centered. Within the crawl space between the roof and third floor, however, they have been corbeled so that they rise evenly on either side of the center of the house, one of several fine architectural features of the building's profile.

Here the symmetry ends and the design of the house becomes asymmetrical, beginning with the "T" plan, which is south of center, and the north and south wall of the front section of the house holding two and one window bays, rather than identical window treatment.

Fenestration for the entire house, however, is vertically aligned and proportionally scaled. Windows are rectangular and double-hung, holding two-over-two lights, terminating on the third floor with gabled roof dormer windows inset into the mansard roof. These hold roman arched, double-hung windows, with two-over-two lights.

Not only the treatment of the north and south elevations of the east section of the house is asymmetrical, but the north and south elevations of the west section, or base of the "T" are also.

The north elevation is simple in treatment, providing a first floor kitchen window in the west bay and a dining room window, similar to those described, in the east bay, to which second and third floor windows are vertically aligned. The south elevation of this section of the house provides interest by the addition of a two story high, bay window.

CONTINUE ON SEPARATE SHEET IF NECESSARY

The interior plan of the house features a central hall in the east section which leads into the dining room-kitchen west wing. Interior cross paneled doors retain china or brass knobs. Floors are of random width, while the handsome staircase of the central hall runs from the first to the third floor. Kitchen and washroom back staircases, which once were used at the base of the "T" no longer exist.

Historically, the building is significant as one of two prominent houses in the mill town of Savage, Maryland. The other, the mansion house, was occupied by the owner of the mill, while the Holte-Grafton house, was occupied by the manager of the mill. The last manager to occupy the house was Mr. William Reeley.

For those reasons, the Holte-Grafton house is significant to the State of Maryland and the Nation and is included in the Savage Mill National Register District. In addition, it, in conjunction with the historic district, is included in the State Critical Areas Program and should be included in any local landmark ordinance, the citizens of Savage might seek to initiate.

**9 MAJOR BIBLIOGRAPHICAL REFERENCES**

Interview with Mrs. Holte, owner, at Savage, March 12, 1979  
Interview with Mrs. William Reeley, former occupant of the house from 1936-1949  
Land Records of Howard County

CONTINUE ON SEPARATE SHEET IF NECESSARY

**10 GEOGRAPHICAL DATA**

ACREAGE OF NOMINATED PROPERTY .476 acres

Please see Attachment 1, Tax Map 47

VERBAL BOUNDARY DESCRIPTION

Please see Howard County Land Records, Liber 551 Folio 004

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE Maryland COUNTY Howard

STATE \_\_\_\_\_ COUNTY \_\_\_\_\_

**11 FORM PREPARED BY**

NAME / TITLE

Cleora Barnes Thompson, Archivist

ORGANIZATION

Office of Planning & Zoning-Comprehensive Planning Section

DATE

STREET & NUMBER

3450 Court House Drive

TELEPHONE

CITY OR TOWN

Ellicott City

STATE

Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust  
The Shaw House, 21 State Circle  
Annapolis, Maryland 21401  
(301) 267-1438

HO 220 140220562

MD. HISTORICAL TRUST  
BOX 1704  
ANNAPOLIS, MD. 21404

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

STATE:	
COUNTY:	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

1. NAME

COMMON: Holte - Galtter house

AND/OR HISTORIC: "The Manager's House"

2. LOCATION

STREET AND NUMBER: West end of Baltimore Street

CITY OR TOWN: Savage

STATE: md CODE: COUNTY: Howard CODE:

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
District <input checked="" type="checkbox"/> <u>Building</u>	Public <input type="checkbox"/>	<input checked="" type="checkbox"/> <u>Occupied</u>	<input checked="" type="checkbox"/> <u>Yes:</u>
Site <input type="checkbox"/> <u>Structure</u>	Private <input checked="" type="checkbox"/>	<input type="checkbox"/> Unoccupied	<input type="checkbox"/> <u>Restricted</u>
Object <input type="checkbox"/>	Both <input type="checkbox"/>	<input type="checkbox"/> Preservation work in progress	<input type="checkbox"/> Unrestricted
PRESENT USE (Check One or More as Appropriate)			
Agricultural <input type="checkbox"/>	Government <input type="checkbox"/>	<input checked="" type="checkbox"/> <u>Private Residence</u>	Comments <input type="checkbox"/>
Commercial <input type="checkbox"/>	Industrial <input type="checkbox"/>	Park <input type="checkbox"/>	Other (Specify) <input type="checkbox"/>
Educational <input type="checkbox"/>	Military <input type="checkbox"/>	Religious <input type="checkbox"/>	
Entertainment <input type="checkbox"/>	Museum <input type="checkbox"/>	Scientific <input type="checkbox"/>	

4. OWNER OF PROPERTY

OWNERS NAME: Sally and Hartley Holte

STREET AND NUMBER: Baltimore Street

CITY OR TOWN: Savage STATE: md CODE:

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:

STREET AND NUMBER: CLERK OF THE CIRCUIT COURT

CITY OR ~~HARFORD~~ COUNTY COURTHOUSE STATE: 40 S. MAIN ST. CODE:

APPROXIMATE ACREAGE OF ~~DOMINATED~~ PROPERTY: MARYLAND

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:

DATE OF SURVEY: Federal  State  County  Local

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN: STATE: CODE:

SEE INSTRUCTIONS

STATE: COUNTY: ENTRY NUMBER DATE FOR NPS USE ONLY

7. DESCRIPTION

CONDITION	(Check One)					
	Excellent <input type="checkbox"/>	Good <input type="checkbox"/>	Fair <input checked="" type="checkbox"/>	Deteriorated <input type="checkbox"/>	Ruins <input type="checkbox"/>	Unexposed <input type="checkbox"/>
INTEGRITY	(Check One)			(Check One)		
	Altered <input checked="" type="checkbox"/>			Unaltered <input type="checkbox"/>		
				Moved <input type="checkbox"/>		
				Original Site <input checked="" type="checkbox"/>		

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

This frame clapboard house with mansard roof has an imposing location at the west end of Baltimore Street. L Shaped, 5 bays by 2 in the main house ~~the wing~~ the wing runs west along the south wall 3 bays x 2. Three stories high the third floor ~~has a mansard roof~~ (3 bays by 1) has dormers with peaked roof over <sup>half</sup> a row and arched windows. Windows throughout are 2 lights over 2. A six-pillared 5 arch porch on the (east) front of the house has a turned balustrade & dentelles at the cornice of the porch ~~and~~ <sup>matching those</sup> of the <sup>cornice of</sup> the house.

Two interior chimneys rise from tiled fireplaces on inside walls.

SEE INSTRUCTIONS

**B. SIGNIFICANCE**

PERIOD (Check One or More as Appropriate)

Pre-Columbian <input type="checkbox"/>	16th Century <input type="checkbox"/>	18th Century <input type="checkbox"/>	20th Century <input type="checkbox"/>
15th Century <input type="checkbox"/>	17th Century <input type="checkbox"/>	<u>19th Century <input checked="" type="checkbox"/></u>	

SPECIFIC DATE(S) (If Applicable and Known)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

Aboriginal <input type="checkbox"/>	Education <input type="checkbox"/>	Political <input type="checkbox"/>	Urban Planning <input type="checkbox"/>
Prehistoric <input type="checkbox"/>	Engineering <input type="checkbox"/>	Religion/Philosophy <input type="checkbox"/>	Other (Specify) <input type="checkbox"/>
Historic <input type="checkbox"/>	Industry <input type="checkbox"/>	Science <input type="checkbox"/>	_____
Agriculture <input type="checkbox"/>	Invention <input type="checkbox"/>	Sculpture <input type="checkbox"/>	_____
Art <input type="checkbox"/>	Landscape <input type="checkbox"/>	Social/Humanitarian <input type="checkbox"/>	_____
Commerce <input type="checkbox"/>	Architecture <input type="checkbox"/>	Theater <input type="checkbox"/>	_____
Communications <input type="checkbox"/>	Literature <input type="checkbox"/>	Transportation <input type="checkbox"/>	_____
Conservation <input type="checkbox"/>	Military <input type="checkbox"/>		_____
	Music <input type="checkbox"/>		_____

STATEMENT OF SIGNIFICANCE (Include Personages, Dates, Events, Etc.)

The house for the manager of the Baldwin-owned Savage Manufacturing Company, now owned by a family whose paycheck comes from Washinton.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Interview with Mrs Robert Matthews, Librarian at  
 Seware Community Building 11/72

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN ONE ACRE		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE

11. FORM PREPARED BY

NAME AND TITLE: **JEAN S. EWING**

ORGANIZATION: **MARYLAND HISTORICAL TRUST** DATE: \_\_\_\_\_

STREET AND NUMBER: **50 STATE CIRCLE**

CITY OR TOWN: **ANNAPOLIS** STATE: **MARYLAND** CODE: \_\_\_\_\_

12. STATE LIAISON OFFICER CERTIFICATION

NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National  State  Local

Name \_\_\_\_\_

Title \_\_\_\_\_

Date \_\_\_\_\_

I hereby certify that this property is included in the National Register.

\_\_\_\_\_  
 Chief, Office of Archeology and Historic Preservation

Date \_\_\_\_\_

ATTEST:

\_\_\_\_\_  
 Keeper of The National Register

Date \_\_\_\_\_

SEE INSTRUCTIONS

SAVAGE PARK

HO-42  
District Boundary

COMMERCIAL

FOUNDRY  
STREET

STREET

BALTIMO

220

FAIR  
ST

ST

221

222

522

219

218

WASHINGTON

217

213

★ ★ ★ ★ ★  
225

216

STREET

215

214

BALDWIN  
COMMON

SAVAGE

WILLIAMS  
STREET

ROAD


BLVD.


SAVAGE

Scale, 1"=200'

RAILROAD

Historic Monument  
BOLLMAN TRUSS BRIDGE  
HO 81






Attachment 3  
 HO-220  
 The Holte-Grafton House  
 Hopkins Atlas of 1878

**SAVAGE FACTORY**

Scale 300 feet per inch



Savage Factory Business Notices.	
CONSTABLE.	WM. OLARK.
MANUFACTURERS.	PAUL KIEFER.
	J. W. VANDERGRIFF.
	PHYSICIAN.
	THOMAS C. WORTHINGTON.
	TINSMITH.
	WM. FERGUSON.
	WEAVERS.
	BALPH LEE.

BY:

[ C. 1820 to 1.

] 1879 to 1940

] 1941 to

== Historic District Boundaries

SAVAGE HISTORIC DISTRICT


SAVAGE, MARYLAND

Attachment 4

HO-220

The Holte-Grafton House


Savage Mill Historic District



J.R. Rivoire, 5/74. Not drawn to scale.

# Savage Mill District Gets National Designation

ie Maryland Historical Places. The district includes the mill and the surrounding area. The map shows the location of the mill and the surrounding area. The map is titled 'SAVAGE HISTORIC DISTRICT' and 'SAVAGE, MARYLAND'. A legend at the top left indicates '== Historic District Boundaries'. A north arrow is on the right side of the map.



Attachment I  
 HO-220  
 The Holte-Grafton House  
 Tax Map 47

7112/11  
 266.73A.  
 RMI

TRAISE LINE  
 7A  
 75 623/159  
 3.86A.  
 P.879  
 740/83  
 2.00A.  
 P.903  
 WM. A. HALL, SR  
 ET AL  
 104/435  
 27.63A

BALTO. GAS & ELEC. CO.  
 588/166  
 14.83A.

LAUREL HARNESS RACING ASSOC INC.  
 306/112  
 P.194  
 P.192


TRAVENOL LAB., INC.  
 634/749  
 11.50A.  
 P.145

TRAVENOL LAB.  
 637/180 INC.  
 23.24A.  
 P.197

CORRIDOR IND PARK  
 SEC. 1  
 A-31/12-20

PAR. UTILITY CO. METRO.  
 HOWARD

SAMUEL A. BRAUN  
 419/183



Attachment 2  
HO-220  
The Holte-Grafton House  
U. S. Geological Survey Map  
Savage, Maryland Quadrangle



HO 220

Holte-Galton house, Savape

11/70 H9







C B THOMPSON, AICP

EAST FACADE  
MAR - 79

H0-220  
HOLTE-GRAFTON HOOD