

Start Here

Scan One Time Only

And

Copy for Multiple Numbers

K-1, K-2

AND

K-3

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

FOR	USE ONLY
RECEIVED	
DATE ENTERED	

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**

SEE INSTRUCTIONS IN HOW TO COMPLETE NATIONAL REGISTER FORMS
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC

K-1 K-2 K-3
Washington College: Middle Hall, East Hall, West Hall

AND/OR COMMON

Hill Dormitories - Washington College

2 LOCATION

STREET & NUMBER West side of Washington Avenue (Maryland Route 213)
on the South side of College Lane

NOT FOR PUBLICATION

CITY, TOWN

Chestertown

VICINITY OF

CONGRESSIONAL DISTRICT

First

STATE

Maryland

CODE

24

COUNTY

Kent

CODE

029

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input checked="" type="checkbox"/> EDUCATIONAL <input type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input checked="" type="checkbox"/> YES UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input checked="" type="checkbox"/> OTHER

Dormitories

4 OWNER OF PROPERTY

NAME Visitors and Governors of Washington College, Attention: Dr. Joseph H. McLain,
President or George E. Hayward

STREET & NUMBER

Washington Avenue

CITY, TOWN

Chestertown

STATE

Maryland

21620

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC

Kent County Courthouse

STREET & NUMBER

Clerks Office

CITY, TOWN

Chestertown

STATE

Maryland

21620

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

FEDERAL STATE COUNTY LOCAL

DEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

K-1, K-2, K-3

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

 DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Middle, East, and West Halls stand on the crest of a low hill (the terrace) at the center of the Washington College campus. The slope to the south (front) is landscaped with large trees and a flight of steps lined with shrubs leading up to the entrance of Middle Hall.

Middle Hall, built in 1844, is the largest of the three brick structures--57'2" x 45'3". It is three stories tall and five bays wide by four deep; it sits on a raised basement of coursed granite blocks. The brick walls are laid in all stretcher bond. It has a hip roof covered with standing seam metal. Early drawings and photographs show that the building had a large cupola at the peak of the roof, removed some time after 1936. Four large, original chimneys have also been removed.

The south facade contains the main entrance in the central bay. A flight of wooden steps leads up to an entrance porch; both have brick foundations. The porch has two chamfered square columns on either side at the front and a pilaster on either side of the entrance. Iron pipe railings replace wooden railings visible in photographs taken in 1936. The porch has a flat roof.

The entrance has a six-panel door with sidelights and a diamond-pattern transom. The surround is flat with roundels in the corners. Above the entrance is a three-part window with 6/6 sash flanked by narrow 2/2 sash. The other windows have 6/6 sash; all have flat arches and stone sills. There are two basement windows on either side of the entrance; these are shorter than the sash above, and several of them are boarded up. The central basement bay on the rear contains a modern door.

The building has a flat board cornice containing small, horizontal windows above the bays below. There is a strip of molding on the cornice below the windows.

The rear facade has a "scar" in the brickwork where an entrance porch, door, and steps were removed in 1956. A window replaces the door.

East and West Halls were built in 1854 flanking Middle Hall. They are smaller, but similar stylistically to Middle Hall. Both are 36'1" x 50'4", three stories tall and three bays wide. East Hall is six bays deep while West Hall is only five. They are also laid in all stretcher bond on a raised basement of coursed granite block. The hip roofs on these buildings have a very shallow pitch, unlike that on Middle Hall. They have bracketed cornices.

The south facades both have a central doorway with entrance porch. The porches have two chamfered square columns and two pilasters, otherwise they resemble that on Middle Hall. (All three buildings have painted board signs on the fascia of the porch giving the names of the buildings.) Each entrance has a six-panel door, sidelights, and transom. The windows on the first and second stories have 6/6 sash, flat arches, and sandstone sills. The third story windows on East Hall have arches and sills like the others, but the sash have only 3/3 lights. Both buildings have basement windows with stone lintels and 6/6 sash shorter than those above, although several windows on the sides extend above the basement and have brick lintels and 9/6 sash on East Hall and 6/6 on West Hall. There is a door in the second basement bay from the front on the east facade of East Hall.

SEE CONTINUATION SHEET #1.

Form No 10-300a
(Rev 10-74)UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICENATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

Washington College
Kent County

CONTINUATION SHEET Maryland . ITEM NUMBER 7 PAGE 1

(DESCRIPTION, continued)

The north (rear) facades of these two structures have doors opening onto fire escapes. These are flanked by windows, which are blocked up on the first floor of West Hall. There is no opening in the central basement bay on this facade of West Hall. In the same location on East Hall is a 3/6 window.

The interiors of all three buildings were renovated in 1956. Still used as dormitories, they have metal stairs and some new partitions. Trim survives around unaltered doors and windows.

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input checked="" type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION		
<input type="checkbox"/> 400-1499	<input checked="" type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE		
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input checked="" type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN		
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER		
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION		
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)		
		<input type="checkbox"/> INVENTION				

SPECIFIC DATES 1844, 1854

BUILDER/ARCHITECT

Elija Reynolds

STATEMENT OF SIGNIFICANCE

In 1723, the Maryland General Assembly authorized each county to purchase land for schools. In 1728 the Visitors of Kent County purchased 100 acres from Simon Wilmer and his wife, Darcus, for 50 pounds.¹ Visitors appointed for Kent County were the Reverend Richard Sewell, the Reverend Alexander Williamson, James Harris, Esq., Colonel Edward Scot, Mr. Gideon Pearce, Mr. Lambert Wickes, and Mr. James Smith. The Kent County School began in 1730, and one of its early headmasters was Charles Peale, father of noted artist Charles Wilson Peale.

Kent County School prospered, having attracted boarding students from some distances. In 1782 the Reverend Dr. William Smith, former Provost of the College of Philadelphia, was named principal of Kent County School. Under his leadership, the Visitors petitioned the General Assembly for a corporate charter to establish "...a college or place of universal learning with the usual privileges..."²

Washington College, chartered on May 24, 1782, is Maryland's oldest college. It is the only private college on Maryland's Eastern Shore and holds the distinction of having been named after George Washington with his expressed consent. Washington contributed the sum of 50 guineas to the original endowment, later served as a Visitor and Governor (trustee), and was granted an honorary Doctor of Laws degree in 1789.

Under its founding President, William Smith, the college began construction of its first building in 1783. Named "Common Building" and completed in 1789, it was destroyed by fire on January 11, 1827. Common Building was composed of three connected units extending 160 feet and reaching a four-story height of 53 feet. It cost \$28,000 to build, \$20,000 of which came from a lottery sanctioned by the State General Assembly in 1784.³ Until the building was erected, it is assumed that classes were held in various town buildings. The contractor for Common Building was a Philadelphian named Robert Allison. The structure itself was one of the largest collegiate buildings of that era.

Middle Hall (1844) and East and West Halls (1854) hold a special place in the history of Washington College in that they are the oldest surviving campus buildings and serve as monuments to the original Common Building, whose site they occupy.

Middle Hall, as it came to be called is the largest of three buildings. It was an idea long before it was built. In 1833, under President Richard Williamson Ringgold, a native of Kent County and alumnus of Princeton, the Visitors and Governors of Kent County resolved to build a college building on the parcel of land occupied until six years earlier by Common Building. A committee of three was appointed to secure estimates and plans for a suitable building to be built at a cost of not more than

SEE CONTINUATION SHEET # 2.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICENATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORMWashington College
Kent County

CONTINUATION SHEET Maryland

ITEM NUMBER 8 PAGE 2

(SIGNIFICANCE, continued)

\$6,000.⁴ The committee urged the acceptance of plans put together with the help of Mr. Burchinall, a builder from Chestertown. The plans called for:

A two-story house, sixty feet by forty, a cellar under the whole house to be eight feet high in the clear, four feet of it below and four feet above the ground. The first story to be twelve feet high in the clear, to have an entry or passage through the center of the building twelve feet wide, and two rooms of equal size on each side of the entry, the adjoining rooms to be connected by a large folding or sliding doors, and a fireplace in each room. The second story to be ten feet in the clear and in all respects the same as in the first story. A stairway from the cellar to the garrett. In the first and second stories the stairway to be in the entry.⁵

After nearly ten years of debate, further investigations, financial stress, and a few resignations of members, the Visitors and Governors finally agreed in 1844 to follow the Burchinall plans and to begin construction on the building. Mr. Elisha Reynolds of Baltimore was selected as the general contractor.

On May 4, 1844, ceremonies were held to mark the laying of the cornerstone in Middle Hall and the festivities on "College Hill" were reported in the Kent (County) News. A zinc box containing a copy of the Charter of the College, the names of faculty and the Visitors and Governors, various newspapers of the day and national coins, was placed in the corner stone. The inscription on the cornerstone on the southeast corner reads as follows:

Founded 1783
Destroyed by Fire 1827
Rebuilt in 1844

During construction of Middle Hall, the building plans underwent many revisions at the request of the Visitors and Governors. For example, Mr. Reynolds was asked to construct a roof over the large cupola atop the building and to erect a lightning rod with a gold point. Reynolds was also asked to install blinds in the attic windows before being given his final payment after construction was completed. Benjamin F. Green, Vice Principal and Professor of Washington College, designed and oversaw the landscaping of the terrace on which Middle Hall, East, and West Halls stand. The first classes were held in Middle Hall in fall, 1845.

In 1854, ten years after Middle Hall opened, construction began on East Hall and West Hall. Crowding of boarding students in the four attic rooms of Middle Hall (then called the Nursery, the Apple Orchard, the Grogg and St. Peters), and an

SEE CONTINUATION SHEET #3.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**Washington College
Kent County

CONTINUATION SHEET Maryland

ITEM NUMBER 8 PAGE 3

(SIGNIFICANCE, continued)

anticipated enrollment increase encouraged the Board of Visitors and Governors to seek plans and cost estimates for a new building or buildings. Again Eliza Reynolds, architect for Middle Hall, was called from Baltimore. He appeared before the Board on March 16, 1854, with several plans of buildings and estimates of cost.

Mr. Reynolds was asked to prepare plans for two buildings, one to be located to the east and one to the west of the existing building. Contractors were asked to bid on the Reynolds plans and Mr. Ringgold of Millington, low bidder, was awarded the construction contract. Ringgold suggested some changes for the front of the buildings and these were accepted, but were the only deviations allowed from the Reynolds plans.

In an effort to conserve construction funds, a committee was sent to Locust Point, near Baltimore, to see Mr. H.F. Smith who had developed a brick-making machine.⁶ Smith's machine made five bricks at a time and was powered by a horse. The committee returned and urged the Board to sign an agreement with Smith for use of his machine.

An operator was provided by Mr. Smith and other arrangements were made to help insure that the brick-making process ran smoothly. Evidently problems occurred in the process, forcing the Board to arrange to purchase Baltimore brick for the fronts of East and West Halls, and later, for the north ends of the buildings and for the east side of East Hall.

The new halls had lecture rooms on the second floors and living quarters on the third floors. Two MacGregor furnaces were purchased from the Baltimore firm of Robbins and Bibs to heat the buildings, but they proved unsatisfactory and the company took them back. The new buildings also provided much needed library space. In 1856 Dr. Francis Waters, the principal of the college, and his family occupied a portion of the East building. A faculty member and his family lived in the West buildings. Years later the north end room in West Hall was considered the gymnasium and contained weight lifting equipment. None of the three buildings contained any plumbing facilities until 1890, when limited plumbing was installed.

It is interesting to note that no record can be found of a celebration of special ceremony being held when East Hall and West Hall were completed in 1854. They were the last buildings to be built until 1897, when Normal Hall or Ladies Hall, a building to accommodate thirty female boarding students, was opened.

SEE CONTINUATION SHEET # 4.

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM**



Washington College
Kent County


CONTINUATION SHEET Maryland . ITEM NUMBER 8 PAGE 4

(SIGNIFICANCE, continued)

SPECIAL CREDIT

Mr. Frederick W. Dumschott, an alumnus of Washington College, Class of 1927, and Vice President Emeritus, is hereby given special credit, recognition, and thanks for his well prepared "History of Washington College," currently being written and edited and from which came much of the material presented in this paper.

- ¹Land Records: Liber 3, Folio 601, Kent County Courthouse.
- ²Acts of the General Assembly of Maryland, 1782, Chapter VIII.
- ³Maryland Journal and Baltimore Advertiser, August 3, 1784.
- ⁴Minutes of the Board of Visitors and Governors of Washington College, August 9, 1833.
- ⁵Ibid., February 12, 1834.
- ⁶Ibid., April 29, 1854.



Washington College
Lands.

Marion det. Smith

Oct 9, 1882

Surveyor.


Variations 4° 19' west

158
250ft. to an inch

TRUE COPY, TEST:


EARL H. BENDER, CLERK

By: Grace S. Nelson
DEPUTY CLERK



1.72

.88



K-1, K-2, K-3

Landing Strip

x 74

70x

76x

20

Radeliffe Creek

PENN

CANTON

Creek

WASHINGTON COLLEGE

High Sch

CHESTERTOWN (BM/22)

Barroll Pt

Hope

Middle, East, and West Halls Washington College

Chestertown Quad

Gasoline

789

QUEEN ANNES CO
KENT CO

Chester River Country Club

Janes Cem

Piney Grove

Emony

Primrose Pt

ROAD 63

LANE

BM 37

DEVILS



K-1

Middle

East

West

New West

Oct 93

Andrews



67 - - PICTURE OF THE ORIGINAL BUILDING AT WASHINGTON COLLEGE.

WASHINGTON COLLEGE - KENT COUNTY
EASTERN SHORE

K-1
Washington College

Credit to State Roads Commission



K-1

WASHINGTON COLLEGE - KENT COUNTY. EASTERN SHORT B-40

K-13 Middle Hall
Washington College

1844

Chestertown

private

Perhaps the only full-fledged Greek Revival building in Chestertown, Washington College's Middle Hall is the oldest standing structure on the campus. It was designed and built by Elijah Reynolds. Its principal architectural feature of interest is the white frieze-like attic which runs around the entire building just below the cornice. The building has lost the wood balusters which decorated its porch, had its sidelights boarded up, and lost a cupola ^{it ~~probably~~ ^{may have} picked up later in the century}, but is otherwise in original form on the exterior. Its interior has been radically altered and student proofed.

(arch)

MARYLAND HISTORICAL TRUST

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

MHT # 15800 11402

1 NAME

HISTORIC Middle College
AND/OR COMMON Middle Hall

K-1
1183

2 LOCATION

STREET & NUMBER Washington College campus

CITY, TOWN Chestertown

CONGRESSIONAL DISTRICT

First

STATE Maryland

COUNTY Kent

3 CLASSIFICATION

CATEGORY OWNERSHIP STATUS PRESENT USE
-DISTRICT -PUBLIC X OCCUPIED -AGRICULTURE -MUSEUM
X BUILDING(S) X PRIVATE -UNOCCUPIED -COMMERCIAL -PARK
-STRUCTURE -BOTH -WORK IN PROGRESS X EDUCATIONAL -PRIVATE RESIDENCE
-SITE PUBLIC ACQUISITION ACCESSIBLE -ENTERTAINMENT -RELIGIOUS
-OBJECT -IN PROCESS X YES: RESTRICTED -GOVERNMENT -SCIENTIFIC
-BEING CONSIDERED -YES: UNRESTRICTED -INDUSTRIAL -TRANSPORTATION
-NO -MILITARY X OTHER dormitory

4 OWNER OF PROPERTY

NAME Washington College
STREET & NUMBER

Telephone #: 778-2800

CITY, TOWN Chestertown

VICINITY OF

STATE, zip code

Maryland 21620

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC. Office of the County Clerk

Liber #: SB 4
Folio #: 224

STREET & NUMBER Kent County Court House

CITY, TOWN Chestertown

STATE Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE "Washington College Lands" Marion Dek. Smith, surveyor

DATE October 9, 1882

-FEDERAL -STATE -COUNTY X LOCAL

DEPOSITORY FOR SURVEY RECORDS Plot included with description of lands on deed.

CITY, TOWN

STATE

7 DESCRIPTION

K-1

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Middle Hall is the central structure in a three-building cluster which faces south toward the downtown area of Chestertown from the crest of high ground at the center of the main Washington College campus.

As it stands today, Middle Hall is a brick 2½-story building with a low hip roof, built basically in the Greek Revival style. It is five bays wide and four deep. There is a high basement of cut granite. Above the basement is all stretcher brick with thin mortar joints.

There is a square-columned portico with wood steps, one story high in the middle bay. Its handrail and newel posts, formerly wood, are now hollow metal pipe. The portico has a plain box cornice and flat roof. There is a double door with a diamond-pane transom. The 3-pane sidelights have been boarded up.

All of the windows in the basement and on the first and second stories are 6/6 double hung sash. The first and second story windows have flat arches and limestone sills. The middle second story window on the facade is flanked by sidelights. Below a molded box cornice is a low "attic" painted white like a freize which has five 3-pane windows, the middle one flanked by 1-pane sidelights. The freize runs around the building, with four attic windows on each side elevation and five in the rear.

The low hip roof is of standing seam tin.

The building has been through several stages of mild renovation. At some relatively early stage the building picked up a cupola; that most removed in the 1950's. The 1950's renovation also replaced the wood handrails and balusters on the portico with metal pipe. The original interior arrangement has also been altered: in the late nineteenth century there were four 21-foot square rooms on each of the three floors. Now there are six rooms on the first floor, eight on the second, and eight on the third. The original wood floors have been covered with linoleum and the ceilings with acoustic tile.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

K-1

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input checked="" type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES 1844

BUILDER/ARCHITECT Elijah Reynolds, architect/builder

STATEMENT OF SIGNIFICANCE

Middle Hall is a handsome restrained representative of its style, notable principally for its white freize-like attic. The only restoration it requires to bring it back to its proper significance as a work of architecture are its wood handrails and balusters on the portico.

Its significance to the history of the college is considerable. It is the oldest college structure in existence and is a monument to one of the principal turning points in the school's perilous early years. The original college building, completed in 1789--just seven years after the school's founding--occupied the same site until it burned to the ground in 1827. Some classes were held in buildings around the town between 1827 and the completion of the new "college building" (only name it had until its flanking sisters, East and West College were built in 1854, when it became Middle College), but no students were graduated.

In 1844, the college's Board of Visitors and Governors decided to get a building up to hold the faltering school together and let a contract almost immediately. The building was up in eight months. Faculty and students moved in at the turn of 1844-45, and a class was graduated in 1849, the first since the fire. It remained the only college building until 1854.

As far back as there is any written remembrance, the use of the building was as follows: the top floor housed borders; the second was allotted to the stewardess, except for the room in the northwest corner which served as a library; and the first floor contained two laboratories and two more rooms allotted to the stewardess. Students ate in the southwest corner of the basement, at one time one of college's two competing boarding rooms.

The building was converted entirely to dormitory use early in this century, the use it serves today.

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Archives of Washington College, Miller Library

Unpublished papers of F.W. Dumschott, who is preparing a history of the college.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE COUNTY

STATE COUNTY

11 FORM PREPARED BY

NAME / TITLE

Robert Neill Historic Site Surveyor

ORGANIZATION

Maryland Historical Trust / Town of Chestertown

DATE

February, 1976

STREET & NUMBER

TELEPHONE

CITY OR TOWN

STATE

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.


The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438


MIDDLE HALL



SOUTH ELEVATION



EAST ELEVATION



WASHINGTON COLLEGE
CHESTERTOWN, MARYLAND


DM. STONE

FLOOR PLAN

K-1

7/6/70

MIDDLE HALL - WASHINGTON COLLEGE




WEST ELEVATION

SCALE 1/8" = 1'-0"

STAIR, WINDOW GUARDS, ETC. TO BE CONSTRUCTED SIMILAR TO DETAIL SHOWN ON DRWG NO 4

NOTE - CHIMNEYS SHOWN ON P. THREE ROOF




RENOVATION 1956

MIDDLE HALL
WASHINGTON COLLEGE
CHESTERTOWN, MARYLAND 21620

6/24/78


K-1




NORTH ELEVATION

SCALE 1/8" = 1'-0"

NOT EXTEND







NORTH ELEVATION

SCALE 1/8" = 1'-0"

NOT EXTEND



SOUTH ELEVATION



FOODS (NEW) FARM

COUNTY

PENNSYLVANIA RAILROAD

KENT

CEMETERY

VITA FOODS

N

LYNCHBURG STREET

STREET

POPLAR RD

PROSPECT ST

STREET

STREET

STREET

KENT STREET

STREET

MT VERNON

CAMPUS

COLLEGE

AVENUE

WASHINGTON

COLLEGE

K-1 183

MORNEC

STREET

ELM STREET

GREENWOOD

VALLEY

STREET

SCHOOL

CEDAR

STREET

BROWN RIVER VIEW RD

WASHINGTON U.S. 213

TERRACE

MILL

CALVERT STREET

WASHINGTON

U.S. 213

SCHOOL AVENUE

SPRING ST

PHILOSOPHERS

KENT

BYFORD DRIVE

WALDO DRIVE

DAVID DRIVE

BARROLL DRIVE

CROSS

ROW STREET

STREET

TWILLEY LANE QUEEN

PARK COURT ST

CHURCH ST

ST

AVENUE

STREET

BYFORD COURT

WATER CANNON

HIGH STREET

STREET

MAPLE

RIVERSIDE TERRACE

River

Chester

U.S. 213



Middle Hall

S W view

Oct 53

Anderson

~~K-1~~

K-1



FOUNDED IN 1783.
DESTROYED BY FIRE IN 1827.
REBUILT IN 1844.

K-1

Middle Hall

Oct 93

Andrews



K-1 MIDDLE HALL, WASHINGTON COLLEGE

B-14-3



Middle Hall
Washington College
Chester town, Maryland

X-1

KLM

Second floor room

6/23/78



Middle Hall
Washington College
Chestertown, Maryland

K-1

KLM

First floor entrance way

6/23/78



211
Middle Hall
Washington College
Chestertown, Maryland

KLM

First floor apartment

6/23/78



K 1
Middle Hall
Washington College
Chester town, Maryland

KLM

Basement staircase

6/23/78

K-2 East Hall, Washington College

1854

Chestertown

private

A fairly bare mid-19th century vernacular building erected ten years ~~after~~ after the adjacent Middle Hall on the Washington College campus, East Hall and its nearly identical sister, West Hall, ~~was obviously~~ ^{was} obviously designed to harmonize with ~~its~~ ^{the} mother building without drawing attention from it. It has lost the wood balusters from the entrance portico but is otherwise in original form on the exterior. Its interior has been radically altered and student-proofed.

MHTB K-2
1500021502

MARYLAND HISTORICAL TRUST

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC "East College" (name it bore from 1854 until W. W. I) K-2
 AND/OR COMMON East Hall ~~1682~~

2 LOCATION

STREET & NUMBER Washington College campus First
 CITY, TOWN Chestertown CONGRESSIONAL DISTRICT
 STATE Maryland VICINITY OF COUNTY Kent

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input checked="" type="checkbox"/> EDUCATIONAL <input type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input checked="" type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input checked="" type="checkbox"/> OTHER dormatory

4 OWNER OF PROPERTY

NAME Washington College Telephone #: 778-2800
 STREET & NUMBER
 CITY, TOWN Chestertown STATE, zip code
Md. 21620

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC. Office of the County Clerk, Kent County Liber #: SB 4
Folio #: 224
 STREET & NUMBER Court House
 CITY, TOWN Chestertown STATE
Md.

6 REPRESENTATION IN EXISTING SURVEYS

TITLE "Washington College Lands" Marion deK. Smith, Surveyor
 DATE October 9, 1882 _FEDERAL _STATE COUNTY _LOCAL
 DEPOSITORY FOR SURVEY RECORDS Plot included with description of lands in Liber SB4, Folio 224 above.
 CITY, TOWN Chestertown STATE Maryland

7 DESCRIPTION

K-2

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

East Hall is at the extreme east in a three-building cluster which faces south toward the downtown area of Chestertown from the crest of high ground at the center of the main Washington College campus.

It looks essentially as it did when it was built, though it, along with its sister buildings, Middle and West Halls, lost its portico's wooden handrails, newel posts, and turned balusters in the renovation of the late 1950's. The original interior has also been altered twice. The floor plan was converted to a dormitory arrangement early in the century: the ceilings and floors were student-proofed with accoustic tile and linoleum in the 1950's. Other alterations in the 1950's project include the strengthening of the building's frame with steel beams and the insertion of steel rods to pull in the side walls which had begun to bow out.

It is a two and one-half story brick structure of no particular style, though it was obviously designed to fit harmoniously with the already existing slightly more elaborate (in its original form) and slightly larger Greek Revival style building, (Middle Hall, ~~renovated~~) immediately west of it. It has a high basement of cut granite. Above the basement is all stretcher brick with thin mortar joints. It is three bays wide and six bays deep. There is a square columned portico with wood steps; its handrails and newel posts are now of hollow metal pipe. The door leading to the portico is double with a transom and side-lights. The windows decrease in size from floor to floor; the third floor windows have three over three sash; the other windows are six over six. There are flat arches over the windows and limestone sills beneath. There is a ^{standing seam} bracketed cornice containing the gutter. The roof is a very low hip and is tin.

~~The flat arches over the windows have gauged brick.~~

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

K-2

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION		
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE		
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE if restored	<input checked="" type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN		
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER		
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION		
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input checked="" type="checkbox"/> OTHER (SPECIFY)	college history	
		<input type="checkbox"/> INVENTION				

SPECIFIC DATES Built: 1854 BUILDER/ARCHITECT Unknown
 Renovated: late 1950's

STATEMENT OF SIGNIFICANCE

As it stands, East Hall's architectural significance is small, though if it were restored - along with its sister buildings, Middle and West Halls - the three building cluster would take on considerable interest as a study in mid-nineteenth century classical restraint.

East Hall's place in the history of the college is as its second oldest existing structure, a distinction it shares with West Hall, built in the same year. Both buildings were begun and completed under the administration of the schools' fourth president, Richard Ringgold, and dedicated by his successor, Reverend Dr. Francis Waters. East Hall served as the residence for the college president and for the vice-president and his family until just before the turn of the present century when several frame structures were built for administrative residences along the Washington Avenue side of the campus. At that time, or soon thereafter, East Hall was converted to a dormitory, the use it serves today.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Archives of Washington College, Miller Library.
Unpublished papers of F. W. Dumschott, who is preparing a history of the college.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE COUNTY

STATE COUNTY

11 FORM PREPARED BY

NAME / TITLE

Robert L. Neill, Architectural Surveyor

ORGANIZATION

Town of Chestertown/Maryland Historical Trust

STREET & NUMBER

CITY OR TOWN

Chestertown

DATE

Feb. 23, 1976

TELEPHONE

STATE

Md.

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.


RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

DOWNSPOUT

METAL LATH & PLASTER FURRING
AROUND PIPE - 522 MICH

NEW WIRE MESH WINDOW GUARDS

NEW DOWNSPOUT



NEW STEEL STAIR

PROVIDE WOOD SHELF WHERE WALL THICKENS AT 1ST FLOOR LINE

INSTALL NEW WIRE WINDOW GUARD.

ALL NEW STAIRS LAI ARE TO BE STEEL.

REMOVE EXIST. BUILD UP MULLI & INSTALL NEW

PROVIDE NEW METAL THRESHOLD

EXIST. PIPE RAIL REMAINS

EXISTING PORC. PROVIDE NEW WOOD SKI CORNICE & M... ALL NEW WORK


(SEE ALTERNATIVE) PROVIDE ALL NEW INTERIOR 32A WINDOWS. REFR. FRAMES.

EXISTING WOOD WINDOW JAMBS

EXISTING BRICK WALL REMAINS


REMOVE EXIST. DOOR

EAST HALL




SOUTH ELEVATION

EAST ELEVATION



FLOOR PLAN

WASHINGTON COLLEGE
CHESTERTOWN, MARYLAND



K-2

N

CEMETERY

VITA FOODS

FOODS (NEW) FARM

KENT COUNTY PENNSYLVANIA RAILROAD

LYNCHBURG STREET

PROSPECT ST.

COLLEGE WASHINGTON COLLEGE

AVENUE

AVENUE

MORNING

STREET

ELM STREET

GREENWOOD VALLEY STREET

POPLAR RD.

STREET

STREET

STREET

STREET

MT. VERNON

CAMPUS

COLLEGE

(82)

PINE

STREET

STREET

KENT

STREET

KENT

CALVERT STREET

WASHINGTON U.S. 213

BROWN VIEW RD.

STREET

SCHOOL

MILL

SPRING ST.

PHILOSOPHERS TERRACE

BYFORD DRIVE

WALDO DRIVE

DAVID DRIVE

SCHOOL STREET

SCHOOL AVENUE

CROSS

ROW STREET

PARK COURT ST.

CHURCH ST.

AVENUE

STREET

BYFORD COURT

TWILLEY LANE QUEEN

WATER CANNON HIGH STREET

MAPLE

STREET

RIVERSIDE TERRACE

DAVID DRIVE

BARROLL DRIVE


MORRIS

Chester

U.S. 213

River

K-2





K-2

Middle

East

West

view W

Oct 93

Andrews



K-2

East Hall

Oct '93

Andrews

5th view

SW



Photo: E. Neill
Processing: C. Engstrom



East Hall
Washington College
Chestertown, Maryland

K-2

KLM

First floor hallway

6/23/78



East Hall
Washington College
Chestertown, Maryland

E-2

KLM

Second floor room

cf 6/23/78




East Hall
Washington College
Chestertown, Maryland

K-2

KLM

Stairway - from 3rd floor

6/23/78



East Hall
Washington College
Chestertown, Maryland

K-2

KLM

Third floor room

6/23/78

K-3 West Hall, Washington College

1854

Chestertown

private

A fairly bare mid-19th century vernacular building erected ten years after the adjacent Middle Hall on the Washington College campus, West Hall and its nearly identical sister, East Hall, were obviously designed to harmonize with their mother building without drawing attention from it. It has lost the wood balusters from the entrance portico but is otherwise in original form on the exterior. Its interior has been radically altered and student-proofed.

K-3
MHTB
1500031502

MARYLAND HISTORICAL TRUST

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC "West College" (name it bore from 1854 until W. W. I)
AND/OR COMMON West Hall K-3 ~~K-4~~

2 LOCATION

STREET & NUMBER Washington College campus First
CITY, TOWN Chestertown VICINITY OF Kent CONGRESSIONAL DISTRICT
STATE Maryland COUNTY

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input checked="" type="checkbox"/> EDUCATIONAL <input type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input checked="" type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input checked="" type="checkbox"/> OTHER dormatory

4 OWNER OF PROPERTY

NAME Washington College Telephone #: 778-2800
STREET & NUMBER
CITY, TOWN Chestertown VICINITY OF Md. STATE, zip code 21620

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, LIBER #: SB 4
REGISTRY OF DEEDS, ETC. Office of the County Clerk, Kent County FOLIO #: 224
STREET & NUMBER Court House
CITY, TOWN Chestertown STATE Md.

6 REPRESENTATION IN EXISTING SURVEYS

TITLE "Washington College Lands" Marion deK. Smith, Surveyor
DATE October 9, 1882 FEDERAL STATE COUNTY LOCAL
DEPOSITORY FOR SURVEY RECORDS Plot included with description of lands, Liber SB 4, Folio 224
Office of the County Clerk of Kent County
CITY, TOWN Chestertown STATE Maryland

K-3

7 DESCRIPTION

CONDITION

<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED

CHECK ONE

UNALTERED
 ALTERED

CHECK ONE

ORIGINAL SITE
 MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

West Hall is at the extreme west in a three-building cluster which faces south toward the downtown area of Chestertown from the crest of high ground at the center of the main Washington College campus.

It looks essentially as it did when it was built, though it, along with its sister buildings, Middle and East Halls, lost its portico's wooden handrail, newel posts, and turned balusters in the renovation of the late 1950's. The original interior has also been altered twice; the floor plan was converted to a dormitory arrangement early in the century, and the building's frame was strengthened with steel and its decaying floors, walls, and ceilings student-proofed in the late 1950's.

It is a three-story brick structure of no particular style, though obviously designed to fit harmoniously with the already existing slightly more elaborate (in its original form) and slightly larger Greek Revival style building (Middle Hall, see K-1) immediately east of it. It has a high basement of cut granite. It is three bays wide and five bays deep. There is a square-columned portico with wood steps; its handrails and newel posts are now of hollow metal pipe. There is a double door with transom and sidelights, both of which have been boarded up. The windows decrease in size on the second and third floors, though they are all six lights over six. They have flat arches above and limestone sills beneath. The bracketed cornice contains the gutter, ~~of galval brick~~. There is a very low hipped roof which is made of tin.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

K-3

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION		
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE		
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE		
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE if	<input checked="" type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN		
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART restored	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER		
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION		
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input checked="" type="checkbox"/> OTHER (SPECIFY)		college history
		<input type="checkbox"/> INVENTION				

SPECIFIC DATES	Built: 1854	BUILDER/ARCHITECT	Unknown
	Renovated: late 1950's		

STATEMENT OF SIGNIFICANCE

As it stands, West Hall's architectural significance is small, though if it were restored - along with its sister buildings, Middle and East Halls - the three building cluster would take on considerable interest as a study in mid-nineteenth century classical restraint.

West Hall's place in the history of the college is as its second oldest existing structure, a distinction it shares with East Hall, built in the same year. Both buildings were begun and completed under the administration of the school's fourth president, Richard Ringgold, and dedicated by his successor, Reverend Dr. Francis Waters. West Hall was a student residence hall from the beginning on its second and third floors. The first floor served originally as a small auditorium and the basement first as a laboratory and later as a gymnasium. Like its sisters, West Hall was further subdivided and converted entirely to dormatory use early in the present century.

CONTINUE ON SEPARATE SHEET IF NECESSARY

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Archives of Washington College, Miller Library.
Unpublished papers of F. W. Dumschott, who is preparing a history of the college.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE COUNTY

STATE COUNTY

11 FORM PREPARED BY

NAME / TITLE

Robert L. Neill, ~~Architectural~~ Surveyor

ORGANIZATION

Town of Chestertown/Maryland Historical Trust

DATE

February, 1976

STREET & NUMBER

TELEPHONE

CITY OR TOWN

Chestertown

STATE


Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.


RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

WEST HALL



SOUTH ELEVATION

EAST ELEVATION



FLOOR PLAN

WASHINGTON COLLEGE
CHESTERTOWN, MARYLAND

K-3

N

FOODS (NEW) FARM

CEMETERY

VITA FOODS

KENT COUNTY

PENNSYLVANIA RAILROAD

KENT

LYNCHBURG STREET

POPLAR RD

PROSPECT ST

WASHINGTON AVENUE

AVENUE

AVENUE

MORNING

STREET

ELM STREET

GREENWOOD STREET

VALLEY

SCHOOL

COLLEGE

COLLEGE

CAMPUS

MT. VERNON

WASHINGTON

U.S. 213

BROWN VIEW RD.

STREET

SCHOOL

AVENUE

STREET

KENT

STREET

MILL

CALVERT

STREET

PHILOSOPHERS

TERRACE

BYFORD DRIVE

WALDO DRIVE

DAVID DRIVE

SCHOOL

STREET

STREET

SPRING ST.

CROSS

ROW

STREET

PARK COURT ST.

CHURCH ST.

AVENUE

STREET

BYFORD

COURT

TWILLEY LANE QUEEN

WATER CANNON

HIGH

STREET

MAPLE

RIVERSIDE TERRACE

Chester

U.S. 213

River



K-3

Middle

East

West

Oct 93

view West

Andrews



K-3

West Hall

Oct 93

Andrews

SE view



Photo: E. Neill
Processing: C. Engstrom



West Hall

K-3

Washington College

Chestertown, Maryland

KLM

First floor hallway

6/23/78



West Hall
Washington College
Chester town, Maryland

K-3

KLM

Second floor hallway

6/23/78



West Hall
Washington College
Chestertown, Maryland

K-11

KLFD

Second floor rooms

6/23/78



West Hall
Washington College
Chestertown, Maryland

K-3

Third floor hallway

6/23/78

KLM

End Here

Scan One Time Only

And

Copy for Multiple Numbers

K-1, K-2

AND

K-3