

K-194

Hildebrand Farm
Near Morgnec
c.1820

The three bay long, two story frame dwelling on the Hildebrand Farm was built around 1820 in a vernacular manner, with hall-parlor plan. Both rooms have enclosed winder stairs with closets beneath and vertical beaded board chimney breasts. The two bay, two story wing was constructed soon after the main house. The building is loosely related in form and plan to the miller's house at Urieville, on the property across Morgan Creek, about a half mile away.

Hildebrand Farm received its name from Grace E. Brooks who married Merrill Hildebrand. After her father, P. A. M. Brooks, died in 1934, the farm was transferred to Grace Hildebrand.¹ Prior to that time, the farm was in the ownership of the Brooks family and appears to have accompanied the northern portion of Thornton since the 18th Century. G. M. Brooks appears as owner of the farm on the 1860 map. He was residing at Thornton at the time. On the same map, School No. 4 is located on the Hildebrand Farm opposite the lane to Thornton.

1. Land Records, Lib. RAS 30, fol. 543.

*HILDEBRAND FARM
Kennedyville, Maryland
(ca 1800)*

The Hildebrand House is significant as an example of a vernacular farm house of the early 19th century. The main house is a frame structure three bays long and two bays deep. Two stories in height, the building is covered with a 90° gable roof without dormers. Adjacent to the main house is a small two-story kitchen wing. Now greatly altered, the house is similiar in size and plan type to two nearby houses; Massey Farm (K-380), and the Urieville Miller's House (K-291).

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC HILDEBRAND FARM

AND/OR COMMON

2 LOCATION

STREET & NUMBER *East side Perkins Hill Road, 1/2 mile south of junction with Wallis Bros. Road*

CITY, TOWN

Kennedyville

VICINITY OF

First

CONGRESSIONAL DISTRICT

Kent

STATE

Maryland 21645

COUNTY

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL <input checked="" type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input checked="" type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER

4 OWNER OF PROPERTY

NAME *Grace Hildebrand*

Telephone #: *unlisted*

STREET & NUMBER

8505 Springvale Lane

CITY, TOWN

Silver Spring

___ VICINITY OF

STATE, zip code

Maryland

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.

Kent County Court House

Liber #: *R A S 30*

Folio #: *543*

STREET & NUMBER

CITY, TOWN

Chestertown, Maryland 21620

STATE

6 REPRESENTATION IN EXISTING SURVEYS

TITLE *Maryland Historical Trust, Survey of Kent County*

DATE

1968

___ FEDERAL STATE ___ COUNTY ___ LOCAL

DEPOSITORY FOR SURVEY RECORDS

Maryland Historical Trust, The Shaw House, 21 State Circle

CITY, TOWN

Annapolis, Maryland 21401

STATE

7 DESCRIPTION

K-194

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input checked="" type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Hildebrand Farm House is situated in open fields on high ground between two tributaries of Morgan Creek.

The main house is a frame structure three bays long and two bays deep. Two stories in height, the building is covered with a 90° gable roof without dormers. East of the main house is a two-bay long, two-bay deep wing. Also two stories in height and covered by a gable roof, the wing is about two feet lower than the main house. The roofs of both sections of the building are finished with verge boards at the gables and box cornices at the eaves. They are covered with asphalt shingles.

The house rests on a stuccoed brick foundation, and on the west gable, the chimney back is exposed to the second floor joists.

The building is currently undergoing an extensive remodeling which includes replacing all windows, removal or rebuilding of chimneys, replacing most interior finishes, covering the exterior of the building with narrow aluminum siding, and construction of a screened porch at the east end of the house. A new six-panel door with denticulated architrave replaces the original door and transom on the south facade of the house. A three-part picture window has been installed in the south wall, first floor of the wing.

The house was a typical hall and parlour house common in this area in the eighteenth and early nineteenth centuries. Its floor plan has been altered but simple paneling remains in the gable ends of

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

K-194

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES *ca 1800*

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

This house is significant as an example of a vernacular farm house of the early 19th century. Although greatly altered, it survives as a document of early farm life on this part of the Eastern Shore.

The house is similiar in size and plan type to other nearby houses: the Massey Farm (K-380), and the Urieville Miller's House (K-291). The two houses are similiar in size, have side wings, and hall and parlour floor plans. They probably typify the modest housing that was affordable by small farmers and rural tradesmen.

The barns and corn cribs on the Hildebrand Farm are interesting and well maintained examples of the kind of farm buildings constructed from the late 19th to the early 20th century. It is interesting to note the similiarity between the framing system of the house (ca 1800-1825) and the barns (ca 1875-1925).

CONTINUE ON SEPARATE SHEET IF NECESSARY

K-194

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Maryland Historical Trust Survey Records, K-194, September 12, 1968

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE COUNTY

STATE COUNTY

11 FORM PREPARED BY

NAME / TITLE
Marsha L. Fritz, Survey Consultant

ORGANIZATION
Kent County Planning Commission

DATE
778-4600 ext.67

STREET & NUMBER
Court House

TELEPHONE

CITY OR TOWN
Chestertown, Maryland 21620

STATE

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.


RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

the first floor rooms.

In both of these rooms, the wooden paneling consists of a door to a corner stair, a door to a closet under the stair, and boarding on the chimney breast. Doors have six raised and beveled panels with a plain ovolo panel moulding. Board paneling consists of random width boards with 3/8" beads. The surrounds of doors and fireplaces are quarterrounds. The fireplace openings are rectangular although the fireplaces themselves have been rebuilt.

Because of ongoing construction, the heavy timber frame of the main house is exposed in some locations. Also visible is the pit-sawn back face of the original weatherboarding which continues around to the east gable of the main house, showing that it predates the wing. Portions of narrow beaded board closets remain on the second story. Original flooring in the building is wide yellow pine.

The outbuildings on the property all appear to date from the later nineteenth or early twentieth century. They are typically frame with pegged frames of heavy timbers, nailed rafters, and vertical siding. Major buildings include barns and corn cribs.



$3/32" = 1'0"$

1501945304

Form 10-445
(5/62)

1. STATE Maryland COUNTY Kent TOWN Chestertown VICINITY Morgnes STREET NO. Perkins Hill Road, 1 mile south of Rt. 213, (east) ORIGINAL OWNER ORIGINAL USE dwelling PRESENT OWNER Mrs. F.M. Hildebrand PRESENT USE tenant house WALL CONSTRUCTION frame NO. OF STORIES two	HISTORIC AMERICAN BUILDINGS SURVEY INVENTORY K - 194
	2. NAME Hildebrand Farm DATE OR PERIOD early 19th century STYLE Federal ARCHITECT BUILDER
	3. FOR LIBRARY OF CONGRESS USE

4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION OPEN TO PUBLIC

The Hildebrand Farm is a 19th century structure with proportions and some detail carried over from the 18th century style of building. It is a two story frame structure, built on a brick foundation, covered with brown shingles, having an "A" roof with a brick chimney on each gable. The back of the brick fireplace on the west gable is exposed to the height of the second floor joists. A very plain door with transom is located off-center between two windows, which have 6/6 sash, white trim and no shutters. On the east side is a two bay long, two story wing with a leanto and a porch on the north side. It is well maintained by the present tenants.

5. PHYSICAL CONDITION OF STRUCTURE Endangered Interior Exterior good

 6. LOCATION MAP (Plan Optional)	7. PHOTOGRAPH
8. PUBLISHED SOURCES (Author, Title, Pages) INTERVIEWS, RECORDS, PHOTOS, ETC.	9. NAME, ADDRESS AND TITLE OF RECORDER Michael Bourne DATE OF RECORD Sept. 12, 1968

SUPPLEMENTAL INFORMATION AND PHOTOGRAPHS MAY BE ADDED ON SHEET OF SAME SIZE

Name Hildebrand Farm MHT# K-194Location Kent Kennedyville
COUNTY townPerkins Hill Road - 1 mile south of Rt 263
address or road#

First owner of record _____ DATE _____

Present owner Mrs. F.M. Hildebrand DATE _____Address Chestertown, Md.

Parcel or Deed # _____

Original use DwellingPresent use Dwelling - tenant

Md. Map Coordinates _____

Long. & Lat. reading _____

Style FederalDate(s) of construction early 19th Century

Architect _____

Builder _____

DESCRIPTION:

2 NUMBER of stories Frame - wood shingle type wall constructionFoundation-basement brick -Wall construction- Frame covered w/ wood shingles

Water table, string course, other decorative work essential to walls

NDChimneys in each gable both - w/ fireplace back exposed
to 2nd floor level

Name

Hildebrand Farm

MHT#

K-194

Entrance type & placement

off center - very plain

Windows

6/6 - 3 bays long x 1 bay deep

Shutters

ND

Roof type

A

covering wood

Cornice, eaves wood - good condition

Dormers, cupolas

ND

Porches

on the N. side of wing

Wings, hyphens

2 bay - 2 stories A⁺ roof - also

lean-to hitch.

Interior:

Stairway

-

Doors

Trim

Other notable work

Name Hildebrand FarmMHT# K-194Physical condition goodEnvironment farm

References:

MHT Color slide # _____

MHT B & W # _____

Owner contacted tenant - Mrs. Clark

OTHER: _____

Recorder Michael BourneDate Sept 12, 1968

Summary: The Hildebrand Farm is a 19th Century structure with proportion and some detail carried over from the 18th Century style of building. It is a 2 story frame structure, ^{built on brick foundation} covered with brown shingles, having an "A" roof with a brick chimney on each gable. The back of the brick fireplace under west gable is exposed to the height of 2nd floor joists. A very plain door with transom is located off-center between 2 windows, which have $\frac{1}{6}$ oak, white trim and no shutters. On the east side is a 2 bay long, 2 story wing with a lean-to and the porch on the north side. It is well maintained by the present tenants.

Enclosures: e.g. Map, Historical significance, sketch of floor plan, and angle of photos, etc.

57
K-194
(CHESTERTON BRANCH) 72

Hepbron PENNSYLVANIA

Stillpond Station

Bigwoods

Cem Fountain Church

Morgnac





K-194

J. Tyler Campbell
FREELANCE PHOTOGRAPHER
CHESTERTOWN, MARYLAND

K-194

MARYLAND HISTORICAL TRUST
LIBRARY

K-194 Hildebrand Farm c.1820

South Façade

HILDEBRAND FARM (K-194)

Kennedyville, Kent County

Photograph: M.L. Fritz, January 1980