

Maryland Historical Trust
 Maryland Inventory of Historic Properties Form
 Intercounty Connector Project

DOE yes no**1. Name:** (indicate preferred name)

historic Josiah Beall Property

and/or common Snyder Property

2. Location:

street & number 15700 Santini Road

 not for publication

city, town Burtonsville

 vicinity of

congressional district

state Maryland

county Montgomery

3. Classification:**Category** district building(s) structure site object**Ownership** public private both**Public Acquisition** in process being considered not applicable**Status** occupied unoccupied work in progress**Accessible** yes: restricted yes: unrestricted no**Present Use** agriculture commercial education entertainment government industrial military transportation museum park private residence religious scientific other:**4. Owner of Property:** (give names and mailing addresses of all owners)

name Roger E. Snyder, Jr.

street & number 15700 Santini Road

telephone no.:

city, town Burtonsville

state and zip code Maryland 20866

5. Location of Legal Description

Land Records of Montgomery County

liber 13195

street & number Montgomery County Judicial Center

folio 408

city, town Rockville

state Maryland

6. Representation in Existing Historical Surveys

title Old Building Survey of the Burtonsville Area

date 1976

 federal state county local

depository for survey records Montgomery County Historical Society

city, town Rockville

state Maryland

7. Description

Survey No.: M: 15-87 (PACS D2.33)

<u>Condition</u>		<u>Check one</u>	<u>Check one</u>	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Resource Count: 5

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Josiah Beall Property is a 2-story, 3-bay side-gable I-house with a 1-story addition on three sides. The asymmetrical fenestration pattern on the front and rear facades indicates the original house was likely a 2-bay structure, with the third bay added at a later date. In addition, the placement of one brick chimney near the center of the house suggests that the chimney was originally located in an end wall. Constructed circa 1880, the house has a standing seam metal roof and is of wood frame construction with horizontal boards and an adhesive applied brick veneer. Visible portions of the foundation are parged. The windows are double-hung wood sash with wood storm windows. The 1-story addition was constructed around the north, east and west sides of the house. The north and east addition has a hipped roof with an asphalt sheet membrane, and the west addition has an interior brick chimney and a shed roof with corrugated metal. The shed roof extends to the south to form a small entry porch, which is screened and has one wood corner post supporting the roof.

The west, or front elevation of the I-house is only partially visible. The 1-story addition conceals two of the three bays on the first story. The fenestration pattern is irregular with one 6/6 double-hung window on the first story and three 6/3 double-hung windows on the second story. The west elevation of the 1-story addition has three 6-light fixed windows.

The south elevation of the I-house has a small lean-to at the center of the facade. There is a 6-light fixed window on the second story in the gable peak. The south elevation of the 1-story addition has a fixed light window and a wood panel door with a wood storm door facing the entry porch.

The east elevation of the I-house is only partially visible. The 1-story addition conceals the first story of the I-house. The fenestration pattern is irregular with three 6/3 double-hung windows on the second story. The east elevation of the 1-story addition has two 6/6 double-hung windows, one 2-light fixed window, and a plywood double door. Adjacent to the two double-hung windows is a recessed area which leads to a door in the exterior wall of the I-house.

The north elevation of the I-house is only partially visible. The 1-story addition conceals the first story of the I-house. There is one 6/3 double-hung window on the second story. The north elevation of the 1-story addition has one 6-light fixed window, one 2-light fixed window, and a wood panel door. A second door on this facade has been blocked with plywood.

There are four outbuildings associated with this property. The first outbuilding is a shed with an asphalt sheet shed roof. Constructed circa 1930, the shed is of wood frame construction with vertical board and batten siding. The shed has two large vehicle openings and a small lean-to which is nearly collapsed; it is located west of the house. The second outbuilding is a shed with an asphalt sheet shed roof. Constructed circa 1930, the shed is of wood frame construction with vertical board siding. This shed has collapsed to one side, and it is located west of the

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Josiah Beall Property

SURVEY NO.: M: 15-87 (PACS D2.33)

ADDRESS: 15700 Santini Road, Burtonsville, Montgomery County

7. Description (Continued)

house and immediately north of the first outbuilding. The third outbuilding is a privy with a standing seam metal roof. Constructed circa 1930, the privy is of wood frame construction with horizontal board siding. The privy is located west of the house and west of the first two outbuildings. The fourth outbuilding is a shed with an asphalt sheet shed roof. Constructed circa 1930, the shed is of log and wood frame construction with thin wood paneling on two sides. This shed is located southwest of the house and south of the other three outbuildings.

The Josiah Beall Property is located at the end of Santini Road in Burtonsville, on a wooded lot overgrown with grasses and weeds. The area around the house is also wooded.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Josiah Beall Property

SURVEY NO.: M: 15-87 (PACS D2.33)

ADDRESS: 15700 Santini Road, Burtonsville, Montgomery County

8. Significance (Continued)

only telephone was in the general store (Daniels). The Great Depression caused much hardship among the area's farmers; farm prices fell drastically and the county could not afford to improve roads, utilities, and schools. Burtonsville did not benefit from the increase in federal employment brought by the New Deal.

In the 1980s, continued growth of federal and private sector employment and the new U.S. 29 highway made Burtonsville accessible to new residents and commercial development. Today Burtonsville retains a rural character. Old working farms still remain, but the area is becoming one of the major suburban centers outside of Washington, D.C.

Although the structure may reflect an earlier period of construction, the Josiah Beall Property's current appearance is typical of an I-house. The standard I-house is one room deep and two stories tall with five openings on each story. From the front, an I-house is often indistinguishable from a Georgian house. The gable view, however, reveals the greater depth of the Georgian house. Chimneys are located on the interior of the gable ends, however, external chimneys are characteristic in the Chesapeake region. Usually, an I-house has a one-story porch running the length or nearly the length of the long side. On the interior, a central hall separates the two rooms on the first floor; the second floor contains either two or four sleeping chambers. Later examples of I-houses are three bays wide rather than five bays. Due to the narrowness of the main core, many I-houses have kitchen wings to the rear. Initially, stone masonry construction was used but by the mid-nineteenth century, as pre-cut lumber became increasingly available, frame construction became the norm (Gowans 1992, 55-6). The Josiah Beall Property has been substantially altered. A previous survey states that the house was partially destroyed by fire and rebuilt, but the extent of damage and reconstruction is not known.

National Register Evaluation:

Constructed circa 1880, the Josiah Beall House is not eligible for the National Register. The house is not eligible under Criterion A or B, as it has no association with historically significant persons or events. The house is not eligible under Criterion C; the house is an undistinguished and deteriorating example of a vernacular I-house that has been altered. The 1-story addition on the west, north and east side has compromised the intent of the original design by introducing elements that have changed the character defining features of the original I-house. Finally the property has no known potential to yield important information, and therefore, does not meet Criterion D.

MARYLAND HISTORICAL TRUST

Eligibility recommended _____

Eligibility Not Recommended XX

Comments

Reviewer, OPS: [Signature]

Date: 8/25/98

Reviewer, NR Program: [Signature]

Date: 8/27/98

9. Major Bibliographical References Survey No.: M:15-87(PACS D2.33)

None Attached

10. Geographical Data

Acreage of nominated property _____
Quadrangle name Beltsville

Quadrangle scale 1:24,000

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Caroline Hall/Ryan P. McKay

Organization P.A.C. Spero & Company

date October 1996

street & number 40 W. Chesapeake Avenue, Suite 412

telephone (410) 296-1635

city or town Baltimore

state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
 DHCP/DHCD
 100 Community Place
 Crownsville, MD 21032-2023
 (410) 514-7600

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Josiah Beall Property

SURVEY NO.: M:15-87 (PACS D2.33)

ADDRESS: 15700 Santini Road, Burtonsville, Montgomery County

9. Major Bibliographical References (Continued)

- Boyd, T.H.S. The History of Montgomery County, Maryland, From its Earliest Settlement in 1650 to 1879. 1879. Reprint. Baltimore: Regional Publishing Co., 1968.
- Coleman, Margaret Marshall, and Anne Dennis Lewis. Montgomery County: A Pictorial History. Norfolk: Donning Co., 1984.
- Cook, William G. Montpelier & the Snowden Family. Privately Printed, 1976.
- Daniels, Lee A. "Burtonsville: A town of the past trapped between the future." Washington Post. no date.
- Dixon-Williams, Gail. "Originally Burtons, this suburb has come a long way from 1800's." Burtonsville Gazette 14 Sept. 1994: A-4.
- Geraci, Ron, Vicki Walker, and Linda Donnary. Old Building Survey of the Burtonsville Area. Burtonsville, Maryland: Burtonsville Bicentennial Committee, 1976.
- Lovans, Alan. Styles and Types of North American Architecture. New York: Harper Collins, 1992.
- Hiebert, Ray Eldon, and Richard K. MacMaster. A Grateful Remembrance: The Story of Montgomery County, Maryland. Rockville, Maryland: Montgomery County Government and the Montgomery County Historical Society, 1976.
- Hopkins, G.M. Atlas of 15 Miles Around Washington including the County of Montgomery, Maryland. Philadelphia, 1879. Reprint.
- Land Records of Montgomery County, Maryland.
- Lord, Elizabeth M. Burtonsville Heritage: Genealogically Speaking. Burtonsville, Maryland: Burtonsville Bicentennial Committee, 1976.
- Martenet, Simon J. Martenet and Bond's Map of Montgomery County, Maryland. Baltimore, Maryland: Simon J. Martenet, 1865. Reprint.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM


RESOURCE NAME: Josiah Beall Property

SRVEY NO.: M:15-87 (PACS D2.33)

ADDRESS: 15700 Santini Road, Burtonsville, Montgomery County

10. Geographical Data (Continued)

Resource Sketch Map



CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Josiah Beall Property

SURVEY NO.: M:15-87 (PACS D2.33)

ADDRESS: 15700 Santini Road, Burtonsville, Montgomery County

Maryland Comprehensive Historic Preservation Plan Data Sheet

Historic Context:

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization: Piedmont

Chronological/Developmental Period Theme (s):

11. Industrial/Urban Dominance A.D. 1870-1930

Prehistoric/Historic Period Theme(s):

2. Architecture

RESOURCE TYPE:

Category (see Section 3 of survey form):

Building

Historic Environment (urban, suburban, village, or rural):

Rural

Historic Function(s) and Use(s):

Dwelling


Known Design Source (write none if unknown):

None

Preparer:
P.A.C. Spero & Company
October 1996

Inter County Connector Project
Mid-County Alternative
Quad Beltsville
Survey No. M:15-87 PACS# D2.33
Josiah Beall House

Josiah Beall House
MHT# M:15-87





111-75-87

Josiah Bealle Property

1. 1. 1.

1. 1.

1. 1.

1. 1. 1.

1. 1. 6

F. 1. 1.



175-81

Joseph Bealle Property

175-81
175-81

175-81
175-81

North

6



M-15-37

Loisak Beale Property

1000

1000

1000

1000

1000

1000

1000

1000

1000

7-2-6



M 15-87

Josiah Bealle Property

1857
1858
1859
1860
1861
1862
1863
1864
1865
1866
1867
1868
1869
1870
1871
1872
1873
1874
1875
1876
1877
1878
1879
1880
1881
1882
1883
1884
1885
1886
1887
1888
1889
1890
1891
1892
1893
1894
1895
1896
1897
1898
1899
1900
1901
1902
1903
1904
1905
1906
1907
1908
1909
1910
1911
1912
1913
1914
1915
1916
1917
1918
1919
1920
1921
1922
1923
1924
1925
1926
1927
1928
1929
1930
1931
1932
1933
1934
1935
1936
1937
1938
1939
1940
1941
1942
1943
1944
1945
1946
1947
1948
1949
1950
1951
1952
1953
1954
1955
1956
1957
1958
1959
1960
1961
1962
1963
1964
1965
1966
1967
1968
1969
1970
1971
1972
1973
1974
1975
1976
1977
1978
1979
1980
1981
1982
1983
1984
1985
1986
1987
1988
1989
1990
1991
1992
1993
1994
1995
1996
1997
1998
1999
2000
2001
2002
2003
2004
2005
2006
2007
2008
2009
2010
2011
2012
2013
2014
2015
2016
2017
2018
2019
2020
2021
2022
2023
2024
2025
2026
2027
2028
2029
2030



A. 15-87

Lost M. ...

...

...

...

...

...

...



M. 15-87

Joshua Beall Property