

Maryland Historical Trust
Maryland Inventory of Historic Properties Form
Intercounty Connector Project

DOE yes no**1. Name:** (indicate preferred name)

historic Calvin Bready Property

and/or common Sherwin Property

2. Location:street & number 16237 Batchellor's Forest Road not for publicationcity, town Olney vicinity of congressional district

state Maryland county Montgomery

3. Classification:

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> education	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> other:
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military	<input type="checkbox"/> other:
			<input type="checkbox"/> transportation	

4. Owner of Property: (give names and mailing addressed of all owners)

name Robert W. and Miriam F. Sherwin

street & number 16237 Batchellor's Forest Road telephone no.:

city, town Olney state and zip code Maryland 20823
20832**5. Location of Legal Description**

Land Records Office of Montgomery County liber 2059

street & number Montgomery County Judicial Center folio 138

city, town Rockville state MD

6. Representation in Existing Historical Surveys

title

date federal state county local

depository for survey records

city, town state

7. Description

Survey No. M:23-131 (PACS D6.22)

Condition		Check one	Check one	
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Resource Count: 3

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Calvin Bready Property is a 2½-story, 4-bay Colonial Revival-style house with Tudor influenced elements on the south side of Batchellor's Forrest Road in Olney, Montgomery County. Constructed circa 1930, the building originally consisted of three symmetrical bays, including three dormers, with a central entryway. A fourth bay was added to the east side of the house consisting of a partially enclosed first floor and an identical dormer on the second floor. Another addition was constructed at the southwest corner of the house and wraps-around onto both the west and south elevations.

The structure has a steeply pitched side-gable roof with asphalt shingles and four gable dormers with 6/6 double-hung windows. The house has two brick chimneys. The first is a central chimney located near the east end of the house, originally an exterior end chimney before the east addition, while the second chimney is an exterior chimney located on the west gable end. The structure is of wood frame construction with wood and brick siding, and it has a brick foundation. The windows are double-hung wood sash. The house has a deck on the west elevation. The deck has an open lattice railing with wood steps lead up to the deck on the north and south sides.

The first story entrance is recessed and asymmetrically placed on the north, or front, elevation. The entrance has a wood panelled door and an storm door with a semi-circular light. The entrance has a transom light and simple square engaged columns. The fenestration pattern is asymmetrical, with two 8/8 double-hung windows and two pairs of 8-light casement windows on the first story. The second story has four gable dormers with 6/6 double-hung windows. The western three bays are covered in brick, while the east bay is sheathed in wood siding.

The west elevation has a wood deck with an open lattice railing and a large exterior brick chimney. The fenestration pattern is asymmetrical, with one 6/6, double-hung window and a one-story projecting bay on the first story. The metal-covered hipped roof, three-sided bay is located at the northwest corner of the facade. It has two pairs of casement windows with 8 lights each and an entrance. The entrance has a wood door with 12 fixed lights and a storm door. The second story has two 6-light casement windows, and there is a triangular vent on either side of the chimney near the roof peak.

The west elevation of the addition at the southwest corner consists of the gable end of the dual-pitched roof. Located in the gable end is a wood door with 4 fixed lights. The grade slopes down from the road toward the rear of the property, allowing for a fully-exposed basement on the south elevation. The south elevation of the addition has a pair of 6-light casement windows on the basement level and two pairs of 6-light casement windows on the first floor. On the east facade of this addition, there is a wood door with 9 fixed-lights and a shed roof hood on the basement level, and two 6-light windows on the first floor.

The original section of the south, or rear, elevation has a symmetrical fenestration pattern. This section consists of three vertically aligned bays, all of which are 6/6 double-hung windows. The basement level has a pair of windows flanked by single windows. The first floor has two pairs of windows and a triple window, while the second floor has three gable dormers, each containing a single window.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Calvin Bready Property

SURVEY NO.: M:23-131 (PACS D6.22)

ADDRESS: 16237 Batchellor's Forest Road, Olney, Montgomery County

7. Description (Continued)

The south elevation of the fourth bay, or east addition, projects out from the plane of the rear elevation. The basement level is open, while the first floor consists of a screened porch. The porch has simple, decorative, engaged, square columns. A large shed roof dormer with a pair of 6/6 double-hung windows is located on the second floor.

The north elevation has a partially exposed basement level. The fenestration pattern is asymmetrical with the north side of the enclosed screened porch and five 8-light casement windows on the first story. The second story has one 6/6 double-hung window and a set of doors centered in the gable end. This opening has french doors with 16 lights and a wood screen door. The second floor opening does not have a deck or balcony and is not accessible from the ground, due to a lack of steps.

There are two outbuildings associated with this property. The first outbuilding is a garage with a front-gable roof. The exterior walls are covered with wood siding. Constructed circa 1930, it is of wood frame construction. The structure is located northeast of the house.

The second outbuilding is a studio with a side gable roof. The structure is located south of the garage and southeast of the house. It is accessed by a small wood footbridge which spans a creek behind the house.

The property is located on the south side of Batchellor's Forest Road, with residential property to the north. There is a park to the northwest; and the Norbeck Memorial Park and the Judea Memorial Gardens are located to the southwest. There is open land to the east. The property's setting is rural. The house sits on a large lot facing north onto Batchellor's Forest Road. The ground slopes steeply south away from the road toward a small creek which flows behind the house, exposing the basement level on the south, or rear, elevation.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Calvin Bready Property

SURVEY NO.: M:23-131 (PACS D6.22)

ADDRESS: 16237 Batchellor's Forest Road, Olney, Montgomery County

8. Significance (Continued)

Colonial Revival houses are usually strictly rectangular in plan with few projections, and have symmetrical facades. They range from one to three stories with hipped, side-gable, cross-gable, or gambrel roofs. Clapboard is the most popular sheathing material, although brick is not uncommon. After World War II, colonial homes frequently featured a brick-sided first story with an overhanging wood-sided second story. In more elaborate homes, a hipped roof is often topped with a flat deck, with a surrounding railing and sometimes a cupola. Pedimented doorways and fanlights are common. Some pediments evolved into porticos with slender columns. The typical form of the windows is rectangular with double-hung sash. Palladian windows are common on more sophisticated dwellings. The addition of side porches, terraces and sunrooms are modern features common to Colonial Revivals homes (McAlester 1984, 321-6).

NATIONAL REGISTER EVALUATION:

The Calvin Bready Property, constructed circa 1930, is not eligible for the National Register of Historic Places. The property does not meet Criterion A or B, as it has no known association with historically significant persons or events. It is not eligible under Criterion C, as the architectural integrity of the structure has been compromised through the substantial enlargement of the building from two additions. In addition, the building is an undistinguished example of a common architectural style. Finally the property has no known potential to yield important information, and therefore, does not meet Criterion D.

MARYLAND HISTORICAL TRUST

Eligibility recommended _____ Eligibility Not Recommended X

Comments _____

Reviewer, OPS: Andrew Lewis Date: 01/03/02
Reviewer, NR Program: [Signature] Date: 3/4/02



9. Major Bibliographical References Survey No.: M:23-131 (PACSD6.22)

See Continuation Sheet

10. Geographical Data

Acreage of nominated property _____
Quadrangle name Kensington

Quadrangle scale 1:24,000

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Caroline Hall/Tim Tamburrino

organization P.A.C. Spero & Company

date October 1996

street & number 40 W. Chesapeake Ave. Suite 412

telephone (410) 296-1635

city or town Baltimore

state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCP/DHCD
100 Community Place
Crownsville, MD 21032-2023
(410) 514-7600

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Calvin Bready Property

SURVEY NO.: M:23-131 (PACS D6.22)

ADDRESS: 16237 Batchellor's Forest Road, Olney, Montgomery County

9. Major Bibliographical References (Continued)

- Boyd, T.H.S. The History of Montgomery County, Maryland, From its Earliest Settlement in 1650 to 1879. Baltimore: Regional Publishing Company, 1968.
- Brugger, Robert A. Maryland, A Middle Temperament 1634-1980. Baltimore and London: Johns Hopkins University Press, 1988.
- Coleman, Margaret Marshall. Montgomery County: A Pictorial History. Norfolk and Virginia Beach: The Donning Company Publishers, 1984, rev. 1990.
- Daniels, Lee A. "Burtonsville: A town of the past trapped between the future." Washington Post. no date.
- Dixon-Williams, Gail. "Originally Burtons, this suburb has come a long way from 1800's." Burtonsville Gazette, 14 September 1994: A-4.
- Farquhar, Roger Brooke. Old Homes and History of Montgomery County, Maryland. Washington: Judd and Detweiller, Inc., 1962.
- Praci, Ron, Vicki Walker, and Linda Donnary. Old Building Survey of the Burtonsville Area. Burtonsville, Maryland: Burtonsville Bicentennial Committee, 1976.
- Hiebert, Ray Eldon, and Richard K. MacMaster. A Grateful Remembrance: the Story of Montgomery County, Maryland. Rockville, Maryland: Montgomery County Government and the Montgomery County Historical Society, 1976.
- Hopkins, G.M. Atlas of 15 Miles Around Washington including County of Montgomery, Maryland. Philadelphia: G.M. Hopkins, 1879; reprint, Rockville, Maryland: Montgomery County Historical Society, 1975.
- Land Records of Montgomery County, Maryland.
- Martenet, Simon J. Martenet and Bond's Map of Montgomery County, Maryland. Baltimore, Maryland: Simon J. Martenet, 1865; reprint, Rockville, Maryland: Montgomery County Historical Society.
- Tindall, George Brown. America: A Narrative History. 2 vols. New York: W.W. Norton & Company, Inc., 1984.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM


RESOURCE NAME: Calvin Bready Property

SURVEY NO.: M:23-131 (PACS D6.22)

ADDRESS: 16237 Batchellor's Forest Road, Olney, Montgomery County

10. Geographical Data (Continued)

Research Sketch Map:



CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Calvin Bready Property

SURVEY NO.: M:23-131 (PACS D6.22)

ADDRESS: 16237 Batchellor's Forest Road, Olney, Montgomery County

Maryland Comprehensive Historic Preservation Plan Data Sheet

Historic Context:

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization: Piedmont

Chronological/Developmental Period Theme (s):

12. Modern Period A.D. 1930 - Present

Prehistoric/Historic Period Theme(s):

2. Architecture

RESOURCE TYPE:

Category (see Section 3 of survey form):

Building

Historic Environment (urban, suburban, village, or rural):

Suburban

Historic Function(s) and Use(s):

Dwelling

Known Design Source (write none if unknown):

None

Preparer:

P.A.C. Spero & Company

October 1996



1. N-23-131

2. Calvin Bready Property

3. Montgomery, Maryland

4. Ao Canton

5. Feb. 1996

6. V.A.C. Special Co. 40 W. Chesapeake #412
Towson, MD 21204

7. 15235 Brite Iris Forest Rd. North
New York

8. 15235



- 1 N:23-151
- 2 Calvin Bready Property
- 3 Montgomery County, Maryland
- 4 Location
- 5 Feb. 1996
- 6 P.A.C. Spire & Co. 40W. Chesapeake Ave
Baltimore MD 21204 #4112
- 7) 16³⁷7 Catchesell Forest Rd.
West Side
- 8



- 1 M: 23-171
- 2 Calla's Body Property
- 3 Montgomery County, Maryland
- 4 A. Cowden
- 5 Feb 1996
- 6 P.A.C. 2 per Co. 10 w. Chesapeake Ave.
Towson Md. 21204 #412
- 7 1634 Batchellors' Crest Rd
Farmingdale
- 3 3 6



- 1 M: 23-131
- 2 Calvin Bready Property
- 3 Montgomery County, Maryland
- 4 A. Cowden
- 5 Feb. 1996
- 6 P.A.C. Sperry Co. 40 W. Chesapeake Ave #412
Towson MD 21204
- 7 16237 Batchellors Forest Rd. E. Fairdale

8 4300



- 1 M-23-131
- 2 Calvin Brady Property
- 3 Montgomery County, Maryland
- 4 A. Cowden
- 5 Feb. 1996
- 6 P.A.C. Spence & Co. 40 W. Chesapeake Ave
Yowson MD 21204 #1112
- 7) 16257 Batchellor Foulst Rd
Studios
- 8) 5 of 6



- 1 M: 23-131
- 2 Calvin Meady Property
- 3 Montgomery County, Maryland
- 4 A. Cowden
- 5 Feb 1996
- 6 P.A.C. Spice & Co. 410 W. Chesapeake Ave.
Towson MD 21204 #4110
- 7 16237 Batchellors Forest Rd
Garage
- 8 6 of 6