

Memo to file

December 30, 2003

From: Peter E. Kurtze
Administrator, Evaluation and Registration

Re: M: 28-56
Colesville United Methodist Church Parsonage

The property documented in the following MIHP form has not been formally evaluated for eligibility for listing in the National Register of Historic Places. The comments in the text are those of the preparer of the documentation. The State Historic Preservation Officer has neither concurred nor disagreed with those comments.

CAPSULE SUMMARY SHEET

Survey No.: M:28-56 (PACS 3.12) Construction Date: Circa 1950

Name: Colesville United Methodist Church Parsonage

Location: 50 Randolph Road, Colesville vicinity, Montgomery County

Private/Private Residence and Religious/Occupied/Good/Restricted

Description:

The Colesville United Methodist Church Parsonage is a 2-story, 3-bay Colonial Revival dwelling located on the south side of Randolph Road in the Colesville vicinity of Montgomery County. Constructed circa 1950, the building has a screened porch on the east and retains its original form. The Colesville United Methodist Church sanctuary and education building are located to the southwest.

Significance:

The Colesville United Methodist Church was originally called Andrew Chapel Methodist Church South. This church was organized in 1866 and dedicated in 1869. The one-room frame building originally stood on the north side Randolph Road. This building was demolished in 1938 and replaced with a larger brick building. In 1948, the Andrew Chapel Church, also known as Colesville Methodist Church, bought 0.44 hectares (1 acre) on the south side of Randolph Road from the heirs of George W. Acorn. The parsonage was constructed soon after and has since been used to house ministers, Sunday School classes and visiting scholars. In 1959, Colesville Methodist Church constructed the present sanctuary on the south side of Randolph Road. The education building was added in 1964, at which time the brick church on the north side of Randolph Road was demolished. In 1968, the name of the church was officially changed to Colesville United Methodist Church (Carter 1996, passim).

Maryland Historical Trust
Maryland Inventory of Historic Properties Form
Montgomery-Prince George's Short-term Congestion Relief

DOE ___yes ___no

1. Name: (indicate preferred name)

historic Colesville United Methodist Church Parsonage

and/or common same

2. Location:

street & number 50 Randolph Road ___ not for publication

city, town Colesville vicinity of congressional district

state Maryland county Montgomery

3. Classification:

Category	Ownership	Status	Present Use	
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> education	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment	<input checked="" type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial	<input type="checkbox"/> other:
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military	
			<input type="checkbox"/> transportation	

4. Owner of Property: (give names and mailing addresses of all owners)

name Colesville United Methodist Church

street & number 52 Randolph Road

telephone no.:

city, town Silver Spring

state and zip code MD 20904

5. Location of Legal Description

Land Records Office of Montgomery County

liber 1162

street & number 50 Maryland Avenue

folio 384

city, town Rockville

state MD

6. Representation in Existing Historical Surveys

title

date ___ federal ___ state ___ county ___ local

depository for survey records

city, town

state

7. Description

Survey No. M:28-56 (PACS 3.12)

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input checked="" type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input type="checkbox"/> altered	<input type="checkbox"/> moved	date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Contributing Resource Count: 1

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Colesville United Methodist Church Parsonage is a 2-story, 3-bay Colonial Revival dwelling located on the south side of Randolph Road in the Colesville vicinity of Montgomery County. Constructed circa 1950, the building has a screened porch on the east and retains its original form. The Colesville United Methodist Church sanctuary and education building are located to the southwest.

The 2-pile Parsonage has a brick foundation and brick exterior walls. The side-gable roof is covered in asphalt shingles and has a plain cornice and bargeboards. An exterior brick chimney is located in the east gable end. The 6/6 double-hung windows have brick jack arches and sills.

On the north, or front elevation, entry is located in the center bay. The paneled door has a wood surround with fluted pilasters and a broken pediment. On each side of the door are 6/6, double-hung windows. Identical windows fill each bay of the second story. The windows on this elevation have louvered shutters.

On the east elevation, a screened porch covers the southern two-thirds of the first story. The porch has a brick foundation, simple wood posts and a gable roof faced with wood weatherboard. Behind the porch is an entry to the house. A window is located north of the porch. The second story has two symmetrically arranged windows. Two 6-light, fixed sash windows are located in the gable.

On the south elevation, retaining walls allow the east end of the basement to be exposed, revealing a garage bay. A short driveway leads to the garage. A window is located directly above the garage on the first story. Paired windows are located west of this window. The west end of the first story has a half-glass door flanked by two windows. Three windows are symmetrically arranged on the second story.

On the west elevation, the first story has three asymmetrically arranged windows. The center window has been filled with brick laid in a herringbone pattern. The second story has two symmetrically arranged windows. A single window is located in the gable.

The house includes several elements of the Colonial Revival style, including symmetry, a side-gable roof, multi-pane windows with shutters and classical ornamentation around the entry. The screened porch is an addition, and one window on the west elevation has been filled. The property is otherwise unaltered.

The Colesville United Methodist Parsonage is located on the south side of Randolph Road and occupies one of several parcels of land owned by Colesville United Methodist Church. The parsonage stands on a landscaped lot and is accessed by a driveway to the east. The church sanctuary, constructed in 1959, and the education building, constructed in 1964, are located on adjacent parcels southwest of the parsonage. The Colesville Cemetery, formerly owned by the church, is located directly across Randolph Road. The property is located in a suburban residential area west of Colesville crossroads and experiences a high volume of traffic.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Colesville United Methodist Church Parsonage

SURVEY NO.: M:28-56 (PACS 3.12)

ADDRESS: 50 Randolph Road, Colesville vicinity, Montgomery County

8. Significance (Continued)

Philadelphia Centennial. Stylistic details in Colonial Revival dwellings were drawn predominantly from Georgian and Federal styles; secondary influences included Dutch Colonial and English Postmedieval types. Late nineteenth century examples of Colonial Revival were often asymmetrical and exhibited a combination of Queen Anne features, such as turrets and wide porches, and Colonial features such as Palladian windows and Adamesque swags or urns. Examples built from 1915 to 1935 reflected colonial precedents more closely, while those built after World War II simplified the style, with details which only suggested rather than duplicated the original examples. Various sub-styles, such as the Dutch Colonial Revival, were popular during the early to mid-twentieth century.

Colonial Revival houses are usually strictly rectangular in plan with few projections and have symmetrical facades. They range from one to three stories with hipped, side-gable, cross-gable, or gambrel roofs. Clapboard is the most popular sheathing material, although brick is not uncommon. After World War II, colonial homes frequently featured a brick-sided first story with an overhanging wood-sided second story. In more elaborate homes, a hipped roof is often topped with a flat deck and balustrade or a cupola. Pedimented doorways and fanlights are common. Some pediments evolved into porticos with slender columns. The typical form of the windows is rectangular with double-hung sash. Palladian windows are common on more sophisticated dwellings. The addition of side porches, terraces and sunrooms are modern features common to Colonial Revival homes (McAlester 1984, 321-6).

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Colesville United Methodist Church Parsonage

SURVEY NO.: M:28-56 (PACS 3.12)

ADDRESS: 50 Randolph Road, Colesville vicinity, Montgomery County

8. Significance (Continued)

National Register Evaluation:

Constructed circa 1950, the Colesville United Methodist Church Parsonage Property is not eligible for the National Register of Historic Places. The property is not eligible under Criterion A, as research conducted indicates no association with any historic events or trends significant in the development of national, state, or local history. Historic research indicates that the property has no association with persons who have made specific contributions to history, and therefore, it does not meet Criterion B. It is not eligible under Criterion C, as better examples of this type exist within the project area. The Colonial Revival style of the mid-twentieth century is quite common within the project area, and this particular example is not outstanding. Aside from the ornamentation around the door, the property has little architectural detail. Other examples of the Colonial Revival style might feature detailed window surrounds, decorative cornices or ornamental brickwork such as water tables and belt courses. Also, the addition of the screened porch and the filling of one window have slightly lessened the integrity of the property. Finally, the structure has no known potential to yield important information, and therefore, is not eligible under Criterion D.

MARYLAND HISTORICAL TRUST

Eligibility recommended _____ Eligibility Not Recommended _____
Comments _____

Reviewer, OPS: _____ Date: _____
Reviewer, NR Program: _____ Date: _____

9. Major Bibliographical References Survey No. M:28-56 (PACS 3.12)

See Attached

10. Geographical Data

Acreage of nominated property _____
Quadrangle name Kensington, MD Quadrangle scale 1:24,000

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state code county code

state code county code

11. Form Prepared By

name/title Julie Darsie

organization P.A.C. Spero & Company

date May 1998

street & number 40 W. Chesapeake Avenue, Suite 412

telephone (410) 296-1635

city or town Baltimore

state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposed only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCP/DHCD
100 Community Place
Crownsville, MD 21032-2023
(410) 514-7600

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Colesville United Methodist Church Parsonage

SURVEY NO.: M:28-56 (PACS 3.12)

ADDRESS: 50 Randolph Road, Colesville vicinity, Montgomery County

9. Major Bibliographical References (Continued)

- Bayley, Ned D. 1986. A Brief History of Colesville. Vertical Files. P.A.C. Spero & Co.
- Boyd, T.H.S. 1968. The History of Montgomery County, Maryland, From its Earliest Settlement in 1650 to 1879. Baltimore: Regional Publishing Company.
- Brugger, Robert A. 1988. Maryland, A Middle Temperament 1634-1980. Baltimore and London: Johns Hopkins University Press.
- Carter, Eveleen H. 1996. Colesville United Methodist Church, A Brief History. Silver Spring, MD: Colesville United Methodist Church.
- Coleman, Margaret Marshall. 1984. Montgomery County: A Pictorial History. Rev. 1990. Norfolk and Virginia Beach: The Donning Company Publishers.
- Farquhar, Roger Brooke. 1962. Old Homes and History of Montgomery County, Maryland. Washington: Judd and Detweiler, Inc.
- Liebert, Ray Eldon, and Richard K. MacMaster. 1976. A Grateful Remembrance: the Story of Montgomery County, Maryland. Rockville, Maryland: Montgomery County Government and the Montgomery County Historical Society.
- Hopkins, G.M. [1879] 1975. Atlas of 15 Miles Around Washington including the County of Montgomery, Maryland. Reprint. Rockville, Maryland: Montgomery County Historical Society.
- Land Records of Montgomery County, Maryland.
- Martenet, Simon J. [1865] 1975. Martenet and Bond's Map of Montgomery County, Maryland. Reprint. Rockville, Maryland: Montgomery County Historical Society.
- McAlester, Virginia and Lee McAlester. 1984. A Field Guide to American Houses. New York: Alfred A. Knopf.
- Tindall, George Brown. 1984. America: A Narrative History. 2 vols. New York: W.W. Norton & Company, Inc.

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM


RESOURCE NAME: Colesville United Methodist Church Parsonage

SURVEY NO.: M:28-56 (PACS 3.12)

ADDRESS: 50 Randolph Road, Colesville vicinity, Montgomery County

10. Geographical Data (Continued)

Resource Sketch Map:



CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Colesville United Methodist Church Parsonage

SURVEY NO.: M:28-56 (PACS 3.12)

ADDRESS: 50 Randolph Road, Colesville vicinity, Montgomery County

Maryland Comprehensive Historic Preservation Plan Data Sheet

Historic Context:

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization:

Piedmont

Chronological/Developmental Period Theme (s):

Modern Period A.D. 1930-Present

Prehistoric/Historic Period Theme(s):

Architecture

Religion

RESOURCE TYPE:

Category (see Section 3 of survey form):

Building

Historic Environment (urban, suburban, village, or rural):

Suburban

Historic Function(s) and Use(s):

Private Residence


Religious

Known Design Source (write none if unknown):

None

Preparer
P.A.C. Spero & Company
May 1998

Montgomery-Prince George's Short-term
Congestion Relief
Town/County Colesville vicinity/Montgomery
Quad Kensington, MD
Survey No. M:28-56 (PACS 3.12)
Property Name Colesville UMC Parsonage





1 m. 28-56

2 Coleridge United Methodist Church Parsonage

3 Montgomery Co. Md

4 Julie Darsie

5 5/98

6 Md SHPS

7 Parsonage + Church

8 1 of 9

2025 RELEASE UNDER E.O. 14176



- 1 011-28-5b
- 2 Coltonville United Methodist Church Passage
- 3 Montgomery Co. Md
- 4 Julie Daisie
- 5 5/98
- 6 Md SHPO
- 7 N elevation.
- 8 2 of 9

DN RPH 1220 050



- 1 M 28-56
- 2 Coleridge United Methodist Church Presby
- 3 Montgomery Co Md
- 4 Julie Darsie
- 5 5/98
- 6 Md STPO
- 7 NE corner
- 8 3 of 9

2-50021 4442



1 M: 28-56

2 Colesville United Methodist Church Personage

3 Montgomery Co, Md

4 Julie Darsie

5 5198

6 Md SHPO

7 E elevation

8 4 of 9

0 2 1 2 2 1 2 2 5 0 7



- 1 M. 28-56
- 2 Colesville United Methodist Church - Parsonage
- 3 Montgomery Co, Md
- 4 Julie Darske
- 5 5/98
- 6 Md SHPC
- 7 SE corner
- 8 5 of 9

2014-11-12 12:00 PM



1 M. 28. 56

2 Colesville United Methodist Church Parsonage

3 Montgomery Co, Md

4 Inlu Darste

5 198

6 Md SHPU

7 s elevation

8 6 57 9



1 M-28-56

2 Colesville United Methodist Church Parsonage.

3 Montgomery Co. Md

4 Julie Darsie

5 5/98

6 Md SHPO

7 SW corner

8 708 9

2008 JUN 12 01 02



WORSHIP
9:30 AM & 11:00 AM
CHURCH SCHOOL
ALL AGES 9:45 AM
187-1944

- 1 M: 28-56
- 2 Colesville United Methodist Church Parsonage
- 3 Montgomery Co, Md
- 4 Julie Barbee
- 5 5/78
- 6 Md SHPO
- 7 W elevation
- 8 P of 9

LE
T CHURCH

1 & 11:00
OL 9:45
OME!
041
UMC.ORG

WORSHIP

1 M:28-56

9

2 Colesville United Methodist Church Passage

3 Montgomery Co, Md

4 Julie Davis

5 5198

6 Md SHPO

7 NW corner

8 9 of 9

2500271 N.M.D.