

United States Department of the Interior
National Park Service

National Register of Historic Places
Registration Form

This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in *How to Complete the National Register of Historic Places Registration Form* (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

1. Name of Property

historic name QUINDOCQUA UNITED METHODIST CHURCH

other names/site number Quindocqua Methodist Episcopal Church

2. Location

street & number Intersection of Quindocqua, Whittington & L.Q. Powell Rds. not for publication N/A

city or town Marion vicinity

state Maryland code MD county Somerset code 039 zip code 21838

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended, I hereby certify that this nomination request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property meets does not meet the National Register criteria. I recommend that this property be considered significant nationally statewide locally. (See continuation sheet for additional comments.)

[Signature] 2-296 STATE HISTORIC PRESERVATION OFFICER
Signature of certifying official/Title Date

State of Federal agency and bureau _____

In my opinion, the property meets does not meet the National Register criteria. (See continuation sheet for additional comments.)

Signature of certifying official/Title Date

State or Federal agency and bureau _____

4. National Park Service Certification

I hereby certify that the property is:

<input type="checkbox"/> entered in the National Register. <input type="checkbox"/> See continuation sheet. <input type="checkbox"/> determined eligible for the National Register <input type="checkbox"/> See continuation sheet. <input type="checkbox"/> determined not eligible for the National Register. <input type="checkbox"/> removed from the National Register. <input type="checkbox"/> other, (explain:) _____ _____ _____	Signature of the Keeper _____ _____ _____ _____ _____	Date of Action _____ _____ _____ _____ _____
---	--	---

Name of Property

5. Classification

Ownership of Property

(Check as many boxes as apply)

- private, public-local, public-State, public-Federal

Category of Property

(Check only one box)

- building(s), district, site, structure, object

Number of Resources within Property

(Do not include previously listed resources in the count.)

Table with columns: Contributing, Noncontributing, buildings, sites, structures, objects, Total

Name of related multiple property listing

(Enter "N/A" if property is not part of a multiple property listing.)

Number of contributing resources previously listed in the National Register

HISTORIC RESOURCES OF SOMERSET COUNTY, MARYLAND

6. Function or Use

Historic Functions

(Enter categories from instructions)

RELIGION/Religious facility

Current Functions

(Enter categories from instructions)

RELIGION/Religious facility

7. Description

Architectural Classification

(Enter categories from instructions)

LATE 19TH AND 20TH CENTURY

REVIVALS/Late Gothic Revival

Materials

(Enter categories from instructions)

foundation Brick

walls Vinyl

roof Asphalt

other

Narrative Description

(Describe the historic and current condition of the property on one or more continuation sheets.)

United States Department of the Interior
National Park Service

S-123

National Register of Historic Places
Continuation SheetQUINDOCQUA UNITED METHODIST CHURCH
Somerset County
MarylandSection number 7 Page 1

DESCRIPTION SUMMARY:

Quindocqua United Methodist Church was erected in 1913 near Tull's Corner in Somerset County, Maryland. The single-story, roughly cruciform frame building rests on a raised foundation of common bond brick. It is sheathed with vinyl siding over narrow weatherboards, and the steeply pitched gable roofs are covered with asphalt shingles. The three principal gabled elevations of the church, facing south, east and west, are marked by pointed arch colored glass windows. The southwest corner is marked by a three-story tower topped by a pyramidal roof with kicked eaves. The interior of the church is distinguished by a well-preserved pressed metal vaulted ceiling, and the pulpit and choir are recessed behind Gothic arched openings. Also on the property is a single-story, concrete block church hall.

See Continuation Sheet No. 2

United States Department of the Interior
National Park Service

S-123

National Register of Historic Places
Continuation Sheet

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 7 Page 2

GENERAL DESCRIPTION:

Quindocqua United Methodist Church, formerly Quindocqua Methodist Episcopal Church, stands on the northwest corner of the intersection of three roads; L. Q. Powell Road, Whittington Road and Quindocqua Road in the vicinity of Tull's Corner, Somerset County, Maryland. The roughly cruciform church faces south with the principal gable roof oriented on an east/west axis.

Built in 1913, the expansive single-story frame structure is supported by a vented common bond brick foundation, and it is sheathed with vinyl siding over narrow weatherboard siding. The steeply pitched roof slopes are covered with asphalt shingles. A three-story tower rises in the southwest corner, containing the entrance on the ground floor and a belfry in the upper stage. Also on the property is a single-story concrete block church hall which does not contribute to the significance of the resource.

The building has a cruciform plan, with intersecting gable roofs with extended eaves and decorative brackets. A three-story tower marks the southwestern re-entrant corner.

The principal elevation faces south. Centered in the gable-front wall is a tripartite colored glass window with three diamond panes above three lancet windows, which together form a large pointed arch. An interior brick stove chimney rises through the east slope of the roof. A marble cornerstone in the southwest corner of the brick foundation is inscribed with the dates 1829, 1847, and 1913.

The south face of the tower is marked by a Gothic-arched double-door opening, now partially obscured by a metal awning. The second level of the tower is a plain weatherboard wall, while the third level is an open belfry. Each of the four open sides of the belfry has a turned post balustrade and corner brackets. The pyramidal roof of the tower is flared at its base, and it is topped by a three-dimensional fleur-de-lis metal cap.

The east gable features a tripartite colored glass window similar to that of the south facade, flanked by single lancet windows. Each of the shorter side walls of the east arm of the

See Continuation Sheet No. 3

United States Department of the Interior
National Park Service

**National Register of Historic Places
Continuation Sheet**

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 7 Page 3

cruciform building has a single lancet window. A brick stove chimney rises through the north slope of the roof.

The fenestration of the west gable is identical to that of the east. Another brick stove chimney rises through the south slope of the roof.

The north wall of the rear arm of the cruciform plan is unfenestrated, except for a pair of small colored glass windows offset to the west lighting the choir loft. The west wall has an identical pair of windows.

The interior retains an exceptionally high level of integrity, remaining virtually unaltered since construction in 1913. The double front doors open into a small vestibule, from which a pair of oak grained double doors open into the sanctuary, and an oak grained door on the right opens into a Sunday school room.

The sanctuary is a large rectangular space with a slightly ramped floor and a high three-sided vaulted ceiling of decorative pressed metal. The altar and choir are recessed on the north wall behind two Gothic arched openings. The sanctuary walls are plastered above beaded board wainscoting. The pressed metal ceiling remains in excellent condition, featuring a coffered grid pattern with classical and foliate decorations. A cove cornice of wreaths and garlands extends across the front and back walls. The sanctuary is furnished with curved pews arranged in a semi-circular plan oriented to the north wall. A slightly curved altar rail has turned balusters anchored by square posts. Early twentieth century chandeliers and light fixtures remain in place. In the rear (south) sanctuary wall is a series of three triple-door openings with oak-grained doors topped by three-light frosted glass transoms; these doors were opened when there was a need for additional seating.

The church retains a high degree of integrity to the period of significance. The interior remains virtually intact. The only exterior alteration is the application of vinyl siding, carried out in 1988. The application of siding did not disturb character-defining features. The profile of the siding corresponds to that of the original weatherboards, which are preserved beneath it.

See Continuation Sheet No. 4

United States Department of the Interior
National Park Service

**National Register of Historic Places
Continuation Sheet**

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 7 Page 4

Trim details were not disturbed in the course of applying the siding.

Standing north of the church is a single-story, five-bay, rectangular concrete block church hall covered with a medium pitched asphalt shingle gable roof. Metal casement-type windows pierce each wall, and an interior brick stove chimney rises through the south roof slope. This mid-20th century building does not contribute to the significance of the resource.

QUINDOCOUA UNITED METHODIST CHURCH
Name of Property

Somerset County, Maryland
County and State

S-123

8. Statement of Significance

Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing.)

- A** Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B** Property is associated with the lives of persons significant in our past.
- C** Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D** Property has yielded, or is likely to yield, information important in prehistory or history.

Criteria Considerations

(Mark "x" in all the boxes that apply.)

Property is:

- A** owned by a religious institution or used for religious purposes.
- B** removed from its original location.
- C** a birthplace or grave.
- D** a cemetery.
- E** a reconstructed building, object, or structure.
- F** a commemorative property.
- G** less than 50 years of age or achieved significance within the past 50 years.

Areas of Significance

(Enter categories from instructions)

ARCHITECTURE

Period of Significance

1913

Significant Dates

1913

Significant Person

(Complete if Criterion B is marked above)

N/A

Cultural Affiliation

N/A

Architect/Builder

Unknown

Narrative Statement of Significance

(Explain the significance of the property on one or more continuation sheets.) **SEE CONTINUATION SHEET NO. 5**

9. Major Bibliographical References

Bibliography SEE CONTINUATION SHEET NO. 9

(Cite the books, articles, and other sources used in preparing this form on one or more continuation sheets.)

Previous documentation on file (NPS):

- preliminary determination of individual listing (36 CFR 67) has been requested
- previously listed in the National Register
- previously determined eligible by the National Register
- designated a National Historic Landmark
- recorded by Historic American Buildings Survey # _____
- recorded by Historic American Engineering Record # _____

Primary location of additional data:

- State Historic Preservation Office
- Other State agency
- Federal agency
- Local government
- University
- Other

Name of repository:

Somerset Co. Historical Trust, Inc.

United States Department of the Interior
National Park Service

**National Register of Historic Places
Continuation Sheet**

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 8 Page 5

SIGNIFICANCE SUMMARY:

Quindocqua United Methodist Church is one of thirteen rural white Methodist churches in Somerset County listed on the Maryland Inventory of Historic Properties. Six churches in this group have been listed in the National Register individually or as contributing resources in historic districts. Quindocqua Church is distinguished among the churches in this group by its high degree of integrity; it has undergone exceptionally few exterior or interior modifications since it was originally constructed. The sanctuary is an especially well preserved example of early twentieth century church design with its ramped floor, semi-circular seating, pressed metal ceiling, and period lighting fixtures. Due to the dwindling nature of the congregation and a general respect for the historic church by the remaining members, Quindocqua Church has not suffered modern alterations in the form of large additions or false ceilings experienced by other structures.

The Quindocqua United Methodist Church also reflects the change in taste for church design that occurred across the country during the late nineteenth century. Until the mid-nineteenth century most Methodist congregations worshipped in modest rectangular frame meetinghouse-like buildings. However, by the fourth quarter of the nineteenth century, the national Methodist leadership sponsored the dissemination of professionally prepared plans and specifications that could be ordered through the Board of Church Extension of the Methodist Episcopal Church. Although the exact plans for Quindocqua Church have not been identified, the cross-shaped plan, the ramped floor and semi-circular seating, and the pressed metal ceiling point to a professional source of design and guidance.

The 1913 Quindocqua Church represents a historical pattern of building replacement which characterized many congregations in the lower Eastern Shore region. The 1913 church, the third structure to house the congregation, was built in order to accommodate an enlarged membership which had grown along with the general population of southern Somerset County during the period from 1870 to 1910.

See Continuation Sheet No. 6

S-123

United States Department of the Interior
National Park Service

**National Register of Historic Places
Continuation Sheet**

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 8 Page 6

HISTORIC CONTEXT:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Eastern Shore

Chronological/Developmental Period(s):

Industrial/Urban Dominance - A.D. 1870-1930
Modern Period - A.D. 1930-Present

Prehistoric/Historic Period Theme(s):

Architecture/Landscape Architecture/Community Planning

Resource Type:

Category: Building

Historic Environment: Rural

Historic Function(s) and Use(s):

RELIGION/religious facility

Known Design Source: none

See Continuation Sheet No. 7

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 8 Page 7

HISTORIC CONTEXT:

The early history of Quindocqua Methodist Episcopal Church is shaded by incomplete records. The principal source for the early history of the congregation is the oral account of Leah Adams Chelton (1824-1918), a lifelong community resident, who repeated what her father had been told by his parents. Her account was recorded by Reverend Tilghman Smith in 1912.

Tradition holds that in the late 18th century area residents met in local homes, or attended Episcopal and Presbyterian services at Annemessex Chapel or the Rehobeth churches. The first Methodist congregation for southern Somerset County was established as Miles Meetinghouse, now known as St. Peter's United Methodist Church (S-289), established by 1782 near Hopewell. By the early nineteenth century the population around Tull's Corner had grown sufficiently to warrant a new congregation, independent of St. Peter's. The Quindocqua congregation therefore was organized about 1820, taking its name from that of the Pocomoke River Indian tribe which inhabited the area.

Leah Chelton stated that the initial church was a converted agricultural outbuilding, probably a blacksmith shop located on her parents' farm, and it was that structure in which she was married in 1844. The converted blacksmith shop was used until 1847 when a larger, gable-front, frame structure was erected on the present church site. The deed for the lot, executed on August 17, 1847, confirmed a transfer that had occurred a year earlier between Josiah Cottingham and trustees, Joshua Tull, Sr., Smith Lankford, George L. Holland, and Thomas Somers. Following the Civil War, the 1847 church was enlarged several times to accommodate a growing membership and to provide a Sunday School room.

In 1912, the congregation decided to replace the 65-year old frame church with a new structure to house an ever-increasing congregation. The 1847 church was deemed too small and in poor repair, so it was torn down to clear the site for the new building. An abnormally high tide destroyed the strawberry crop and a severe drought that summer led to a general crop failure for the year. Despite these difficulties, building plans progressed and the cornerstone was laid on September 23, 1913. Several carpenters

See Continuation Sheet No. 8

United States Department of the Interior
National Park Service

**National Register of Historic Places
Continuation Sheet**

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 8 Page 8

donated their work, including Harold Maddox, Samuel Maddox, Howard Hinman, Harold Taylor, James Dorsey, and Henry Evans. Completion and dedication of the church followed on June 14, 1914.

United States Department of the Interior
National Park Service

**National Register of Historic Places
Continuation Sheet**

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 9 Page 9

BIBLIOGRAPHY:

- Hallman, E.C. The Garden of Methodism. Peninsula Annual Conference of the Methodist Church, 1948.
- Maryland Inventory of Historic Properties, Maryland Historical Trust, Crownsville, Maryland.
- Somerset County Land Record, WP 2/367, 17 August 1847, Somerset County Courthouse, Princess Anne, Maryland.
- Touart, Paul B. Somerset: An Architectural History. Princess Anne and Annapolis: Somerset County Historical Trust, Inc. and the Maryland Historical Trust, 1990.
- Wilson, Woodrow T., Quindocqua, Maryland: Indian Country. Baltimore, Maryland: Gateway Press, Inc., 1980.

QUINDOCQUA UNITED METHODIST CHURCH, S-123
Name of Property

Some Point County, Maryland
County and State

10. Geographical Data

Acreeage of Property 82/100 acre

UTM References

(Place additional UTM references on a continuation sheet.)

1	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing
2	<input type="text"/>	<input type="text"/>	<input type="text"/>

3	<input type="text"/>	<input type="text"/>	<input type="text"/>
	Zone	Easting	Northing
4	<input type="text"/>	<input type="text"/>	<input type="text"/>

See continuation sheet

Verbal Boundary Description

(Describe the boundaries of the property on a continuation sheet.)

Boundary Justification

(Explain why the boundaries were selected on a continuation sheet.)

11. Form Prepared By

name/title Paul B. Touart, Architectural Historian

organization Private Consultant date 9/19/94

street & number P. O. Box 5 telephone 410-651-1094

city or town Westover state MD zip code 21871

Additional Documentation

Submit the following items with the completed form:

Continuation Sheets

Maps

A USGS map (7.5 or 15 minute series) indicating the property's location.

A Sketch map for historic districts and properties having large acreage or numerous resources.

Photographs

Representative black and white photographs of the property.

Additional items

(Check with the SHPO or FPO for any additional items)

Property Owner

(Complete this item at the request of SHPO or FPO.)

name Trustees of Quindocqua United Methodist Church
% Reverend Olivia Costango

street & number 216 Myrtle Street telephone 410-968-1098

city or town Crisfield state MD zip code 21817

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 et seq.).

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P.O. Box 37127, Washington, DC 20013-7127; and the Office of Management and Budget, Paperwork Reductions Projects (1024-0018), Washington, DC 20503.

United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 10 Page 10

BOUNDARY DESCRIPTION:

Boundaries are shown on the plat which accompanies this documentation, comprising Parcels A and B, with dimensions and bearings indicated.

BOUNDARY JUSTIFICATION:

The nominated property, 0.82 acre, comprises the entire property historically associated with the resource. Boundary lines coincide with current property boundaries. The boundary follows the course of the county roads on the south and east sides.


See Continuation Sheet No. 11

United States Department of the Interior
National Park Service

National Register of Historic Places
Continuation Sheet

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 10 Page 11





United States Department of the Interior
National Park Service

National Register of Historic Places Continuation Sheet

QUINDOCQUA UNITED METHODIST CHURCH
Somerset County
Maryland

Section number 10 Page 11





S-123

5-123
QUINDOCQUA
METHODIST CHURCH

SOMERSET CO.,
MD

18-434220-420770



CRISFIELD 8 MI.
MARION 1.6 MI.

Hudso

4211

2'30"

MARION 1.1 MI.

Paul Corner

BM. 8

S-123
QUINDOCQUA
METHODIST CHURCH

Liberia Ch

SOMERSET CO.,
MD

Calbourne

70 000
FEET

18-434220-420770

Quindocqua Ch

BM. 22

Conners Corner

MARUMSCO


Marumsc

4207


4206


22000






S-123
 Quindocqua Methodist Church
 Kingston, MD Quadrangle, 1972





S-123
 Quindocqua Methodist Church
 Kingston, MD Quadrangle, 1972





S-127

3-11-11 = 12

10-11-11 = 11

11-11-11

11-11-11

1 of 6



5-11-23

6-11-23

11-11-23


11-11-23

11-11-23

11-11-23

11-11-23











Quindocqua Methodist Church S-123
Near Tulls Corner, Somerset County
South Elevation
4/85, Photographer, Paul Touart
Neg./MD. Historical Trust



Quindocqua Methodist Church S-123
Near Tulls Corner, Somerset County
North Elevation
4/85, Photographer, Paul Touart
Neg./MD. Historical Trust



Quindocqua Methodist Church S-123
Near Tulls Corner, Somerset County
Southwest Elevation
4/85, Photographer, Paul Touart
Neg/Md. Historical Trust



Quindocqua Methodist Church S-123
Near Tulls Corner, Somerset County
Window Details
4/85, Photographer, Paul Touart
Neg./MD. Historical Trust



Quindocqua Methodist Church S-123
Near Tulls Corner, Somerset County
Bell Tower
4/85, Photographer, Paul Touart
Neg/Md. Historical Trust