

Easement

2

Form 10-300
(July 1969)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

STATE Maryland	
COUNTY Somerset	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

1. NAME

COMMON
Beverly

AND OR HISTORIC
Beverly

2. LOCATION

STREET AND NUMBER:
Route 13 (Perry Road) 300 9/10/90

CITY OR TOWN:
Princess Anne

STATE
Maryland

CODE
24

COUNTY:
Somerset

CODE

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object	<input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure <input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both	<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No

PRESENT USE (Check One or More as Appropriate)

<input type="checkbox"/> Agricultural	<input type="checkbox"/> Government	<input type="checkbox"/> Park	<input type="checkbox"/> Transportation	<input type="checkbox"/> Comments
<input checked="" type="checkbox"/> Commercial	<input type="checkbox"/> Industrial	<input checked="" type="checkbox"/> Private Residence	<input checked="" type="checkbox"/> Other (Specify)	
<input type="checkbox"/> Educational	<input type="checkbox"/> Military	<input type="checkbox"/> Religious	real estate	
<input type="checkbox"/> Entertainment	<input type="checkbox"/> Museum	<input type="checkbox"/> Scientific	office	

4. OWNER OF PROPERTY

OWNER'S NAME:
Francis Lake Hayman

STREET AND NUMBER:
Beverly

CITY OR TOWN:
Princess Anne

STATE:
Maryland

CODE
24

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.
Somerset County Courthouse

STREET AND NUMBER:
Main Street

CITY OR TOWN:
Princess Anne

STATE
Maryland

CODE
24

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:
Maryland Register of Historic Places

DATE OF SURVEY: 1969 Federal State County Local

DEPOSITORY FOR SURVEY RECORDS:
Maryland Historical Trust

STREET AND NUMBER:
2525 Riva Road

CITY OR TOWN:
Annapolis

STATE
Maryland

CODE
24

SEE INSTRUCTIONS

STATE: Maryland
COUNTY: Somerset
ENTRY NUMBER:
SITE:

FOR NPS USE ONLY

7. DESCRIPTION

CONDITION	(Check One)					
	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input type="checkbox"/> Altered	<input checked="" type="checkbox"/> Unaltered		<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site	

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE.

Beverly combines the traditional Georgian elements of symmetry, repetition and regularity, with a prominently placed Federal period three-planed projection off the eastern facade of the house. The house measures forty feet by sixty feet and is of brick, now (1972) painted white, and laid in Flemish bond. There are two-and-a-half stories, the first and second stories being divided by a belt course of rubbed brick. The house stands on an "English basement" with a watertable. Two regularly spaced chimneys rise through the interior of the house. Under the eaves of the hip-roof is a cornice with rectangular dentils and modillions.

The eastern facade of the house contains a three-sided central-bay projection which rises two-and-a-half-stories. Within this projection is the main doorway of the house. The door panels are simple and beneath the broken pediment there is a fanlight. The two narrower flanking planes of the projection at the first floor level contain identical arch-capped windows. The entrance bay is flanked on each side by two rectangular windows of twenty-eight panes, sixteen over twelve - four across, seven down. These windows with their flat lintels are repeated on the second floor.

The western facade is flat but has an uncovered porch with Chipendale balustrade similar to that of the eastern facade. The central doorway with fanlight and flanking arched windows of the eastern facade are repeated on the western facade. There are four evenly spaced sixteen over twelve paned windows on the western facade.

The northern and southern end elevations have three evenly spaced windows on each floor. There are two dormer windows on each of the eastern and western facades and one each on the northern and southern roof hips. There are shutters on all of the first floor windows although there are none on the second floor windows or the dormers.

The interior of the house was partially destroyed by fire in 1937 but was restored from plans drawn from the original house. The first floor is divided by a twelve foot wide central hall which extends the forty foot depth of the house. On the north side is the present dining room and staircase. On the south side of the hall are the living room and library. The second floor is a copy of the first with three bedrooms and a bath flanking the central hall.

The interior walls throughout are of plaster covered with canvas. The first floor ceilings are fourteen feet high and those of the second floor are thirteen and a half feet high. There are five fireplaces in the main section of the house. The interior woodwork, although not original, consists of cornices,

S E M I N S T R U C T I O N S

(See Continuation Sheet)

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- Pre-Columbian 16th Century 18th Century 20th Century
 15th Century 17th Century 19th Century

SPECIFIC DATE(S) (If Applicable and Known) 1785-1796

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|--|--|---|--|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Philosophy | <input type="checkbox"/> Other (Specify) _____ |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | <input type="checkbox"/> Science | _____ |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Sculpture | _____ |
| <input checked="" type="checkbox"/> Architecture | <input checked="" type="checkbox"/> Landscape Architecture | <input checked="" type="checkbox"/> Social/Humanitarian | _____ |
| <input type="checkbox"/> Art | <input type="checkbox"/> Literature | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Military | <input type="checkbox"/> Transportation | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Music | | |
| <input type="checkbox"/> Conservation | | | |

STATEMENT OF SIGNIFICANCE

Beverly represents the social status and wealth achieved by a successful eighteenth century planter and his ancestors. The house was built by Nehemiah King II between 1785 and 1796. King was the great-grandson of Robert King, one of the most affluent early landholders in Somerset County. Robert King is traditionally known as an Irish baronet who first appeared in Somerset County in the late seventeenth century from Northampton County, Virginia. From his original 300 acre tract, King's heirs acquired over 1,500 acres which were then known corporately as Kingsland. Beginning in 1857, the estate was subdivided. Beverly, a part of the original Kingsland, today entails eighteen acres.

Though little is known about Nehemiah King II, who received the land from Nehemiah King I, the family seems to have been both politically and commercially active. The Kings were Protestant sympathizers during the American Revolution and certain members of the family were elected to public office.

Robert King I held numerous political offices including that of His Lordship's Justice of the Peace, and membership in the Provincial Court of Justice. He also represented Somerset County in the pre-Revolutionary provincial government and served as a military and naval officer respectively for Somerset. His son, Robert King II, was one of Maryland's first representatives to the General Assembly.

Nehemiah King, the builder of Beverly, became a friend of Jerome Bonaparte, brother of Napoleon, through Jerome's marriage in 1803 to Betsy Patterson of Baltimore. Historians have included Beverly in a plot to rescue Napoleon from exile on St. Helena Island. Plans were made for the Emperor to be transported up the Chesapeake Bay and into the Manokin River where he was to arrive at Beverly through a tunnel leading under the house from the nearby creek! Napoleon died before the rescue was attempted.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Torrence, Clayton. Old Somerset on the Eastern Shore of Maryland. Baltimore Regional Publishing Company. 1966.

Scarborough, Catherine. Homes of the Cavaliers. Macmillan Company. New York. 1930.

Footner, Hulbert. Rivers of the Eastern Shore. Rinehart and Company, Inc. 1944.

(See Continuation Sheet)

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY				LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES								
CORNER	LATITUDE			LONGITUDE			LATITUDE		LONGITUDE			
	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds
NW	38	09	56	75	41	53	0			0		
NE	38	09	56	75	41	07						
SE	38	09	26	75	41	08						
SW	38	09	27	75	41	54						

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: 212.4 acres

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE

11. FORM PREPARED BY

NAME AND TITLE:
Louise H. Burnett

ORGANIZATION: **Maryland Historical Trust** DATE: **July 28, 1972**

STREET AND NUMBER:
2525 Riva Road

CITY OR TOWN: **Annapolis** STATE: **Maryland 21401** CODE: **24**

12. STATE LIAISON OFFICER CERTIFICATION

NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National State Local

Name Orlando Ridout IV

Title State Liaison Officer of Maryland

Date August 10, 1972

I hereby certify that this property is included in the National Register.

Chief, Office of Archeology and Historic Preservation

Date _____

ATTEST: _____

Keeper of The National Register

Date _____

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Maryland	
COUNTY	
Somerset	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

#7. DESCRIPTION continued

moldings, door stiles and frames, and mantelpieces. All of this interior work was hand carved in the Adamesque style, using risettes, basketweave, and organic designs.


Extending from the western facade is an earlier two-story dependency. Much of the material and floor plan are original, including the flooring, mantelpieces, and solid brick end. There are four rooms on the second floor and two on the first. This structure is connected to the main house by a kitchen wing and colonnade, both added in the twentieth century.

#9. MAJOR BIBLIOGRAPHICAL REFERENCES continued

Writers Project of the Works Projects Administration. Maryland: A guide to the Old Line State. Oxford Press. 1941. New York.

PRINCESS ANNE QUADRANGLE
USGS 7.5 minute map
scale: 1: 24 000
1942

TEWART NECK



BEVERLY

Kings Creek

Kings

	LAT.	LONG.
NW	38° 09' 56"	75° 41' 53"
NE	38° 09' 56"	75° 41' 07"
SE	38° 09' 26"	75° 41' 08"
SW	38° 09' 27"	75° 41' 54"

PENNSYLVANIA

U.S. ARMY
RESERVATION

Westover



42° 00' 00" 10 20 30

GREENVILLE TOWNSHIP (KINGSTON)

40'

SCALE 1:24000







Beverly

S-34

Near Princess Anne, Somerset County

East Elevation

8/84 Paul Touart

Neg/MD. Historical Trust



Beverly

S-340



Beverly-534

MARYLAND HISTORICAL TRUST
2525 RIVA ROAD
ANNAPOLIS, MARYLAND 21401

F.L. Hayman
1970



519.17 1/2 3/4

Edwinset Courney

3000 - S. 34

MARYLAND HISTORICAL TRUST
525 RIVA ROAD
ANNAPOLIS, MARYLAND 21401


1970



Beverly-S-34

MARYLAND HISTORICAL TRUST
2525 RIVA ROAD
ANNAPOLIS, MARYLAND 21401

F.L. Hayman
1968



Beverly-5-34

MARYLAND HISTORICAL TRUST
2525 RIVA ROAD
ANNAPOLIS, MARYLAND 21401

F.L. Hayman
1968



Beverly

S-34

619

David A. Gibb 1967



BEVERLY

S-37



BEVERLY

S-39



BEVERLY

5-34



BEVERLY

S-3A



Beverly

S-34

Near Princess Anne, Somerset County

Stair Hall

8/84 Paul Touart

Neg/MD. Historical Trust



Beverly

S-34

Princess Anne vic. Somerset Co.

Photograph of stair hall, c. 1915

Copied 7/87, Neg. Md Hist. Trust

Courtesy of Hodgson family



Beverly

S-34

Princess Anne vic. Somerset Co.

First floor hall, c. 1915

Copied 7/87, Neg. Md Hist Trust

Courtesy of Hodgson family



Beverly S-34
Princess Anne vic. Somerset Co.
Documentary photograph of hall
Copied 7/87, Neg. Md Hist. Trust
Courtesy of Hodgson family



S-34

Beverly

Near Princess Anne, Somerset County


2nd Floor Hall Door

8/84 Paul Touart

Neg/MD. Historical Trust



Beverly S-34
Princess Anne vic. Somerset Co.
First floor hall ceiling, c.1915
Copied 7/87, Neg. Md Hist Trust
Courtesy of Hodgson family



Beverly

S-34

Near Princess Anne, Somerset County

Parlor Mantel

8/84 Paul Touart

Neg/MD. Historical Trust



Beverly


S-34

Princess Anne vic. Somerset Co.

Photograph of parlor, c. 1915

Copied 7/87, Neg. Md. Hist. Trust

Courtesy of Hodgson family



Beverly

S-34

Near Princess Anne, Somerset County

Hall Arch Detail

8/84 Paul Touart

Neg/MD. Historical Trust



Beverly S-34
Princess Anne vic. Somerset Co.
Northeast elevation, c. ~~1815-25~~ 1960
Courtesy of Maryland Hist. Society