

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

STATE: Maryland
COUNTY: Somerset
FOR NPS USE ONLY
ENTRY DATE

(Type all entries - complete applicable sections)

1. NAME

COMMON:
Sudler's Conclusion

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER:
Hood Road, 1 mile northwest of intersection of Md. 361

CITY OR TOWN:
Manokin

CONGRESSIONAL DISTRICT:
First Congressional Dist.

STATE: Maryland CODE: 24 COUNTY: Somerset CODE: 039

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input type="checkbox"/> Site <input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure <input type="checkbox"/> Object	<input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both	Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered	<input type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress
PRESENT USE (Check One or More as Appropriate)			
<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input checked="" type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify)

4. OWNER OF PROPERTY

OWNER'S NAME:
Mr. & Mrs. Joseph Eberly

STREET AND NUMBER:

CITY OR TOWN:
Fairmont

STATE:
Maryland

CODE:
24

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:
Hall of Records

STREET AND NUMBER:
St. John's College Campus

CITY OR TOWN:
Annapolis

STATE:
Maryland

CODE:
24

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:
Maryland Register

DATE OF SURVEY: 1968

DEPOSITORY FOR SURVEY RECORDS:
Maryland Historical Trust

STREET AND NUMBER:
2525 Riva Road

CITY OR TOWN:
Annapolis

STATE:
Maryland

CODE:
24

SEE INSTRUCTIONS

STATE: Maryland

COUNTY: Somerset

FOR NPS USE ONLY

ENTRY NUMBER

DATE

7. DESCRIPTION

CONDITION	(Check One)					
	<input type="checkbox"/> Excellent	<input type="checkbox"/> Good	<input checked="" type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input type="checkbox"/> Altered	<input checked="" type="checkbox"/> Unaltered		<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site	

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

The initial stage of Sudler's Conclusion now constitutes the east wing of this two part house. Of a one and one half story height, having a single chimney enclosed within the east end wall, the house is of brick, Flemish bond, construction displaying a regular usage of glazed headers throughout. The original principle facade at the north elevation is three bays in length with a centrally positioned door flanked by a single window at each side. The former rear (south) facade was two bays in length with a centered door flanked by a single window at its east side. This door was filled in circa 1800 and a window installed flush to the west side of the former opening. At both front and rear roof slopes are two pedimented dormer windows, also installed circa 1800. At the east end elevation of this same block is a door positioned near the southeast corner. Near the northeast corner of this same elevation is a small window which has been bricked in. Both this window and the door, as well as a small attic level window (positioned close to the barge board of the north roof slope), constitute later installations. All original ground floor door and window openings are headed by segmental arches of header brick. At the east end elevation, at a line even with the front and rear eave cornices, is an indented two brick belt course with the bricks of both courses set on the diagonal. This same decorative treatment is seen on several other brick houses of this type and apparently was fairly popular with lower Eastern Shore builders of the first half of the eighteenth century.

Although renovated on the interior at an approximate date of circa 1800, Sudler's Conclusion, now undergoing a renovation by its present owners, displays several interesting features. Its plan is of the hall and parlor type with the hall being a rather narrow room extending the length of the north side. It has a tall but narrow fireplace opening at the east end, positioned close to the brick partition wall. This room is presently being renovated for use as a modern kitchen. The adjoining parlor is somewhat larger and has a more expansive fireplace opening, also the east wall, measuring approximately seven feet in length and six and one half feet in height. On each interior side wall is a small bake (warming) oven. The original brick hearth (now removed) protruded about four feet into the room flush with the floor level. Flanking the fireplace, on the right (south) side is a door opening into a small hall which leads outside. Flanking this is a small door which opens into a closet. The wall surfaces of this closet display evidence of its having formerly served as an enclosed stair. The top two treads (winders) are still in place and the bottom two treads (now removed), projected out into the room from the stair door.

While all interior wall surfaces are plastered there is (see cont. sheet 1)

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

S-56

STATE	
Maryland	
COUNTY	
Somerset	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Continuation Sheet)

(Number all entries)

7. DESCRIPTION

evidence that the fireplace wall had been originally sheathed with large fielded pine panels. The exposed ceiling joists of both this room and the hall display a very wide bead on their lower edges. The floor boards of this level are apparently original although they have been repaired and patched, especially in the fireplace and stair areas.

The attic level, now reached by ascending the main stair of the later west wing, has suffered several major renovations. Its initial floor plan consisted of a hall (east end) flanked by two small chambers to one side (west). The two partition walls were of vertical painted boards. The present arrangement is of two chambers, partitioned laterally. The roof collars display the same beaded edge as the ceiling joists of the first floor. In both cases the area above is sheathed with lapped boards. The small area above the roof collars is gained by a narrow "stair-ladder" positioned against the south wall of the chimney stack. This ladder is enclosed within a small closet flanking the former stair. At the west end of the attic is a small gable window which was now been sealed shut. Its original purpose was to serve the former south bed chamber. It is not known whether this window was flanked by one lighting the north chamber since that area has been altered with the introduction of a door opening into the later addition.

The frame two story west wing was probably erected circa 1840. It has a single stair hall at the east end flanked by a single parlor on the west side. This same floor plan is repeated at the second floor level. The addition is two bays in length at both the front (south) and rear (north) elevations with the transomed entrance door positioned toward the east end of both facades. A single chimney is enclosed within the west end wall with its rear (exterior) face exposed at the first floor level. The south wall of this wing is flush to the south wall of the first stage and extends back about three quarters the depth of the west end elevation. Within several years of the erection of this wing a small two story outshut was constructed against the east end of the north wall. It contains an exterior cellar entrance at the first floor level and a small closet chamber above.

Standing in close proximity to the east end of the house are two domestic dependencies, one a log smokehouse and the other a frame tobacco barn. Both date circa 1800 and both are in a ruinous state. At a short distance from the northwest corner of the west wing of the house is a small private cemetery with most of the graves dating from within the first half of the nineteenth century.

(see Cont. sheet 2)

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

S-56

STATE	
Maryland	
COUNTY	
Somerset	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Continuation Sheet)

(Number all entries)

7. DESCRIPTION

Sudler's Conclusion was recorded during a 1971 architectural recording survey of Tidewater Maryland architecture sponsored by the Maryland Historical Trust and the St. Mary's City Commission (St. Mary's City, Md.) resulting in architectural drawings of the house and a site plan of this small complex. This material will eventually become part of the National Park Services HABS collection at the Library of Congress, Washington, D. C.

11. FORM PREPARED BY

J. Richard Rivoire, Field Surveyor
Maryland Historical Tr st
2525 Riva Road
Annapolis, Maryland 21401

E. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- Pre-Columbian
- 15th Century
- 16th Century
- 17th Century
- 18th Century
- 19th Century
- 20th Century

SPECIFIC DATE(S) (If Applicable and Known)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|--|--------------------------------------|---|---|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Phi- | <input checked="" type="checkbox"/> Other (Specify) |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | losophy | <u>local history</u> |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Science | _____ |
| <input checked="" type="checkbox"/> Architecture | <input type="checkbox"/> Landscape | <input type="checkbox"/> Sculpture | _____ |
| <input type="checkbox"/> Art | Architecture | <input type="checkbox"/> Social/Human- | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Literature | itarian | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Military | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Conservation | <input type="checkbox"/> Music | <input type="checkbox"/> Transportation | _____ |

STATEMENT OF SIGNIFICANCE

Sudler's Conclusion is situated on a tract of land patented in 1789 by Thomas Leon Sudler. This tract, known as Sudler's Conclusion, was formed from parts of five tracts patented as early as 1665. A 1754 transfer of one of the tracts, Littleworth, mentions a building which may be the same house mentioned in the 1783 Tax Assessment owned by Mary Wheatley and described as "brick dwelling house with two rooms below in middling good repair".¹ This house was probably part of a transfer made to Thomas Sudler in 1789 from Jones Willis.²

The first definite reference to the house occurred in the Federal Tax Assessment of 1798 when Thomas Leon Sudler was the owner of "1 dwelling house built of Bricke 28 feet by 24 feet, all one story high." 3 *

The house remained in the Sudler family until 1815 when it passed along a chain of local Somerset County owners. During these years, the original 419 3/4 acre tract was reduced to its present 7.91 acres. In 1971 the house was sold to Mr. and Mrs. Joseph Eberly who are in the process of restoration.

Sudler's Conclusion represents one of Maryland's few remaining early eighteenth century dwellings. Its significance lies in its architecture. The diagonally set belt course on the east end is one of three found in Somerset County houses of the period. Other significant elements are the decorative interior details and the laterally partitioned floor plan. The house is so little altered that it is possible to reconstruct the original floor plan.

- * 1. Federal Direct Tax Assessment
Somerset County
Great Annessex Hundred.
Particular list of Dwellings.
- 2. Somerset County Land Records. H/524,
- 3. Federal District Tax Assessment
Somerset, Great Annessex Hundred
List of Particular Dwellings

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Hall of Records, Annapolis, Maryland
Somerset County Land Records
Somerset County Probate Records

Federal Direct Tax Assessment. 1798. Great Annessex Hundred.

Tax Assessment of 1783. Somerset County.

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	38° 07' 20"	75° 46' 52"		° ' "	° ' "	
NE	38° 07' 28"	75° 46' 36"		° ' "	° ' "	
SE	38° 07' 13"	75° 46' 21"		° ' "	° ' "	
SW	38° 07' 03"	75° 46' 37"		° ' "	° ' "	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: 51.2 Square Acres

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE

11. FORM PREPARED BY

NAME AND TITLE:
Louise L. Hayman, Assistant Historian

ORGANIZATION: Maryland Historical Trust DATE: 2/15/73

STREET AND NUMBER:
2525 Riva Road (see cont. sheet 2)

CITY OR TOWN: Annapolis STATE: Maryland CODE: 24

12. STATE LIAISON OFFICER CERTIFICATION

NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National State Local

Name Orlando Ridout IV

Title State Liaison Officer

Date February 20, 1973

I hereby certify that this property is included in the National Register

Director, Office of Archeology and Historic Preservation

Date _____

ATTEST:

Keeper of The National Register

Date _____

SEE INSTRUCTIONS


NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY PHOTOGRAPH FORM

S-56

(Type all entries - attach to or enclose with photograph)

1. NAME		
COMMON	AND/OR HISTORIC	NUMERIC CODE (Assigned by NPS)
Sudler's Conclusion		
2. LOCATION		
STATE	COUNTY	TOWN
Maryland	Somerset	Manokin
STREET AND NUMBER		
Hood Road, 1 mile northwest of intersection of Md. 361		
3. PHOTO REFERENCE		
PHOTO CREDIT	DATE	NEGATIVE FILED AT
Maryland Historical Trust	2/20/73	Maryland Historical Trust
4. IDENTIFICATION		
DESCRIBE VIEW, DIRECTION, ETC.		

Southeast Facade.



UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE
NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY MAP FORM
(Type all entries - attach to or enclose with map)

S-56

NAME COMMON Sudler's Conclusion		AND/OR HISTORIC	NUMERIC CODE (Assigned by NPS)
2. LOCATION STATE Maryland		COUNTY Somerset	TOWN Manokin
STREET AND NUMBER Hood Road, 1 mile northwest of intersection of Maryland Route 361			
3. MAP REFERENCE SOURCE U.S.G.S. 7 1/2 Minute Map, Marion Quadrangle		DATE 1942	SCALE 1:24000
REQUIREMENTS: PROPERTY BOUNDARIES, WHERE REQUIRED, AND NORTH ARROW.			



Sudler's Conclusion

S-56

Manokin vicinity, Somerset Co.,Md.

Southwest Elevation

3/84, Paul Touart, Photographer

Neg./Md. Historical Trust



CUMBERLAND DEPARTMENT

S. 56

1892

Phot. Lab.

173

* 2001 225 C. 122



Sudler's Conclusion - ~~5-56~~

Sudler's Conclusion ~~5-56~~

MARYLAND HISTORICAL TRUST
2525 RIVA ROAD
ANNAPOLIS, MARYLAND 21401

J.R.R. - 1971



SUPPLEMENTARY SECTION 3

S-56

HALLS

1000 1/2 1/2 1/2 1/2 1/2

55



SUTLER'S CONCLUSION

S-56

6/13




STUDENTS' SELECTIONS

2-56

UPPER

STUDENTS' SELECTIONS

53



SMALLER SECTION

2-56

MAPS

1940-1945

69



SMULERS SECLUSION

3-56

HATS

28





67



S-56

Sudlers Conclusion

Near Manokin, Somerset County

Tilted False - Plate

2/84 Paul Touart

Neg./Md. Historical Trust



S-56

Sudler's Conclusion
Near Manokin, Md. Somerset County
Plate Construciton
Photographer - Paul Touart - 10/83
Neg./Md. Historical Trust



STUDYING SCIENCE
LIFE

2-56

1. The study of life is called biology.

96



8/11/12 2012

2-56

HAS

Page

49



S-56


Studler's Conclusion

Near Manokin, Md. Somerset County

West Elevation of Barn

Photographer - Paul Touart - 10/83

Reg./Md. Historical Trust



Sudlers Conclusion
Near Manokin, Somerset County
East Gate End of Tobacco House
10/83 Paul Touart
Neg./Md. Historical Trust

S-56