

Easement on CE-127 - Indian Queen  
Easement on CE-128 - Red Lion Tavern

CE - 127, 128

Form 10-300  
Rev. 6-72

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

STATE: Maryland
COUNTY: Cecil
FOR NPS USE ONLY
ENTRY DATE

1. NAME

COMMON:  
Indian Queen and Black's Store

AND/OR HISTORIC:  
Red Lion Inn's Indian Queen Hotel

2. LOCATION

STREET AND NUMBER:  
Market Street

CITY OR TOWN:  
Charlestown

CONGRESSIONAL DISTRICT:  
First

STATE: Maryland      CODE: 24      COUNTY: Cecil      CODE: 015

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input checked="" type="checkbox"/> Building <input type="checkbox"/> Site <input type="checkbox"/> Structure <input type="checkbox"/> Object	<input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both	Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered	<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress
PRESENT USE (Check One or More as Appropriate)			
<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input checked="" type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify) _____ <input type="checkbox"/> Comments _____ Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No

4. OWNER OF PROPERTY

OWNER'S NAME:  
Winthrop D. Allen

STREET AND NUMBER:  
Indian Queen

CITY OR TOWN:  
Charlestown

STATE:  
Maryland

CODE:  
24

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:  
Cecil County Courthouse

STREET AND NUMBER:

CITY OR TOWN:  
Elkton

STATE:  
Maryland

CODE:  
24

8. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:

DATE OF SURVEY:       Federal     State     County     Local

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN:      STATE:      CODE:

STATE

COUNTY

FOR NPS USE ONLY

ENTRY NUMBER

DATE

7. DESCRIPTION

CONDITION	(Check One)					
	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site		

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

SEE INSTRUCTIONS

Standing on an embankment facing south on Market Street between Bladen and Cecil Streets in Charlestown, Cecil County, Maryland is the Indian Queen Tavern complex.

The property comprises approximately two acres. On the south side, facing Market Street, behind picket fences enclosing small yards are two mid-eighteenth century structures. On the left is Black's Store, originally the Red Lyon Inn, and on the right is the Indian Queen Tavern, later called Hotel. The two taverns and their remaining outbuildings form a court on the north side. Behind the Indian Queen is a log Kitchen with a loft over; behind the Red Lyon is a weatherboarded Spring House. Between these two is a two-story Smoke House. The lower story of the Smoke House is stone with a door on the west side and a brick grill set in stone on the south. The second story is brick with a door in the south wall. Traces of an exterior wood stair up to the second floor remain.

The Indian Queen is a two-story frame structure, thirty feet square, with the interior quartered into four rooms. A massive chimney rises through the middle of the tavern with a corner fireplace in each room on the first floor and two corner fireplaces on the second. On the first and second floors, the sides of the chimney are slightly curved giving a curiously "contemporary" or sculptured quality to those fireplaces without mantels. The middle of the low cellar is filled by the stone foundation of the chimney, approximately two feet square.

The house is of post and beam construction with brick nogging for insulation. The front and rear are covered by wide boards fitted shiplap fashion, each with a beaded lower edge. The gable ends were recovered with weatherboard in the nineteenth century, and the eighteenth century gable ends and the bargeboard which trimmed them were restyled. The rebuilt Victorian roof extends fourteen inches beyond the gable with a dripboard of repetitive fleurs-de-lis design. A galleried porch extends across the front.

Throughout the house all exterior room walls are lathed and plastered. Gunstock swells occur at the upper portion of the four corner posts of the second floor giving additional strength to carry the hewn plates which crown the walls. The exposed posts and girts are boxed with boards having beaded edges. The original interior partitions are of vertical boards, usually beaded on one edge.

Two paneled and battened doors open from the first floor porch. Each door is flanked by a nine over nine double hung window with paneled shutters. The left door gives access to a square room with a stair winding up from the far left corner. The corner fireplace in this room is framed by a mantel dating from about 1830.

The original stair rose three steps with a banister and rail and was enclosed beyond with vertical, beaded boards

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet) #1

STATE	Maryland	
COUNTY	Cecil	
FOR NPS USE ONLY		
ENTRY NUMBER		DATE

CE-127  
CE-128

(Number all entries)

Indian Queen and Black's Store

7. DESCRIPTION, continued

and a door of six fielded panels. In 1924 the steep steps were replaced with an open flight of stairs with grained oak columns. At the same time the vertical board partition between the front rooms was replaced with grain oak columns to create a "double-parlor" across the front of the house. The parlor on the right also has a corner fireplace with a mantel dating from about 1830. A paneled and battened door and two windows open onto the porch. A six-paneled door on the inner wall opens into the northeast room equipped as a kitchen in the early twentieth century.

The northwest room was probably a sitting room for the innkeeper's family. A door with six panes of glass and two fielded panels, now reused upstairs, probably opened between this room and the southwest room allowing the family to see through to the public room and the stair.

Each back room has a corner fireplace without a mantel and each has a twelve over twelve light window and a door opening onto a porch with a shed roof. This porch is also connected to the log kitchen behind the house.

Originally the second floor was also quatered by vertical boards with beaded edges, over the four rooms below. The two front rooms were altered at an early date when other vertical board partitions were added to make passageways for private access to all the rooms and a door to the gallery.

There are two fireplaces on the second floor; one in the corner of the northeast chamber and the other in the corner of what was the southwest chamber and now part of the passage by the stairs. Both fireplaces are molded into the chimney stack and the bricks are plastered. The fireplaces do not have mantels and the mass of the masonry with its bowed sides is highly sculptural.

A variant of the vertical board partition was used near the stair on the second floor with the alternate boards deeply fielded.

Throughout the interior of the house, the typical moldings and trim are of the style characteristic of the mid-eighteenth century. After layers of wallpaper were removed, the original blue paint on the board partitions and other woodwork was found in good condition.

The hardware exhibits a great variety of period work from crude wood latches to neat iron box locks fitted with brass drop handles. Hinges include a range of styles from wrought HL to cast iron Eastlake examples.

In 1967 at the time of the purchase of the property by the Maryland Historical Trust, the later, open stair and columns were removed and an enclosed stair similar to the original, but

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet) #2

STATE	
Maryland	
COUNTY	
Cecil	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Indian Queen and Black's Store

7. DESCRIPTION, continued

with an easier tread to riser ratio was built. The columns between the two front rooms were also removed and a vertical board partition installed. On the second floor, an early twentieth century bathroom built in the end of the passage was taken out. All wallpaper was removed to expose the original partitions.

The present owner has replaced the porch on the north between the house and the log kitchen with a new porch, partly open and partly enclosed.

West of the Indian Queen is the Red Lyon Inn, used as a store by the Black family in the nineteenth century. This is an L-shaped, one and a half story, frame building with a gambrel roof across the south elevation and a gable roof on the ell.

The Red Lyon was built in three stages. The core of the building is a room twenty-three feet wide and nineteen feet deep, constructed of square hewn poplar logs covered on the exterior with siding. The siding on the front is identical with the wide shiplap planks on the front of the Indian Queen. The shiplap siding on the back is different with the beads cut in the upper edge of each plank.

Ruble stone walls form a cellar with an entrance on the south toward the street. The cellar fireplace has a five foot wide opening. A floor joist with a curved segment cut out of it under the existing stair and evidence of risers and treads against the cellar wall indicate the location of the missing winding steps that lead to the first floor.

On the first floor, a wide, paneled and battened door, mounted with 26 inch strap hinges, opens in the middle of the front wall. A similar door opens onto the back courtyard. Flanking each door is a doublehung window with twelve over twelve lights and one and one quarter inch wide muntions.

The walls are plastered above a board wainscot capped by a chair rail. The fireplace wall is paneled. To the left of the fireplace a door opens into a later eighteenth century addition. To the right is the stair. A banister and rail, now missing, enclosed the first four steps, then a four paneled door opens into the winding stairs as they rise to the chamber above. A crown molding forms the cornice of the first floor room.

The second floor of the original section consists of one large and two smaller rooms. The fireplace wall in the larger room is paneled similarly to the one on the first floor below it.

Later in the eighteenth century, an addition was built to the west of the original building. The cellar is of the same

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet) #3

STATE	Maryland	
COUNTY	Cecil	
FOR NPS USE ONLY		
ENTRY NUMBER		DATE

(Number all entries)

Indian Queen and Black's Store

7. DESCRIPTION, continued

rubble stone as the original section, but the first floor is of post and beam construction. The shiplap boards of the south elevation continue across the facade. The gambrel roof was also continued across.

There is one room on the first floor, twelve and a half feet wide by nineteen feet deep. From the south another six panel door with battens opens into the room. To the left of the door is a window similar to the earlier ones, but with three quarter inch muntins.

The interior is finished with a 43 inch wainscot of vertical beaded boards with a chair rail applied to the wainscot 32 inches above the floor. At the back of the room, the fireplace is faced with a mantel, corresponding in style to the two mantels in the front rooms of the Indian Queen. The former posts and girts are faced with planks with beaded edges. A crown molding runs around the room for a cornice. There is a single chamber on the second floor.

To the north of the first addition, a second addition forms an ell at the rear of the house. The single room on the first floor was used as a kitchen and has a deep fireplace without a mantel. To the left of the fireplace is a door connecting the kitchen to the first floor of the first addition. To the right of the fireplace is a winding stair up to a passage and a bedroom. In the passage are three steps leading to the second floor of the first addition.

At the time of the purchase of the property by the Maryland Historical Trust, later porches across the south and north elevations were removed. Some of the early four and a half inch wide "fish scale" shingles with rounded edges were found where the second addition joined the roof of the first two sections of the house. The gambrel roof was recovered with new wood shingles to match these early ones. The ell was stabilized to prevent further deterioration. A new picket fence was built to enclose the front yard facing Market Street.

The present owner is now beginning the restoration of the Red Lyon Inn.

8. SIGNIFICANCE, continued

The Blacks were storekeepers through the century; their record books are extant from 1813 to 1896. These document the activities at the store and provide important insights into nineteenth century commerce.

6. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

<input type="checkbox"/> Pre-Columbian	<input type="checkbox"/> 16th Century	<input checked="" type="checkbox"/> 18th Century	<input type="checkbox"/> 20th Century
<input type="checkbox"/> 15th Century	<input type="checkbox"/> 17th Century	<input checked="" type="checkbox"/> 19th Century	

SPECIFIC DATES (If Applicable and Known)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

<input type="checkbox"/> Aboriginal	<input type="checkbox"/> Education	<input type="checkbox"/> Political	<input type="checkbox"/> Urban Planning
<input type="checkbox"/> Prehistoric	<input type="checkbox"/> Engineering	<input type="checkbox"/> Religion/Philosophy	<input type="checkbox"/> Other (Specify) _____
<input type="checkbox"/> Historic	<input type="checkbox"/> Industry	<input type="checkbox"/> Science	_____
<input type="checkbox"/> Agriculture	<input type="checkbox"/> Invention	<input type="checkbox"/> Sculpture	_____
<input checked="" type="checkbox"/> Architecture	<input type="checkbox"/> Landscape Architecture	<input type="checkbox"/> Social/Humanitarian	_____
<input type="checkbox"/> Art	<input type="checkbox"/> Literature	<input type="checkbox"/> Theater	_____
<input checked="" type="checkbox"/> Commerce	<input type="checkbox"/> Military	<input checked="" type="checkbox"/> Transportation	_____
<input type="checkbox"/> Communications	<input type="checkbox"/> Music		_____
<input type="checkbox"/> Conservation			_____

STATEMENT OF SIGNIFICANCE

SEE INSTRUCTIONS

The Indian Queen and Black's Store are two eighteenth century taverns that date from the period of prosperity of Charlestown, Maryland. Chartered in 1742, Charlestown prospered largely because of its location on the Annapolis--Philadelphia post road at the ferry crossing on the Chesapeake Bay. The traffic on the post road generated enough business to support several taverns in Charlestown.

By the turn of the nineteenth century, Elkton had eclipsed Charlestown as the urban center of Cecil County. The financial decline worked as a freezing agent to retain Charlestown's eighteenth century character and many of its original buildings. The Indian Queen and Black's Store found new uses illustrative of the changing nature of the town from an important transportation center to a rural village.

Architectural and archaeological evidence points to an eighteenth century date for both structures. The documents begin their story in 1742 with the laying out of Charlestown into lots. Both buildings stand on Lot 82 bounded by Market Street on the south, the main thoroughfare, and by the market space on the east. The original owner Zebulon Hollingsworth, a charter member of the town council, sold the westernmost quarter on which the original section of Black's Store, the Red Lyon tavern, was constructed. The 1755 town minutes tell of a council meeting at the Red Lyon. Immediately to the east of this gambrel-roofed log structure stands the Indian Queen, a two-story competitor for the Red Lyon. The Indian Queen is one of the several places on the eastern seaboard to hold the distinction: "George Washington slept here."

Both buildings operated independently until the mid-nineteenth century. In 1830 Indian Queen became the property of Major John Nelson Black through marriage. He made several improvements to the property notably the "gingerbread" cornice and the alteration to the roof line when he converted it to a residence.

Two decades later the Black family obtained the Red Lyon which through the nineteenth century was known as Black's Store consisting of the original log section and a gambrel roof wing which served as a sometime school for the Black children.

CE-127, CE-128

Form 10-300a  
(July 1959)

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet) #4

STATE	Maryland	
COUNTY	Cecil	
FOR NPS USE ONLY		
ENTRY NUMBER		DATE

(Number all entries)

Indian Queen and Black's Store

11. Form prepared by, continued

Nancy Miller, Historian  
Maryland Historical Trust  
1615 Liva Road  
Annapolis, Maryland 21401  
May, 1974

SEE INSTRUCTIONS

**9. MAJOR BIBLIOGRAPHICAL REFERENCES**

Ridout, Orlando IV. "The Indian Queen." Winterthur Portfolio 5.  
 (Charlottesville: University of Virginia Press, 1969.)  
 pp. 189-204.

**10. GEOGRAPHICAL DATA**

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY				O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES													
CORNER	LATITUDE				LONGITUDE													
	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds									
NW	°	'	"	°	'	"	39	°	34	'	27	"	76	°	58	'	39	"
NE	°	'	"	°	'	"												
SE	°	'	"	°	'	"												
SW	°	'	"	°	'	"												

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: Less than one acre

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY:	CODE

**11. FORM PREPARED BY**

NAME AND TITLE:  
Michael F. Trostel, AIA (See continuation sheet No. 4)

ORGANIZATION: Baltimore City Committee, Maryland Historical Trust DATE: May, 1974

STREET AND NUMBER:  
1307 Bolton Street

CITY OR TOWN: Baltimore STATE: Maryland CODE: 24

**12. STATE LIAISON OFFICER CERTIFICATION**      **NATIONAL REGISTER VERIFICATION**

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National     State     Local

Name: Arthur C. Townsend

Title: State Historic Preservation Officer

Date: October 21, 1974

I hereby certify that this property is included in the National Register

\_\_\_\_\_  
 Director, Office of Archeology and Historic Preservation

Date: \_\_\_\_\_

ATTEST:

\_\_\_\_\_  
 Keeper of The National Register

Date: \_\_\_\_\_

CE-127, CE-128

Form 10-301  
(July 1968)

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE  
**NATIONAL REGISTER OF HISTORIC PLACES**  
**PROPERTY MAP FORM**  
(Type all entries - attach to or enclose with map)

1. NAME		
COMMON	AND/OR HISTORIC	NUMERIC CODE (Assigned by NPS)
Indian Queen and Black's Store	Red Lyon Inn's Indian Queen Hotel	

2. LOCATION		
STATE	COUNTY	TOWN
Maryland	Cecil	Charlestown
STREET AND NUMBER		
Market Street		

3. MAP REFERENCE		
SOURCE	DATE	SCALE
U.S.G.S. 7.5 minute map North East Quadrangle	1953	1:24000

REQUIREMENTS: PROPERTY BOUNDARIES, WHERE REQUIRED, AND NORTH ARROW.

CE-127, CE-128


FORM 10-301 A  
(6-72)

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

1. NAME		
COMMON	AND/OR HISTORIC	NUMERIC CODE (Assigned by NPS)
Store Indian Queen & Black's/	Red Lyon Inn's Indian Queen Hotel	
2. LOCATION		
STATE	COUNTY	TOWN
Maryland	Cecil	Charlestown
STREET AND NUMBER		
Market Street		
3. PHOTO REFERENCE		
PHOTO CREDIT	DATE	NEGATIVE FILED AT
Orlando Ridout IV	1968	Maryland Historical Trust
4. IDENTIFICATION		
DESCRIBE VIEW, DIRECTION, ETC.		
south elevation		



## INDIAN QUEEN CE-127

Lot #82

First owned by Zebulon Hollingsworth, one of the original Town Commissioners of Charlestown, this house was used for many years as a tavern and changed hands a number of times, until in 1845, it became the property of John N. Black, whose descendents were in possession until 1967. At that time, it was purchased, along with the Red Lyon Tavern, by the Maryland Historic Trust and partially restored.


## RED LYON CE-128

Lot #82

The Red Lyon was built circa 1755 on the same lot as the Indian Queen. Later the left portion was known as Stephen Porter's Tavern and the right section as John Black's Store. In 1804 the building was purchased by Capt. Jonas Owens. In the yard there stands a stone meat house, probably erected by Capt. Owens. An archaeological dig in the area revealed the remains of many animals bones—mostly pig, sheep and squirrel. Altho Charlestown was the center of a fishing community, not many fish bones were found.

Present owners are Mr. and Mrs. Winthrop Allen.

NORTH EAST  
USGS 7.5  
scale: 1  
1953



*diken Queen*

CE-127

0.8 MI. TO US 40  
5763 FT SE (HAVRE DE GRACE)  
32'30"

NORTH EAST

MORNING CHEER CAMP

Roach Pt.

Hance Pt.

Seneca Pt.

Charlestown

PENNSYLVANIA

GENERAL ROAD

4382

35'

4979


4378

32'30"



Indica Quem

CE-127



INDIAN QUEEN, CHARLESTON, CECIL CTY

CE  
127

Glenn Little neg.

NE corner of I. Queen - foundation.



3&Y

SS

INDIAN QUEEN, CHARLESTON, CECIL CT, S. 512V.

CE-1287

during restoration 1968

8-1-68  
of  
14

1008

1.45

11

MD. HISTORICAL TRUST  
BOX 1704  
ANN. POLIS, MD. 21404



Black's store

CE-128



CE-127

The Indian Queen Hotel  
Circa 1750  
Charlestown, Md.



C-128

The Red Lyon Inn

Circa 1750

Charlestown, Md.



● Ce-127 Indian Queen Tavern 1968 O. Ridout IV

100



INDIAN QUEEN MEAT HOUSE

CE-128

The Indian Queen

Meat House from SW

MARYLAND HISTORICAL TRUST  
2525 RIVA ROAD  
ANNAPOLIS, MARYLAND 21401

OR 67