

UNITED STATES DEPARTMENT OF THE INTERIOR  
 NATIONAL PARK SERVICE  
**NATIONAL REGISTER OF HISTORIC PLACES**  
**INVENTORY -- NOMINATION FORM**  
 FOR FEDERAL PROPERTIES

FOR NPS USE ONLY	
RECEIVED	
DATE ENTERED	

SEE INSTRUCTIONS IN *HOW TO COMPLETE NATIONAL REGISTER FORMS*  
 TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

**1 NAME**

HISTORIC Patowmack Canal at Great Falls Historic District  
 AND/OR COMMON

**2 LOCATION**

STREET & NUMBER (within Great Falls Park, Virginia)  
 9200 Old Dominion Drive  
 CITY, TOWN Great Falls  
 STATE Virginia  
 VICINITY OF CODE 51  
 COUNTY Fairfax  
 CONGRESSIONAL DISTRICT 10th  
 COUNTY CODE 059

**3 CLASSIFICATION**

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input checked="" type="checkbox"/> DISTRICT	<input checked="" type="checkbox"/> PUBLIC	<input type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input type="checkbox"/> BUILDING(S)	<input type="checkbox"/> PRIVATE	<input checked="" type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input checked="" type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL <input type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	<input type="checkbox"/> PUBLIC ACQUISITION	<input type="checkbox"/> ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input checked="" type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER:

**4 AGENCY**

REGIONAL HEADQUARTERS: (If applicable)  
 National Capital Region, National Park Service  
 STREET & NUMBER 1100 Ohio Drive, S.W.  
 CITY, TOWN Washington  
 VICINITY OF D.C.  
 STATE 20242

**5 LOCATION OF LEGAL DESCRIPTION**

COURTHOUSE, REGISTRY OF DEEDS, ETC. Fairfax County Courthouse  
 STREET & NUMBER 4000 Chain Bridge Road  
 CITY, TOWN Fairfax, Virginia  
 STATE 22030

**6 REPRESENTATION IN EXISTING SURVEYS**

TITLE Historic American Engineering Record  
 DATE 1974-1975  
 DEPOSITORY FOR SURVEY RECORDS Library of Congress  
 CITY, TOWN Washington  
 STATE D.C.  
 FEDERAL  STATE  COUNTY  LOCAL

**DESCRIPTION**

CONDITION		CHECK ONE	CHECK ONE
<input type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input type="checkbox"/> GOOD	<input checked="" type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

## DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Patowmack Canal at the Great Falls of the Potomac in Virginia is a skirting canal approximately 3/4 of a mile long and containing five locks, a large holding basin, two guard gates, a wing dam, and several other related features. It was constructed by the Patowmack Canal Company between 1785 and 1802 to provide passage around the Great Falls of the Potomac.

The canal consisted of: a large wing dam at its upper terminus, an upper guard gate, the canal bed, a large holding basin, a lower guard gate, the five locks including their attendant gates, and a stone jetty at its lower terminus. In addition, the town of Matildaville was to be constructed as an accompanying trade center and headquarters for the Patowmack Company.

Wing Dam (canal inlet)

At the upper terminus of the canal, a wing dam extended into the river approximately 1,200 feet. Its purpose was to channel water into the canal, especially at times of low water. Remnants of this structure indicate it was constructed of stones, possibly in wooden cribs, and its upper elevation would have been the operating level of the canal. Thus, surplus water simply flowed over the top of the dam. This structure is located 1,600 feet above the Great Falls Park Visitors Center.

Upper Spillway

Below the wing dam in the river side of the canal wall, there was a low masonry dam constructed in the bed of an existing stream channel. Its upper elevation was again the working level of the canal and it allowed excess water to spill over the dam and return to the river. This structure is only barely visible and is located 1,300 feet above the Great Falls Park Visitors Center.

Upper Guard Gate

Immediately below the upper spillway was the upper guard gate. This controlled the entrance of water into the entire canal system below this point. Evidence indicates that the gates were of the swing or mitre type. On the berm bank a heavy stone wall 20 feet thick extends nearly 40 feet into the berm wall to resist flood waters. On the river side, below the guard gate, the canal walls are about 20 feet thick and constructed of large stones, dry laid with a slight batter. In places these walls, extending 10 feet from the canal bed, rise from bedrock, and in places the canal bed was cut into bedrock from 1 foot to 3 feet. The guard gate is located 1,300 feet above the Great Falls Park Visitors Center.

Holding Basin

About 2,800 feet below the upper guard gates, a large holding basin was constructed. It is roughly triangular in shape, covering approximately 2 acres, with the long axis parallel to the canal. This basin provided for the turning and docking of the canal boats and a large impound area providing water to the locks located below it. The river side wall of this basin is constructed of stone of a size and manner similar to that below the upper guard gate. The berm-side wall no longer exists, but it is assumed it was constructed in a like manner. Water from the holding basin was

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICENATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 2

channeled into the locks of the canal through a lower guard gate, and the excess was returned to the river via a waste weir/spillway. This basin and its attendant waste weir and guard gate are located approximately 1,500 feet below the Great Falls Visitor Center.

Waste Weir/Spillway

In the river side of the basin wall there is a break in the masonry where the waste weir was located. The exact configuration of this structure cannot be determined at this time, but it may have been constructed of wood. Its purpose was to maintain a maximum operating level for the water in the holding basin.

Lower Guard Gate

The lower guard gate, located at the southwest end of the holding basin enabled the water in the locks below to be regulated. Hollow quoin stones of well dressed Seneca sandstone are visible in the walls on either side, thus indicating the use of a swing-type mitre gate. An extra 4-inch recess in the quoins accommodated two sliding wicket gates in each of the swing gates. The guard gate channel was 14 feet in width, and there was apparently extensive use of flat strap iron cramps in the coping and stones beneath them in the channel walls.

Locks

Below the guard gates were the locks which were numbered in descending order, with number I being at the upper end, adjacent to the holding basin, and number V being located near the weir.

Lock I

From the lower guard gate the canal wall is constructed of native stone. Lock I is approximately 100 yards below the guard gate and seems to have been 14 feet wide and 100 feet long, pocket to pocket. Its lift capacity was 10 feet. The walls were probably a composite of ashlar dressed red Seneca sandstone face over a rubble interior. The two pairs of gates were of a swing-type with sliding wicket gates. The upper lock gates and quoin stone coping were 2 feet, 2 inches above the level of the coping of the lower lock gates. The upper course is the only one currently in view and it consists of four stones with a recess of 8½ inches deep to receive the mitre sill. There was evidently little use of iron cramps in the lock walls, except in the gate pockets. There are currently a few bulges in the lock walls, and there has been some repair to the walls with brick, rubble, and cement in modern times. This feature is located 1,700 feet below the Great Falls Visitor Center.

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICENATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 3

Lock II

Lock II is 12 feet wide, 88 feet long between gate pockets and had a lift capacity of 15 feet. There were several types of stone used in the construction of this lock, with free stone used in all of the gate pockets. Ashlar red sandstone was used on the river side wall, except for a small section of rough cut nature stone. There are a large number of stonecutters' marks found in the stones of this lock, particularly in the free stone.

The lock gates were of the swing mitre type with butterfly wicket gates. There are indications that the cut stone in the gate pockets were cramped, but all pockets have since collapsed. About 30 feet of the upper end of the berm wall have collapsed below the breast wall, as have about 16 feet below the lower gate pocket, on the river side. This lock is located 1,800 feet below the Great Falls Visitor Center.

Locks III, IV, and V

Locks III, IV, and V were a riser, or stairstep, of locks, each being immediately adjacent to the other, and sharing the common gate between them. Lock III is 12 feet wide, 111 feet long, and has a lift of 15 feet. Locks IV and V, however, were blasted from the bedrock with black powder in hand-drilled holes. Lock III is unique in that the lock bends 18 degrees within the lock itself. These locks are 2,100 feet below the Great Falls Visitor Center.

Jetty

At the lower end of the gorge of Locks IV and V, the canal returns to the Potomac River. On the river side of this gorge, a stone jetty was built into the river to protect the entrance/exit to the canal. Presently there are no known remnants of this jetty remaining.

ASSOCIATED FEATURESMill Site

Just below the Great Falls Visitor Center and adjacent to the river side canal wall are the foundations of an old mill. Period maps refer to the existence of a grist mill, while more recent maps refer to a saw mill. Ruins of masonry walls indicate the water wheel pit was adjacent to the wall of the canal and that it was fed from the canal by a wooden flume from some distance above the location. The remains of an existing masonry weir which now feeds water to the complex seems to be of more recent construction and probably is not original to the construction of the mill.

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER 7 PAGE 4

Forge/Foundry Site

Just below the mill site are the remains of footings and foundation for a forge/foundry. Archeological evidence has revealed the function of this building through excavation of both artifacts and slag. There are also the remains of a cast iron pipe below the foundation which seems to lead from the canal bank to the river bed. It is assumed this would have enabled the use of a turbine as power necessary for a forge.

Matildaville

Initially it was planned for a small town of 40 acres to accompany the development of the canal as a trade center and headquarters of the Canal Company. Lighthorse Harry Lee, father of General Robert E. Lee, was the founder of this town. Due to the financial failure of the canal the town never fully developed and all that currently remains are the ruins of a few structures. It is known that there were additional wooden structures, including, among others, warehouse and workmen's quarters, but no remains of these are known.

Dickey's Inn (Myers Tavern)

This building survived for many years following the failure of the canal and Matildaville. It was constructed of logs, squared and whitewashed, of two stories, with five rooms upstairs and two downstairs, and a kitchen. During the Civil War the inn was used for a Confederate Army headquarters. The building burned in 1942, and the chimney still partially stands surrounded by a pile of rubble. The inn is located 1,500 feet below the Great Falls Visitor Center.

Spring House

The spring house, located near Dickey's Inn, served to keep perishables cool. The floor of the spring house was approximately 30 inches below grade. All that currently remain are the foundation walls, the spring inlet, and a small set of stairs.

Superintendent's House

The Superintendent's house was constructed in 1796 of stone and brick. It was two stories with a front elevation of 25 feet and a depth of 35 feet. At present only the foundation and some of the corner stones remain standing. It is located 1,700 feet below the Great Falls Visitor Center.

General Appearance

The Patowmack Canal is currently in "ruin," in that much of the canal bed is filled with debris and silt. It is quite possible, however, that the canal prism is intact throughout the major portion of its length. The lock gates are no longer in existence, as the locks were dismantled in 1830, but significant archeological and documentary evidence exists to accurately interpret their manner of construction.

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER 7

PAGE 5

Associated Historic Artifacts

All historic artifacts and documents original to or historically associated with the property described herein and in National Park Service ownership and control are defined as components of this property for the National Register. Such materials are listed and described in the park's museum catalog.

## **8** SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input checked="" type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input checked="" type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
		<input type="checkbox"/> INVENTION		

SPECIFIC DATES 1785-1830

BUILDER/ARCHITECT

### STATEMENT OF SIGNIFICANCE

The Patowmack Company was organized to construct a canal system making the Potomac River navigable for trade from Georgetown to Harpers Ferry. If the Potomac River could be made navigable, it was a short land passage from Harpers Ferry to the Monongahela or Youghiogheny Rivers and then to the Ohio River, which at that time was a principal route to the west. Canals were to be built at Great Falls, Little Falls, Seneca, Shenandoah, and House Falls. Only at Little Falls and Great Falls were locks required. During this period canals with locks were uncommon in the United States, and thus represented a significant engineering achievement.

The Patowmack Canal at The Great Falls of the Potomac was the largest of the five skirting canals on the Potomac. To re-enter the river below The Great Falls, a channel had to be blasted through solid rock. Holes were bored by hand into the rock and filled with blasting powder, and fired. This constituted one of the first uses of explosives in an American Engineering project.

George Washington, early in his life, realized the importance of the Potomac River as a route to the west. Before the Revolutionary War he was active in soliciting the interest of Virginia and Maryland legislators in a canal venture, and he was successful in securing the passage of an act in Virginia in 1772 for improving the Potomac. Due largely to Washington's influence, the legislators of Maryland and Virginia passed laws incorporating the Patowmack Company in 1784; Washington served as the Company's first president. Shares in the Patowmack Company were sold to subscribers. Although the country was in a period of financial stress, the stock was quickly taken with a large number of Alexandria residents participating. The states of Maryland and Virginia originally purchased 50 shares each, and by 1821 Virginia had 70 shares and Maryland held 220. These states purchased almost half of the 701 shares of the Patowmack Company, a sizable investment during a period when states did not promote extensive public works. The Patowmack Company's venture was one of the first state financed internal improvements in the USA.

Work on the canal began in 1785 and was completed in 1802, under the direction of several canal engineers, John Rumsey appears to have been the principal engineer. The Patowmack Company was a financial failure; however, it is significant for its early recognition of the need for an effective means of transportation between the east and west, and the development of canal building in the United States.

On August 15, 1826, the bankrupt Patowmack Canal Company dissolved and its charter and its charter and official papers passed to the Chesapeake and Ohio Canal Company.

Form No. 10-300a  
(Rev. 10-74)

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

FOR NPS USE ONLY
RECEIVED
DATE ENTERED

**NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY -- NOMINATION FORM**

CONTINUATION SHEET

ITEM NUMBER 8 PAGE 2

The town of Matildaville was a speculative venture to parallel the development of the Patowmack Canal at The Great Falls. In a letter of February 13, 1789, to Thomas Jefferson George Washington stated, "...I conceive that place [future town site] must become very valuable... I cannot entertain a doubt of the establishment of a town in that place." The establishment of the town was financially undertaken by General Henry ("Light Horse Harry" Lee, who obtained a charter for the 40 acre townsite from the Virginia Assembly in 1790.

Lee and his business associates hoped that Matildaville would grow into an important industrial center in which surplus water from the canal could be used for power. With the failure of the Patowmack Canal at The Great Falls, Matildaville lost its economic base and ceased to function as a community, never realizing the expectations of Lee and the other investors.

The Patowmack Canal at The Great Falls survives today as an example of the Patowmack Company's pioneering canal venture in the United States. Although it, and the various structures associated with it, are in ruins, they still constitute significant remains of early canal technology and represent commercial speculation by individuals and states that marked much of the nation's growth.

**9 MAJOR BIBLIOGRAPHICAL REFERENCES**

See attached.

**10 GEOGRAPHICAL DATA**

ACREAGE OF NOMINATED PROPERTY 19

UTM REFERENCES

A	1, 8	3, 0, 4	6, 2, 0	4, 3	1, 9	1, 8, 0	B	1, 8	3, 0, 5	0, 8, 0	4, 3	1, 8	6, 9, 0
	ZONE	EASTING		NORTHING			ZONE	EASTING		NORTHING			
C	1, 8	3, 0, 5	3, 1, 0	4, 3	1, 7	7, 5, 0	D	1, 8	3, 0, 4	7, 8, 0	4, 3	1, 8	4, 3, 0

VERBAL BOUNDARY DESCRIPTION

The entire canal is within the boundaries of Great Falls Park, Virginia. The canal enters the river above Great Falls. Its southern terminus is through a man made cut entering Mather Gorge. The nominated property includes only the canal and related ruins of the foundry, grist mill and Matildaville. The modern park visitor center abutting the canal is excluded. (See enclosed park leaflet for sketch map.)

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	Virginia	CODE	COUNTY	CODE
			Fairfax	
STATE		CODE	COUNTY	CODE

**11 FORM PREPARED BY**

NAME / TITLE	Gary Scott, Historian Nicolas Veloz, Curator	DATE	May 2, 1978 July 12, 1979
ORGANIZATION	George Washington Memorial Parkway	TELEPHONE	557-3635
STREET & NUMBER	Turkey Run Park	CITY OR TOWN	STATE
	Mc Lean, Virginia 22101		

**12 CERTIFICATION OF NOMINATION**

STATE HISTORIC PRESERVATION OFFICER RECOMMENDATION

YES  NO  NONE

Tucker Hill, Executive Director  
Virginia Historic Landmarks Commission

STATE HISTORIC PRESERVATION OFFICER SIGNATURE

In compliance with Executive Order 11593, I hereby nominate this property to the National Register, certifying that the State Historic Preservation Officer has been allowed 90 days in which to present the nomination to the State Review Board and to evaluate its significance. The evaluated level of significance is      National      State      Local.

FEDERAL REPRESENTATIVE SIGNATURE

TITLE DATE

FOR NPS USE ONLY	
I HEREBY CERTIFY THAT THIS PROPERTY IS INCLUDED IN THE NATIONAL REGISTER	DATE
DIRECTOR, OFFICE OF ARCHEOLOGY AND HISTORIC PRESERVATION	DATE
ATTEST:	DATE
KEEPER OF THE NATIONAL REGISTER	



UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY -- NOMINATION FORM

CONTINUATION SHEET

ITEM NUMBER 9 PAGE 2

Fitzpatrick, John C., editor, *The Writings of George Washington*, Government Printing Office, 1931-1944, 39 vols; *The Diaries of George Washington*, Houghton Mifflin Company, New York, 1925, 4 vols. These two sources are the best for background information on the organization of the Potomac Company and the first four years of canal construction.

Hening, William Waller, *The Statutes at Large; being a collection of all the Laws of Virginia*, Richmond, 1823.

Lear, Tobias, *Letters and Recollections of George Washington*, Doubleday, Page and Company, New York, 1906.

Sparks, Jared, *The Writings of George Washington*, Boston, 1835.

*The American Historical Review*, XXVIII, No. 3 (April 1923) and No. 4 (July 1923). This volume contains numerous letters of Washington and others dealing with the Potomac project, from the Minnesota Historical Society.

Specialized works:

*A Treatise of Internal Navigation*, U. F. Doubleday, 1817.

Phillips, J., *A General History of Inland Navigation, Foreign and Domestic*, London, 1792.

*Recueil De Planches, sur Les Sciences, Les Arts Libéraux*, A Paris, 1767.

Vallancey, Charles, *A Treatise on Inland Navigation, or, the art of making Rivers navigable, of making canals in all sorts of soils, and of constructing Locks and sluices*, Dublin, 1763.

Encyclopedias:

*Encyclopaedia Britannica*, Edinburgh, 1771, II.

*Harper's Encyclopaedia of United States History*, VII.

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

**NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY -- NOMINATION FORM**

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER 9 PAGE 3

Newspapers:

The Evening Star, Washington, D. C., May 13, 1893, W. S. Jackson, "The Potomac Canal." Illustrations from photographs taken April 17, by Henry G. Wagner.

General works:

Bacon-Foster, Corra, "Early Chapters in the Development of the Potomac Route to the West," *Records of the Columbia Historical Society*, Washington, D. C., 1912, XV. This is the best source on the subject of the Potomac canals; numerous documents of the Potomac Company are reproduced, especially minutes of meetings and reports of presidents.

Boardman, For W., Jr., *Canals*, Henry Z. Walck, Inc., New York, 1959.

Bryan, Wilhelmus Bogart, *A History of the National Capital*, The Macmillan Company, New York, 1914, I.

Buehr, Walter, *Through the Locks, Canals Today and Yesterday*, G. P. Putnam's Sons, New York, 1954.

De Moré, Eric, *The Canals of England*, The Architectural Press, London, 1961.

"Diary of Mrs. William Thornton," *Records of the Columbia Historical Society*, Washington, D. C., X.

Gutheim, Frederick, *The Potomac*, Rinehart and Company, Inc., New York, 1949.

Hadfield, Charles, *Introducing Canals*, Ernest Benn Limited, London, 1955; *The Canal Age*, Frederick A. Praeger, New York, 1969.

Hulbert, Archer Butler, "The Great American Canals," *Historic Highways of America*, The Arthur H. Clark Company, Cleveland, Ohio, Xiii; *Washington and the West*, New York, 1905, Journal of 1784.

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

**NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY -- NOMINATION FORM**

CONTINUATION SHEET

ITEM NUMBER 9 PAGE 4

Nelson, Thomas Forsythe, *Washington's Canal Around the Great Falls of the Potomac*, Washington, D. C., 1910.

Payne, Robert, *The Canal Builders, the Story of Canal Engineers Through the Ages*, The Macmillan Company, New York, 1959.

Pilkington, Roger, *How Boats Go Uphill*, Abelard-Schuman, New York, 1959.

Rolt, L. T. C., *Navigable Waterways*, Longmans, Green and Co., London, 1969.


Scharf, Thomas J., *History of Maryland*, 1879, II.

Smith, Jo Anna, *History of the Great Falls Canal and Locks*, ASCE National Meeting on Transportation Engineering, Washington, D. C., 1969.

Taggard, Hugh T., "Old Georgetown," *Records of the Columbia Historical Society*, 1908, XI.

Vernon-Harcourt, Leveson Francis, *Rivers and Canals*, Oxford, Clarendon Press, 1896, 2 vols.

Warden, D. B., *Description of the District of Columbia*, Paris, 1816.



UTM REFERENCES

M:29-48

- |                      |                      |
|----------------------|----------------------|
| A. 18 304620 4319180 | C. 18 305310 4317750 |
| B. 18 305080 4318690 | D. 18 304780 4318430 |

VIENNA QUADRANGLE  
 VIRGINIA-MARYLAND  
 7.5 MINUTE SERIES (TOPOGRAPHIC)



77° 15'

FAI  
 7.5

M:29-48



M:29-48



Patowmack Canal at Great Falls  
Fairfax County, Virginia  
Lock # 1

Patowmack Canal at Great Falls  
Fairfax County, Virginia  
Lock # 2

Patowmack Canal at Great Falls  
Fairfax County, Virginia  
Locks # 3,4,5, looking toward  
the river

should be

Engineering

her

If required, credit should be


Historic American Engineering Record  
Federal Art Service  
Washington, D.C.

Jack Boucher

Photographer

19-7-1

M:29-48





M:29-48

M:29-48

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

FOR NPS USE ONLY

RECEIVED

DATE ENTERED

NATIONAL REGISTER OF HISTORIC PLACES  
PROPERTY MAP FORM

SEE INSTRUCTIONS IN HOW TO COMPLETE NATIONAL REGISTER FORMS  
TYPE ALL ENTRIES -- ENCLOSE WITH MAP

**1** NAME

HISTORIC Patowmack Canal at Great Falls

AND/OR COMMON

**2** LOCATION

CITY, TOWN

VICINITY OF

COUNTY Fairfax

STATE Virginia

**3** MAP REFERENCE

SOURCE U.S.G.S. 7.5 Minute Series, Vienna, Seneca, Falls Church, & Rockville, Md.  
Quadrangles

SCALE 1:24 000

DATE 1965, Photorevised 1971

**4** REQUIREMENTS

TO BE INCLUDED ON ALL MAPS

1. PROPERTY BOUNDARIES
2. NORTH ARROW
3. UTM REFERENCES

M:29-48

