

MARYLAND HISTORICAL TRUST WORKSHEET

NOMINATION FORM
for the
NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

1. NAME				
COMMON: Franklin Street Presbyterian Church				
AND/OR HISTORIC:				
2. LOCATION				
STREET AND NUMBER: 100 West Franklin Street				
CITY OR TOWN: Baltimore				
STATE: Maryland			COUNTY:	
3. CLASSIFICATION				
CATEGORY (Check One)	OWNERSHIP		STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object	<input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure <input type="checkbox"/> Both		<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input type="checkbox"/> Restricted <input checked="" type="checkbox"/> Unrestricted <input type="checkbox"/> No
PRESENT USE (Check One or More as Appropriate)				
<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input type="checkbox"/> Private Residence <input checked="" type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify)	<input type="checkbox"/> Comments
4. OWNER OF PROPERTY				
OWNER'S NAME: Committee of the Presbyterian Church				
STREET AND NUMBER:				
CITY OR TOWN: Baltimore			STATE: Maryland	
5. LOCATION OF LEGAL DESCRIPTION				
COURTHOUSE, REGISTRY OF DEEDS, ETC.: Records Office, Room 601, Baltimore City Courthouse				
STREET AND NUMBER: Fayette and Calvert Streets				
CITY OR TOWN: Baltimore			STATE: Maryland	
			21202	
Title Reference of Current Deed (Book & Pg. #): RHB 3091-485				
6. REPRESENTATION IN EXISTING SURVEYS				
TITLE OF SURVEY: City of Baltimore Neighborhood Survey				
DATE OF SURVEY: 1975 <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> County <input checked="" type="checkbox"/> Local				
DEPOSITORY FOR SURVEY RECORDS: Commission for Hist. and Arch. Pres.				
STREET AND NUMBER: 26 S. Calvert St.				
CITY OR TOWN: Baltimore			STATE: Maryland	
			21202	

SEE INSTRUCTIONS

7. DESCRIPTION

CONDITION	(Check One)					
	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site		

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

This masonry church was built in Tudor Gothic style. The facade is divided into three sections delineated by two towers which flank the pitched-roofed center section.

The main entrance is in the form of a compound Tudor arch set in a rectangular frame. The spandrels above the arch are decorated with floral carvings. Flanking the arch, and hanging from a projecting string course which spans the center section and towers, are two pendant-like corbels. On either outer side of these are two buttresses which rise to the string course. The doors of the outer sections of the facade have identical configurations and ornamentation, except that they have no flanking buttresses, and they are of smaller dimensions.

Above the belt course in the facade is a course of talon-like mouldings. Directly above this is a large stained glass window which breaks into tracery towards the crown. This window is set in a four-centered, pointed (Tudor) arch which is accentuated by moulding about the crown of the arch. The moulding ends in corbels.

Towards the top of the center section of the facade, the roof line is emphasized by pitched moulding, above which appears a stepped rampart, a motif which is carried onto the rooftops of the outer sections of the building and the tops of the towers.

The towers are octagonal and are divided into six levels by cornice-like projectures which wrap around them. The first and second levels are blank; a rectangular, single hung window with four lights appears in the third level of each tower. Above the flat-arched lintels are mouldings which follow the lintels' line and fall into corbels on either side of the window. Windows of identical design appear at the fourth level. The fifth level contains eight louvred, pointed arch windows with ovoid tracery spandrels set in tall, flat-arched recesses. Sills and lintels are flat stone slabs. The abbreviated sixth level is blank, and is topped by the crenelated rampart.

The outer sections of the facade have a low-pitched roof, buttressed corners perpendicular to the facade, and large pointed arch tracery windows with corbeled mouldings over the doorways.

The sides of the building are broken into seven bays which are formed by buttresses. In each bay is a large, pointed arch tracery window with a simple stone sill and a partial moulding ending in corbels.

The church was lengthened in 1865. The original architect was Robert Carey Long, Jr.

SEE INSTRUCTIONS

B. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- | | | | |
|--|---------------------------------------|--|---------------------------------------|
| <input type="checkbox"/> Pre-Columbian | <input type="checkbox"/> 16th Century | <input type="checkbox"/> 18th Century | <input type="checkbox"/> 20th Century |
| <input type="checkbox"/> 15th Century | <input type="checkbox"/> 17th Century | <input checked="" type="checkbox"/> 19th Century | |

SPECIFIC DATE(S) (If Applicable and Known) C. 1844

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|--|---|---|--|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input checked="" type="checkbox"/> Religion/Philosophy | <input type="checkbox"/> Other (Specify) |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | <input type="checkbox"/> Science | _____ |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Sculpture | _____ |
| <input checked="" type="checkbox"/> Architecture | <input type="checkbox"/> Landscape Architecture | <input type="checkbox"/> Social/Humanitarian | _____ |
| <input type="checkbox"/> Art | <input type="checkbox"/> Literature | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Military | <input type="checkbox"/> Transportation | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Music | | _____ |
| <input type="checkbox"/> Conservation | | | _____ |

STATEMENT OF SIGNIFICANCE

Refer to 505 Park Avenue

SEE INSTRUCTIONS

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Blank area for Major Bibliographical References.

10 GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreage Justification:

88'x140'

SEE INSTRUCTIONS

11. FORM PREPARED BY

NAME AND TITLE:
Joseph Potts, Planning Assistant

ORGANIZATION: Commission for Hist. and Arch. Pres. DATE: 11/6/75

STREET AND NUMBER: 26 S. Calvert St.

CITY OR TOWN: Baltimore, STATE: Maryland 21202

12. State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National State Local

Signature _____

REVISIONS

LOT 110, BLOCK 550, WARD 11, DISTRICT 13


B-23

532


W. CENTRE ST.

ST.

AVE.



ALLEY
PLOY




ST.

549

W. HAMILTON ST.

ST.

PARK



CATHEDRAL

551

W. FRANKLIN ST.

ST.

564

CITY OF BALTIMORE
DEPARTMENT OF PUBLIC WORKS

PROPERTY LOCATION DIVISION

WARD 11, SECTION 10
BLOCK 550

NOTICE

THIS IS A REVISION TO THE ORIGINAL PLAN...
FOR THE PURPOSE OF CORRECTING THE...
OF THE...
DATE: 11/15/1993

SCALE: 1"=50'

DATE: 11/15/1993

DATE: 11/15/1993

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM**

(Type all entries - complete applicable sections)

STATE: Maryland	
COUNTY: Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

1. NAME

COMMON:
Franklin Street Presbyterian Church and Parsonage

AND/OR HISTORIC:
Franklin Street Presbyterian Church and Parsonage

2. LOCATION

STREET AND NUMBER: 504 Cathedral Street (parsonage) 21201
100 West Franklin Street (northwest corner, at Cathedral St.)

CITY OR TOWN:
Baltimore

STATE Maryland	CODE 24	COUNTY: Baltimore City	CODE 510
-------------------	------------	---------------------------	-------------

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District <input checked="" type="checkbox"/> Building <input type="checkbox"/> Site <input type="checkbox"/> Structure <input type="checkbox"/> Object	<input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both	Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered	<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress
PRESENT USE (Check One or More as Appropriate)			
<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input type="checkbox"/> Private Residence <input checked="" type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify) _____ _____ _____
ACCESSIBLE TO THE PUBLIC Yes: <input type="checkbox"/> Restricted <input checked="" type="checkbox"/> Unrestricted <input type="checkbox"/> No			

4. OWNER OF PROPERTY

OWNER'S NAME:
Franklin St. Presbyterian Congregation in the City of

STREET AND NUMBER: /Baltimore, Md.
100 West Franklin Street

CITY OR TOWN: Baltimore

STATE: Maryland	CODE 24
--------------------	------------

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.:
Land Record Office of the Circuit Court of Baltimore City

STREET AND NUMBER:
Room 610, Courthouse, 100 North Calvert Street

CITY OR TOWN: Baltimore

STATE Maryland	CODE 24
-------------------	------------

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:
Maryland Register of historic sites and landmarks

DATE OF SURVEY: 1970 Federal State County Local

DEPOSITORY FOR SURVEY RECORDS:
Maryland Historical Trust

STREET AND NUMBER:
94 College Avenue

CITY OR TOWN: Annapolis

STATE: Maryland	CODE 24
--------------------	------------

SEE INSTRUCTIONS

STATE: Maryland
COUNTY: Baltimore City
ENTRY NUMBER
DATE

FOR NPS USE ONLY

SEE CONTINUATION SHEET

7. DESCRIPTION

CONDITION	(Check One)					
	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input type="checkbox"/> Altered	<input checked="" type="checkbox"/> Unaltered		<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site	

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

The Franklin Street Presbyterian Church is located on the northwest corner of the intersection of Franklin and Cathedral Streets, Baltimore, Maryland. The Franklin Street Presbyterian Church Parsonage is located directly north of the church on the west side of Cathedral Street.

Designed by the Baltimore architect, Robert Cary Long, Jr., in 1844 and dedicated in 1847, the Church heralded a turning point of architectural taste in Baltimore and marked the maturation of Robert Cary Long, Jr., as an architect, who later became the distinguished Greek-Revival architect of Baltimore. The church is significant because an action taken by its congregation immediately after the Civil War led directly to the formation of the Presbytery of Maryland (known familiarly as the Southern Church) which is still in existence (January 1971).

Prior to 1844 only two churches in Baltimore had been constructed in the Gothic idiom: the small and secluded chapel of St. Mary's Seminary, built in 1807 by French emigré Maximilian Godefroy, and St. Alphonsus' Roman Catholic Church, in 1842, by Robert Cary Long, Jr. Both structures, however, had been commissioned by religious groups only recently arrived from Europe. The Sulpician fathers, of St. Mary's, came in 1795; the Redemptorists, builders of St. Alphonsus', in 1840. The architectural taste of those two groups cannot be said to have reflected that of the native population of Baltimore. Long, Jr.'s 1844 Tudor Gothic Revival design for the Franklin Street Presbyterian Church was a different case as it was approved and accepted as a church by a session composed of Baltimoreans, not Europeans. That it represented a shift of local taste away from the neo-classicism that had dominated Baltimore architecture since the commencement of Benjamin Henry Latrobe's Old Roman Catholic Cathedral (the Basilica of the Assumption) in 1808 can be demonstrated by noting that after the completion of the Franklin Street Presbyterian Church no major ecclesiastical structure in Baltimore was built in the neoclassic style until the early twentieth century.

Because it is situated one block north of Latrobe's neo-classic cathedral, the Basilica, and one block west of Maximilian Godefroy's Roman-inspired Unitarian Church of 1817, the Franklin Street Presbyterian Church--within sight of both the others--allows a viewer to grasp the degree to which the introduction of Gothic revival styles redirected American church architecture in the middle of the nineteenth century in Baltimore.

SEE CONTINUATION SHEET

SEE INSTRUCTIONS

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- | | | | |
|--|---------------------------------------|--|---------------------------------------|
| <input type="checkbox"/> Pre-Columbian | <input type="checkbox"/> 16th Century | <input type="checkbox"/> 18th Century | <input type="checkbox"/> 20th Century |
| <input type="checkbox"/> 15th Century | <input type="checkbox"/> 17th Century | <input checked="" type="checkbox"/> 19th Century | |

SPECIFIC DATE(S) (If Applicable and Known) 1844-1847

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|--|---|---|--|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input checked="" type="checkbox"/> Religion/Philosophy | <input type="checkbox"/> Other (Specify) _____ |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | <input type="checkbox"/> Science | _____ |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Sculpture | _____ |
| <input checked="" type="checkbox"/> Architecture | <input type="checkbox"/> Landscape Architecture | <input type="checkbox"/> Social/Humanitarian | _____ |
| <input type="checkbox"/> Art | <input type="checkbox"/> Literature | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Military | <input type="checkbox"/> Transportation | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Music | | _____ |
| <input type="checkbox"/> Conservation | | | _____ |

STATEMENT OF SIGNIFICANCE

In American religious history the Franklin Street Presbyterian Church holds an important place as the founder of the Southern Presbyterian Church (1866).

The architect of the church, Robert Cary Long, Jr., 1810-1849, and of the parsonage, R. Snowden Andrews (1830-1903), were important mid-nineteenth-century Maryland architects.

The Franklin Street Presbyterian Church is significant part of the street scape of the City of Baltimore. The church is located in a section of the city which within a four block radius encompasses Benjamin Latrobe's Basilica, a National Register of Historic Places property; Mount Vernon Place which contains Robert Mills' monument to George Washington; Stanford White's (architect, New York) Jerome Mansion; Maximilian Godefroy's First Unitarian Church; the Mount Vernon United Methodist Church, Jacobs Mansion, Thomas Jenkins-Gladdings House. All of these buildings including the Franklin Street Presbyterian Church, are located in what was an important residential section of Baltimore developed in the mid-nineteenth century. Political and social leaders of both the city and the state lived in this neighborhood.

Dr. Phoebe B. Stanton, an outstanding student and author of Gothic Revival architecture has attested to the architectural significance of the Franklin Street Presbyterian Church in her book, The Gothic Revival of American Church Architecture An Episode in Taste 1840-1856 and in written correspondence. Her opinion is supported by Wilbur H. Hunter, Jr., Director of the Municipal Museum of the City of Baltimore, in "Robert Cary Long, Jr., and the Battle of Styles," Journal of the Society of Architectural Historians, XIV (March 1957), 28-30.

Talbot Hamlin (New York 1944, 1961) in Greek Revival Architecture in America called Robert Cary Long, Jr., the distinguished Greek Revival Architect of Baltimore.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Recorders:

William Morgan, Maryland Historical Trust, Annapolis, Maryland, June 1969.

Catherine Black, Maryland Historical Trust, Annapolis, Maryland, November 1970.

James Waesche, Baltimore Magazine, 1971

10. GEOGRAPHICAL DATA

SEE CONTINUATION SHEET

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY				O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES				
CORNER	LATITUDE		LONGITUDE		LATITUDE		LONGITUDE		
	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds
NW	°	'	"	°	'	"	39 °	17 '	58.59"
NE	°	'	"	°	'	"	76 °	36 '	52.16"
SE	°	'	"	°	'	"			
SW	°	'	"	°	'	"			

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: 0.28 acre

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE

11. FORM PREPARED BY

NAME AND TITLE:

Mrs. Preston Parish, Keeper of the Maryland Register

ORGANIZATION

Maryland Historical Trust

DATE

June 9, 1971

STREET AND NUMBER:

94 College Avenue

CITY OR TOWN:

Baltimore

STATE

Maryland

CODE

24

12. STATE LIAISON OFFICER CERTIFICATION

NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National State Local

Name Orlando Ridout IV
Orlando Ridout IV

Title State Liaison Officer
for Maryland

Date JUN 9 1971

I hereby certify that this property is included in the National Register.

Chief, Office of Archeology and Historic Preservation

Date _____

ATTEST:

Keeper of The National Register

Date _____

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

Maryland	
COUNTY Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Franklin Street Presbyterian Church and Parsonage

#6. REPRESENTATION IN EXISTING SURVEYS continued

Historic American Buildings Survey

1958 Federal

Library of Congress
Washington, D. C. code: 11

Commission for Historical and Architectural Preservation

1970 Local

402 City Hall
Baltimore, Maryland code: 24

#7. DESCRIPTION continued

Robert Cary Long, Jr., was born in Baltimore in 1810, the son of a master carpenter who had himself achieved considerable local recognition as a designer of buildings. Unlike his father, Robert Cary Long, Jr. received formal training in architecture, studying in New York with Martin Euclid Thompson. It was not until 1833, at the death of his father, that he returned to Baltimore. His earliest buildings and designs in that city were in the "classical" and Egyptian modes. His first introduction to the Gothic style was St. Alphonsus', which can be seen more as an experiment than as a work displaying complete self-assurance. With the Franklin Street Presbyterian Church, however, although he drew certain motives from works of Thomas Hope (specifically, An Historical Essay on Architecture) and A. W. Pugin (Specimens of Gothic Architecture and Examples of Gothic Architecture), Long, Jr. revealed a mastery of the Gothic idiom and an understanding of its principles rather than a mere facility in the application of its decorative devices.

In 1866, 17 years after Long, Jr.'s death and one year after the end of the Civil War, the congregation of the Franklin Street Presbyterian Church, under the leadership of the Reverend J. J. Bullock, D.D., severed its connections with the Presbytery of Baltimore because of a dispute with the General Assembly of the Presbyterian Church. The dispute arose because the General Assembly, the governing body of the Presbyterian Church, required

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM**

(Continuation Sheet)

Maryland	
COUNTY Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Franklin Street Presbyterian Church and Parsonage

#7. DESCRIPTION continued

its member congregations to give allegiance to the Federal government rather than to the governments of the various states. The result of the separation was the formation of the Presbytery of Maryland and the southern branch of American Presbyterianism, the Presbyterian Church, U. S.

The building is still (January 1971) used for worship and other religious purposes by the congregation of the Franklin Street Presbyterian Church.

The architectural description of the Franklin Street Presbyterian Church from the files of the Historic American Buildings Survey is on file at the Library of Congress. Excerpts of it are as follows:

Generally, the main part of the church is a rectangle with gabled roof. The front facing south has a large main entrance with double oak doors and nicely trimmed with stone, with pilasters each side, the door having a Tudor-gothic arched head and a stone Gothic cornice between the door head and the main window. The church window is divided into five vertical sections with stone mullions ending in trefoils, the window head is a larger Tudor-gothic arch trimmed in stone.

On each side of the main entrance is an octagonal belfry about ten feet in diameter. These belfries or towers are about 60 feet high and are topped by embattlements. The top sections have louvered windows with small windows on the front below.

On each side of the towers are secondary entrances, similar to the main entrance but smaller, with Tudor arches of stone and arched windows above. These windows are trimmed with moulded brick.

The front gable of the church has crenels and merlons running up the rake, and is contained by the towers, the side entrances being topped by horizontal parapets with embattlements, forming returns for the parapet at the sides of the building.

Both sides of the building have seven bays with stained glass windows between and buttresses dividing the bays.

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM**

(Continuation Sheet)

STATE	
Maryland	
COUNTY	
Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Franklin Street Presbyterian Church and Parsonage

#7. DESCRIPTION continued

The parapets on each side are approximately 35 feet above the first floor and are enriched with embattlements, consisting of crenels and merlons, the crenels having copper flashing and a sort of false gutter behind.

The gabled roof is of tar and felt covering and probably has scissor trusses spanning the church, although only the bottom chord is visible on the interior.

The Church is set back from the street about 15 feet on both the front and side. The forecourt in the front is raised three steps from the street and the side is sunken to the basement level. The property is enclosed with a cast-iron, Gothic-Revival fence with octagonal granite posts; the tops of the railings have crestings and a trefoil design. Both the forecourt and the sunken court are paved with brick laid in a herringbone pattern. Due to the slope of Cathedral Street the rear of the Church is sufficiently above grade to allow basement entrances in the last bay.

The main doors of the church are of oak and the main floor is raised three steps from the forecourt. Steps are of granite.

The interior of the church consists of a front vestibule about 12 feet wide and two ante-rooms into which the two front secondary doors enter. The belfries have circular stairs leading down to the basement and upward to the choir loft and towers. Both the vestibule and ante-rooms lead into the nave of the church which is approximately 55 feet wide and without columns. The length of the nave is about 78 feet exclusive of the pulpit. Six of the stained glass windows on each side show in the nave; the seventh or front window shows in the ante-rooms.

The nave has oak paneling 4'-8" high, in Gothic design, with high oak panels about 9 feet high at both sides of the altar, which is recessed from the rear of the church and backed by a high oak screen, back-of the pulpit.

The ceiling of the nave is about 28 feet high at the side walls, sloping to a flat section in the center

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE Maryland	
COUNTY Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Franklin Street Presbyterian Church and Parsonage

#7. DESCRIPTION continued

of the church about 32 feet high. The bottom chord of the trusses are exposed with knees trussed down at the buttresses and resting on brackets at the walls. These brackets rest on half round pilasters which in turn terminate on brackets about 6 feet above the floor. The trusses and decorative grilles are of wood, with all molding details in superimposed plaster.

The walls of the church, above the paneling, are of plaster, painted gray with painted joints simulating stone.

The church is lighted with suspended lanterns of iron and colored glass, one row of two fixtures to each bay.

The pews are of oak, the sides carved with poppy heads and finials.

The choir occupies a balcony over the front vestibule into which the main front window shows.

The basement of the church consists of a lobby at the foot of the stairs, with paneling to the ceiling and quarry tile floors, with rest rooms and a mechanical equipment room at the west side. The church has no boiler room as such, being heated by the district steam system.

The lobby leads into a parish hall, the full width of the church and about 50 feet long, ending in a stage at the north. Rooms flanking the stage are a kitchen at the west and an entrance lobby at the east, both with double doors to the outside.

The parish hall has a double row of wood-paneled columns, a plaster ceiling with lacunars or plaster panels, the ceiling being 9'-4" high. The floors are of wood parquet laid diagonally.

The foundation walls of the church are of stone below grade and brick above.

At the rear of the church, extending to Hamilton Street is a three story parish house, the full width of the church and about 30 feet deep. The design is similar

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

S E Maryland	
COUNTY Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Franklin Street Presbyterian Church, and Parsonage

#7. DESCRIPTION continued

to the church, the windows topped with brick Tudor-Gothic arches.

In general, the property is well maintained, although there is some spalling of the stone work. The rough, pinkish brick was originally painted.

While discussing Robert Cary Long, Jr., and the Franklin Street Presbyterian Church in The Gothic Revival of American Church Architecture An Episode in Taste, 1840-1856, Dr. Phoebe B. Stanton points out the architectural sources of the church. Illustrations in Thomas Hope's An Historical Essay on Architecture guided Long, Jr.'s conception of the general aspect of the facade of the church. Two Pugin books, Specimens of Gothic Architecture and Examples of Gothic Architecture contained details that Long, Jr. incorporated into the Franklin Street Church. Dr. Stanton draws a parallel between the octagonal towers and crenelated parapets of the Franklin Street Presbyterian Church and John Notman's Laurel Hill Cemetery Chapel (1837) in Philadelphia which was modeled after Hampton Court. The Ann Boelyn Gate at Hampton Court has been mentioned as the source for the southern facade of the Franklin Street Presbyterian Church.

The Board of Trustees of the Franklin Street Presbyterian Church enlarged the church in 1872. One bay was added at the north end of the church to accomodate additional pews. In 1911 the original painted exterior of the church was removed by sand blasting. Additional interior changes were made in 1888, 1902, 1911 and 1925-1926.

#8. SIGNIFICANCE continued

The Franklin Street Presbyterian Church stands out in American religious heritage owing to the church's separation from the Presbytery of Baltimore, part of the General Assembly of the Presbyterian Church. In 1866 the congregation of the Franklin Street Church led by their minister, the Reverend J. J. Bullock, D.D., severed its connection with the city and national organization because of those organizations' decision to require its members to swear allegiance to the United States of America. The Franklin Street congregation formed a separate

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM**

(Continuation Sheet)

STATE Maryland	
COUNTY Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Franklin Street Presbyterian Church, and Parsonage

#8. SIGNIFICANCE continued

organization, the Presbytery of Maryland, which later became the Southern Presbyterian Church, U. S.

In 1844 a group of Baltimore Presbyterians led by the Reverend John C. Backus of the First (and at that time the only) Presbyterian Church, felt that Baltimore needed another Presbyterian church located in the expanding northern section of the city. This group without Reverend Backus left the First Presbyterian Church and founded the Franklin Street Presbyterian Church in the heart of this growing neighborhood on the corner of Franklin and Cathedral Streets. The First Presbyterian Church in 1853 followed the Franklin Street Church by moving north to a site on Madison and Park Avenue. This is an early example of the phenomenon of a church moving to follow the migration of its congregation out of the center of the city.

The first Board of Trustees of the Franklin Street Presbyterian Church chose Robert Cary Long, Jr., (1810-1849) for the architect of their church. Son of a Baltimore architect of the same name, Long would have been known to the Board members as the designer of residences in the neighborhood of the church site, Charles Street and Mount Vernon Place. Long had earlier designed a city jail (1832), the gates for Greenmount Cemetery (1837) and a Gothic Revival Roman Catholic Church, St. Alphonsus (1842), a few blocks away. Long, architecturally ambidextrous, persuaded the Board to accept his Tudor-Gothic design instead of plans for a Greek revival church by stating that the classical style would be more costly to erect. This initial financial concern did not continue throughout the construction for the total cost of the church ran \$10,000 over the original estimate of \$28,000.

In 1857, ten years after the completion of the church, Colonel R. Snowden Andrews (1830-1903) had completed the parsonage of the Franklin Street Presbyterian Church. The parsonage has Gothic Revival trim reflecting Robert Cary Long's church next door. Andrews, who had worked for the Baltimore architectural firm of Niernsee and Neilson was responsible for the Eastern Female High School (1862) and for the original Governor's Mansion on State Circle in Annapolis which was covered with a colonial revival facade in the twentieth century.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

5. State Maryland	
COUNTY Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Franklin Street Presbyterian Church and Parsonage

#9. REFERENCES continued

Hamlin, Talbot. Greek Revival Architecture in America: Being an Account of Important Trends in American Architecture and American Life Prior to the War Between the States. New York: Dover, 1944.

Historic American Buildings Survey. Data pages on the Franklin Street Presbyterian Church. March 1959. Library of Congress, Washington, D. C.

Howland, Richard H. and Eleanor P. Spencer. The Architecture of Baltimore A Pictorial History. Baltimore: Johns Hopkins Press, 1953.

Hunter, Wilbur H. "Robert Cary Long, Jr., and the Battle of Styles." Journal of the Society of Architectural Historians. XVI (March 1957), 28-30.

"Report of a Joint Committee Appointed by Act of Assembly, Passed January Session, 1867, to Purchase a Lot and Erect a Mansion for the Governor of the State." Annapolis: William Thompson, 1870. Maryland Public Documents 1870. Document H. Hall of Records, Annapolis, Maryland.

Royal Commission on Historical Monuments, England. Photographs of Hampton Court Palace. London: n.p., 1938.

Scharf, J. Thomas. A History of Baltimore City and County, Maryland.... Philadelphia: Louis H. Everts, 1881.

Stanton, Phoebe B. The Gothic Revival of American Church Architecture An Episode in Taste 1840-1856. Baltimore: Johns Hopkins Press, 1968.

Withey, Henry F. and Elsie Rathburn Withey. Biographical Dictionary of American Architects (Deceased). Los Angeles: New Age Publishing, 1956.

NATIONAL REGISTER OF HISTORIC PLACES

PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

STATE Maryland 8-23	
COUNTY Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Franklin Street Presbyterian Church and Parsonage			
AND OR HISTORIC: Franklin Street Presbyterian Church and Parsonage			
2. LOCATION			
STREET AND NUMBER: 100 W. Franklin St. (church); 504 Cathedral St. (parsonage)			
CITY OR TOWN: Baltimore			
STATE: Maryland	CODE 24	COUNTY: Baltimore City	CODE 510
3. PHOTO REFERENCE			
PHOTO CREDIT: Baltimore Department of Planning, Filip Sibley			
DATE OF PHOTO: 1968			
NEGATIVE FILED AT: Commission for Historical & Architectural Preservation, 402 City Hall, Baltimore, Maryland			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC. Franklin Street Presbyterian Church, from southeast			



STATE Maryland	
COUNTY Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

NATIONAL REGISTER OF HISTORIC PLACES


PROPERTY PHOTOGRAPH FORM

(Type all entries - attach to or enclose with photograph)

SEE INSTRUCTIONS

MHT B-23

1. NAME			
COMMON: Franklin Street Presbyterian Church and Parsonage			
AND/OR HISTORIC: Franklin Street Presbyterian Church and Parsonage			
2. LOCATION			
STREET AND NUMBER: 100 W. Franklin St. (church); 504 Cathedral St. (parsonage)			
CITY OR TOWN: Baltimore			
STATE: Maryland	CODI: 24	COUNTY: Baltimore City	COM: 510
3. PHOTO REFERENCE			
PHOTO CREDIT: Baltimore Department of Planning, Filip Sibley			
DATE OF PHOTO: 1968			
NEGATIVE FILED AT: Commission for Historical and Architectural Preservation, 402 City Hall, Baltimore, Maryland			
4. IDENTIFICATION			
DESCRIBE VIEW, DIRECTION, ETC. Franklin Street Presbyterian Church Parsonage, from the east			



**NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY MAP FORM**

(Type all entries - attach to or enclose with map)

STATE	
Maryland	
COUNTY	
Baltimore City	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

SEE INSTRUCTIONS

1. NAME			
COMMON: Franklin Street Presbyterian Church and Parsonage			
AND/OR HISTORIC: Franklin Street Presbyterian Church and Parsonage			
2. LOCATION			
STREET AND NUMBER:			
100 W. Franklin St. (church); 504 Cathedral St. (parsonage)			
CITY OR TOWN:			
Baltimore			
STATE:	CODE	COUNTY:	CODE
Maryland	24	Baltimore City	510
3. MAP REFERENCE			
SOURCE:			
U.S.G.S. 7.5 minute map, Baltimore East Quadrangle			
SCALE: 1: 24 000			
DATE: 1953 photorevised 1966			
4. REQUIREMENTS			
TO BE INCLUDED ON ALL MAPS			
1. Property boundaries where required.			
2. North arrow.			
3. Latitude and longitude reference.			



B-23

BALTIMORE EAST QUADRANGLE
Scale 1 inch = 0.5 mile
24,000 feet
photorevised 1966

BALTIMORE

17'30"

4348

20 000 FEET
MIDDLE BRANCH



B-23 + 234
(R-B-1988)

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

STATE:	
COUNTY:	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

1. NAME

COMMON:
Franklin Street Presbyterian Church and Parsonage

AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER:
100 W. Franklin St. (church); 502 Cathedral Street (parsonage)

CITY OR TOWN:
Baltimore

STATE: Maryland CODE: 24 COUNTY: Baltimore City CODE: 570

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
District <input type="checkbox"/> Building <input checked="" type="checkbox"/>	Public <input type="checkbox"/> Private <input type="checkbox"/> Both <input checked="" type="checkbox"/>	Occupied <input checked="" type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress <input type="checkbox"/>	Yes: Restricted <input checked="" type="checkbox"/> Unrestricted <input type="checkbox"/> No: <input type="checkbox"/>
Site <input type="checkbox"/> Structure <input type="checkbox"/> Object <input type="checkbox"/>	Public Acquisition: In Process <input type="checkbox"/> Being Considered <input type="checkbox"/>		

PRESENT USE (Check One or More as Appropriate)

Agricultural <input type="checkbox"/>	Government <input type="checkbox"/>	Park <input type="checkbox"/>	Transportation <input type="checkbox"/>	Comments <input type="checkbox"/>
Commercial <input type="checkbox"/>	Industrial <input type="checkbox"/>	Private Residence <input type="checkbox"/>	Other (Specify) <input type="checkbox"/>	
Educational <input checked="" type="checkbox"/>	Military <input type="checkbox"/>	Religious <input checked="" type="checkbox"/>		
Entertainment <input type="checkbox"/>	Museum <input type="checkbox"/>	Scientific <input type="checkbox"/>		

4. OWNER OF PROPERTY

OWNERS NAME:
Franklin Street Presbyterian Church

STREET AND NUMBER:
100 W. Franklin Street

CITY OR TOWN: Baltimore STATE: Maryland CODE: 24

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC.: Liber; GES 206 Folio: 445
Land Record Office of the Circuit Court of Baltimore City

STREET AND NUMBER:
Room 610, Court House, 100 N. Calvert Street

CITY OR TOWN: Baltimore STATE: Maryland CODE: 24

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: .28 acres

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:
Historic American Buildings Survey

DATE OF SURVEY: 1958 Federal State County Local

DEPOSITORY FOR SURVEY RECORDS:
Library of Congress

STREET AND NUMBER:
Washington, 1st St. between Capitol & Independence Ave., S.E.

CITY OR TOWN: Washington, District of Columbia STATE: D.C. CODE: 08

SEE INSTRUCTIONS

Old Reg

STATE:
COUNTY:
ENTRY NUMBER
DATE
FOR NPS USE ONLY

7. DESCRIPTION

CONDITION	(Check One)					
	Excellent <input checked="" type="checkbox"/>	Good <input type="checkbox"/>	Fair <input type="checkbox"/>	Deteriorated <input type="checkbox"/>	Ruins <input type="checkbox"/>	Unexposed <input type="checkbox"/>
INTEGRITY	(Check One)			(Check One)		
	Altered <input checked="" type="checkbox"/>			Unaltered <input type="checkbox"/>		
			Moved <input type="checkbox"/>			Original Site <input checked="" type="checkbox"/>

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

Designed and built by Robert Cary Long, Jr. in 1847, the Franklin Street Presbyterian Church is one of his major works in Baltimore. Long was influential in introducing the Gothic style to the city and his choice of the Tudor Gothic style for this Scottish Presbyterian congregation was especially fitting.

The church facade bears a striking resemblance to Anne Boleyn's Gatehouse at Hampton Court Palace, ^(1.) and details were drawn directly from plates in Specimens of Gothic Architecture by A.C. and A.W.N. Pugin, according to the ⁽²⁾ Historic American Buildings Survey.

Built of red brick with stone trim, the building is set back from the street by a small brick courtyard paved in herringbone pattern and enclosed by a cast iron fence of Gothic Revival design. On each side of the main entrance is an octagonal tower topped by embattlements.

The tracery of the stained glass windows is entirely cast in iron which was locally produced. The interior of the building is richly decorated with oak panelling and the oak pews have finials carved in the shape of poppies. Michael Cornell, master carpenter, was responsible for these.

The Parsonage, called Kirk House, was added in 1857 and was the design of R. Snowden Andrews. It is similar in style to the church and is one of only a few gabled roof residences of the period remaining in Baltimore.

(1). See photograph in "Photographs of Hampton Court Palace, Middlesex" Royal Commission on Historical Monuments, England. (Pub. by His Majesty's Stationery Office, London. 1938) p.5.

(continued)

SEE INSTRUCTIONS

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

Pre-Columbian 16th Century 18th Century 20th Century
 15th Century 17th Century 19th Century

SPECIFIC DATE(S) (If Applicable and Known) 1844-45

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

Aboriginal	Education	<input type="checkbox"/>	Political	<input type="checkbox"/>	Urban Planning	<input type="checkbox"/>
Prehistoric	Engineering	<input type="checkbox"/>	Religion/Phi-		Other (Specify)	<input type="checkbox"/>
Historic	Industry	<input type="checkbox"/>	losophy	<input checked="" type="checkbox"/>	_____	
Agriculture	Invention	<input type="checkbox"/>	Science	<input type="checkbox"/>	_____	
Art	Landscape		Sculpture	<input type="checkbox"/>	_____	
Commerce	Architecture	<input type="checkbox"/>	Social/Human-		_____	
Communications	Literature	<input type="checkbox"/>	itarian	<input type="checkbox"/>	_____	
Conservation	Military	<input type="checkbox"/>	Theater	<input type="checkbox"/>	_____	
	Music	<input type="checkbox"/>	Transportation	<input type="checkbox"/>	_____	

STATEMENT OF SIGNIFICANCE (Include Personages, Dates, Events, Etc.)

The Franklin Street Presbyterian Church was incorporated in 1844 by a group of men from the First Presbyterian Church who felt the need for a new church in the fast growing northern section of the city. They purchased the lot on the corner of Franklin and Cathedral Streets and chose Robert Cary Long, Jr. as the architect. Long persuaded the Trustees that the popular neo-classical style of architecture was too costly and selected the Tudor instead. Business relationships between Long and the Trustees were frequently strained by lack of funds and the claim that Long was too slow in submitting his drawings. The structure, however, was dedicated February 22, 1847. A parsonage, designed by R. Snowden Andrews, was constructed next to the church on the Cathedral Street side, in 1857.

In the ensuing years, the congregation has thrived and members have been instrumental in organizing other Presbyterian churches in the city. At the close of the Civil War, in 1866, the Franklin Street congregation severed connections with the Presbytery of Baltimore because of a dispute over the requirement of paying allegiance to the Federal government.

(continued)

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Howland, Richard H. and Eleanor P. Spencer. The Architecture of Baltimore. (Baltimore, 1953)
 Hunter, Wilbur H., Jr. "Robert Cary Long, Jr and the Battle of Styles". Journal of the Society of Architectural Historians, Vol. XVI, no. 1 (March 1957).
 Royal Commission on Historical Monuments, England. Photographs of Hampton Court Palace, Middlesex. (London, 1938).
 Scharf, J. Thomas. History of Baltimore City and County, Maryland. (Baltimore, 1881). Continued

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN ONE ACRE		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE

11. FORM PREPARED BY

NAME AND TITLE:
Catharine F. Black

ORGANIZATION: Maryland Historical Trust DATE: Nov. 1970

STREET AND NUMBER:
Box 1704

CITY OR TOWN: Annapolis STATE: Maryland CODE: _____

12. STATE LIAISON OFFICER CERTIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National State Local

Name _____

Title _____

Date _____

NATIONAL REGISTER VERIFICATION

I hereby certify that this property is included in the National Register.

 Chief, Office of Archeology and Historic Preservation

Date _____

ATTEST:

 Keeper of The National Register

Date _____

SEE INSTRUCTIONS

Continuation Sheet

Franklin Street Presbyterian Church and Parsonage

Baltimore

#7. Note (2.) Historic American Buildings Survey. HABS No. MD-187
November, 1958. Prepared by Wilbur H. Hunter, Jr.

#8. This resulted in the formation of the Presbytery of Maryland, or
the "Southern" Presbyterian Church.

Among the outstanding clergymen who have served the church
are: Rev. J.J. Bullock, D.D., Harris E. Kirk, D.D. and Rev.
Iain Wilson.

#9. Stanton, Thoebe E., The Gothic Revival and American Church
Architecture. (Baltimore, 1968).

Additional Map Information:

City of Baltimore - Department of Public Works Map
Ward: 11 Section: 10 Block: 550 Lot: 1
Scale: 1" = 50'

Historic American Building Survey ^{Full} copies of
data sheets & HNT files - MD 187